

LEAD-SAFE WORK PRACTICES SURVEY PROJECT REPORT

November 2006

Prepared for



**1201 15th St NW
Washington, D.C. 20005**

November 9, 2006

Prepared by



11495 Sunset Hills Road Suite 210
Reston, Virginia 20190
Phone: 703-689-9482
Fax: 703-689-3998
www.atriumehs.com

TABLE OF CONTENTS

| | |
|---|-----------------------------------|
| EXECUTIVE SUMMARY | 1 |
| 1.0 INTRODUCTION | 7 |
| 2.0 BACKGROUND | 8 |
| 3.0 PROJECT APPROACH | 9 |
| 3.1 Terms used in this Report | 9 |
| 3.2 Renovation and Remodeling (R&R) Activities | 13 |
| 3.3 Work Practices | 14 |
| 3.4 Property Selection | 15 |
| 3.5 Work Force | 17 |
| 3.6 Data Collection Procedures and Sampling Techniques | 17 |
| 3.6.1 On-Site Project Introduction and Orientation | 17 |
| 3.6.2 Worker Protection | 17 |
| 3.6.3 Cross-Contamination Control | 18 |
| 3.6.4 Environmental Sampling | 19 |
| 3.7 Statistical Analysis Techniques | 23 |
| 4.0 RESULTS | 24 |
| 4.1 Quality Control Review of Field Data Collection Efforts | 26 |
| 4.2 Summary of Tools Used and Time Required to Complete Work | 27 |
| 4.3 Overall Summary of Sampling Results | 29 |
| 4.4 Results by Activity | 31 |
| 4.5 Results for Specific Tasks | 32 |
| 4.6 Results by Work Practice and Scenario | 32 |
| 4.7 Results by Property | 33 |
| 4.8 Worker Exposures | 33 |
| 5.0 DISCUSSION | 72 |
| 6.0 CONCLUSIONS | 79 |
| 7.0 REFERENCES | 82 |
| | |
| Exhibit A | FIELD DATA COLLECTION TOOL |
| | |
| Exhibit B | PROJECT DATA SUMMARIES |

TABLES AND FIGURES

TABLES

| | | |
|------|---|----|
| 3.1 | Terminology Used in This Report | 9 |
| 3.2 | Key and Miscellaneous Renovation and Remodeling Activities Evaluated | 13 |
| 3.3 | Summary of Events Evaluated by Activity/Work Practice Scenario and Assigned ID Codes | 15 |
| 3.4 | Number of Air Samples Collected During Each Event | 19 |
| 3.5 | Number of Surface Dust Samples Collected During Each Event | 22 |
| 4.1 | Number of Events Evaluated by Scenario | 24 |
| 4.2 | Summary of R&R Events Evaluated | 25 |
| 4.3 | Summary of Work Practices and Tools Used | 28 |
| 4.4 | Labor Required to Complete Work by R&R Activity | 28 |
| 4.5 | Labor Required to Complete Work by Work Practice | 29 |
| 4.6 | PBZ Air Sampling Results Summarized by Work Activity | 35 |
| 4.7 | Area Air Sampling Results Summarized by Work Activity | 37 |
| 4.8 | Surface Dust Sampling Results Summarized by Work Activity | 39 |
| 4.9 | Changes in Settled Dust Lead Loadings in Work Area by Work Area | 41 |
| 4.10 | PBZ Air Sampling Results Summarized by Sanding and Sawing Tasks | 42 |
| 4.11 | Area Air sampling Results Summarized by Sanding and Sawing Tasks | 44 |
| 4.12 | Surface Dust Sampling Results Summarized by Sanding and Sawing Tasks | 46 |
| 4.13 | PBZ Air Sampling Results Summarized by Scenario (Activity & Work Practice) | 48 |
| 4.14 | Area (During) Air Sampling Results Summarized by Scenario (Activity & Work Practice) | 53 |
| 4.15 | Surface Dust Sampling Results Summarized by Scenario | 58 |
| 4.16 | Changes in Settled Dust Lead Loadings in Work Area by Work | 62 |
| 4.17 | PBZ Air Sampling Results Summarized by Property | 63 |
| 4.18 | Area (During) Air Sampling Results Summarized by Property | 65 |
| 4.19 | Surface Dust Sampling Results Summarized by Property | 67 |
| 4.20 | Changes in Settled Dust Lead Loadings in Work Area by Property | 69 |
| 4.21 | Calculated 8-Hour Time Weighted Average (TWA) Exposures To Lead During Renovation and Remodeling Activities | 70 |

FIGURES

| | | |
|-----|---|----|
| 3.0 | Work Practice and Tool Checklist | 16 |
| 3.1 | Photograph of an Area Air Sample Collected During an R&R Work Event | 20 |
| 3.2 | Photograph of a PBZ Air Sample on an R&R Worker | 20 |
| 4.1 | Comparison of the GM of PBZ Air Sampling Results by Activity to the GM of the PBZ Air Sampling Results for all Activities | 36 |

FIGURES Continued

| | | |
|------|---|----|
| 4.2 | Comparison of the GM of Area (During) Air Sampling Results by Activity to the GM of the Area (During) Air Sampling Results for All Activities | 38 |
| 4.3 | Difference Between Post-Work Dust Samples and Pre-Work Dust Samples Based on GM of All Surfaces Sampled | 40 |
| 4.4 | Comparison of the GM of PBZ Air Sampling Results by Specific Task to the GM of the PBZ Air Sampling Results for All Activities | 43 |
| 4.5 | Comparison of the GM of Area Air Sampling Results by Specific Task to the GM of the Area Air Sampling Results for All Activities | 45 |
| 4.6 | Difference Between Post-Work Dust Samples and Pre-Work Dust Samples by Task Based on GM of All Surfaces Sampled | 47 |
| 4.7A | Comparison of the GM of PBZ Air Sampling Results by Scenario to the GM of the PBZ Air Sampling Results for All Activities | 51 |
| 4.7B | Comparison of the GM of PBZ Air Sampling Results by Scenario to the GM of the PBZ Air Sampling Results for All Activities | 52 |
| 4.8A | Comparison of the GM of the Area (During) Air Sampling Results by Scenario to the GM of the Area (During) Air Sampling Results for All Activities | 56 |
| 4.8B | Comparison of the GM of Area (During) Air Sampling Results by Scenario to the GM of the Area (During) Air Sampling Results for All Activities | 57 |
| 4.9A | Difference Between Post-Work Dust Samples and Pre-Work Dust Samples Based on GM of All Surfaces Sampled by Scenario | 60 |
| 4.9B | Difference Between Post-Work Dust Samples and Pre-Work Dust Samples Based on GM of All Surfaces Sampled by Scenario | 61 |
| 4.10 | Comparison of the GM of PBZ Air Sampling Results by Property to the GM of the PBZ Air Sampling Results for All Properties | 64 |
| 4.11 | Comparison of the GM of Area (During) Air Sampling Results by Property to the GM of the Area (During) Air Sampling Results for All Properties | 66 |
| 4.12 | Difference Between Post-Work Dust Samples and Pre-Work Dust Samples by Location Based on GM of All Surfaces Sampled | 68 |
| 4.13 | Estimated Projected 8-Hour Time Weighted Average (TWA) Exposures by Work | 71 |
| 5.1 | Effect of Misting with Water During Work on Air Sampling Results | 74 |
| 5.2 | Effect of Tool Used During Work on Air Sampling Results | 75 |
| 5.3 | Effect of Clean-Up Practice Used on Wipe Samples | 78 |

EXECUTIVE SUMMARY

The National Association of Home Builders (NAHB) has conducted an assessment of renovation/ remodeling (R&R) activities to measure levels of lead dust generated by home improvement contractors. The objective of this project was to measure the amount of lead dust generated during typical R&R activities and assess whether routine R&R activities increased lead dust levels in the work area and property.

In conducting this project, 342 air samples and 407 surface dust wipe samples were collected during 60 typical R&R activities conducted in five separate residential properties in Roselle, IL, Wallingford, CT, Farmington, CT, Cheshire, CT and Milwaukee, WI. This project evaluated complete renovation and remodeling (R&R) activities as they would occur in the marketplace. The activities evaluated during this project were selected in consultation with remodeling contractors, and represent the most common jobs performed by renovation and remodeling firms. The R&R work was performed by professional renovation and remodeling contractors from each of the areas where the properties were located.

Field data collection was performed by Atrium Environmental Health and Safety Services, LLC (Atrium). The National Center for Healthy Housing (NCHH) reviewed the data, conducted a quality control review of field activities, and conducted statistical analyses of the sampling results.

1. The properties included in this study had higher lead levels than is typical for housing containing LBP. Many of the R&R activities assessed were on surfaces and fixtures that contained lead levels of more than 9.9 mg/cm². While the lead content of the paint was relatively high, pre-work surface dust levels measured on floors and window sills in the work areas of these properties were within the ranges of surface dust levels measured in occupied dwellings during a similar HUD-funded study.
2. Fewer events where EPA/HUD LSWP were used were evaluated than events where Routine or Modified (Mod) LSWP were used.
3. The air and surface dust sampling data values were widely distributed.
4. Based on the data collected during this project, EPA/HUD Lead Safe Work Practices (LSWP) took approximately twice the labor effort to implement when compared to routine work practices.


Responses to three fundamental questions that formulated the objectives of this project are offered as follows:

1. Do typical renovation and remodeling activities create lead hazards?

Renovation and remodeling activities evaluated during this project did not create new lead dust hazards.


In all of the properties tested, pre-work (baseline) testing identified surface dust levels that exceeded current HUD/EPA criteria for floors and window sills. When considering R&R activities where no sanding was performed, the post-work samples collected from all surfaces were lower than the pre-work dust samples in all of the activities evaluated.

DIFFERENCE BETWEEN POST-WORK AND PRE-WORK DUST SAMPLES BY ACTIVITY BASED ON THE GEOMETRIC MEAN (GM) OF ALL SURFACES SAMPLED



| Activity Label Legend | |
|-----------------------|---|
| Label | Activity |
| A | Wall and Ceiling Removal |
| B | Wall and Ceiling Modification |
| C | Window Replacement (no sanding involved) |
| C' | Window Alteration (no sanding involved) |
| D | Kitchen and Bath Work |
| E | Floor Covering Removal |
| G | Sawing into Wood & Plaster Covered by LBP |
| All Sand | All Sanding Events |
| C Sand | Window and Door Replacement, Removal or Alteration (sanding events) |
| F Sand | Surface Preparation (sanding) |

When considering lead dust loading on surfaces throughout a single property, results showed that overall all but one of the properties evaluated (Farmington, CT) showed lower levels of lead dust when the R&R contractors completed the work than when they arrived.




2. When applying EPA’s lead-safe work practices to a set of typical renovation and remodeling activities, are surface lead hazards (>40 µg/ft² on floors, >250 µg/ft² on window sills), or airborne hazards (> 50 µg/m³ in the air) created?

In reviewing the results from all activities and all work practices, the trend was a reduction in both lead loading in surface dust as well as airborne lead based on the personal breathing zone (PBZ) air sample results. These results demonstrate that in most cases, no new hazards were created as a result of the renovation and remodeling activities conducted.


Based on the results of the wipe samples collected during this project, pre-work surface dust loading results already exceeded 40 µg/ft² on floors and 250 µg/ft² on window sills for all activities and all work practices employed – Routine, Mod LSWP, and LSWP.

There are several work practices that were demonstrated to have obvious benefits. Misting surfaces with water during work appears to significantly reduce airborne lead dust. Events where misting was used showed a significant reduction in airborne lead dust levels when compared to events where no misting was used.



Airborne lead dust levels were substantially lower when only hand tools or only hand sanding were used when compared to events where one or more power tools were used. Ventilated (shrouded) tools connected to HEPA filter-equipped vacuum cleaners showed a reduction when compared to sanding using non-shrouded orbital sanders and belt sanders, respectively.

For surface dust, reductions in the lead loading were observed when either re-useable drop cloths or disposable drop cloths were used. However, a more substantial reduction was shown in events where disposable drop cloths were used. The use of HEPA filter-equipped vacuum cleaners combined with either wet wiping or Swiffer® mops during post-work clean-up showed the greatest effect on reducing lead loading in surface dust.



3. Do modified lead-safe work practices reduce lead exposures below the PEL?

The PBZ samples collected during this project represented 35 workers’ 8-hour TWA exposures. Twenty-six of the calculated 8-hour TWA exposures were less than the OSHA Action Level of 30 µg/m³; and 29 were below the PEL of 50 µg/m³.


Estimating 8-hour TWA exposures by activity, regardless of work practice, showed that the following tasks can likely be performed for an entire work shift without exceeding the OSHA Action Level:

- Wall and ceiling demolition;
- Wall and ceiling modification;
- Window replacement with no sanding;
- Cabinet removal; and,
- Baseboard removal.

It is likely that window alterations with no sanding involved may be conducted using routine practices for shorter periods of time (e.g. less than 5 hours during a shift) without exceeding the OSHA PEL. Activities involving sanding resulted in projected 8-hour TWA exposures that exceeded the OSHA Action Level and PEL.

In most instances, those employees’ whose 8-hour TWA exposures exceeded the action level performed some type of sanding activity during their work day. Using ventilated (shrouded) tools connected to HEPA filter-equipped vacuum cleaners and other dust

control measures during sanding reduced airborne concentrations of lead dust, in most cases. During window and door alterations where sanding was conducted, employing some degree of dust control showed a reduction in airborne dust levels, in most cases, when compared to sanding with no controls. Performing surface preparation activities using dust control devices or techniques also showed a reduction over uncontrolled sanding during surface preparation.



1.0 INTRODUCTION

The National Association of Home Builders (NAHB) has conducted an assessment of renovation/ remodeling (R&R) activities to measure levels of lead dust generated by home improvement contractors. The objective of this project was to measure the amount of lead dust generated during typical R&R activities and assess whether routine R&R activities increased lead dust levels in the work area and property.

Air and surface dust samples were collected during typical R&R activities conducted from the following residential properties:

- A single family home in Roselle, IL;
- A two-story duplex in Wallingford, CT;
- A single family home in Farmington, CT;
- A single family home in Cheshire, CT; and,
- An apartment above a retail store front in Milwaukee, WI.

This project evaluated complete R&R activities as they would occur in the marketplace. The activities evaluated during this project were selected in consultation with remodeling contractors, and they represent the most common jobs performed by renovation and remodeling firms. The R&R work was performed by professional renovation and remodeling contractors from each of the communities where the properties were located. All of the R&R workers who participated in this project had previously attended and successfully completed the EPA/HUD curriculum for *Lead Safety for Remodeling, Repair, & Painting*.

Field data collection was performed by Atrium Environmental Health and Safety Services, LLC (Atrium). The National Center for Healthy Housing (NCHH) reviewed the data and conducted statistical analyses of the sampling results.

2.0 BACKGROUND

The Residential Lead-Based Paint Hazard Reduction Act (Title X), passed in 1992, directs the Environmental Protection Agency (EPA), the Department of Housing and Urban Development (HUD), and the Occupational Safety and Health Administration (OSHA) to develop programs to eliminate lead-based paint (LBP) hazards in all “target housing.” Target housing is defined as all residential structures built prior to 1978 that could be occupied by a child under the age of six. Approximately 68 percent of the existing housing stock meets this definition.

Title X directed EPA to issue appropriate LBP rules for the renovation and remodeling industry by 1996. Within this directive, EPA was tasked with conducting a study to determine which segments of the renovation and remodeling industry conduct activities which result in the creation of lead hazards. Additionally, the statute grants the EPA Administrator the discretion to exempt certain segments of the industry from regulation if they do not create lead hazards.

EPA spent the past few years working on a voluntary program incorporating lead-safe work practices for the renovation and remodeling industry. In 2003, EPA and HUD developed a joint curriculum, *Lead Safety for Remodeling, Repair, & Painting*, designed to teach lead-safe work practices to firms working in government-assisted housing. However, within the past year, facing mounting pressure due to the long past statutory deadline, the Agency abruptly abandoned work on the voluntary program and resumed the process of developing a mandatory program.ⁱ

EPA conducted an exposure study, published in 2000, on renovation and remodeling activities the Agency deemed typical. It found seven specific activities which resulted in lead dust levels near or above the OSHA exposure limit for workers (manual paint removal, paint removal with power tools, large structure removal (interior demolition), interior surface preparation for painting, HVAC work, sawing in wood covered by LBP, sawing in plaster covered by LBP). However, EPA did not examine whether modifying or initiating lead safe work practices might reduce worker and occupant exposure levels. Nor has it ever tested the efficacy of its own suite of lead-safe work practices.

On January 10, 2006, the EPA published its proposed Lead; Renovation, Repair, and Painting Program Rule in the Federal Register. EPA closed the comment period on this proposed rule on May 25, 2006.

Furthermore, OSHA is facing the possibility of a review of the lead in construction standard under section 610 of the Regulatory Flexibility Act and section 5 of Executive Order 12866 on Regulatory Planning and Review. In 2002, the Office of Management and Budget (OMB) directed OSHA to accept public comment on the LBP rule. OSHA began accepting public comments on the Rule in June, 2005.ⁱⁱ

3.0 PROJECT APPROACH

Research on lead-safe work practices could be instrumental in helping to modify OSHA’s Lead in Construction Rule, and to adjust EPA’s proposed Renovation and Remodeling Rule for greater relevance to the residential construction industry. To help make scientifically sound decisions and recommendations as new regulations and guidelines are developed for the construction industry, NAHB conducted research to answer the following fundamental questions related to lead-safe work practices:

1. Do typical renovation and remodeling activities create lead hazards?
2. When applying EPA’s lead-safe work practices to a set of typical renovation and remodeling activities, are surface lead hazards ($>40 \mu\text{g}/\text{ft}^2$ on floors, $>250 \mu\text{g}/\text{ft}^2$ on window sills), or airborne hazards ($> 50 \mu\text{g}/\text{m}^3$ in the air) created?
3. Do modified lead-safe work practices reduce lead exposures below the PEL?

To answer these questions, air monitoring and surface dust measurements were collected in homes that contain LBP during renovation and remodeling activities. The following types of measurements were collected:

- Work area air measurements (measured in μ/m^3)
- Personal breathing zone (PBZ) measurements (measured in μ/m^3)
- Surface dust wipe samples following completion of work (measured in $\mu\text{g}/\text{ft}^2$)

3.1 Terms used in this Report

The terminology used during this Project and in this report is defined in Table 3.1 below.

| TABLE 3.1 TERMINOLOGY USED IN THIS REPORT | |
|--|--|
| Property | <i>A property</i> refers to a residential building (single family home, apartment, or duplex) where renovation and remodeling activities were conducted during this Project. |
| Event | An <i>event</i> is a specific evaluation effort, including air and dust sampling, of a specific renovation and remodeling activity at a specific property. Each event has a specific date and time, and represents a specific scenario (see below). A total of sixty events were evaluated during this Project. |
| Activity | An <i>activity</i> is a specific renovation and remodeling effort. A listing of Key and Miscellaneous activities, which is summarized in Table 3.2, was provided by NAHB prior to beginning this Project. For the data analysis purposes, some activities were segregated further. Table 3.3 is a listing of the activities evaluated and analyzed during this effort. Six key activities and two miscellaneous activities were evaluated during this Project. |
| Work Practice | <i>Work practice</i> refers to the type and detail of the controls used to minimize dust generation during renovation and remodeling activities and the techniques used to clean the work area following work. Three types of work practices were evaluated during this |

**TABLE 3.1
TERMINOLOGY USED IN THIS REPORT**

| | |
|---|---|
| | Project: routine; modified lead-safe work practices; and lead-safe work practices as described by HUD and the EPA. These work practices are discussed in detail under the Project Approach section of this report. |
| Scenario | A <i>scenario</i> is the combination of renovation and remodeling activity and work practice used during a single event. There were 24 possible scenarios evaluated during this Project. Each scenario was assigned an alpha-numeric identification code for data management. A summary of the scenario codes is included in Table 3.3. |
| Work Area | A <i>work area</i> is a specific room or location within a property where a specific renovation and remodeling event was conducted. Work areas were segregated from adjacent areas of the property by fixed walls and doors; or, where walls or doors were not present, by polyethylene (plastic) sheeting barriers installed by the renovation and remodeling contractors. |
| Task | A <i>task</i> is a specific type of work performed during an activity. For the purposes of classifying and analyzing data collected during this project, activities that involved the tasks of sanding or sawing were categorized into the miscellaneous activities of surface preparation (sanding) and sawing. |
| Wall or Ceiling Removal (Demolition) | <i>Wall or ceiling removal (demolition)</i> refers to the removal of wall or ceiling finishes exposing the frame. These tasks were generally conducted using hand tools, including hammers and pry bars. The tasks and methods necessary to accomplish the activity were left to the professional judgment of the experienced renovation and remodeling contractor performing the work. |
| Wall or Ceiling Modification | <i>Wall or ceiling modification</i> refers to activities where walls or ceilings were modified or altered. Activities including installing recessed lighting, installing wall outlets and light switches, and installing windows or doors in walls were classified as modifications. These tasks were typically conducted using hand tools (hammers and pry bars) and electric saws (such as sawsalls). The tasks and methods necessary to accomplish the activity were left to the professional judgment of the experienced renovation and remodeling contractor performing the work. |
| Window or Door Removal and/or Replacement | <i>Window or door removal</i> and/or replacement refers to an activity involving removal of an existing window or door. This may include removal of the frame, casing, sash, or door, and may include installing a new door or window. Due to material limitations and the planned disposition of the properties, window replacements were simulated using raw lumber materials (planks and plywood) rather than finished materials and windows. The tasks and methods necessary to accomplish the activity were left to the professional judgment of the experienced renovation and remodeling contractor performing the work. |
| Window or Door Alteration | <i>Window or door alteration</i> refers to an activity involving the modification or alteration – other than replacement – of a door or |

**TABLE 3.1
TERMINOLOGY USED IN THIS REPORT**

| | |
|------------------------------|--|
| | <p>window. Alteration may involve work on the trim, molding, casing, sash or sill; but does not remove or replace an existing door or window. The tasks and methods necessary to accomplish the activity were determined by the professional judgment of the experienced renovation and remodeling contractor performing the work.</p> |
| Surface Preparation | <p><i>Surface preparation</i> refers to any activity where manual or mechanical sanding was performed to prepare a surface for a new finish. The surface condition and the extent of sanding and finishing necessary were determined by the professional judgment of the experienced renovation and remodeling contractor performing the work.</p> |
| Controlled Sanding | <p><i>Controlled sanding</i> refers to a sanding task where a ventilated or shrouded mechanical tool (such as an orbital sander) was connected to a vacuum cleaner equipped with a high efficiency particulate air (HEPA) filter.</p> |
| Manual Sanding | <p><i>Manual sanding</i> refers to hand sanding using a sheet of sand paper or a sanding block.</p> |
| Uncontrolled Sanding | <p><i>Uncontrolled sanding</i> refers to a sanding task where a power tool (such as an orbital sander or belt sander) was used without any supplemental or integrated ventilation or dust collection system.</p> |
| Disposable Drop Cloth | <p>A <i>disposable drop cloth</i> was a plastic (polyethylene or “poly”) sheet or other material that was laid out within the work area to protect the floor, floor covering and other non-moveable objects in the room. Disposable drop cloths were HEPA-vacuumed and/or wiped cleaned, then folded inward during the clean-up phase of the work. Disposable drop cloths were treated as waste following the work event, and were placed into waste bags at the completion of work.</p> |
| Re-usable Drop Cloth | <p>A <i>re-usable drop cloth</i> refers to a canvas or other drop cloth that was not disposed of as waste following R&R work. Re-useable drop cloths were typically folded inward during clean-up.</p> |
| HEPA-equipped vacuum cleaner | <p>A <i>HEPA-equipped vacuum cleaner</i> is a vacuum cleaner that is equipped with a high efficiency particulate air (HEPA) filter. A HEPA filter is capable of filtering 99.97% of particles greater than or equal to 0.3µm in diameter.</p> |
| Area Air Sample | <p>An <i>area air sample</i> is an air sample collected inside or nearby a work area. During this project, area air samples were collected by connecting the sampling media to a portable air sampling pump using Tygon® tubing. The sampling media were positioned to a height approximate to the breathing zone. Six types of area air samples were collected during this Project:</p> <ol style="list-style-type: none"> 1. “Pre-work - Inside” area air samples were collected inside of work areas before work began. These samples were used to document background levels of airborne lead dust. 2. “During - Inside” area air samples were collected inside of work areas while R&R work was performed. These samples were |

**TABLE 3.1
TERMINOLOGY USED IN THIS REPORT**

| | |
|-----------------------|--|
| | <p>used to document levels of airborne lead dust during work activities.</p> <ol style="list-style-type: none"> 3. “Post-work - Inside” area air samples were collected inside of work areas following the completion of R&R work activities, including clean-up. These samples were used to document levels of airborne lead dust following completion of work activities. 4. “Pre-work - Outside” area air samples were collected in interior areas adjacent to or nearby work areas before work began. These samples were used to document background levels of airborne lead dust. 5. “During - Outside” area air samples were collected in interior areas adjacent to or nearby work areas while R&R work was performed. These samples were used to document levels of airborne lead dust outside of the work areas during work activities. 6. “Post-work - Outside” area air samples were collected in interior areas adjacent to or nearby work areas following the completion of R&R work activities, including clean-up. These samples were used to document levels of airborne lead dust outside of the work areas following completion of work activities. <p>An area air sample configuration is depicted in Figure 3.2.</p> |
| PBZ Air Sample | <p>A <i>personal breathing zone (PBZ) air sample</i> is an air sample worn by a worker during sample collection. The sample collection media is placed within the worker’s breathing zone, typically near the worker’s collar. The sampling media is connected to a portable, battery-operated air sampling pump by Tygon® tubing, and the worker wears the pump on his or her belt. A PBZ air sample configuration is depicted in Figure 3.3.</p> <p>The purpose of PBZ air sampling during this Project was to measure the concentration of airborne lead dust in the workers’ breathing zone during R&R work activities. The concentration measured and reported represents the worker’s exposure to airborne lead during the duration of the event evaluated.</p> |
| Time Weighted Average | <p>A <i>time-weighted average (TWA)</i> measurement is a worker’s exposure over a period of time. The OSHA action level (AL) and permissible exposure limit (PEL) for lead are based on an 8-hour exposure period. For this Project, the results from PBZ air samples were used to calculate 8-hour TWA exposures for comparison to the PEL. If multiple events were conducted by a single worker over an 8-hour period, the PBZ air sampling results from each event conducted were used to calculate the worker’s 8-hour TWA exposure using the following formula:</p> $TWA = (C_a T_a + C_b T_b + \dots + C_n T_n) \div 480$ <p>Where: TWA is the equivalent exposure for the working shift;</p> |

| TABLE 3.1 TERMINOLOGY USED IN THIS REPORT | |
|--|---|
| | <p><i>C</i> is the concentration during any period of time <i>T</i> where the concentration remains constant; and, <i>T</i> is the duration in minutes of the exposure at the concentration <i>C</i>.ⁱⁱⁱ</p> <p>For periods where no work was conducted, it was assumed that there was no exposure to lead.</p> |
| Wipe Sampling | <p>A wipe sample is a dust sample collected from surfaces inside the work area. The purpose of wipe sampling was to document lead dust loading on surfaces. Because the EPA and HUD have developed dust loading criteria based on the surface tested, wipe sampling was conducted on the following surfaces:</p> <ol style="list-style-type: none"> 1. Floors within each work area; 2. Window sills within each work area; and, 3. Floor outside of or adjacent to work areas. <p>“Pre-work” wipe sampling was conducted before R&R work began to document background lead loading in surface dust. “Post-work” wipe sampling was conducted following the completion of R&R work, including clean-up, to document lead loading in surface dust following the R&R activity.</p> |

3.2 Renovation and Remodeling (R&R) Activities

To answer the three questions above, the project had to evaluate specific R&R activities performed using different work practice controls.

Table 3.2 includes list of key and miscellaneous activities, developed by NAHB in consultation with remodeling contractors, that represent the most common jobs performed by renovation and remodeling firms that have the potential to disturb surfaces coated with LBP. All of the key activities and most of the miscellaneous activities listed in this table were evaluated during this project. The only miscellaneous activity not evaluated during this project was HVAC work. No heating, ventilation and air conditioning (HVAC) components in the properties included in this project were tested for lead-based paint.

| TABLE 3.2 KEY AND MISCELLANEOUS RENOVATION AND REMODELING ACTIVITIES EVALUATED | |
|---|---|
| Key Activities | |
| 1) | Wall and ceiling removal (demolition) [e.g.; for an addition], including: <ol style="list-style-type: none"> a. Removing a wall to open a room b. Removing a finished ceiling to install a suspended ceiling system |
| 2) | Wall and ceiling modification (e.g.;. for adding a door), including: <ol style="list-style-type: none"> a. Cutting into a wall for new door or window b. Cutting into a ceiling to install new lighting |
| 3) | Window and door replacement which involves the removal or alteration of trims, moldings and jambs or anything else that may have LBP applied to the surface, including: <ol style="list-style-type: none"> a. Replacing a window |

| TABLE 3.2 KEY AND MISCELLANEOUS RENOVATION AND REMODELING ACTIVITIES EVALUATED | |
|---|---|
| Key Activities | |
| | b. Replacing a door c. Modifying or altering a door or window, including trim, moldings, and jambs. |
| 4) | Kitchen and bath work (e.g.; cabinet replacement.) |
| 5) | Floor covering removal, including: a. Removing baseboards coated with LBP. b. Stripping floor finishings. |
| Miscellaneous Activities | |
| 6) | Surface preparation. |
| 7) | Sawing into wood & plaster covered by LBP. |
| 8) | HVAC work – NOT EVALUATED DURING THIS PROJECT |

3.3 Work Practices

To determine the effect that specific work practices had on the lead dust levels generated, each R&R activity was evaluated using one or more of the following work practice controls.

Routine. Routine practices are those work practices typically conducted by R&R contractors, and are not specialized for LBP on building components.

Modified Lead Safe Work Practices (LSWP). Modified LSWP work practices include using one or more of the dust control and clean-up methods discussed in the EPA/HUD curriculum for *Lead Safety for Remodeling, Repair, & Painting*.

Figure 3.0 is a modified checklist from EPA/HUD curriculum for *Lead Safety for Remodeling, Repair, & Painting* that includes specific LSWP that may be used using modified LSWP.

EPA/HUD LSWP. EPA/HUD LSWP include implementing those dust control and clean-up methods discussed in the EPA/HUD curriculum for *Lead Safety for Remodeling, Repair, & Painting*. These methods include:

- 1) Removing or covering all objects in the work area.
- 2) Closing and covering all forced air HVAC ducts in the work area.
- 3) Closing all windows in the work area.
- 4) Closing and sealing all doors in the work area. Doors within the work area that must be used while the job is being performed must be covered with plastic sheeting or other impermeable material in a manner that allows workers to pass through, while confining dust and debris to the work area.
- 5) Covering the floor surface, including installed carpet, with taped-down plastic sheeting in the work area.
- 6) All personnel, tools, and other items, including the exterior of containers of waste, must be free of dust and debris when leaving the work area.

Exhibit A includes the completed field data collections sheets for all of the events evaluated during this project. The work practices used during each event are shown on these sheets.

Table 3.3 is a matrix of the activity/work practice combinations, or scenarios, evaluated during this effort. Each scenario was assigned a unique code (ID) so that data collected during each scenario could be tracked.

| TABLE 3.3 SUMMARY OF EVENTS EVALUATED BY ACTIVITY / WORK PRACTICE SCENARIO AND ASSIGNED ID CODES | | | |
|---|---------------------------------------|--|---|
| Activities | Work Practices | | |
| | Routine R&R Activities | Modified Lead Safe Work Practices | EPA/HUD Lead Safe Work Practices |
| <i>Key Activities</i> | | | |
| Wall and ceiling removal (demolition) | A1 | A2 | A3 |
| Wall and ceiling modification | B1 | B2 | B3 |
| Window and door removal and/or replacement | C1 | C2 | C3 |
| Window and door alteration | C'1 | C'2 | C'3 |
| Kitchen and bath work | D1 | D2 | D3 |
| Floor covering removal. | E1 | E2 | E3 |
| <i>Miscellaneous Activities</i> | | | |
| Surface preparation. | F1 | F2 | F3 |
| Sawing into wood & plaster covered by LBP. | G1 | G2 | G3 |
| HVAC work | H1 | H2 | H3 |

During field evaluations, key data on the work practices and tools used during R&R event were recorded using the checklist shown in Figure 3.0. This checklist provided a standard list of tools and work practices associated with R&R work, and expedited the recording of key work practices and tools used during each event. The purpose of using this standardized checklist to collect work practice and tool information was to provide a method for easily comparing and analyzing the activities, and determine the influence work practices and tools influenced had on air and dust sample results.

3.4 Property Selection

Residential properties used for testing during this project were selected from a listing of eligible properties provided by NAHB. Decision criteria used in unit selection included:

- Available testing data to demonstrate age (pre-1978) and presence of LBP;
- Number of housing units or potential test areas at a single property;
- Contractor and property schedule for availability and access to work areas;
- Separation and isolation from nearby occupants and community residents; and,
- Geographic accessibility of the property.

One other key criterion in the selection of properties included in this study involved the planned future use of the property. In order to capitalize on the number of events that could be evaluated in a single property, and with a view toward limiting possible tort allegations, vacant properties that were scheduled for demolition or extensive renovation were selected for this Project.

All properties considered for this project were assessed for the presence of LBP by an EPA-accredited Lead Inspector. Surveys previously conducted for property owners in accordance with HUD guidelines were used, if they existed. NAHB contracted with accredited firms to assess target properties for the presence of LBP. At a minimum, assessments included the surfaces tested, the room(s) where those surfaces exist, and the XRF or laboratory result for paint or coating on the surface.

FIGURE 3.0 – WORK PRACTICE AND TOOL CHECKLIST

| WORK PRACTICE AND TOOL CHECKLIST | | | |
|--|--|--------------------------------------|--|
| Hygienist | | Work Practices/Tools (cont.) | |
| Activity | | Shop or Industrial Vacuum | |
| Work Practice | | HEPA-equipped Vacuum | |
| | | HEPA-rated Vacuum | |
| DATE | | Shrouded Sander/Grinder/Planer | |
| LOCATION | | Power Washing Equipment | |
| SCENARIO | | Needle Gun connected to HEPA | |
| Work Area Preparation | | Belt Sander | |
| Pre-cleaning w/ wet wiping and vac | | Orbital Sander | |
| Rope | | Other Non-ventilated Power Tools | |
| Barrier Tape | | Heavy Duty Garbage Bags | |
| Saw Horses | | Work Area/Personnel Clean-up | |
| Orange Cones | | Roll Dropcloths Inward | |
| Signs | | Wet Wipe Surfaces or Use | |
| Doorways/Openings Covered | | Reusable Wet Mop w/ One | |
| HVAC Openings Sealed | | Reusable Wet Mop w/ Two | |
| Reusable Drop Cloth | | Use Swifter or Similar Disposable | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | | Disposable Hand Towels | |
| Disposable Mesh | | Pump Sprayer | |
| Staple Gun | | HEPA-equipped Vacuum | |
| Tape | | Shop or Industrial Vacuum | |
| Utility Knife | | Brooms | |
| Tack Pad | | Shovels | |
| Disposable Towels for Wipe Down | | Personal Protective Equipment | |
| Work Practices/Tools | | Full Body Disposable Coveralls | |
| Hammers/Prybars | | N100 Respirator | |
| Misting Bottle | | Gloves | |
| Sandpaper/Sanding Sponge | | Disposable Shoe Covers | |
| Chemical Stripper | | Safety Glasses | |
| Heat Gun | | Disposable Towels | |

A property was considered acceptable for research purposes if multiple surfaces that would be affected by any of the R&R activities included in this study are found to contain LBP present at 1.0 mg/cm² or greater by XRF testing or 0.5% or greater by paint-chip sampling. In order to maximize the number of activities evaluated, this study focused on properties with LBP on multiple surfaces.

Once the property test sites were selected, specific events, dates, times, locations and testing needs were scheduled. In order to organize this process, property-specific work plans were prepared defining:

- Dates of work activities
- Location of the property
- A list of possible activities that could be evaluated at the property based on lead paint inspection results
- A tentative testing schedule for each day

3.5 Work Force

The R&R work was performed by professional renovation and remodeling contractors from each of the communities where the properties were located. All of the R&R workers who participated in this project had previously attended and successfully completed the EPA/HUD curriculum for *Lead Safety for Remodeling, Repair, & Painting*.

3.6 Data Collection Procedures and Sampling Techniques

3.6.1 On-site Project Introduction and Orientation.

At the beginning of each day that testing was conducted, a project orientation session was conducted after all contractor personnel arrived at the property. This introduction and orientation session included:

- A review of the purpose and schedule of the project as it related to the property.
- A walk-through of the property to verify location and layout of the work areas and R&R events, as well as a review of general property specific safety issues.
- Confirmation that on site R&R personnel received (at a minimum):
 - training on the EPA/HUD curriculum for *Lead Safety for Remodeling, Repair, & Painting*;
 - information and training necessary to comply with standard construction safety guidelines and OSHA requirements for their assigned tasks; and,
 - each R&R professional participating in the Project received a medical evaluation by a physician or licensed health care provider and was found to be medically able to wear an N100 filtering-facepiece respirator.
- Confirmation that R&R contractors had sufficient labor, tools and materials to complete the scheduled test activity.
- An explanation of testing methods and analysis planned for the environmental monitoring data collected.
- Questions and answers, as needed.

3.6.2 Worker Protection.

Personal breathing zone (PBZ) air samples were collected on workers to determine if typical R&R activities on surfaces with lead-based paint result in lead exposures that exceed the OSHA permissible exposure limit (PEL) of 50 micrograms of lead per cubic meter of air (50 $\mu\text{g}/\text{m}^3$). The OSHA Lead in Construction standard (29 CFR 1926.62) requires that until exposure monitoring shows that the PEL is not exceeded, employees must be provided appropriate protection when performing the certain activities on surfaces with lead-based paint, assuming that exposures will not exceed ten (10) times the PEL. These regulated activities include:

- manual demolition of structures (e.g., dry wall);
- manual scraping; and
- manual sanding.^{iv}

Because these regulated activities were also activities that were evaluated during this project, workers were required to wear personal protective equipment, including respiratory protection, to comply with the OSHA standard. The personal protective equipment worn by workers performing R&R work during this project included:

- Full-body disposable coveralls with hoods, elastic wrists, and elastic ankles;
- Disposable non-skid shoe covers;
- Safety glasses; and
- N100 filtering face-piece respirators approved by the National Institute for Occupational Safety and Health (NIOSH).

Only those workers determined to be medically qualified to wear a respirator were allowed to conduct R&R work during this project. Prior to beginning work, all R&R contractor personnel were medically qualified to wear a respirator, and were trained and fit-tested on a 3M 8322 N100 filtering face-piece respirator.

Fit testing was performed using the BitrexTM (Denatonium Benzoate) Solution Aerosol Qualitative Fit Test (QLFT) Protocol referenced in Appendix A of the OSHA Respiratory Protection standard, 29 CFR 1910.134.

Workers were also provided wetted wipes to wipe their hands and face following work. Where running water was available, workers were provided soap to wash their hands and face. Workers were advised to wash their hands and face prior to eating, smoking or drinking.

3.6.3 Cross-Contamination Control.

Due to the nature of this project and the limited availability of properties, multiple R&R activities were performed and evaluated simultaneously to maximize the amount of data collected from each property. To obtain useful data, each event had to be considered discreet, with little or no impact from adjacent or nearby activities. Therefore, minimizing the possibility of dust migration and contamination from one work area to another was critical.

Strategies for separating work areas to control dust migration were highly dependant on the activities evaluated, the configuration of the work area, and the overall configuration of the property. However the following methods and procedures were used to control dust migration and cross-contamination:

- When separate work activities were performed simultaneously, they were separated as much as possible (e.g.; separate rooms as far apart as possible, different floors, etc.).

- When physical barriers did not exist between two work areas, plastic sheeting (4- or 6-mil thick) was used to construct a floor-to-ceiling barrier between work areas, regardless of whether activities in the areas were conducted simultaneously.
- When plastic sheeting barriers were constructed and a passageway was necessary, an opening with at least two overlaying flaps was constructed. The flapped opening was constructed to minimize air movement between the two areas.
- Workers were instructed to don clean (unused), disposable, slip-resistant shoe covers upon entry into work areas, and doff the shoe covers prior to leaving a work area. Worn shoe covers remained in the work area until all air and wipe sampling was completed.

3.6.4 Environmental Sampling.

Two types of dust lead measurements were collected during this project: air samples and dust wipe samples. Air samples included area air samples and personal breathing zone (PBZ) samples. Area air samples were collected before, during and after the work activity. The PBZ sample was collected during the work activity. Dust wipe samples were collected before work started and after final clean-up. Dust wipe samples were routinely collected from floors near the work activity and in some cases collected from a window sill and/or window well. Floor dust wipe samples were also collected before and after work from outside of the work area. The location of each sample is reported in the appendix.

Air Sampling Strategy. Area and PBZ air samples were collected during each event conducted. Area air samples were collected to measure airborne lead dust concentrations in the property and work area before R&R activities began, during the work, and after all work and clean-up was completed. PBZ air samples were collected during each scenario to measure worker exposures during work activities, and to calculate the 8-hour time weighted average (TWA) exposure for comparison to the OSHA action level (AL) of 30 $\mu\text{g}/\text{m}^3$ and the PEL of 50 $\mu\text{g}/\text{m}^3$. A summary of the locations of air samples collected during each event evaluated during this project are summarized in Table 3.3.

| Sample Location | Prior to Work (Background) | During Work | Following Completion of Work |
|------------------------|---|---|---|
| Area Air Samples | 1 to 2 depending on size of work area | Same number as background | Same number as background |
| PBZ Samples | None collected | 1 to 2 depending on the number of workers | None collected |
| Outside of work area | 1 to 2 depending on configuration of area | 1 to 2 depending on configuration of area | 1 to 2 depending on configuration of area |

Field blanks were submitted with each batch of air samples sent to the laboratory for analysis. One field blank was submitted for every 10 air samples submitted.

Air Sampling Methodology. All personal breathing zone air samples and ambient area air samples collected during this project were collected and analyzed in accordance with the National Institute for Occupational Safety and Health (NIOSH) Method 7300, *Element by*

ICP. All air samples were collected at a flow rate of 1.0 to 4.0 liters of air per minute (lpm). The volume of air sampled was determined based on the duration of the task, the amount of airborne dust present in the area where samples are collected, and the minimum reportable limit for the method. The minimum reportable limit is based on the analytical limit of detection (LOD). The analytical LOD for this project was 2.0 µg of lead/sample filter.

Area air samples were collected by connecting a 37-millimeter cassette loaded with a 0.8 micrometer (µm) pore size cellulose ester fiber (MCEF) membrane filter to a battery-operated portable air sampling pump by flexible Tygon® tubing. The cassettes were placed at a height approximately to the breathing zone. A photograph depicting an area air sample configuration is shown in Figure 3.1.



Figure 3.1 - Photograph of an Area Air Sample Collected During an R&R Work Event



Figure 3.2 - Photograph of a PBZ Air Sample on an R&R Worker

PBZ samples were collected in the same manner; but the air sampling pump was connected to the worker's belt and the cassette was placed in the worker's breathing zone by connecting the tubing to the collar. A photograph depicting a PBZ air sample configuration is shown in Figure 3.2.

All air sampling pumps were calibrated at the beginning and end of each sampling period using a BIOS DryCal, a primary calibration standard.

Air Sampling Data Quality Objectives. Air samples collected during this project achieved a reporting limit that was sufficiently below the OSHA action level of 30 micrograms of lead per cubic meter of air (µg/m³), which is equivalent to 0.03 milligrams of lead per cubic meter of air (mg/m³). To ensure a sufficient reporting limit, the sampling and analytical error (SAE) for the method was determined. The SAE for 95% confidence in the air sampling result was determined as follows:

$$SAE_{95\%} = (SQRT(C_{vA}^2 + C_{vS}^2)) * 1.645$$

Where: C_{vA} = coefficient of variability for the analytical method
C_{vS} = coefficient of variability for the sampling method

The sampling and analytical method used during this project was NIOSH method 7300, *Element by ICP*. The C_{VA} for air samples analyzed for lead using this technique is 0.024. The assumed sampling error is 5%, or 0.05. Based on these errors, the SAE for NIOSH Method 7300 is 0.091.^v

The OSHA Technical Manual (OTM) states that determining compliance with a permissible exposure limit (PEL) is based on a 95% confidence that the PEL is exceeded. The OTM states:

1. a violation of the PEL exists if the upper confidence limit (UCL) exceeds unity, or 1;
2. a violation of the PEL does not exist if the lower confidence limit (LCL) is less than unity, or 1; and,
3. a violation of the PEL may exist if the LCL is greater than 1 and the UCL is less than 1.

According to the OTM; UCL and LCL values are calculated as follows:

$$UCL = \frac{\text{Measured result}}{\text{Exposure limit}} - SAE$$

$$LCL = \frac{\text{Measured result}}{\text{Exposure limit}} + SAE^{vi}$$

For the purposes of this Project, it was important that the minimum reportable limit for air samples is less than the LCL. When no measurable concentration of lead was detected on the sampling media, the laboratory reports the result as “<” the minimum reportable limit. In order to achieve a 95% confidence that a result reported as a “<” value is below the 30 $\mu\text{g}/\text{m}^3$ OSHA action level (AL) for lead, the LCL calculation had to be manipulated to determine the minimum reportable limit as follows:

$$\text{Measured result (minimum reportable limit)} = AL (1 - SAE)$$

The minimum reportable limit required to achieve 95% confidence that the action level was not exceeded when no lead was detected on the sample using NIOSH Method 7300 is 27.27 $\mu\text{g}/\text{m}^3$. For this Project, air sampling was conducted to achieve a minimum reportable concentration of 25 $\mu\text{g}/\text{m}^3$ (0.025 mg/m^3). In other words, there is at least 95% confidence that the OSHA action level was not been exceeded if the laboratory reports results as <25 $\mu\text{g}/\text{m}^3$ (<0.025 mg/m^3).

Based on the limit of quantification for the analytical method (2 μg per sample), and to achieve a 95% confidence interval relative to the OSHA AL, the minimum volume collected on each air sample was 80 liters of air.

Air samples results were reported in micrograms of lead per cubic meter of air ($\mu\text{g}/\text{m}^3$). Laboratory results reported in milligrams of lead per cubic meter of air (mg/m^3) were converted to $\mu\text{g}/\text{m}^3$ prior to data analysis for consistency.

All air samples were analyzed by an American Industrial Hygiene Association (AIHA) accredited laboratory.

Surface Dust Sampling Strategy. Surface dust samples were collected to measure surface lead dust loading in the property and work area before R&R activities began and after all work and clean-up was completed. Surface dust samples were collected from the floor and a window sill (or other relevant surface) in each work area. A summary of the locations of surface dust samples collected during each event evaluated during this project are summarized in Table 3.4.

| TABLE 3.5 NUMBER OF SURFACE DUST SAMPLES COLLECTED DURING EACH EVENT | | |
|---|--|-------------------------------------|
| Sample Location | Prior to Work (Background) | Following Completion of Work |
| Floors inside work area | 2 | Same number as background |
| Sills or other surfaces in work area | 1 or 2, depending on area | Same number as background |
| Outside of work area | 1 or 2 on floor, depending on area; 1 or 2 on sill or other surface, depending on area | Same number as background |

Field blanks were submitted with each batch of wipe samples sent to the laboratory for analysis. One field blank was submitted for every 10 air samples submitted.

Surface Dust Sampling Methodology. Settled dust was collected using wipe sampling techniques referenced in Chapter 15 of the HUD publication *Guidelines for the Evaluation and Control of Lead-Based Paint in Public Housing*. Sampling was conducted using “ghost wipes.” Samples were analyzed in accordance with NIOSH Method 7082, *Lead by Flame AAS* (Atomic Absorption Spectrophotometer). This technique is equivalent to EPA Method 3050/7420. The limit of quantification for this method was 10 µg of lead per wipe sample.

Surface Dust Sampling Data Quality Objectives. Surface dust sampling was conducted by lead professionals who maintained appropriate accreditation and licensure required by local authorities.

For consistency of results, the area sampled were measured and reported in square foot (ft²) units. Each wipe sample represented approximately 1.0 ft² of area sampled, if feasible.

Wipe samples results were reported in micrograms of lead per square foot (µg/ft²). Laboratory results reported in milligrams of lead per square foot (mg/ft²) were converted to µg/ft² prior to data analysis for consistency.

All wipe samples were analyzed by a laboratory that participates in the AIHA Environmental Lead Laboratory Accreditation Program (ELLAP), which is recognized by the EPA.

Field Data Documentation. All field data collected, including key property information, work data, and air and wipe sampling data were recorded for each event conducted during this Project.

To ensure consistent comparison of work practices used, work practices used during each event were documented. Photographs of work areas prior to the beginning of work, during work activities, and at the completion (including any clean-up) were taken for each event.

The field data collection form used during this project is included in Exhibit A.

3.7 Statistical Analysis Techniques

Field data collected was entered onto an Microsoft® Office Excel 2003 spreadsheet. The Excel data was read into SAS Version 9.1, which was used for all computations (Copyright © 2002-2003 by SAS Institute Inc., Cary, NC, USA.)

A paired t-test on the log-transformed dust lead was used to test the null that the geometric mean (GM) dust lead loadings was the same pre and post-work. Fisher's exact test was used to test the null that the percentages of dust lead or air lead samples above an applicable cut-point were the same for different activities.

Significance was defined as having an observed significance level (p-value) below 0.05. If the p-value was less than 0.10 and at least 0.05 then the result was marginally significant.

4.0 RESULTS

In conducting this project, 342 air samples and 407 surface dust (wipe) samples (not including field blanks) were collected during 60 typical R&R activities conducted in five separate properties. The R&R work was conducted on interior surfaces and building components with paint containing between 0.9 mg/cm² and 25.3 mg/cm², as measured by X-ray fluorescence (XRF) instrumentation, which is considered lead-based paint (LBP).

Based on observations made when evaluating the R&R work performed during this Project, some of the activities included in NAHB's original list of R&R activities (as shown in Table 3.2) were further defined so the data analysis provided information that NAHB could use in issuing guidance to its members. Some scenarios were not evaluated due to limitations in surfaces and building components with lead-based paint to test.

Table 4.1 is a matrix of the activity/work practice combinations, or scenarios, evaluated during this project. This table also shows the number of events that were evaluated in each scenario. Table 4.2 is a summary of each of the events evaluated during this Project.

| TABLE 4.1 NUMBER OF EVENTS EVALUATED BY SCENARIO | | | |
|--|---|---|--|
| Activities [ID Code] | Work Practices [ID Code] | | |
| | Routine R&R Activities [1] | Modified Lead Safe Work Practices (Mod LSWP) [2] | EPA/HUD Lead Safe Work Practices (LSWP) [3] |
| <i>Key Activities</i> | | | |
| Wall and ceiling removal (demolition) [A] | 1 | 3 | 0 |
| Wall and ceiling modification [B] | 6 | 7 | 1 |
| Window and door replacement which involves the removal or alteration of trims, moldings and jambs or anything else that may have LBP applied to the surface, including | | | |
| Window and door removal and/or replacement (no sanding involved) [C] | 1 | 3 | 1 |
| Window and door alteration (no sanding involved) [C'] | 1 | 0 | 1 |
| Sanding on windows and doors [C-sand] | 6 | 3 | 0 |
| Kitchen and bath work (only cabinet removal was performed) [D] | 2 | 2 | 1 |
| Floor covering removal (only baseboard and stair removal were performed) [E] | 3 | 4 | 1 |
| <i>Miscellaneous Activities</i> | | | |
| Surface preparation (sanding) [F] | 4 | 5 | 0 |
| Sawing into wood & plaster covered by LBP [G] | 2 | 2 | 0 |
| HVAC work [H] | 0 | 0 | 0 |

**TABLE 4.2
SUMMARY OF R&R EVENTS EVALUATED**

| Event | Location | Date | Scenario | XRF Result | Scenario ID | | No. of Workers |
|-------|----------|--------|--|------------|-------------|---------------|----------------|
| | | | | | Activity | Work Practice | |
| 1 | ROSL | 012506 | WINDOW REPLACEMENT - JAMBS REMOVED - ROUTINE | 20.1 | C | 1 | 1 |
| 2 | ROSL | 012506 | WINDOW REPLACEMENT - JAMBS NOT REMOVED - LSWP | 22.7 | C | 3 | 2 |
| 3 | ROSL | 012606 | WINDOW REPLACEMENT - JAMBS NOT REMOVED - MOD LSWP | 13.6 | C | 2 | 1 |
| 4 | ROSL | 012606 | INSTALL RECESSED LIGHTING IN CEILING - MOD LSWP | 2.9 | B | 2 | 1 |
| 5 | ROSL | 012606 | INSTALL DOOR IN CLOSET WALL - MOD LSWP | 2.9 | G | 2 | 1 |
| 6 | WLFD | 041906 | REMOVE PLASTER WALL & CEILING - ROUTINE - BATH 2 | 8.7 | A | 1 | 1 |
| 7 | WLFD | 041806 | REMOVE PLASTER WALL & CEILING - MOD LSWP - BSMNT | 1.5 | A | 2 | 1 |
| 8 | WLFD | 041806 | CEILING MODIFICATION CUTTING WOOD - MOD LSWP - R FOYER 1 | 9.9 | B | 2 | 1 |
| 9 | WLFD | 041806 | REMOVING WINDOW SASH - ROUTINE - LIV RM 2 | 9.9 | C' | 1 | 1 |
| 10 | WLFD | 041806 | SANDING DOORS - ROUTINE - BED 4 | 9.9 | C-SAND | 1 | 1 |
| 11 | WLFD | 041806 | SANDING WINDOW STOPS - ROUTINE - BED 4 | 9.9 | C-SAND | 1 | 1 |
| 12 | WLFD | 041806 | SANDING DOORS - MOD LSWP - BED 1 | 9.9 | C-SAND | 2 | 1 |
| 13 | WLFD | 041806 | SANDING WINDOW STOPS - MOD LSWP - BED 1 | 9.9 | C-SAND | 2 | 1 |
| 14 | WLFD | 041806 | CABINET REMOVAL - ROUTINE - KIT 2 | 6.9 | D | 1 | 1 |
| 15 | WLFD | 041806 | BASEBOARD WORK - ROUTINE - BED 3 | 9.9 | E | 1 | 1 |
| 16 | WLFD | 041806 | REMOVING BASEBOARDS - MOD LSWP - BED 2 | 9.9 | E | 2 | 1 |
| 17 | WLFD | 041906 | REMOVE & SAND MOLDING - ROUTINE - LIV RM 2 | 1.0 | F-SAND | 1 | 1 |
| 18 | WLFD | 041906 | SANDING STAIRS - ROUTINE - STAIRWELL | 9.9 | F-SAND | 1 | 1 |
| 19 | WLFD | 041806 | SANDING STAIRS - MOD LSWP - STAIRWELL | 9.9 | F-SAND | 2 | 1 |
| 20 | CHSR | 042106 | WALL MODIFICATION - PLASTER - ROUTINE - BATH 6 | 1.0 | B | 1 | 1 |
| 21 | CHSR | 042106 | WALL MODIFICATION - PLASTER - MOD LSWP - 1ST FL BATH | 1.4 | B | 2 | 1 |
| 22 | CHSR | 042106 | WALL MODIFICATION - PLASTER - MOD LSWP - BATH 5 | 1.0 | B | 2 | 1 |
| 23 | FGTN | 042006 | WINDOW REPAIR - ROUTINE - BED 2 | 9.9 | C-SAND | 1 | 1 |
| 24 | FGTN | 042007 | WINDOW REPAIR - ROUTINE - LIVING ROOM | 9.9 | C-SAND | 1 | 1 |
| 25 | FGTN | 042006 | WINDOW REPAIR - MOD LSWP - BED 3 | 9.9 | C-SAND | 2 | 1 |
| 26 | FGTN | 042006 | CABINET REMOVAL - ROUTINE - 1ST FL BATH | 2.1 | D | 1 | 1 |
| 27 | FGTN | 042007 | CABINET REMOVAL - MOD LSWP - DINING ROOM | 9.9 | D | 2 | 1 |
| 28 | FGTN | 042006 | BASEBOARDS - ROUTINE - FAMILY ROOM | 0.9 | E | 1 | 1 |
| 29 | FGTN | 042006 | DOOR WORK - MOD LSWP - BED 1 | 9.9 | F | 2 | 1 |
| 30 | FGTN | 042006 | CUT SHELVING - ROUTINE - REAR FOYER | 1.6 | G | 1 | 1 |
| 31 | FGTN | 042006 | BASEBOARDS - MOD LSWP - REAR FOYER | 9.9 | E | 2 | 1 |
| 32 | FGTN | 042006 | CUT SHELVING - ROUTINE - BED 2 | 1.4 | G | 1 | 1 |
| 33 | FGTN | 042006 | CUT SHELVING - MOD LSWP - BED 3 | 9.9 | G | 2 | 1 |
| 34 | MIL | 050206 | CEILING MODIFICATION - 3RD FL BR1 | 2.8 | B | 1 | 1 |
| 35 | MIL | 050206 | WALL MODIFICATION (OUTLET INSTALLATION)- 2ND FL BR2 | 13.4 | B | 1 | 1 |
| 36 | MIL | 050206 | WINDOW INSTALLATION - LIVING ROOM | 22.5 | C | 2 | 1 |
| 37 | MIL | 050206 | OUTLET INSTALLATION - 2ND FL BR1 | 13.4 | B | 3 | 1 |
| 38 | MIL | 050206 | WINDOW MODIFICATION (SASHES AND STOPS) - LIVING ROOM | 18.9 | C' | 3 | 1 |
| 39 | MIL | 050206 | WINDOW WORK - SANDING - 2ND FL BR1 | 13.8 | C-SAND | 1 | 1 |
| 40 | MIL | 050306 | BANISTER REMOVAL AND INSTALLATION - 3RD FL | 4.4 | A | 2 | 2 |
| 41 | MIL | 050206 | BASEBOARD REMOVAL - 3RD FL BR1 | 9.9 | E | 1 | 1 |
| 42 | MIL | 050206 | FLOOR SANDING - PANTRY | 2.3 | F-SAND | 2 | 1 |
| 43 | MIL | 050306 | BASEBOARD REMOVAL - PANTRY | 19.2 | E | 3 | 1 |
| 44 | MIL | 050306 | CEILING MODIFICATION (RECESSED LIGHTS) - 3RD FL BR1 | 2.8 | B | 1 | 1 |
| 45 | MIL | 050306 | CEILING SANDING - LIVING ROOM | 16.5 | F-SAND | 2 | 1 |
| 46 | MIL | 050306 | WALL MODIFICATION (DOOR INSTALLATION) - 2ND FL BR2 | 13.4 | B | 1 | 1 |
| 47 | MIL | 050306 | WALL MODIFICATION (WINDOW INSTALLATION) - 2ND FL BR1 | 13.4 | B | 1 | 1 |
| 48 | MIL | 050306 | CABINET REMOVAL - BATHROOM | 9.6 | D | 3 | 1 |
| 49 | MIL | 050306 | SURFACE PREPARATION (WINDOW FRAME) - 3RD FL BR2 | 6.0 | F-SAND | 2 | 1 |
| 50 | MIL | 050406 | WALL DEMOLITION - 2ND FL BR1 | 13.4 | A | 2 | 2 |
| 51 | MIL | 050406 | WALL MODIFICATION (OUTLET INSTALLATION) - 3RD FL BR1 | 4.5 | B | 2 | 1 |
| 52 | MIL | 050406 | WINDOW REMOVAL - DINING ROOM | 11.0 | C | 2 | 1 |
| 53 | MIL | 050406 | SURFACE PREP (SAND STAIR TREADS) - STAIRWELL | 13.0 | F-SAND | 1 | 1 |
| 54 | MIL | 050506 | REMOVE SHELF SUPPORTS - CLOSET | 25.3 | B | 2 | 1 |
| 55 | MIL | 050506 | CEILING MODIFICATION (RECESSED LIGHTING) - 3RD FL BR1 | 2.9 | B | 2 | 2 |
| 56 | MIL | 050506 | WINDOW MODIFICATION - LIVING ROOM | 22.5 | C-SAND | 1 | 2 |
| 57 | MIL | 050506 | CABINET REMOVAL - KITCHEN | 9.4 | D | 2 | 1 |
| 58 | MIL | 050506 | BASEBOARD REMOVAL - BATH | 7.4 | E | 2 | 1 |
| 59 | MIL | 050506 | STAIR REPLACEMENT | 13.0 | E | 2 | 1 |
| 60 | MIL | 050506 | CEILING SANDING - LIVING ROOM | 16.5 | F-SAND | 1 | 2 |

Note: The highest possible readings in the Connecticut properties were 9.9 mg/cm². This was the maximum reportable limit for the XRF instrument used. Actual lead concentrations may be higher.

Tables summarizing air and wipe sampling data (Tables 4.6 through 4.21) and all graphical representations of sampling results are included at the end of this Section.

Exhibit B includes the field data summaries for each of the events evaluated during this project.

4.1 Quality Control Review of Field Data Collection Efforts

NCHH conducted an on-site evaluation of quality control procedures used during the collection of air and wipes samples, as well as other work activity data collection methods. This evaluation was conducted at the Milwaukee, Wisconsin property. NCHH's trip report is summarized as follows:

Property Description. All work was being done on the upper two stories of the structure. No electrical power was on in the upper two stories, necessitating the use of power cords running down the stairs to the lower level. Surfaces containing lead-based paint had been marked with red spray paint. A review of the XRF data on site showed that appropriate calibration checks and other documentation were satisfactory, although NCHH did not directly observe collection of XRF data.

Worker Training. It was reported to NCHH that all workers had been trained in a one-day course in lead-safe work practices. Different workers were used on different days. Workers were told they would be doing three levels of work practices, which were described as follows: "traditional, lead-safe, and modified lead-safe." No definitions of these terms were provided to workers. The work was to be done by experienced housing renovators, remodelers and painters and the construction/demolition or repair techniques to be used were to be based on their expert judgment to represent real world conditions.

Worker Protection. Workers were qualitatively fit tested with N-100 3M dust masks using a small shroud fitted over the worker's head. A "bitter" challenge aerosol was introduced into the shroud near the worker's breathing zone. Workers provided documentation from a medical health care provider that they were fit to wear a respirator. The respirator qualitative fit testing technique was observed to be adequate. All workers also wore disposable Tyvek suits and other personal protective equipment which was observed to be adequate.

Air and Wipe Sampling. Personal breathing zone and area air samples were collected using air sampling pumps operating at a nominal flow rate of approximately 2.5 liters per minute using 0.8 ug mixed cellulose ester filters housed in closed-face 35 mm cassettes. The cassettes were labeled with an expiration date of April 2009. Calibration was done before and after each sample was collected with the filter in line. All air samples were collected for at least one hour, reportedly to achieve sufficient sampling volume to gain a low enough detection limit, even if the work being studied did not last for the entire hour. All pump calibrations were performed with the filter in line and were observed to be done correctly.

Wipe samples were collected by two individuals licensed to do so in Wisconsin. Their technique was observed to be adequate. No spikes were inserted into the sampling stream.

In those cases where the work was completed in less than an hour, air sampling pumps, tubing, and filter cassettes used to collect personal breathing zone samples were left in the work area.

Other Observations. Each room at the property was separated by two-flap overlapping plastic sheets draped over doorway openings in order to minimize airborne dust migration from one work site to another. Air vents in each room were also covered with plastic and taped in a dust tight manner. The building's air ventilation system was kept off during the work. Although workers were told to don or remove disposable shoe coverings when moving through the airlocks, compliance with this directive by workers was inconsistent.

Air and dust wipe samples were collected inside the room and in the adjacent room outside the work site. Post-cleanup wipe samples were collected one hour after the work was completed to permit airborne dust to settle. For the work observed, compliance with the one hour requirement was adequate.

Measurements of the size of the painted areas to be treated were reportedly collected, but this was not observed directly. For some work practices, not all layers of paint were removed. The extent of paint removal was based instead on the expert judgment of the individual remodeling contractor. In some cases, the paint surface preparation involved removal of or abrading the top paint layer, which could mean that the lead paint layer(s), which are likely to be underneath non-lead paint layers, was not disturbed. For some work practices, there was dry vacuuming or dry sweeping only. Both HEPA vacuum and non-HEPA shop vacuums were used. For others, a "wet" cleaning step was used in addition to the vacuuming. The wet cleaning consisted of using a wet "Swiffer."™ Mops and mop buckets were not observed to be used, although in some cases paper towels moistened with water but no cleaning agent were used in addition to the Swiffer.™ The Swiffer™ failed to moisten significant portions of floors, some of which were uneven and deteriorated. Some of the workers stated they would not be using the Swiffer in their typical work. The chemical content of the moistening agent used in the Swiffer™ was not identified on the package label, although a white residue was observed on the hard wood floors after drying.

Waste generated by the work was placed into large plastic bags or covered with plastic sheeting. Given the layout of the house and the restrictions reportedly stated by the owner, cross-area dust contamination control measures were problematic, especially during waste removal.

A review of data collection forms and chain of custody forms indicated they were adequate. Samples were observed to be adequately labeled and field notes taken by Atrium personnel and those collecting wipe samples were collected on standardized forms.

4.2 Summary of Tools Used and Time Required to Complete Work

As part of this project, data on the work area preparation activities, work practices and tools used, work area clean-up practices, and personal protection equipment used were recorded. In addition, the number of person-hours required to complete each event were collected. A

summary of the work practices and tools used, shown as a percentage of the events conducted using each work practice is shown in Table 4.3.

| Work Area Preparation | ROUTINE (n = 26) | Mod LSWP (n = 29) | EPA/HUD LSWP (n = 5) | Work Area/Personnel Clean-up | ROUTINE (n = 26) | Mod LSWP (n = 29) | EPA/HUD LSWP (n = 5) |
|---|-----------------------------|------------------------------|-------------------------------------|--------------------------------------|-----------------------------|------------------------------|-------------------------------------|
| Pre-cleaning w/ wet wiping and vac | 13.0% | 12.5% | 80.0% | Roll Dropcloths Inward | 76.0% | 89.3% | 80.0% |
| Saw Horses | 8.7% | 18.5% | 0.0% | Reusable Wet Mop w/ Two Buckets | 0.0% | 0.0% | 20.0% |
| Signs | 0.0% | 0.0% | 0.0% | Disposable Hand Towels | 36.0% | 61.5% | 80.0% |
| Doorways/Openings Covered | 96.0% | 92.9% | 100.0% | Pump Sprayer | 0.0% | 0.0% | 60.0% |
| HVAC Openings Sealed | 0.0% | 8.3% | 20.0% | HEPA-equipped Vacuum | 4.3% | 89.3% | 60.0% |
| Reusable Drop Cloth | 48.0% | 12.0% | 0.0% | Shop or Industrial Vacuum | 80.0% | 11.1% | 0.0% |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | 48.0% | 85.7% | 80.0% | Brooms | 30.4% | 16.0% | 0.0% |
| Staple Gun | 30.4% | 40.7% | 100.0% | | | | |
| Tape | 88.0% | 89.3% | 100.0% | | | | |
| Utility Knife | 72.0% | 75.0% | 80.0% | | | | |
| Tack Pad | 0.0% | 0.0% | 0.0% | | | | |
| Disposable Towels for Wipe Down | 0.0% | 4.2% | 60.0% | | | | |
| Work Practices/Tools | ROUTINE (n = 26) | Mod LSWP (n = 29) | EPA/HUD LSWP (n = 5) | Personal Protective Equipment | ROUTINE (n = 26) | Mod LSWP (n = 29) | EPA/HUD LSWP (n = 5) |
| Hammers/Prybars | 68.0% | 74.1% | 60.0% | Full Body Disposable Coveralls | 100.0% | 100.0% | 100.0% |
| Misting Bottle | 0.0% | 12.5% | 100.0% | N100 Respirator | 100.0% | 100.0% | 100.0% |
| Sandpaper/Sanding Sponge | 17.4% | 20.8% | 0.0% | Gloves | 43.5% | 52.0% | 80.0% |
| Chemical Stripper | 0.0% | 0.0% | 0.0% | Disposable Shoe Covers | 100.0% | 100.0% | 80.0% |
| Heat Gun | 0.0% | 0.0% | 0.0% | Safety Glasses | 17.4% | 40.0% | 80.0% |
| Shop or Industrial Vacuum | 48.0% | 0.0% | 0.0% | Disposable Towels | 88.0% | 80.0% | 80.0% |
| HEPA-equipped Vacuum | 0.0% | 67.9% | 60.0% | | | | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | 0.0% | 20.0% | 0.0% | | | | |
| Belt Sander | 8.7% | 25.9% | 0.0% | | | | |
| Orbital Sander | 16.0% | 12.5% | 0.0% | | | | |
| Other Non-ventilated Power Tools | 48.0% | 53.8% | 40.0% | | | | |
| Heavy Duty Garbage Bags | 47.8% | 70.4% | 60.0% | | | | |

The time to complete each event, by activity and by work practice, is summarized in Tables 4.4 and 4.5.

| Activities | Range | | Average Time to Complete (min) |
|--|------------------------------|-----------------------------|---------------------------------------|
| | Shortest Period (min) | Longest Period (min) | |
| <i>Key Activities</i> | | | |
| A. Wall and ceiling removal | 48 | 518 | 230 |
| B. Wall and ceiling modification | 18 | 165 | 65 |
| C. Window and door replacement, removal or alteration. | 18 | 420 | 111 |
| D. Kitchen and bath work | 48 | 150 | 93 |
| E. Floor covering removal. | 18 | 240 | 80 |
| <i>Miscellaneous Activities</i> | | | |
| F. Surface preparation. | 41 | 108 | 62 |
| G. Sawing into wood & plaster covered by LBP. | 41 | 75 | 52 |

| Work Practices | Range | | Average Time to Complete (min) |
|-----------------------------------|-----------------------|----------------------|--------------------------------|
| | Shortest Period (min) | Longest Period (min) | |
| Routine R&R Activities | 18 | 282 | 71 |
| Modified Lead Safe Work Practices | 42 | 518 | 109 |
| EPA/HUD Lead Safe Work Practices | 36 | 210 | 142 |

4.3 Overall Summary of Sampling Results

In analyzing the air and wipe sampling results, the arithmetic mean (mean) and the geometric mean (GM) were used to assess the data sets. The GM of the data set is typically used to describe environmental and occupational exposure data that is lognormally distributed, consisting of mostly lower results (many less than the analytical limit of quantification) and few higher results. The arithmetic mean of the data set is commonly used by industrial hygienists to make decisions regarding exposures, particularly when assessing exposures to substances with chronic toxicity, such as lead.^{vii}

Many of air samples collected had results that were below the limit of quantification (LOQ). Because these results provide critical information regarding the exposure profile, they were not discarded in the analysis of the data. Because of the wide distribution of the air sampling data sets, samples reported as less than the LOQ were considered to have lead concentrations of 50% of the LOQ. This approach is referenced in the American Industrial Hygiene Association (AIHA) publication *A Strategy for Assessing and Managing Occupational Exposures*.^{viii}

Personal Breathing Zone Samples: The Occupational Safety and Health Administration (OSHA) has established an Action Level of 30 µg/m³ during construction activities and has set a permissible exposure limit (PEL) of 50 µg/m³. These exposure limits are based on an 8-hour time weighted average exposure (TWA).

During this project, 65 PBZ air samples were collected during 60 R&R events evaluated. Activity-based exposure measurements – worker exposures measured for the duration of the R&R event - were widely distributed, ranging from less than the LOQ to 1,700 µg/m³.

- Results of 31 (48%) of the PBZ samples had no measurable lead on the sample (less than the LOQ).
- The mean of all PBZ air sample results for all of the R&R activities evaluated was 121 µg/m³.
- The GM of all PBZ air sample results was 26.4 µg/m³.

Area Air Samples: A total of 278 area air samples were collected during this project. Of the 209 samples collected inside work areas, 163 results (78%) were less than the LOQ.

Pre-work area air samples were collected in each room before work began to establish background airborne lead levels. Post-work samples were collected in each work area for approximately one hour following completion of the work activities. Because multiple work activities occurred consecutively in the same room, the results from the post-work area air samples from a morning activity were used as the pre-work, background levels for the afternoon activity in the same room.

- Results of 64 of 65 (99%) of the pre-work area air samples were less than the LOQ. The levels measured ranged from less than the limit of quantification to $190 \mu\text{g}/\text{m}^3$. The only pre-work area sample with a result above the LOQ was a post-work sample from a morning R&R event that was used as the pre-work sample for an afternoon R&R event.
- Results of 62 of 67 (93%) of the post-work area air samples less than the LOQ. The levels measured ranged from less than the LOQ to $190 \mu\text{g}/\text{m}^3$.

Results of the area air samples collected during work were similar to the PBZ results.

- Results of 37 of 74 (50%) of work area air samples were below the limit of quantification. The levels measured ranged from less than the LOQ to $1,780 \mu\text{g}/\text{m}^3$.
- The mean of all area sample results collected during work for all of the R&R activities evaluated was $85.5 \mu\text{g}/\text{m}^3$.
- The GM of area sample results collected during work was $17.6 \mu\text{g}/\text{m}^3$.

Sixty-nine area air samples were collected outside of each work area prior to and during each R&R event. Generally, the area samples collected during work activities were similar to those collected before work began.

- Results from 36 of 38 (95%) of the pre-work air samples collected outside of the work area were less than the LOQ. The levels measured ranged from less than the LOQ to $53 \mu\text{g}/\text{m}^3$.
- Result from 26 of 31 (90%) of air samples collected outside of the work area during work were less than the LOQ. The levels measured ranged from less than the LOQ to $83 \mu\text{g}/\text{m}^3$.

Surface Dust Sampling. Pairs of settled dust lead samples were collected from each work area and outside the work area. Pre-work samples were collected prior to R&R activities. Post-work samples were collected following completion of the work and clean-up of the work area by the R&R contractor. Samples were collected after at least one hour had passed to allow for airborne dust to settle. This strategy is consistent with the HUD *Guidelines for the Evaluation and Control of Lead-Based Paint in Public Housing*. Post-work samples were collected in approximately the same area where the pre-work samples were collected.

During this project, 241 pairs of surface dust samples were collected and analyzed. The results were highly variable.

- Pre-work dust loading measurements ranged from less than the LOQ ($< 10 \mu\text{g}/\text{ft}^2$) to $108,000 \mu\text{g}/\text{ft}^2$. Only one sample result was less than the LOQ. The mean pre-work measurement was $3,423 \mu\text{g}/\text{ft}^2$. The GM of all pre-work measurements was $499 \mu\text{g}/\text{ft}^2$.

- Post-work dust loading measurements ranged from less than the LOQ ($< 15 \mu\text{g}/\text{ft}^2$) to $39,200 \mu\text{g}/\text{ft}^2$ *. Only two sample results were less than the LOQ. The mean post-work measurement was $1,185 \mu\text{g}/\text{ft}^2$. The GM of all post-work measurements was $320 \mu\text{g}/\text{ft}^2$.

A total of 160 pairs of surface dust samples were analyzed from floors and window sills within work areas. The larger data set (241 pairs) represents all surfaces that were sampled. Therefore, fewer pairs of wipe samples representing floors and window sills were included in the analysis of lead dust loading on these surfaces.

- For 106 pairs of surface dust samples collected from floors:
 - Pre-work sample results ranged from less than the LOQ to $6,080 \mu\text{g}/\text{ft}^2$. One sample was less than the LOQ. The GM of the pre-work dust loading measurements was $239 \mu\text{g}/\text{ft}^2$. For comparison, pre-intervention levels measured on floors in 424 occupied residential dwellings as part of a HUD-funded study ranged from $0.1 \mu\text{g}/\text{ft}^2$ to $9,407 \mu\text{g}/\text{ft}^2$.^{ix} Therefore, the pre-work dust loadings in the subject study were within the range of occupied housing.
 - Post-work sample results ranged from $18.2 \mu\text{g}/\text{ft}^2$ to $11,400 \mu\text{g}/\text{ft}^2$. The GM of the post-work dust loading measurements was $225 \mu\text{g}/\text{ft}^2$.
- For 54 pairs of surface dust samples collected from window sills:
 - Pre-work sample results ranged from $136 \mu\text{g}/\text{ft}^2$ to $108,000 \mu\text{g}/\text{ft}^2$. The GM of the pre-work dust loading measurements was $1,850 \mu\text{g}/\text{ft}^2$. These numbers are within the range of pre-intervention levels measured on window sills in 424 occupied residential dwellings as part of a HUD-funded study, which ranged from $3 \mu\text{g}/\text{ft}^2$ to $129,188 \mu\text{g}/\text{ft}^2$.^x
 - Post-work sample results ranged from $19.9 \mu\text{g}/\text{ft}^2$ to $10,800 \mu\text{g}/\text{ft}^2$. The GM of the post-work dust loading measurements was $553 \mu\text{g}/\text{ft}^2$.

The difference between the GM of the post-work dust sampling results ($320 \mu\text{g}/\text{ft}^2$) and the GM of the pre-work dust sampling results ($499 \mu\text{g}/\text{ft}^2$) for all surfaces and all activities represented a 36% reduction in lead dust loading.

The difference between the GM of the post-work dust sampling results from floors ($225 \mu\text{g}/\text{ft}^2$) and the GM of the pre-work dust sampling results from floors ($239 \mu\text{g}/\text{ft}^2$) for all activities represented a 6% reduction in lead dust loading.

The difference between the GM of the post-work dust sampling results from window sills ($553 \mu\text{g}/\text{ft}^2$) and the GM of the pre-work dust sampling results from window sills ($1,850 \mu\text{g}/\text{ft}^2$) for all activities represented a 71% reduction in lead dust loading.

4.4 Results by Activity

The air and wipe sample data collected was analyzed by R&R activity to assess the airborne lead levels and surface dust lead loading resulting from each activity. For the purpose of providing guidance to R&R contractors, all activities where sanding was conducted were segregated and analyzed separately from the other activities.

* This result represents a composite sample from a sill and trough.

The PBZ air sampling results are summarized by activity in Table 4.6. Figure 4.1 shows the how GM of the PBZ air sampling results for each activity compared to the GM of the PBZ air sampling results for all activities.

The area air sampling results collected inside the work area during work are summarized by activity in Table 4.7. Figure 4.2 shows the GM of the area air sampling results for each activity compared to the GM of the area air sampling results for all activities.

The surface dust sampling results collected inside the work area are summarized by activity in Table 4.8. Figure 4.3 shows the difference between post-work surface dust samples and the pre-work surfaces dust samples by activity based on the GM of all surfaces sampled.

Surface dust sampling by surface tested is summarized for each activity in Table 4.9.

4.5 Results for Specific Tasks

For the purpose of providing guidance to R&R contractors, the air and dust sampling results for specific tasks likely to generate dust - sanding (surface preparation) and sawing - were analyzed. Each of these tasks was analyzed by the substrate (wood or plaster) on which the work was performed.

The PBZ air sampling results are summarized by sanding and sawing tasks in Table 4.10. Figure 4.4 shows the how GM of the PBZ air sampling results for each task compared to the GM of the PBZ air sampling results for all activities.

The area air sampling results collected inside the work area during work are summarized by sanding and sawing tasks in Table 4.11. Figure 4.5 shows the GM of the area air sampling results for each task compared to the GM of the area air sampling results for all activities.

The surface dust sampling results collected inside the work area are summarized by sanding and sawing tasks in Table 4.12. Figure 4.6 shows the difference between post-work surface dust samples and the pre-work surfaces dust samples by sanding and sawing task based on the GM of all surfaces sampled.

4.6 Results by Work Practice and Scenario

The PBZ air sampling results are summarized by work practice and scenario (activity and work practice combination) in Table 4.13. Figures 4.7A & 4.7B show the how GM of the PBZ air sampling results for each work practice and scenario compared to the GM of the PBZ air sampling results for all activities.

The area air sampling results collected inside the work area during work are summarized by work practice and scenario in Table 4.14. Figures 4.8A & 4.8B show the GM of the area air sampling results for each work practice and scenario compared to the GM of the area air sampling results for all activities.

The surface dust sampling results collected inside the work area are summarized by work practice and scenario in Table 4.15. Figures 4.9A & 4.9B show the difference between post-work surface dust samples and the pre-work surfaces dust samples by work practice and scenario based on the GM of all surfaces sampled.

Surface dust sampling by surface tested is summarized for each work practice in Table 4.16.

4.7 Results by Property

The PBZ air sampling results are summarized by property in Table 4.17. Figure 4.10 shows the how GM of the PBZ air sampling results for each property compared to the GM of the PBZ air sampling results for all activities.

The area air sampling results collected inside the work area during work are summarized by property in Table 4.18. Figure 4.11 shows the GM of the area air sampling results for each property compared to the GM of the area air sampling results for all activities.

The surface dust sampling results collected inside the work area are summarized by property in Table 4.19. Figure 4.12 shows the difference between post-work surface dust samples and the pre-work surfaces dust samples by property based on the GM of all surfaces sampled.

Surface dust sampling by surface tested is summarized for each property in Table 4.20.

4.8 Worker Exposures

The OSHA action level and permissible exposure limit (PEL) are based on an 8-hour time-weighted average (TWA) exposure. During this Project, personal breathing zone (PBZ) air samples were collected for the duration of the work activity being evaluated. For example, if the scenario being evaluated was a Window Replacement using Routine Work Practices (C1) and the activity took 90 minutes to complete (including set-up and clean-up), the PBZ sample was collected for the 90 minutes the worker was performing the work.

Utilizing this sampling strategy allowed for measuring worker exposures during each activity performed, and results from each activity could be used to calculate each worker's 8-hour TWA exposure. The data was also used to estimate projected 8-hour TWA exposures for each activity.

When multiple events were conducted by a single worker over an 8-hour period, the PBZ air sampling results from each event conducted were used to calculate the worker's 8-hour TWA exposure using the following formula:

$$8\text{-hour TWA} = (C_a T_a + C_b T_b + \dots + C_n T_n) \div 480$$

Where:

8-hour TWA is the equivalent exposure for the working shift;

C is the concentration during any period of time T where the concentration remains constant; and,

T is the duration in minutes of the exposure at the concentration C.^{xi}

For periods where no work was conducted, it was assumed that there was no exposure to lead.

The calculated 8-hour TWA results, which are directly comparable to the OSHA AL of 30 $\mu\text{g}/\text{m}^3$ and the PEL of 50 $\mu\text{g}/\text{m}^3$, are summarized in Table 4.21.

The PBZ samples collected represent 35 workers' 8-hour TWA exposures. The 8-hour TWA exposures ranged from 0.7 $\mu\text{g}/\text{m}^3$ to 197 $\mu\text{g}/\text{m}^3$.

- For all R&R events evaluated during this project, the duration of work ranged from 18 minutes to 259 minutes. The average work duration was 81.5 minutes.
- Twenty-six (74%) of the calculated 8-hour TWA exposures were less than the OSHA Action Level of 30 $\mu\text{g}/\text{m}^3$.
- Twenty-nine (83%) of the 8-hour TWA exposures were below the PEL of 50 $\mu\text{g}/\text{m}^3$.
- The mean 8-hour TWA exposure was 29.5 $\mu\text{g}/\text{m}^3$. The GM of the 8-hour TWA exposures was 8.5 $\mu\text{g}/\text{m}^3$.
- The highest calculated TWA exposures were measured on workers during sanding activities. Calculated 8-hour TWAs for workers who performed sanding work ranged from 32.8 $\mu\text{g}/\text{m}^3$ and 197 $\mu\text{g}/\text{m}^3$.

Projected 8-hour TWA Exposure Estimates. While the 8-hour TWA measured for each worker is useful in identifying which tasks can result in exposures that exceed the OSHA action level and PEL, the data is limited on estimating exposures for specific activities that take longer to complete than those evaluated during this Project. The PBZ air sampling data was used to estimate projected 8-hour TWA exposures for each activity and scenario.

R&R activities took between 18 minutes and 259 minutes to complete. Because exposure monitoring was conducted over the entire activity period, including set-up, work, and clean-up, the duration of the activity represents the period of time the worker was exposed to airborne lead dust. The mean PBZ result and mean exposure time (the time required to complete the event) were used to estimate 8-hour TWA exposures for various work durations for each activity. These estimated exposure projections are shown in Figure 4.22.

It is critical to note that these are estimated exposures assume that the mean exposures for the activity or work practice are representative and consistent over the course of the work shift. These estimates are not intended to replace the requirement to conduct personal exposure monitoring under the OSHA standard.

**TABLE 4.6
PBZ AIR SAMPLING RESULTS SUMMARIZED BY WORK ACTIVITY**

| Activity | PBZ ($\mu\text{g}/\text{m}^3$) | | | | |
|---|----------------------------------|------------|------|------|-----|
| | n | Range | Mean | GM | GSD |
| All Activities ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 65 , Range = 0.9 - 25.3 , Mean = 10.0) | 65 | 2.0 - 1700 | 122 | 26.4 | 5.4 |
| A - Wall and Ceiling Removal ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 5 , Range = 1.5 - 13.4 , Mean = 6.5) | 5 | 2.0 - 92.0 | 23.5 | 7.9 | 5.0 |
| B - Wall and Ceiling Modification ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 15 , Range = 1.0 - 25.3 , Mean = 7.4) | 15 | 2.5 - 68.0 | 21.7 | 13.5 | 2.7 |
| C - Window Replacement (no sanding involved) ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 6 , Range = 11.0 - 22.7 , Mean = 18.8) | 6 | 2.5 - 20.0 | 6.9 | 5.0 | 2.3 |
| C' - Window Alteration (no sanding involved) ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 2 , Range = $>9.9^1$ - 18.9 , Mean = 14.4) | 2 | 3.5 - 78 | 40.8 | 16.5 | 9.0 |
| D - Kitchen and Bath Work ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 5 , Range = 2.1 - $>9.9^1$, Mean = 7.6) | 5 | 6.0 - 49.0 | 26.4 | 20.6 | 2.3 |
| E - Floor Covering Removal ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 8 , Range = 0.9 - 19.2 , Mean = 10.0) | 8 | 6.5 - 56.0 | 26.0 | 18.2 | 2.6 |
| G - Sawing into Wood & Plaster Covered by LBP ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 4 , Range = 1.4 - $>9.9^1$, Mean = 3.9) | 4 | 7.0 - 111 | 42.8 | 23.0 | 3.9 |
| All Sanding Events ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 20 , Range = 1.0 - 22.5 , Mean = 11.5) | 20 | 6.0 - 1700 | 341 | 129 | 5.4 |
| C - Window and Door Replacement, Removal or Alteration (sanding events) ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 10 , Range = $>9.9^1$ - 22.5 , Mean = 12.8) | 10 | 8.0 - 1050 | 414 | 210 | 4.6 |
| F - Surface Preparation (sanding) ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 10 , Range = 1.0 - 16.5 , Mean = 10.2) | 10 | 6.0 - 1700 | 269 | 79.3 | 5.5 |
| LC_{XRF} = Lead content of affected surfaces based on measurement by X-Ray Fluorescence (XRF) instrumentation. ¹ The XRF measurement reported (9.9) was the maximum reportable limit for the XRF instrument used. | | | | | |

FIGURE 4.1 - COMPARISON OF THE GM OF PBZ AIR SAMPLING RESULTS BY ACTIVITY TO THE GM OF THE PBZ AIR SAMPLING RESULTS FOR ALL ACTIVITIES





TABLE 4.7
AREA AIR SAMPLING RESULTS SUMMARIZED BY WORK ACTIVITY

| Activity | Area During ($\mu\text{g}/\text{m}^3$) | | | | |
|---|--|------------|------|------|-----|
| | n | Range | Mean | GM | GSD |
| All Activities (LC_{XRF} (mg/cm^2) n = 74 , Range = 0.9 - 25.3 , Mean = 10.5) | 74 | 1.0 - 1780 | 85.5 | 17.6 | 4.8 |
| A - Wall and Ceiling Removal (LC_{XRF} (mg/cm^2) n = 4 , Range = 1.5 - 13.4 , Mean = 8.3) | 4 | 1.5 - 52.0 | 14.4 | 4.1 | 5.5 |
| B - Wall and Ceiling Modification (LC_{XRF} (mg/cm^2) n = 15 , Range = 1.0 - 25.3 , Mean = 8.4) | 15 | 2.0 - 54.0 | 13.0 | 9.1 | 2.3 |
| C - Window Replacement (no sanding involved) (LC_{XRF} (mg/cm^2) n = 7 , Range = 11 - 22.7 , Mean = 19.3) | 7 | 1.5 - 7.5 | 3.6 | 2.9 | 1.9 |
| C' - Window Alteration (no sanding involved) (LC_{XRF} (mg/cm^2) n = 4 , Range = $>9.9^1$ - 18.9 , Mean = 14.4) | 4 | 4.5 - 63.0 | 30.0 | 15.7 | 4.3 |
| D - Kitchen and Bath Work (LC_{XRF} (mg/cm^2) n = 6 , Range = 2.1 - $>9.9^1$, Mean = 8.0) | 6 | 2.5 - 21.0 | 12.4 | 10.4 | 2.1 |
| E - Floor Covering Removal (LC_{XRF} (mg/cm^2) n = 10 , Range = 0.9 - 19.2 , Mean = 9.4) | 10 | 7.0 - 140 | 28.7 | 17.1 | 2.6 |
| G - Sawing into Wood & Plaster Covered by LBP (LC_{XRF} (mg/cm^2) n = 4 , Range = 1.4 - $>9.9^1$, Mean = 3.9) | 4 | 2.0 - 69.0 | 29.3 | 14.3 | 4.9 |
| All Sanding Events (LC_{XRF} (mg/cm^2) n = 24 , Range = 1.0 - 22.5 , Mean = 11.3) | 24 | 6.0 - 1780 | 227 | 69.7 | 5.2 |
| C - Window and Door Replacement, Removal or Alteration (sanding events) (LC_{XRF} (mg/cm^2) n = 11 , Range = $>9.9^1$ - 22.5 , Mean = 12.5) | 11 | 32.0 - 868 | 267 | 163 | 3.0 |
| F - Surface Preparation (sanding) (LC_{XRF} (mg/cm^2) n = 10 , Range = 1.0 - 16.5 , Mean = 10.2) | 10 | 6.0 - 1780 | 194 | 34.0 | 5.7 |

LC_{XRF} = Lead content of affected surfaces based on measurement by X-Ray Fluorescence (XRF) instrumentation.

¹The XRF measurement reported (9.9) was the maximum reportable limit for the XRF instrument used.

FIGURE 4.2 - COMPARISON OF THE GM OF AREA (DURING) AIR SAMPLING RESULTS BY ACTIVITY TO THE GM OF THE AREA (DURING) AIR SAMPLING RESULTS FOR ALL ACTIVITIES




**TABLE 4.8
SURFACE DUST SAMPLING RESULTS SUMMARIZED BY WORK ACTIVITY**

| Activity | n | Pre ($\mu\text{g}/\text{ft}^2$) | | | Post ($\mu\text{g}/\text{ft}^2$) | | | Δ GM | % Increase |
|---|-----|-----------------------------------|-------|-----|------------------------------------|------|-----|-------------|------------|
| | | Range | Mean | GM | Range | Mean | GM | | |
| All Activities | 241 | 10.0 - 108000 | 3423 | 499 | 15.0 - 39200 | 1185 | 320 | -179 | -36.0% |
| A - Wall and Ceiling Removal | 15 | 40.3 - 98000 | 10118 | 857 | 74.0 - 3800 | 604 | 307 | -550 | -64.2% |
| B - Wall and Ceiling Modification | 56 | 13.4 - 12300 | 1286 | 401 | 18.2 - 3000 | 518 | 213 | -187 | -46.7% |
| C - Window Replacement (no sanding involved) | 25 | 117 - 36000 | 2592 | 784 | 22.4 - 11400 | 1496 | 367 | -417 | -53.2% |
| C' - Window Alteration (no sanding involved) | 6 | 152 - 16000 | 2958 | 575 | 33.2 - 1360 | 749 | 464 | -111 | -19.3% |
| D - Kitchen and Bath Work | 20 | 15.0 - 43600 | 3996 | 436 | 16.3 - 2840 | 633 | 278 | -158 | -36.3% |
| E - Floor Covering Removal | 33 | 13.0 - 108000 | 4549 | 528 | 15.9 - 39200 | 1716 | 242 | -286 | -54.2% |
| G - Sawing into Wood & Plaster Covered by LBP | 16 | 10.0 - 10800 | 1651 | 208 | 14.9 - 2880 | 458 | 134 | -73.8 | -35.5% |
| All Sanding Events | 69 | 15.0 - 91200 | 3734 | 545 | 19.8 - 14600 | 1873 | 606 | 60.8 | 11.1% |
| C - Window and Door Replacement, Removal or Alteration (sanding events) | 32 | 15.0 - 91200 | 5938 | 471 | 19.8 - 10800 | 2193 | 638 | 145.0 | 29.4% |
| F - Surface Preparation (sanding) | 37 | 27.0 - 14600 | 1836 | 595 | 48.7 - 14600 | 1589 | 579 | -15.5 | -2.6% |

n = no. of pairs of samples, where a pair equals one pre-work sample and one post-work sample from approximately the same location.

Figure 4.3 - DIFFERENCE BETWEEN POST-WORK DUST SAMPLES AND PRE-WORK DUST SAMPLES BASED ON GM OF ALL SUFACES SAMPLED



**TABLE 4.9
CHANGES IN SETTLED DUST LEAD LOADINGS IN WORK AREA BY WORK ACTIVITY**

| Surface | Activity | No. | Pre-Work Results ($\mu\text{g}/\text{ft}^2$) | | Post-Work Results ($\mu\text{g}/\text{ft}^2$) | | Change |
|--------------------------|---|------------|---|----------------|--|----------------|-------------------------|
| | | | Range | Geometric Mean | Range | Geometric Mean | |
| Floor in Work Area | Wall and ceiling removal | 7 | 40.3 - 1,200 | 327 | 74 - 3,800 | 418 | 28% |
| | Wall and ceiling modification | 26 | 13.4 - 5,020 | 144 | 18.2 - 3,000 | 84 | -42% ^a |
| | Window and door replacement, removal or alteration. | 29 | 33.6 - 1,320 | 266 | 33.2 - 11,400 | 314 | 18% |
| | Kitchen and bath work (cabinet removal) | 6 | 15.4 - 4,060 | 88 | 84.4 - 1,490 | 119 | 35% |
| | Floor covering removal (baseboard removal) | 16 | 13 - 4,700 | 344 | 26.4 - 5,020 | 192 | -44% |
| | Surface preparation. | 16 | 33.2 - 6,080 | 516 | 48.7 - 9,700 | 788 | 53% |
| | Sawing into wood & plaster covered by LBP. | 6 | <10 - 4,320 | 116 | 49.2 - 1,040 | 156 | 34% |
| | All | 106 | <10 - 6,080 | 239 | 18.2 - 11,400 | 225 | -6% |
| Window Sill in Work Area | Wall and ceiling removal | 2 | 263 - 44,000 | 3,402 | 200 - 896 | 423 | -88% |
| | Wall and ceiling modification | 14 | 252 - 12,300 | 1,176 | 19.9 - 2,700 | 242 | -79% ^b |
| | Window and door replacement, removal or alteration. | 21 | 366 - 91,200 | 1,927 | 79.4 - 10,800 | 1,102 | -43% |
| | Kitchen and bath work (cabinet removal) | 5 | 213 - 43,600 | 2,409 | 95.7 - 2,840 | 536 | -78% ^a |
| | Floor covering removal (baseboard removal) | 5 | 136 - 108,000 | 2,004 | 81.8 - 873 | 272 | -86% |
| | Surface preparation. | 5 | 683 - 3,300 | 1,683 | 58.7 - 3,200 | 595 | -65% ^b |
| | Sawing into wood & plaster covered by LBP. | 2 | 6440 - 10,800 | 8,340 | 133 - 872 | 341 | -96% |
| | All | 54 | 136 - 108,000 | 1,850 | 19.9 - 10,800 | 553 | -71%^b |

a = marginally significant change ($p < 0.10$); b = statistically significant change ($p < 0.05$)

Note: This analysis was limited to only samples collected from floors and window sills within work areas, and only included pairs from a specific location. Other surfaces within work areas were also sampled, and samples were also collected outside of the work area. Therefore, more pairs of wipe samples were collected but not included in the analysis of lead dust loading on floors and window sills.

TABLE 4.10**PBZ AIR SAMPLING RESULTS SUMMARIZED BY SANDING AND SAWING TASKS**

| Expanded by Sanding and Cutting Tasks | PBZ ($\mu\text{g}/\text{m}^3$) | | | | |
|---|----------------------------------|------------|------|------|-----|
| | n | Range | Mean | GM | GSD |
| All Activities ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 65 , Range = 0.9 - 25.3 , Mean = 10.0) | 65 | 2.0 - 1700 | 122 | 26.4 | 5.4 |
| Surface Preparation (sanding plaster) ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 3 , Range = 16.5 - 16.5 , Mean = 16.5) | 3 | 6.0 - 95.0 | 50.7 | 30.7 | 4.3 |
| Surface Preparation (sanding wood) ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 12 , Range = 1.0 - 13.8 , Mean = 8.8) | 12 | 6.5 - 1700 | 372 | 155 | 4.5 |
| Sawing & Cutting LBP Covered Surfaces (plaster) ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 10 , Range = 1.0 - 13.4 , Mean = 6.6) | 10 | 2.5 - 68.0 | 19.4 | 10.4 | 2.9 |
| Sawing & Cutting LBP Covered Surfaces (wood) ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 8 , Range = 1.4 - >9.9 ¹ , Mean = 4.5) | 8 | 7.5 - 111 | 36.9 | 24.6 | 2.7 |
| LC_{XRF} = Lead content of affected surfaces based on measurement by X-Ray Fluorescence (XRF) instrumentation. ¹ The XRF measurement reported (9.9) was the maximum reportable limit for the XRF instrument used. | | | | | |

FIGURE 4.4 - COMPARISON OF THE GM OF PBZ AIR SAMPLING RESULTS BY SPECIFIC TASK TO THE GM OF THE PBZ AIR SAMPLING RESULTS FOR ALL ACTIVITIES




TABLE 4.11
AREA AIR SAMPLING RESULTS SUMMARIZED BY SANDING AND SAWING TASKS

| Expanded by Sanding and Cutting Tasks | Area During ($\mu\text{g}/\text{m}^3$) | | | | |
|---|--|--------------|-------------|-----------|------------|
| | n | Range | Mean | GM | GSD |
| All Activities (LC_{XRF} (mg/cm^2) n = 74 , Range = 0.9 - 25.3 , Mean = 10.5) | 74 | 1.0 - 1780 | 85.5 | 17.6 | 4.8 |
| Surface Preparation (sanding plaster) (LC_{XRF} (mg/cm^2) n = 4 , Range = 16.5 - 16.5 , Mean = 16.5) | 4 | 6.0 - 30.0 | 16.4 | 12.8 | 2.3 |
| Surface Preparation (sanding wood) (LC_{XRF} (mg/cm^2) n = 9 , Range = 1.0 - 13.0 , Mean = 7.3) | 9 | 6.5 - 1780 | 272 | 52.5 | 6.7 |
| Sawing & Cutting LBP Covered Surfaces (plaster) (LC_{XRF} (mg/cm^2) n = 9 , Range = 1.0 - 13.4 , Mean = 8.1) | 9 | 2.0 - 28.0 | 8.7 | 6.7 | 2.1 |
| Sawing & Cutting LBP Covered Surfaces (wood) (LC_{XRF} (mg/cm^2) n = 8 , Range = 1.4 - $>9.9^1$, Mean = 4.5) | 13 | 7.5 - 69.0 | 28.1 | 19.8 | 2.5 |

LC_{XRF} = Lead content of affected surfaces based on measurement by X-Ray Fluorescence (XRF) instrumentation.

¹The XRF measurement reported (9.9) was the maximum reportable limit for the XRF instrument used.

FIGURE 4.5 - COMPARISON OF THE GM OF AREA AIR SAMPLING RESULTS BY SPECIFIC TASK TO THE GM OF THE AREA AIR SAMPLING RESULTS FOR ALL ACTIVITIES




TABLE 4.12
SURFACE DUST SAMPLING RESULTS SUMMARIZED BY SANDING AND SAWING TASKS

| Activity | n | Pre ($\mu\text{g}/\text{ft}^2$) | | | Post ($\mu\text{g}/\text{ft}^2$) | | | GM Δ | % Increase |
|---|-----|-----------------------------------|------|------|------------------------------------|------|-----|-------------|------------|
| | | Range | Mean | GM | Range | Mean | GM | | |
| All Activities | 241 | 10.0 - 108000 | 3423 | 499 | 15.0 - 39200 | 1185 | 320 | -179 | -36.0% |
| Surface Preparation (sanding plaster) | 8 | 642 - 5440 | 2739 | 2009 | 186 - 2350 | 945 | 657 | -1352 | -67.3% |
| Surface Preparation (sanding wood) | 29 | 27.0 - 14600 | 1617 | 444 | 48.7 - 14600 | 1773 | 559 | 116 | 26.0% |
| Sawing & Cutting LBP Covered Surfaces (plaster) | 37 | 13.4 - 11400 | 913 | 261 | 14.9 - 1470 | 276 | 110 | -151 | -57.7% |
| Sawing & Cutting LBP Covered Surfaces (wood) | 31 | 10.0 - 12300 | 1760 | 393 | 16.3 - 3000 | 613 | 295 | -97.8 | -24.9% |

n = no. of pairs of samples, where a pair equals one pre-work sample and one post-work sample from approximately the same location.

FIGURE 4.6 - DIFFERENCE BETWEEN POST-WORK DUST SAMPLES AND PRE-WORK DUST SAMPLES BY TASK BASED ON GM OF ALL SURFACES SAMPLED




TABLE 4.13

PBZ AIR SAMPLING RESULTS SUMMARIZED BY SCENARIO (ACTIVITY & WORK PRACTICE)

| Activity | PBZ ($\mu\text{g}/\text{m}^3$) | | | | |
|--|----------------------------------|-------------|------|------|-----|
| | n | Range | Mean | GM | GSD |
| All Routine Activities ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 28 , Range = 0.9 - 22.5 , Mean = 9.8) | 28 | 6.5 - 1700 | 203 | 49.2 | 5.5 |
| All Mod LSWP Activities ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 31 , Range = 1.0 - 25.3 , Mean = 8.6) | 31 | 2.0 - 805 | 69.1 | 20.3 | 4.6 |
| All LSWP Activities ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 6 , Range = 9.6 - 22.7 , Mean = 17.8) | 6 | 2.5 - 52.0 | 11.8 | 5.5 | 3.2 |
| A1 - Wall and Ceiling Removal (Routine) ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 1 , Range = 8.7 - 8.7 , Mean = 8.7) | 1 | 17.0 - 17.0 | 17.0 | 17.0 | NA |
| A2 - Wall and Ceiling Removal (Mod LSWP) ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 4 , Range = 1.5 - 13.4 , Mean = 5.9) | 4 | 2.0 - 92.0 | 25.1 | 6.5 | 6.0 |
| B1 - Wall and Ceiling Modification (Routine) ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 6 , Range = 1.0 - 13.4 , Mean = 7.8) | 6 | 6.5 - 68.0 | 28.5 | 18.3 | 2.7 |
| B2 - Wall and Ceiling Modification (Mod LSWP) ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 8 , Range = 1.0 - 25.3 , Mean = 6.3) | 8 | 2.5 - 63.0 | 18.9 | 12.5 | 2.7 |
| B3 - Wall and Ceiling Modification (LSWP) ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 1 , Range = 13.4 - 13.4 , Mean = 13.4) | 1 | 4.0 - 4.0 | 4.0 | 4.0 | NA |
| C1 - Window Replacement (no sanding involved) (Routine) ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 1 , Range = 20.1 - 20.1 , Mean = 20.1) | 1 | 20.0 - 20.0 | 20.0 | 20.0 | NA |
| C2 - Window Replacement (no sanding involved) (Mod LSWP) ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 3 , Range = 11.0 - 22.5 , Mean = 15.7) | 3 | 2.5 - 7.0 | 5.5 | 5.0 | 1.8 |
| C3 - Window Replacement (no sanding involved) (LSWP) ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 2 , Range = 22.7 - 22.7 , Mean = 22.7) | 2 | 2.5 - 2.5 | 2.5 | 2.5 | 1.0 |
| C'1 - Window Alteration (no sanding involved) (Routine) ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 1 , Range = $>9.9^1$ - $>9.9^1$, Mean = $>9.9^1$) | 1 | 78.0 - 78.0 | 78.0 | 78.0 | NA |
| C'3 - Window Alteration (no sanding involved) (LSWP) ($\text{LC}_{\text{XRF}} (\text{mg}/\text{cm}^2)$ n = 1 , Range = 18.9 - 18.9 , Mean = 18.9) | 1 | 3.5 - 3.5 | 3.5 | 3.5 | NA |

| TABLE 4.13 (cont'd) | | | | | |
|---|--|--------------|-------------|-----------|------------|
| PBZ AIR SAMPLING RESULTS SUMMARIZED BY SCENARIO (ACTIVITY & WORK PRACTICE) | | | | | |
| Activity | PBZ ($\mu\text{g}/\text{m}^3$) | | | | |
| | n | Range | Mean | GM | GSD |
| D1 - Kitchen and Bath Work (Routine) (LC_{XRF} (mg/cm^2) n = 2 , Range = 2.1 - 6.9 , Mean = 4.5) | 2 | 15.0 - 20.0 | 17.5 | 17.3 | 1.2 |
| D2 - Kitchen and Bath Work (Mod LSWP) (LC_{XRF} (mg/cm^2) n = 2 , Range = 9.4 - >9.9 ¹ , Mean = 9.7) | 2 | 42.0 - 49.0 | 45.5 | 45.4 | 1.1 |
| D3 - Kitchen and Bath Work (LSWP) (LC_{XRF} (mg/cm^2) n = 1 , Range = 9.6 - 9.6 , Mean = 9.6) | 1 | 6.0 - 6.0 | 6.0 | 6.0 | NA |
| E1 - Floor Covering Removal (Routine) (LC_{XRF} (mg/cm^2) n = 3 , Range = 0.9 - >9.9 ¹ , Mean = 6.9) | 3 | 7.0 - 56.0 | 23.7 | 14.6 | 3.2 |
| E2 - Floor Covering Removal (Mod LSWP) (LC_{XRF} (mg/cm^2) n = 4 , Range = 7.4 - 13.0 , Mean = 10.1) | 4 | 6.5 - 38.0 | 21.3 | 16.4 | 2.4 |
| E3 - Floor Covering Removal (LSWP) (LC_{XRF} (mg/cm^2) n = 1 , Range = 19.2 - 19.2 , Mean = 19.2) | 1 | 52.0 - 52.0 | 52.0 | 52.0 | NA |
| G1 - Sawing into Wood & Plaster Covered by LBP (Routine) (LC_{XRF} (mg/cm^2) n = 2 , Range = 1.4 - 1.6 , Mean = 1.5) | 2 | 8.0 - 111 | 59.5 | 29.8 | 6.4 |
| G2 - Sawing into Wood & Plaster Covered by LBP (Mod LSWP) (LC_{XRF} (mg/cm^2) n = 2 , Range = 2.9 - >9.9 ¹ , Mean = 6.4) | 2 | 7.0 - 45.0 | 26.0 | 17.7 | 3.7 |
| All Sanding Events (Routine) (LC_{XRF} (mg/cm^2) n = 11 , Range = 1.0 - 22.5 , Mean = 12.1) | 12 | 6.5 - 1700 | 432 | 160 | 6.0 |
| All Sanding Events (Mod LSWP) (LC_{XRF} (mg/cm^2) n = 8 , Range = 2.3 - 16.5 , Mean = 9.3) | 8 | 6.0 - 805 | 206 | 93.0 | 4.4 |
| C1 - Window and Door Replacement, Removal or Alteration (sanding events) (Routine) (LC_{XRF} (mg/cm^2) n = 6 , Range = >9.9 ¹ - 22.5 , Mean = 12.7) | 7 | 8.0 - 1050 | 455 | 233 | 5.3 |
| C2 - Window and Door Replacement, Removal or Alteration (sanding events) (Mod LSWP) (LC_{XRF} (mg/cm^2) n = 3 , Range = >9.9 ¹ - >9.9 ¹ , Mean = 9.9) | 3 | 60.0 - 805.0 | 319 | 164 | 4.0 |
| F1 - Surface Preparation (sanding) (Routine) (LC_{XRF} (mg/cm^2) n = 5 , Range = 1.0 - 16.5 , Mean = 11.4) | 5 | 6.5 - 1700 | 400 | 95.1 | 7.4 |
| F2 - Surface Preparation (sanding) (Mod LSWP) (LC_{XRF} (mg/cm^2) n = 5 , Range = 2.3 - 16.5 , Mean = 8.9) | 5 | 6.0 - 420 | 138 | 66.1 | 4.8 |

TABLE 4.13 (cont'd)

PBZ AIR SAMPLING RESULTS SUMMARIZED BY SCENARIO (ACTIVITY & WORK PRACTICE)

| Expanded by Sanding and Cutting Tasks | PBZ ($\mu\text{g}/\text{m}^3$) | | | | |
|--|--|--------------|-------------|-----------|------------|
| | n | Range | Mean | GM | GSD |
| All Activities (LC_{XRF} (mg/cm^2) n = 65 , Range = 0.9 - 25.3 , Mean = 10.0) | 65 | 2.0 - 1700 | 122 | 26.4 | 5.4 |
| Surface Preparation (sanding plaster) (Routine) (LC_{XRF} (mg/cm^2) n = 2 , Range = 16.5 - 16.5 , Mean = 16.5) | 2 | 51.0 - 95.0 | 73.0 | 69.6 | 1.6 |
| Surface Preparation (sanding plaster) (Mod LSWP) (LC_{XRF} (mg/cm^2) n = 1 , Range = 16.5 - 16.5 , Mean = 16.5) | 1 | 6.0 - 6.0 | 6.0 | 6.0 | NA |
| Surface Preparation (sanding wood) (Routine) (LC_{XRF} (mg/cm^2) n = 3 , Range = 1.0 - 13.0 , Mean = 8.0) | 3 | 6.5 - 1700 | 617 | 117 | 16.3 |
| Surface Preparation (sanding wood) (Mod LSWP) (LC_{XRF} (mg/cm^2) n = 4 , Range = 2.3 - 9.9 , Mean = 7.0) | 4 | 47.0 - 420 | 171 | 120 | 2.6 |
| Sawing & Cutting LBP Covered Surfaces (plaster) (Routine) (LC_{XRF} (mg/cm^2) n = 5 , Range = 1.0 - 13.4 , Mean = 8.8) | 5 | 6.5 - 68.0 | 31.8 | 20.0 | 3.0 |
| Sawing & Cutting LBP Covered Surfaces (plaster) (Mod LSWP) (LC_{XRF} (mg/cm^2) n = 4 , Range = 1.0 - 2.9 , Mean = 2.0) | 4 | 2.5 - 12.0 | 7.6 | 6.6 | 2.0 |
| Sawing & Cutting LBP Covered Surfaces (plaster) (LSWP) (LC_{XRF} (mg/cm^2) n = 1 , Range = 13.4 - 13.4 , Mean = 13.4) | 1 | 4.0 - 4.0 | 4.0 | 4.0 | NA |
| Sawing & Cutting LBP Covered Surfaces (wood) (Routine) (LC_{XRF} (mg/cm^2) n = 3 , Range = 1.4 - 2.8 , Mean = 1.9) | 3 | 8.0 - 111 | 43.7 | 22.0 | 4.1 |
| Sawing & Cutting LBP Covered Surfaces (wood) (Mod LSWP) (LC_{XRF} (mg/cm^2) n = 5 , Range = 2.9 - 9.9 , Mean = 6.0) | 5 | 7.5 - 63.0 | 32.9 | 26.4 | 2.3 |

LC_{XRF} = Lead content of affected surfaces based on measurement by X-Ray Fluorescence (XRF) instrumentation.

¹ The XRF measurement reported (9.9) was the maximum reportable limit for the XRF instrument used.

FIGURE 4.7A - COMPARISON OF THE GM OF PBZ AIR SAMPLING RESULTS BY SCENARIO TO THE GM OF THE PBZ AIR SAMPLING RESULTS FOR ALL ACTIVITIES





FIGURE 4.7B - COMPARISON OF THE GM OF PBZ AIR SAMPLING RESULTS BY SCENARIO TO THE GM OF THE PBZ AIR SAMPLING RESULTS FOR ALL ACTIVITIES



| TABLE 4.14 | | | | | |
|---|--|--------------|-------------|-----------|------------|
| AREA (DURING) AIR SAMPLING RESULTS SUMMARIZED BY SCENARIO (ACTIVITY & WORK PRACTICE) | | | | | |
| Activity | Area During ($\mu\text{g}/\text{m}^3$) | | | | |
| | n | Range | Mean | GM | GSD |
| All Routine Activities (LC_{XRF} (mg/cm^2) n = 28 , Range = 0.9 - 22.5 , Mean = 9.8) | 33 | 3.0 - 1780 | 142 | 30.7 | 5.1 |
| All Mod LSWP Activities (LC_{XRF} (mg/cm^2) n = 31 , Range = 1.0 - 25.3 , Mean = 8.6) | 34 | 1.5 - 428 | 47.0 | 13.8 | 4.6 |
| All LSWP Activities (LC_{XRF} (mg/cm^2) n = 6 , Range = 9.6 - 22.7 , Mean = 17.8) | 7 | 2.0 - 28.0 | 6.9 | 4.3 | 2.5 |
| A1 - Wall and Ceiling Removal (Routine) (LC_{XRF} (mg/cm^2) n = 1 , Range = 8.7 - 8.7 , Mean = 8.7) | 0 | 0.0 - 0.0 | NA | NA | NA |
| A2 - Wall and Ceiling Removal (Mod LSWP) (LC_{XRF} (mg/cm^2) n = 4 , Range = 1.5 - 13.4 , Mean = 8.2) | 4 | 1.5 - 52.0 | 14.4 | 4.1 | 5.5 |
| B1 - Wall and Ceiling Modification (Routine) (LC_{XRF} (mg/cm^2) n = 7 , Range = 1.0 - 13.4 , Mean = 8.6) | 7 | 3.5 - 54.0 | 17.5 | 11.8 | 2.5 |
| B2 - Wall and Ceiling Modification (Mod LSWP) (LC_{XRF} (mg/cm^2) n = 7 , Range = 1.0 - 25.3 , Mean = 6.8) | 7 | 2.0 - 27.0 | 9.8 | 7.7 | 2.1 |
| B3 - Wall and Ceiling Modification (LSWP) (LC_{XRF} (mg/cm^2) n = 1 , Range = 13.4 - 13.4 , Mean = 13.4) | 1 | 4.5 - 4.5 | 4.5 | 4.5 | NA |
| C1 - Window Replacement (no sanding involved) (Routine) (LC_{XRF} (mg/cm^2) n = 1 , Range = 20.1 - 20.1 , Mean = 20.1) | 1 | 3.0 - 3.0 | 3.0 | 3.0 | NA |
| C2 - Window Replacement (no sanding involved) (Mod LSWP) (LC_{XRF} (mg/cm^2) n = 4 , Range = 11.0 - 22.5 , Mean = 17.4) | 4 | 1.5 - 7.5 | 4.5 | 3.5 | 2.3 |
| C3 - Window Replacement (no sanding involved) (LSWP) (LC_{XRF} (mg/cm^2) n = 2 , Range = 22.7 - 22.7 , Mean = 22.7) | 2 | 2.0 - 2.0 | 2.0 | 2.0 | 1.0 |
| C'1 - Window Alteration (no sanding involved) (Routine) (LC_{XRF} (mg/cm^2) n = 1 , Range = 9.9 - 9.9 , Mean = 9.9) | 2 | 48.0 - 63.0 | 55.5 | 56.0 | 1.2 |
| C'3 - Window Alteration (no sanding involved) (LSWP) (LC_{XRF} (mg/cm^2) n = 2 , Range = 18.9 - 18.9 , Mean = 18.9) | 2 | 4.5 - 4.5 | 4.5 | 4.5 | 1.0 |

| TABLE 4.14 (cont'd) | | | | | |
|--|--|--------------|-------------|-----------|------------|
| AREA (DURING) AIR SAMPLING RESULTS SUMMARIZED BY WORK ACTIVITY | | | | | |
| Activity | Area During ($\mu\text{g}/\text{m}^3$) | | | | |
| | n | Range | Mean | GM | GSD |
| D1 - Kitchen and Bath Work (Routine) (LC_{XRF} (mg/cm^2) n = 2 , Range = 2.1 - 6.9 , Mean = 4.5) | 2 | 9.0 - 15.0 | 12.0 | 11.6 | 1.4 |
| D2 - Kitchen and Bath Work (Mod LSWP) (LC_{XRF} (mg/cm^2) n = 3 , Range = 9.4 - >9.9 ¹ , Mean = 9.7) | 3 | 13.0 - 21.0 | 16.0 | 15.6 | 1.3 |
| D3 - Kitchen and Bath Work (LSWP) (LC_{XRF} (mg/cm^2) n = 1 , Range = 9.6 - 9.6 , Mean = 9.6) | 1 | 2.5 - 2.5 | 2.5 | 2.5 | NA |
| E1 - Floor Covering Removal (Routine) (LC_{XRF} (mg/cm^2) n = 4 , Range = 0.9 - 9.9 , Mean = 5.4) | 4 | 7.5 - 33.0 | 14.5 | 11.7 | 2.0 |
| E2 - Floor Covering Removal (Mod LSWP) (LC_{XRF} (mg/cm^2) n = 5 , Range = 7.4 - 13.0 , Mean = 10.6) | 5 | 7.0 - 140 | 40.2 | 21.0 | 3.3 |
| E3 - Floor Covering Removal (LSWP) (LC_{XRF} (mg/cm^2) n = 1 , Range = 19.2 - 19.2 , Mean = 19.2) | 1 | 28.0 - 28.0 | 28.0 | 28.0 | NA |
| G1 - Sawing into Wood & Plaster Covered by LBP (Routine) (LC_{XRF} (mg/cm^2) n = 2 , Range = 1.4 - 1.6 , Mean = 1.5) | 2 | 8.0 - 69.0 | 38.5 | 23.5 | 4.6 |
| G2 - Sawing into Wood & Plaster Covered by LBP (Mod LSWP) (LC_{XRF} (mg/cm^2) n = 2 , Range = 2.9 - 9.9 , Mean = 6.4) | 2 | 2.0 - 38.0 | 20.0 | 8.7 | 8.0 |
| All Sanding Events (Routine) (LC_{XRF} (mg/cm^2) n = 14 , Range = 1.0 - 22.5 , Mean = 11.2) | 15 | 6.0 - 1780 | 286 | 79.1 | 5.9 |
| All Sanding Events (Mod LSWP) (LC_{XRF} (mg/cm^2) n = 9 , Range = 2.3 - 16.5 , Mean = 10.1) | 9 | 6.0 - 428 | 129 | 56.4 | 4.5 |
| C1 - Window and Door Replacement, Removal or Alteration (sanding events) (LC_{XRF} (mg/cm^2) n = 7 , Range = 9.9 - 22.5 , Mean = 12.3) | 8 | 32.0 - 868 | 298 | 186 | 3.0 |
| C2 - Window and Door Replacement, Removal or Alteration (sanding events) (LC_{XRF} (mg/cm^2) n = 3 , Range = 9.9 - 9.9 , Mean = 9.9) | 3 | 52.0 - 428.0 | 183 | 1115 | 3.2 |
| F1 - Surface Preparation (sanding) (Routine) (LC_{XRF} (mg/cm^2) n = 7 , Range = 1.0 - 16.5 , Mean = 10.1) | 7 | 6.0 - 1780 | 271 | 29.9 | 7.1 |
| F2 - Surface Preparation (sanding) (Mod LSWP) (LC_{XRF} (mg/cm^2) n = 6 , Range = 2.3 - 16.5 , Mean = 10.2) | 6 | 6.0 - 411 | 103 | 39.6 | 5.1 |

TABLE 4.14 (cont'd)
AREA (DURING) AIR SAMPLING RESULTS SUMMARIZED BY WORK ACTIVITY

| Expanded by Sanding and Cutting Tasks | Area During ($\mu\text{g}/\text{m}^3$) | | | | |
|--|--|-------------|------|------|------|
| | n | Range | Mean | GM | GSD |
| All Activities ($\text{LC}_{\text{XRF}}(\text{mg}/\text{cm}^2)$ n = 65 , Range = 0.9 - 25.3 , Mean = 10.0) | 74 | 1.0 - 1780 | 86 | 17.6 | 4.8 |
| Surface Preparation (sanding plaster) (Routine) ($\text{LC}_{\text{XRF}}(\text{mg}/\text{cm}^2)$ n = 2 , Range = 16.5 - 16.5 , Mean = 16.5) | 2 | 23.0 - 30.0 | 26.5 | 26.3 | 1.2 |
| Surface Preparation (sanding plaster) (Mod LSWP) ($\text{LC}_{\text{XRF}}(\text{mg}/\text{cm}^2)$ n = 2 , Range = 16.5 - 16.5 , Mean = 16.5) | 2 | 6.0 - 6.5 | 6.3 | 6.2 | 1.1 |
| Surface Preparation (sanding wood) (Routine) ($\text{LC}_{\text{XRF}}(\text{mg}/\text{cm}^2)$ n = 5 , Range = 1.0 - 13.0 , Mean = 7.6) | 5 | 6.0 - 1780 | 369 | 31.4 | 10.9 |
| Surface Preparation (sanding wood) (Mod LSWP) ($\text{LC}_{\text{XRF}}(\text{mg}/\text{cm}^2)$ n = 4 , Range = 2.3 - 9.9 , Mean = 7.0) | 4 | 42.0 - 411 | 151 | 99.6 | 2.7 |
| Sawing & Cutting LBP Covered Surfaces (plaster) (Routine) ($\text{LC}_{\text{XRF}}(\text{mg}/\text{cm}^2)$ n = 5 , Range = 1.0 - 13.4 , Mean = 10.9) | 5 | 3.5 - 28.0 | 10.9 | 8.4 | 2.1 |
| Sawing & Cutting LBP Covered Surfaces (plaster) (Mod LSWP) ($\text{LC}_{\text{XRF}}(\text{mg}/\text{cm}^2)$ n = 4 , Range = 1.0 - 2.9 , Mean = 2.0) | 4 | 2.0 - 9.0 | 5.3 | 4.1 | 2.3 |
| Sawing & Cutting LBP Covered Surfaces (plaster) (LSWP) ($\text{LC}_{\text{XRF}}(\text{mg}/\text{cm}^2)$ n = 1 , Range = 13.4 - 13.4 , Mean = 13.4) | 1 | 4.5 - 4.5 | 4.5 | 4.5 | NA |
| Sawing & Cutting LBP Covered Surfaces (wood) (Routine) ($\text{LC}_{\text{XRF}}(\text{mg}/\text{cm}^2)$ n = 4 , Range = 1.4 - 2.8 , Mean = 2.2) | 4 | 8.0 - 69.0 | 36.3 | 25.4 | 2.8 |
| Sawing & Cutting LBP Covered Surfaces (wood) (Mod LSWP) ($\text{LC}_{\text{XRF}}(\text{mg}/\text{cm}^2)$ n = 4 , Range = 2.9 - 9.9 , Mean = 6.8) | 4 | 7.5 - 38.0 | 20.0 | 15.5 | 2.3 |

LC_{XRF} = Lead content of affected surfaces based on measurement by X-Ray Fluorescence (XRF) instrumentation.

¹The XRF measurement reported (9.9) was the maximum reportable limit for the XRF instrument used.

FIGURE 4.8A - COMPARISON OF THE GM OF AREA (DURING) AIR SAMPLING RESULTS BY SCENARIO TO THE GM OF THE AREA (DURING) AIR SAMPLING RESULTS FOR ALL ACTIVITIES





FIGURE 4.8B - COMPARISON OF THE GM OF AREA (DURING) AIR SAMPLING RESULTS BY SCENARIO TO THE GM OF THE AREA (DURING) AIR SAMPLING RESULTS FOR ALL ACTIVITIES



**TABLE 4.15
SURFACE DUST SAMPLING RESULTS SUMMARIZED BY SCENARIO**

| Activity | n | Pre ($\mu\text{g}/\text{ft}^2$) | | | Post ($\mu\text{g}/\text{ft}^2$) | | | Δ GM | % Change |
|--|-----|-----------------------------------|-------|------|------------------------------------|------|------|-------------|----------|
| | | Range | Mean | GM | Range | Mean | GM | | |
| All Activities | 241 | 10.0 - 108000 | 3423 | 499 | 15.0 - 39200 | 1185 | 320 | -179 | -36.0% |
| All Activities (Routine) | 100 | 10.0 - 6200 | 3336 | 407 | 15.9 - 39200 | 1898 | 413 | 5.9 | 1.5% |
| All Activities (Mod LSWP) | 120 | 13.4 - 108000 | 4371 | 567 | 14.9 - 11400 | 1022 | 262 | -305 | -53.8% |
| All Activities (LSWP) | 21 | 141 - 8540 | 1335 | 687 | 36.2 - 1470 | 623 | 471 | -216 | -31.4% |
| A - Wall and Ceiling Removal (Routine) | 2 | 1200 - 44000 | 22600 | 7266 | 503 - 896 | 700 | 671 | -6595 | -90.8% |
| A - Wall and Ceiling Removal (Mod LSWP) | 13 | 40.3 - 98000 | 8197 | 617 | 74.0 - 3800 | 589 | 272 | -345 | -55.9% |
| B - Wall and Ceiling Modification (Routine) | 24 | 17.8 - 11400 | 1189 | 414 | 30.1 - 1470 | 486 | 327 | -87.3 | -21.1% |
| B - Wall and Ceiling Modification (Mod LSWP) | 28 | 13.4 - 12300 | 1411 | 355 | 18.2 - 3000 | 553 | 133 | -222 | -62.6% |
| B - Wall and Ceiling Modification (LSWP) | 4 | 210 - 2090 | 998 | 748 | 402 - 535 | 459 | 456 | -292 | -39.0% |
| C - Window Replacement (no sanding involved) (Routine) | 4 | 117 - 1640 | 713 | 451 | 22.4 - 113 | 73.9 | 63.4 | -388 | -85.9% |
| C - Window Replacement (no sanding involved) (Mod LSWP) | 16 | 340 - 36000 | 3139 | 881 | 42.6 - 11400 | 2173 | 644 | -237 | -26.9% |
| C - Window Replacement (no sanding involved) (LSWP) | 5 | 141 - 8540 | 2344 | 840 | 36.2 - 1140 | 466 | 246 | -594 | -70.7% |
| C' - Window Alteration (no sanding involved) (Routine) | 3 | 152 - 16000 | 5436 | 722 | 33.2 - 1360 | 773 | 347 | -375 | -52.0% |
| C' - Window Alteration (no sanding involved) (LSWP) | 4 | 324 - 800 | 560 | 527 | 402 - 1320 | 677 | 599 | 71.7 | 13.6% |
| D - Kitchen and Bath Work (Routine) | 8 | 15.0 - 43600 | 5982 | 365 | 16.3 - 2840 | 590 | 181 | -184 | -50.5% |
| D - Kitchen and Bath Work (Mod LSWP) | 8 | 15.0 - 19600 | 3607 | 419 | 20.5 - 1490 | 510 | 250 | -170 | -40.5% |
| D - Kitchen and Bath Work (LSWP) | 4 | 213 - 1210 | 805 | 673 | 354 - 1470 | 966 | 813 | 140 | 20.8% |
| E - Floor Covering Removal (Routine) | 11 | 13.0 - 8760 | 1713 | 384 | 15.9 - 39200 | 3797 | 229 | -155 | -40.3% |
| E - Floor Covering Removal (Mod LSWP) | 18 | 16.3 - 108000 | 6911 | 612 | 15.9 - 5020 | 696 | 212 | -399 | -65.3% |
| E - Floor Covering Removal (LSWP) | 4 | 150 - 5440 | 1717 | 653 | 231 - 888 | 583 | 499 | -153 | -23.5% |
| G - Sawing into Wood & Plaster Covered by LBP (Routine) | 8 | 10.0 - 6440 | 1078 | 116 | 16.3 - 2880 | 638 | 212 | 95.6 | 82.3% |
| G - Sawing into Wood & Plaster Covered by LBP (Mod LSWP) | 8 | 26.1 - 10800 | 2225 | 373 | 14.9 - 1040 | 278 | 85.1 | -288 | -77.2% |

n = no. of pairs of samples, where a pair equals one pre-work sample and one post-work sample from approximately the same location.

TABLE 4.15 (cont'd)

SURFACE DUST SAMPLING RESULTS SUMMARIZED BY SANDING AND SAWING TASKS

| Activity | n | Pre ($\mu\text{g}/\text{ft}^2$) | | | Post ($\mu\text{g}/\text{ft}^2$) | | | GM Δ | % Increase |
|--|-----|-----------------------------------|-------|------|------------------------------------|------|------|-------------|------------|
| | | Range | Mean | GM | Range | Mean | GM | | |
| All Activities | 241 | 10.0 - 108000 | 3423 | 499 | 15.0 - 39200 | 1185 | 320 | -179 | -36.0% |
| All Sanding Events (Routine) | 40 | 15.0 - 62000 | 2572 | 422 | 20.5 - 14600 | 2090 | 725 | 303 | 72.0% |
| All Sanding Events (Mod LSWP) | 29 | 50.2 - 91200 | 5351 | 781 | 19.8 - 10800 | 1581 | 477 | -304 | -39.0% |
| C - Window and Door Replacement, Removal or Alteration (sanding events) (Routine) | 22 | 15.0 - 62000 | 3720 | 440 | 20.5 - 10200 | 1845 | 603 | 162 | 36.8% |
| C - Window and Door Replacement, Removal or Alteration (sanding events) (Mod LSWP) | 10 | 50.2 - 91200 | 11358 | 650 | 19.8 - 10800 | 2959 | 723 | 74 | 11.3% |
| F - Surface Preparation (sanding) (Routine) | 18 | 27.0 - 4560 | 1087 | 399 | 48.7 - 14600 | 2408 | 922 | 523 | 131% |
| F - Surface Preparation (sanding) (Mod LSWP) | 19 | 54.2 - 14600 | 2505 | 852 | 58.7 - 5440 | 856 | 383 | -469 | -55.1% |
| Surface Preparation (sanding plaster) (Routine) | 4 | 3300 - 4560 | 3787 | 3748 | 186 - 2350 | 1414 | 1015 | -2733 | -72.9% |
| Surface Preparation (sanding plaster) (Mod LSWP) | 4 | 642 - 5440 | 1954 | 1258 | 253 - 888 | 476 | 425 | -833 | -66.2% |
| Surface Preparation (sanding wood) (Routine) | 14 | 27.0 - 1630 | 508 | 247 | 48.7 - 14600 | 2714 | 895 | 648 | 263% |
| Surface Preparation (sanding wood) (Mod LSWP) | 15 | 54.2 - 14600 | 2652 | 767 | 58.7 - 5440 | 958 | 372 | -395 | -51.5% |
| Sawing & Cutting LBP Covered Surfaces (plaster) (Routine) | 16 | 17.8 - 11400 | 1622 | 522 | 30.1 - 1470 | 479 | 281 | -241 | -46.1% |
| Sawing & Cutting LBP Covered Surfaces (plaster) (Mod LSWP) | 17 | 13.4 - 898 | 227 | 105 | 14.9 - 118 | 42.1 | 32.8 | -72.2 | -68.7% |
| Sawing & Cutting LBP Covered Surfaces (plaster) (LSWP) | 4 | 210 - 2090 | 998 | 748 | 402 - 535 | 459 | 456 | -292 | -39.0% |
| Sawing & Cutting LBP Covered Surfaces (wood) (Routine) | 16 | 10.0 - 6440 | 727 | 177 | 16.3 - 2880 | 568 | 306 | 129 | 73.2% |
| Sawing & Cutting LBP Covered Surfaces (wood) (Mod LSWP) | 15 | 108 - 12300 | 2861 | 922 | 27.0 - 3000 | 661 | 284 | -638 | -69.2% |

n = no. of pairs of samples, where a pair equals one pre-work sample and one post-work sample from approximately the same location.

Figure 4.9A - DIFFERENCE BETWEEN POST-WORK DUST SAMPLES AND PRE-WORK DUST SAMPLES BASED ON GM OF ALL SURFACES SAMPLED BY SCENARIO





FIGURE 4.9B - DIFFERENCE BETWEEN POST-WORK DUST SAMPLES AND PRE-WORK DUST SAMPLES BASED ON GM OF ALL SURFACES SAMPLED BY SCENARIO



**TABLE 4.16
CHANGES IN SETTLED DUST LEAD LOADINGS IN WORK AREA BY WORK PRACTICE**

| Surface | Work Practice | Number | Pre-Work Results ($\mu\text{g}/\text{ft}^2$) | | Post-Work Results ($\mu\text{g}/\text{ft}^2$) | | Change |
|--------------------------|-----------------------|--------|---|----------------|--|----------------|-------------------|
| | | | Range | Geometric Mean | Range | Geometric Mean | |
| Floor in Work Area | EPA/HUD LSWP | 6 | 150 - 1210 | 238 | 36.2 - 1470 | 196 | -18% |
| | MOD LSWP | 52 | 13.4 - 6080 | 246 | 18.2 - 11400 | 202 | -18% |
| | Routine Work Practice | 48 | <10 - 4700 | 231 | 26.4 - 9,700 | 258 | 12% |
| | All | 106 | <10 - 6080 | 239 | 18.2 - 11400 | 225 | -6% |
| Window Sill in Work Area | EPA/HUD LSWP | 8 | 213 - 2090 | 995 | 354 - 1140 | 694 | -30% |
| | MOD LSWP | 25 | 136 - 108000 | 1,779 | 19.9 - 10,800 | 355 | -80% ^a |
| | Routine Work Practice | 21 | 366 - 62000 | 2,454 | 79.4 - 10,200 | 783 | -68% ^a |
| | All | 54 | 136 - 108000 | 1,850 | 19.9 - 10800 | 553 | -71% ^a |

a = Statistically significant change ($p < 0.05$)

**TABLE 4.17
PBZ AIR SAMPLING RESULTS SUMMARIZED BY PROPERTY**

| Location | PBZ ($\mu\text{g}/\text{m}^3$) | | | | |
|--|----------------------------------|------------|------|------|-----|
| | n | Range | Mean | GM | GSD |
| All (LC_{XRF} (mg/cm^2) n = 65 , Range = 0.9 - 25.3 , Mean = 10.0) | 65 | 2.0 - 1700 | 122 | 26.4 | 5.4 |
| Roselle, IL (LC_{XRF} (mg/cm^2) n = 6 , Range = 2.9 - 22.7 , Mean = 14.1) | 6 | 2.5 - 20.0 | 6.2 | 4.2 | 2.4 |
| Wallingford, CT (LC_{XRF} (mg/cm^2) n = 14 , Range = 1.0 - >9.9 ¹ , Mean = 8.4) | 14 | 6.5 - 1700 | 278 | 82.2 | 4.8 |
| Farmington, CT (LC_{XRF} (mg/cm^2) n = 11 , Range = 0.9 - >9.9 ¹ , Mean = 6.8) | 11 | 8.0 - 926 | 213 | 58.8 | 5.7 |
| Cheshire, CT (LC_{XRF} (mg/cm^2) n = 3 , Range = 1.0 - 1.4 , Mean = 1.1) | 3 | 9.0 - 12.0 | 10.2 | 10.1 | 1.2 |
| Milwaukee, WI (LC_{XRF} (mg/cm^2) n = 31 , Range = 2.3 - 25.3 , Mean = 11.9) | 31 | 2.0 - 420 | 51.7 | 18.6 | 4.3 |

LC_{XRF} = Lead content of affected surfaces based on measurement by X-Ray Fluorescence (XRF) instrumentation.

¹ The XRF measurement reported (9.9) was the maximum reportable limit for the XRF instrument used.

FIGURE 4.10 - COMPARISON OF THE GM OF PBZ AIR SAMPLING RESULTS BY PROPERTY TO THE GM OF THE PBZ AIR SAMPLING RESULTS FOR ALL PROPERTIES




TABLE 4.18
AREA (DURING) AIR SAMPLING RESULTS SUMMARIZED BY PROPERTY

| Location | AREA (DURING) ($\mu\text{g}/\text{m}^3$) | | | | |
|--|--|------------|-------|------|-----|
| | n | Range | Mean | GM | GSD |
| All (LC_{XRF} (mg/cm^2) n = 74 , Range = 0.9 - 25.3 , Mean = 10.5) | 74 | 1.0 - 1780 | 85.5 | 17.6 | 4.8 |
| Roselle, IL (LC_{XRF} (mg/cm^2) n = 6 , Range = 2.9 - 22.7 , Mean = 14.1) | 6 | 2.0 - 3.0 | 2.2 | 2.1 | 1.2 |
| Wallingford, CT (LC_{XRF} (mg/cm^2) n = 15 , Range = 1.0 - >9.9 ¹ , Mean = 8.0) | 15 | 8.0 - 1780 | 209.9 | 56.6 | 4.5 |
| Farmington, CT (LC_{XRF} (mg/cm^2) n = 14 , Range = 0.9 - >9.9 ¹ , Mean = 6.9) | 14 | 8.0 - 868 | 135 | 39.2 | 5.1 |
| Cheshire, CT (LC_{XRF} (mg/cm^2) n = 3 , Range = 1.0 - 1.4 , Mean = 1.1) | 3 | 7.5 - 9.0 | 8.2 | 8.1 | 1.1 |
| Milwaukee, WI (LC_{XRF} (mg/cm^2) n = 36 , Range = 2.3 - 25.3 , Mean = 13.1) | 36 | 1.5 - 411 | 34.6 | 12.0 | 3.9 |

LC_{XRF} = Lead content of affected surfaces based on measurement by X-Ray Fluorescence (XRF) instrumentation.

¹The XRF measurement reported (9.9) was the maximum reportable limit for the XRF instrument used.

FIGURE 4.11 - COMPARISON OF THE GM OF AREA (DURING) AIR SAMPLING RESULTS BY PROPERTY TO THE GM OF THE AREA (DURING) AIR SAMPLING RESULTS FOR ALL PROPERTIES





TABLE 4.19
SURFACE DUST SAMPLING RESULTS SUMMARIZED BY PROPERTY

| Activity | n | Pre ($\mu\text{g}/\text{ft}^2$) | | | Post ($\mu\text{g}/\text{ft}^2$) | | | Δ GM | % Change |
|-----------------|-----|-----------------------------------|----------|---------|------------------------------------|---------|--------|-------------|----------|
| | | Range | Mean | GM | Range | Mean | GM | | |
| All Activities | 241 | 10 - 108000 | 3422.56 | 499.07 | 15 - 39200 | 1185.23 | 320.39 | -178.68 | -36% |
| Roselle, IL | 22 | 26.1 - 36000 | 2445.96 | 354.53 | 14.9 - 5380 | 402.48 | 86.70 | -267.83 | -76% |
| Wallingford, CT | 45 | 33.2 - 108000 | 12415.67 | 1621.83 | 19.8 - 39200 | 2581.67 | 452.75 | -1169.08 | -72% |
| Farmington, CT | 44 | 10 - 10800 | 840.18 | 127.58 | 15.9 - 10800 | 883.09 | 188.39 | 60.81 | 48% |
| Cheshire, CT | 12 | 13.4 - 898 | 269.28 | 93.60 | 18.2 - 183 | 52.37 | 39.85 | -53.75 | -57% |
| Milwaukee, WI | 118 | 27 - 19600 | 1365.90 | 644.25 | 27 - 11400 | 1038.33 | 541.46 | -102.79 | -16% |

n = no. of pairs of samples, where a pair equals one pre-work sample and one post-work sample from approximately the same location.

FIGURE 4.12 - DIFFERENCE BETWEEN POST-WORK DUST SAMPLES AND PRE-WORK DUST SAMPLES BY LOCATION BASED ON GM OF ALL SURFACES SAMPLED



**TABLE 4.20
CHANGES IN SETTLED DUST LEAD LOADINGS IN WORK AREA BY PROPERTY**

| Surface Tested | Location | # of Paired Samples | % with Increase | Pre-Work ($\mu\text{g}/\text{ft}^2$) | | Post-Work ($\mu\text{g}/\text{ft}^2$) | | % Change |
|----------------|-------------|---------------------|-----------------|--|----------------|---|----------------|-------------------|
| | | | | Range | Geometric Mean | Range | Geometric Mean | |
| Floor | Cheshire | 6 | 50% | 13.4 - 231 | 38 | 18 - 61.5 | 30 | -21% |
| | Farmington | 17 | 82% | <10 - 4320 | 64 | 27 - 4320 | 163 | 155% ^a |
| | Milwaukee | 38 | 63% | 54.3 - 6080 | 512 | 69 - 11400 | 657 | 28% |
| | Roselle | 6 | 17% | 76.5 - 824 | 218 | 27 - 111 | 51 | -77% ^a |
| | Wallingford | 27 | 44% | 33.2 - 4700 | 440 | 26 - 9700 | 290 | -34% |
| | All | 94 | 57% | <10 - 6080 | 270 | 18 - 11400 | 281 | 4% |
| Window Sill | Cheshire | 3 | 0% | 554 - 898 | 725 | 20 - 183 | 75 | -90% ^a |
| | Farmington | 8 | 38% | 366 - 10800 | 1,103 | 59 - 10800 | 793 | -28% |
| | Milwaukee | 20 | 20% | 136 - 19600 | 1,337 | 82 - 3300 | 603 | -55% ^a |
| | Roselle | 5 | 20% | 252 - 1960 | 739 | 79 - 1140 | 298 | -60% ^a |
| | Wallingford | 10 | 0% | 1360 - 108000 | 23,491 | 120 - 10200 | 1,758 | -93% ^a |
| | All | 46 | 17% | 136 - 108000 | 2,172 | 20 - 183 | 645 | -70% ^a |

a = Statistically significant change ($p < 0.05$)

**TABLE 4.21
CALCULATED 8-HOUR TIME WEIGHTED AVERAGE (TWA) EXPOSURES TO LEAD DURING RENOVATION AND REMODELING ACTIVITIES**


| Date | Location | ID | TWA | OSHA Exposure Criteria (µg/m ³) | | | | | | X Over PEL | Activity with the greatest contribution to exposure |
|-----------|-----------------|----------|--------------|---|-----|----|-------------|--------------|-------------|--|---|
| | | | | 8-hour TWA* (µg/m ³) | PEL | AL | AL Exceeded | PEL Exceeded | | | |
| 25-Jan-06 | Roselle, IL | Worker 1 | 2.5 | 0.8 | 50 | 30 | NO | NO | 0.02 | | |
| 25-Jan-06 | Roselle, IL | Worker 2 | 11.3 | 6.6 | 50 | 30 | NO | NO | 0.13 | | |
| 26-Jan-06 | Roselle, IL | Worker 3 | 4.0 | 3.6 | 50 | 30 | NO | NO | 0.07 | | |
| 18-Apr-06 | Wallingford, CT | Worker 1 | 343.9 | 100 | 50 | 30 | YES | YES | 2.01 | Sanding window stops with belt sander-Routine Work Practices = 545 µg/m ³ | |
| 18-Apr-06 | Wallingford, CT | Worker 2 | 427.2 | 141 | 50 | 30 | YES | YES | 2.81 | Sanding doors - Routine Work Practices = 1050 µg/m ³ | |
| 18-Apr-06 | Wallingford, CT | Worker 3 | 47.3 | 12.2 | 50 | 30 | NO | NO | 0.24 | | |
| 18-Apr-06 | Wallingford, CT | Worker 4 | 70.7 | 18.0 | 50 | 30 | NO | NO | 0.36 | | |
| 18-Apr-06 | Wallingford, CT | Worker 5 | 865.7 | 197 | 50 | 30 | YES | YES | 3.93 | Sanding stair stringers with belt sander - Routine Work Practices = 1700 µg/m ³ | |
| 19-Apr-06 | Wallingford, CT | Worker 1 | 60.0 | 9.0 | 50 | 30 | NO | NO | 0.18 | | |
| 19-Apr-06 | Wallingford, CT | Worker 2 | 17.0 | 1.9 | 50 | 30 | NO | NO | 0.04 | | |
| 19-Apr-06 | Wallingford, CT | Worker 3 | 6.5 | 0.8 | 50 | 30 | NO | NO | 0.02 | | |
| 19-Apr-06 | Wallingford, CT | Worker 4 | 38.0 | 4.8 | 50 | 30 | NO | NO | 0.10 | | |
| 20-Apr-06 | Farmington, CT | Worker 1 | 565.7 | 112 | 50 | 30 | YES | YES | 2.24 | Window jamb removal and sanding with orbital sander - Routine Work Practices = 926 µg/m ³ | |
| 20-Apr-06 | Farmington, CT | Worker 2 | 393.7 | 127 | 50 | 30 | YES | YES | 2.54 | Window jamb removal and sanding with shrouded orbital sander- Mod LSWP = 805 µg/m ³ | |
| 20-Apr-06 | Farmington, CT | Worker 3 | 27.3 | 9.1 | 50 | 30 | NO | NO | 0.18 | | |
| 20-Apr-06 | Farmington, CT | Worker 4 | 122.3 | 38.7 | 50 | 30 | YES | NO | 0.77 | Window jamb removal and sanding with orbital sander - Routine Work Practices = 324 µg/m ³ | |
| 21-Apr-06 | Cheshire, CT | Worker 1 | 12.0 | 1.2 | 50 | 30 | NO | NO | 0.02 | | |
| 21-Apr-06 | Cheshire, CT | Worker 2 | 9.0 | 0.8 | 50 | 30 | NO | NO | 0.02 | | |
| 21-Apr-06 | Cheshire, CT | Worker 3 | 9.5 | 1.1 | 50 | 30 | NO | NO | 0.02 | | |
| 2-May-06 | Milwaukee, WI | Worker 1 | 5.0 | 1.6 | 50 | 30 | NO | NO | 0.03 | | |
| 2-May-06 | Milwaukee, WI | Worker 2 | 36.4 | 20.5 | 50 | 30 | NO | NO | 0.41 | | |
| 2-May-06 | Milwaukee, WI | Worker 3 | 238.9 | 68.7 | 50 | 30 | YES | YES | 1.37 | Floor sanding (not ventilated) - Mod LSWP = 420 µg/m ³ | |
| 3-May-06 | Milwaukee, WI | Worker 1 | 6.3 | 3.5 | 50 | 30 | NO | NO | 0.07 | | |
| 3-May-06 | Milwaukee, WI | Worker 2 | 2.0 | 0.7 | 50 | 30 | NO | NO | 0.01 | | |
| 3-May-06 | Milwaukee, WI | Worker 3 | 9.1 | 2.5 | 50 | 30 | NO | NO | 0.05 | | |
| 3-May-06 | Milwaukee, WI | Worker 4 | 93.7 | 32.8 | 50 | 30 | YES | NO | 0.66 | Sanding window frames/surface prep w/ belt sander (not ventilated)- Mod LSWP = 140 µg/m ³ | |
| 3-May-06 | Milwaukee, WI | Worker 5 | 21.9 | 10.3 | 50 | 30 | NO | NO | 0.21 | | |
| 4-May-06 | Milwaukee, WI | Worker 1 | 4.0 | 2.2 | 50 | 30 | NO | NO | 0.04 | | |
| 4-May-06 | Milwaukee, WI | VOIDED | | | | | | | | | |
| 4-May-06 | Milwaukee, WI | Worker 3 | 7.1 | 4.2 | 50 | 30 | NO | NO | 0.08 | | |
| 4-May-06 | Milwaukee, WI | Worker 4 | 145.0 | 15.4 | 50 | 30 | NO | NO | 0.31 | | |
| 5-May-06 | Milwaukee, WI | Worker 1 | 17.0 | 3.6 | 50 | 30 | NO | NO | 0.07 | | |
| 5-May-06 | Milwaukee, WI | Worker 2 | 28.3 | 9.0 | 50 | 30 | NO | NO | 0.18 | | |
| 5-May-06 | Milwaukee, WI | Worker 3 | 126.7 | 36.4 | 50 | 30 | YES | NO | 0.73 | Window modification w/ hand sanding (147 µg/m ³) & ceiling prep w/ hand sanding (95 µg/m ³) - Routine Work Practices | |
| 5-May-06 | Milwaukee, WI | Worker 4 | 24.8 | 7.0 | 50 | 30 | NO | NO | 0.14 | | |
| 5-May-06 | Milwaukee, WI | Worker 5 | 34.8 | 12.6 | 50 | 30 | NO | NO | 0.25 | | |

Exposure monitoring was conducted over the entire activity period, including set-up, work, and clean-up.

* The 8-hour TWA assumes no exposures to lead during periods where no work was being conducted.

Results reported as "<" were recorded as actual values when calculating TWAs.

Figure 4.13
ESTIMATED PROJECTED 8-HOUR TIME WEIGHTED AVERAGE (TWA) EXPOSURES BY WORK PRACTICE



5.0 DISCUSSION OF FINDINGS

Based on the findings analyzed and reported in this report, the following observations are offered:

1. **Property Selection.** The properties included in this study had higher lead levels than is typical for housing containing LBP. Most painted surfaces, even in older housing, are not coated with LBP. HUD estimates that only 2% of all interior painted surfaces contain LBP. With time, this percentage continues to fall.^{xiii} The properties included in this study were selected because of the prevalence of LBP on surfaces, and the amount of lead measured in painted surfaces using XRF instrumentation. Many of the R&R activities assessed were on surfaces and fixtures that contained $>9.9 \text{ mg/cm}^2$ (the highest level reported by the XRF instrument used in the Farmington and Cheshire properties).
2. **R&R Professionals.** The R&R professionals who performed the work during this project had all attended and successfully completed the EPA/HUD curriculum for *Lead Safety for Remodeling, Repair, & Painting* prior to participating in the project. Different R&R professionals participated in the project each day that work was performed and evaluated in Roselle, IL and Milwaukee, WI. The same R&R contractor team performed the work evaluated in Wallingford, Farmington and Cheshire, CT. While the variability in the R&R professionals who participated in the project may cause variability in how work is performed, it did provide a more representative sample of R&R work performed throughout the United States. Therefore, the results from this project are likely to be more representative of work conducted by R&R contractors throughout the country than if a single contractor crew was used for the entire project.
3. **Time Required to Complete Work.** Wall and ceiling demolition was the most time-consuming activity averaging approximately four person-hours to complete. EPA/HUD LSWP was the most time-consuming work practice to employ, averaging approximately 2.3 person-hours to complete an activity using these practices. This was approximately twice the labor effort when compared to using routine work practices.
4. **Air Sampling Results.** The personal breathing zone and area air measurements during routine renovation and remodeling (R&R) activities were widely distributed, ranging from less than the LOQ to $1,700 \text{ } \mu\text{g/m}^3$ for PBZ air samples and from less than the LOQ to $1,780 \text{ } \mu\text{g/m}^3$ for area air samples. Approximately half (49%) of these air measurements were below the analytical LOQ. When the data is segregated by specific activity and task, the following observations can be made:
 - a. Seven typical R&R activities generated relatively low levels of airborne lead dust, based on the mean and GM of the PBZ and area air samples.
 - o Wall and ceiling removal (demolition)
 - o Wall and ceiling modification
 - o Window replacement (no sanding involved)
 - o Cabinet removal (kitchen and bath work)
 - o Floor covering removal and baseboard removal
 - o Sawing into wood and plaster covered by LPB

The geometric mean (GM) of the PBZ air sampling results measured during these activities ranged from 5 $\mu\text{g}/\text{m}^3$ to 23 $\mu\text{g}/\text{m}^3$. The GM for all PBZ air samples collected was 26.4 $\mu\text{g}/\text{m}^3$.

The GM of the area air sampling results measured inside the work area during these activities ranged from 3 2.9 $\mu\text{g}/\text{m}^3$ to 17.1 $\mu\text{g}/\text{m}^3$. The GM for all area air samples collected inside work areas during work was 17.6 $\mu\text{g}/\text{m}^3$.

As shown in Tables 4.6 and 4.7, the GM of the PBZ and area air sampling results for these activities were less than the GM for the PBZ and area air sampling results for all activities.

- b. Three activities generated higher airborne lead dust concentrations. These were:
- o Window alteration
 - o Window and door replacement, removal and alteration (sanding involved)
 - o Surface preparation (sanding)

The GM of the PBZ air sampling results measured during these activities ranged from 23.8 $\mu\text{g}/\text{m}^3$ to 225 $\mu\text{g}/\text{m}^3$. The GM for all PBZ air samples collected was 26.4 $\mu\text{g}/\text{m}^3$.

The GM of the area air sampling results measured inside the work area during these activities ranged from 21.9 $\mu\text{g}/\text{m}^3$ to 161 $\mu\text{g}/\text{m}^3$. The GM for all area air samples collected inside work areas during work was 17.6 $\mu\text{g}/\text{m}^3$.


As shown in Tables 4.6 and 4.7, the GM of the PBZ and area air sampling results for these activities were greater than the GM for the PBZ and area air sampling results for all activities.

- c. Sanding and cutting tasks generated the highest levels of airborne lead dust. The GM of the PBZ air sampling results measured during sanding and cutting tasks was 58.7 $\mu\text{g}/\text{m}^3$. The GM of the area air sampling results measured during sanding and cutting tasks was 33.3 $\mu\text{g}/\text{m}^3$. The GM of the PBZ (58.7 $\mu\text{g}/\text{m}^3$) and area air sampling (33.3 $\mu\text{g}/\text{m}^3$) results for these activities was greater than the GM for the PBZ and area air sampling results for all activities (26.4 $\mu\text{g}/\text{m}^3$ for PBZ samples and 17.6 $\mu\text{g}/\text{m}^3$ for area air samples). Of these tasks, sanding wood surfaces, including surface preparation and window alteration, generated the highest levels of airborne dust (PBZ GM = 205 $\mu\text{g}/\text{m}^3$; area GM = 78.3 $\mu\text{g}/\text{m}^3$).
- d. Work practices. Employing a modified set of the EPA/HUD LSWP (Mod LSWP) reduces airborne lead dust concentrations when compared to routine work practices. In comparing the GM of the PBZ air sampling results, the GM for samples collected during events where Mod LSWP were used were 23% lower than the GM for all PBZ air samples collected. (GM = 20.3 $\mu\text{g}/\text{m}^3$ for Mod LSWP PBZ; GM = 26.4 $\mu\text{g}/\text{m}^3$ for all PBZ samples). For comparison, the GM for PBZ air samples collected during events where Routine work practices were used, were 86% higher than the GM for all PBZ air samples collected. (GM = 203 $\mu\text{g}/\text{m}^3$ for Routine PBZ; GM = 26.4 $\mu\text{g}/\text{m}^3$ for


all PBZ samples). Using the EPA/HUD LSWP reduced airborne concentration even lower (80% lower than the GM for all PBZ air samples).

In reviewing the results from all activities and all work practice, the trend was a reduction in airborne lead based on the PBZ sample results as more dust control techniques were employed (Routine > Mod LSWP > EPA LSWP), as would be expected.

- e. Misting surfaces with water during work appears to reduce airborne lead dust substantially. Misting was used during work in 11% of the events evaluated where Mod LSWP were employed, and 100% of the events evaluated where EPA/HUD LSWP were employed. Events where misting was used (n = 10, GM = 5.5 $\mu\text{g}/\text{m}^3$) showed an 84% reduction in airborne lead dust levels when compared to events where no misting was used (n = 55, GM = 35.5 $\mu\text{g}/\text{m}^3$). Area air samples showed the same trend. Figure 5.1 shows the effect misting during work had on airborne lead levels measured by PBZ and area air sampling.



- f. Tools used. Airborne lead dust levels were substantially lower when only hand tools (n = 14, GM = 12.1 $\mu\text{g}/\text{m}^3$) or only hand sanding (n = 7, GM = 19 $\mu\text{g}/\text{m}^3$) was used when compared to events where one or more power tools were used. Ventilated (shrouded) tools connected to HEPA filter-equipped vacuum cleaners (n = 5, GM = 91.2 $\mu\text{g}/\text{m}^3$) were used in 20% of the events conducted using Mod LSWP. Power tool sanding conducted using shrouded tools showed a 64% to 65% reduction when compared to sanding using non-shrouded belt sanders (n = 4, GM = 252 $\mu\text{g}/\text{m}^3$) and orbital sanders (n = 6, GM = 257 $\mu\text{g}/\text{m}^3$), respectively.



- g. Results by property. When comparing the PBZ air sampling results by property, the lowest levels of airborne lead dust were measured during work in Roselle, IL (n = 6, GM = 4.2 $\mu\text{g}/\text{m}^3$), and the highest levels were measured in Farmington, CT (n = 11, GM = 59 $\mu\text{g}/\text{m}^3$) and Wallingford, CT (n = 14, GM = 82 $\mu\text{g}/\text{m}^3$). The largest sample data set was collected from the Milwaukee, WI property (n = 31, GM = 18.6 $\mu\text{g}/\text{m}^3$), which represented the median for airborne lead dusts levels measured during this project. Area air samples collected inside work areas during work activities showed the same trend.
- h. Worker exposures. The PBZ samples collected during this project represented 35 workers' 8-hour TWA exposures. The 8-hour TWA exposures measured during this project ranged from 0.7 $\mu\text{g}/\text{m}^3$ to 197 $\mu\text{g}/\text{m}^3$. Twenty-six (74%) of the calculated 8-hour TWA exposures were less than the OSHA Action Level of 30 $\mu\text{g}/\text{m}^3$; and 29 (83%) were below the PEL of 50 $\mu\text{g}/\text{m}^3$. The highest calculated TWA exposures were measured on workers performing window repair work in Farmington, CT and during sanding activities.

Worker's 8-hour TWA exposures for a specific activity and work practice were estimated using the mean PBZ result and mean sampling time for each activity. In projecting exposures, it is estimated that the following work can be performed for an 8-hour work shift without exceeding the OSHA Action Level as an 8-hour TWA:

- Wall and ceiling demolition;
- Wall and ceiling modification;
- Window replacement with no sanding;
- Cabinet removal; and,

- Baseboard removal;

It is critical to note that these are estimated exposures intended to show relative exposures based on activity. Because of the limited number of samples collected, they are not intended to be used as objective data for negative exposure assessments required under OSHA standards. Full-shift personal breathing zone air monitoring is the only acceptable method for verifying that worker exposures are below the Action Level.

1. **Surface Dust Sampling Results.** The wipe samples collected to measure lead loading in surface dust before and after renovation and remodeling (R&R) activities were conducted were widely distributed. Pre-work sample results from all surfaces ranged from less than the LOQ to 108,000 $\mu\text{g}/\text{ft}^2$. The results of pre-work samples collected from floors within work areas ranged from less than the LOQ to 6,080 $\mu\text{g}/\text{ft}^2$. For comparison, pre-intervention levels measured on floors in 424 occupied residential dwellings as part of a HUD-funded study ranged from 0.1 $\mu\text{g}/\text{ft}^2$ to 9,407 $\mu\text{g}/\text{ft}^2$.^{xiii} The results of pre-work samples collected from window sills within work areas ranged from 110 $\mu\text{g}/\text{ft}^2$ to 91,200 $\mu\text{g}/\text{ft}^2$. Again, for comparison, pre-intervention levels measured on window sills in 424 occupied residential dwellings as part of a HUD-funded study ranged from 3 $\mu\text{g}/\text{ft}^2$ to 129,188 $\mu\text{g}/\text{ft}^2$.^{xiv} Based on comparison to known reference points, the pre-work levels measured during this project should be considered to be representative of potential work conditions.

Post-work sample results for all surfaces ranged from less than the LOQ to 39,200 $\mu\text{g}/\text{ft}^2$ *. Comparing the paired (n = 241 pairs) pre-work (GM = 499 $\mu\text{g}/\text{ft}^2$) and post-work (GM = 320 $\mu\text{g}/\text{ft}^2$) surface lead dust measurements from all surfaces sampled within work areas showed a 35% reduction in lead dust loading following completion of work.

When the data is segregated by specific activity and work practice (i.e. scenario), the following observations can be made:

- a. Results by activity. (Please see Table 4.9) When comparing the paired pre-work and post-work surface lead dust measurements from all surfaces sampled within work areas, all activities showed a reduction in lead dust loading following completion of work.

When comparing the paired results based on the surface tested (floor or window sill), a statistically significant reduction (-42%) was measured in the floor samples following wall and ceiling modifications (n = 26). There was no increase in lead dust in floor samples overall, nor was there any statistically significant increase in floor samples after any activity, including those with large sample sizes. Significant reductions were measured on window sills following wall and ceiling modifications (-79%, n = 14), cabinet removal (-78%, n = 5), and surface preparation (-65%, n = 5). No activity produced an increase in the sill loading samples; all activities produced lower readings. Many of the changes were larger, and several were significant. For all activities combined, the reduction in surface dust on window sills (n = 54) was statistically significant (-71%).

* This result represents a composite sample from a sill and trough.

- b. Results by work practice. (Please see Table 4.15) When comparing the paired pre-work and post-work surface lead dust measurements from all surfaces sampled, Mod LSWP (n = 120) and EPA/HUD LSWP (n = 21) showed a reduction in lead dust loading following completion of all R&R activities (-53% and -31%, respectively). Reductions in lead dust loading were measured for all activities performed using Routine work practices, except window alteration with no sanding involved (27.0% increase, n = 7) and sawing into wood or plaster (82% increase, n = 8).


Regardless of the work practice employed, window alteration with no sanding involved showed an increase in lead dust loading (21.8% increase, n = 11).

When comparing the paired results based on the surface tested (floor or window sill)(Table 4.16), statistically significant reductions were measured on window sills following Mod LSWP (-80%, n = 25) and routine work practices (-68%, n = 21). For all work practices combined, the reduction in surface dust on window sills was significant (-71%, n = 54).

Based on the results of the wipe samples collected, it appears that Mod LSWP and EPA/HUD LSWP are more effective at reducing lead loading in surface dust than Routine work practices.

- c. Preparation and clean-up methods used. Figure 5.3 shows a comparison of different cleaning methods employed and their effect on the reduction of lead dust loading in work areas. When comparing the paired pre-work and post-work surface lead dust measurements from all surfaces sampled, the use of HEPA filter-equipped vacuum cleaners (n = 121) and the use of wet wiping or Swiffer® mops (n = 97) appear to have the most significant effect on reducing lead loading in surface dust. These techniques showed a reduction of lead surface dust of 53% and 46.5%, respectively.

When comparing the use of drop cloths, reductions in the lead loading in surface dust were observed when either re-useable drop cloths or disposable drop cloths were used. However, a more significant reduction was shown in events where disposable drop cloths were used (-79%, n = 237) compared to events where only re-useable drop cloths were used (-41%, n = 66).



- d. Results by property. (Please see Table 4.19) The differences between pre-work and post-work surface lead dust loading was similar for the Roselle (-75.5%, n = 22), Wallingford (-72%, n = 45) and Cheshire (-57%, n = 12) properties when comparing measurements from all surfaces. While sampling in Milwaukee showed a reduction in lead dust loading (-16%, n = 118), the reduction was smaller than the overall reduction for all activities at all properties (-36%, n = 241). The Farmington property showed a 48% (n = 44) increase in lead loading in surface dust.

When comparing the paired results based on the surface tested (floor or window sill)(Table 4.20), statistically significant reductions were measured on the floors in Roselle (-77%, n = 6) and on the window sills in Cheshire (-90%, n = 3), Milwaukee (-55%, n = 20), Roselle (-60%, n = 5), and Wallingford (-93%, n = 10). For all properties combined, the reduction in surface dust on window sills was statistically significant (-70%, n = 46), and there was no statistically significant overall increase in dust on floors.

6.0 CONCLUSIONS

Responses to three fundamental questions that formulated the objectives of this project are offered as follows:

1. **Do typical renovation and remodeling activities create lead hazards?** Renovation and remodeling activities evaluated during this project did not create new lead dust hazards. In all of the properties tested, pre-work (baseline) testing identified surface dust levels that exceeded current HUD/EPA criteria for floors and window sills. Although post-work lead loading measurements were widely distributed, the post-work samples collected from all surfaces were lower than the pre-work dust samples in 8 of the 9 (89%) of the R&R activities evaluated. When considering lead dust loading on surfaces throughout a single property, results showed that overall 4 of the 5 properties evaluated (80%) had lower lead dust levels when the R&R contractors completed the work than when they arrived.
2. **When applying EPA's lead-safe work practices to a set of typical renovation and remodeling activities, are surface lead hazards ($>40 \mu\text{g}/\text{ft}^2$ on floors, $>250 \mu\text{g}/\text{ft}^2$ on window sills), or airborne hazards ($> 50 \mu\text{g}/\text{m}^3$ in the air) created?** When comparing the paired pre-work and post-work surface lead dust measurements from all surfaces sampled, 89% of the R&R activities evaluated showed a reduction in lead dust loading following completion of the activities.

When comparing the paired pre-work and post-work surface lead dust measurements, Mod LSWP and EPA/HUD LSWP, on average, showed reduction in lead dust loading. Reductions in lead dust loading were measured for all activities performed using Routine work practices, except sawing into wood or plaster.

When comparing the paired results based on the surface tested (floor or window sill), statistically significant reductions were measured on window sills following Mod LSWP and routine work practices. For all work practices combined, the reduction in surface dust on window sills was significant.

Based on the results of the wipe samples collected during this project, surface dust loading results exceeded $40 \mu\text{g}/\text{ft}^2$ on floors and $250 \mu\text{g}/\text{ft}^2$ on window sills for all work practices employed – Routine, Mod LSWP, and LSWP. The results do indicate that Mod LSWP and EPA/HUD LSWP are more effective at reducing lead loading in surface dust than Routine work practices.

Employing a modified set of the EPA/HUD LSWP (Mod LSWP) reduces airborne lead dust concentrations when compared to Routine work practices. Using the EPA/HUD LSWP reduced airborne concentration even lower. In reviewing the results from all activities and all work practice, the trend was a reduction in airborne lead based on the personal breathing zone (PBZ) air sample results as more dust control techniques were employed (Routine $>$ Mod LSWP $>$ EPA/HUD LSWP), as would be expected.

Misting surfaces with water during work appears to significantly reduce airborne lead dust. Events where misting was used showed an 84% reduction in airborne lead dust levels when compared to events where no misting was used.

Airborne lead dust levels were significantly lower when only hand tools or only hand sanding were used when compared to events where one or more power tools were used. Ventilated (shrouded) tools connected to HEPA filter-equipped vacuum cleaners showed a 64% to 65% reduction when compared to sanding using non-shrouded orbital sanders and belt sanders, respectively.

When comparing the use of drop cloths, reductions in the lead loading in surface dust were observed when either re-useable drop cloths or disposable drop cloths were used. However, a more significant reduction was shown in events where disposable drop cloths were used. The use of HEPA filter-equipped vacuum cleaners and wet wiping or Swiffer® mops during post-work clean-up showed the most significant effect on reducing lead loading in surface dust.

3. **Do modified lead-safe work practices reduce lead exposures below the PEL?** The PBZ samples collected during this project represented 35 workers' 8-hour TWA exposures. The 8-hour TWA exposures measured during this project ranged from 0.7 $\mu\text{g}/\text{m}^3$ to 197 $\mu\text{g}/\text{m}^3$. Twenty-six (74%) of the calculated 8-hour TWA exposures were less than the OSHA Action Level of 30 $\mu\text{g}/\text{m}^3$; and 29 (83%) were below the PEL of 50 $\mu\text{g}/\text{m}^3$.

It was difficult to assess and estimate 8-hour TWA exposures by work practice for the following reasons:

- Each worker performed multiple work activities using different work practices in a work day; and,
- A smaller number of events using EPA/HUD LSWP were evaluated when compared to the number of events where Routine or Mod LSWP were used.

Estimating 8-hour TWA exposures by activity, regardless of work practice, showed that the following tasks can be performed for an entire work shift without exceeding the OSHA Action Level:

- Wall and ceiling demolition;
- Wall and ceiling modification;
- Window replacement with no sanding;
- Cabinet removal; and,
- Baseboard removal.

It is likely that window alterations with no sanding involved may be conducted using routine practices for shorter periods of time (e.g. less than 5 hours during a shift) without exceeding the OSHA PEL. Activities involving sanding resulted in projected 8-hour TWA exposures that exceeded the OSHA Action Level and PEL.

In most instances, those employees' whose 8-hour TWA exposures exceeded the action level performed some type of sanding activity during their work day. Using ventilated (shrouded) tools connected to HEPA filter-equipped vacuum cleaners and other dust

control measures during sanding reduced airborne concentrations of lead dust, in most cases. During window and door alterations where sanding was conducted, employing some level of dust control showed a reduction in airborne dust levels, in most cases, when compared to sanding with no controls. Performing surface preparation activities using dust control devices or techniques also showed a reduction over uncontrolled sanding during surface preparation.

Employing a modified set of the EPA/HUD LSWP (Mod LSWP) reduces airborne lead dust concentrations when compared to routine work practices. Using the EPA/HUD LSWP reduced airborne concentration even lower. In reviewing the results from all activities and all work practices, the trend was a reduction in airborne lead based on the personal breathing zone (PBZ) air sample results as more dust control techniques were employed (Routine > Mod LSWP > EPA/HUD LSWP), as would be expected.

Recommendations for future studies or research include:

1. By comparison, fewer events where EPA/HUD LSWP were employed were evaluated during this project. A robust comparison of work practices relative to EPA/HUD LSWP is somewhat limited by the number of samples collected during activities where this work practice was employed. Additional evaluations of R&R events where EPA/HUD LSWP are employed would provide a better comparison of work practices.
2. Notably higher levels of airborne lead dust were measured in air samples collected at the Wallingford, CT and Farmington, CT as compared to the other three properties. The work performed in these properties and the lead concentrations in the paint in these properties were similar to the other properties, as measured by XRF. While outside the scope of this study, a more detailed analysis of the data collected from these two properties could be performed to research possible causes of this difference.
3. Notably higher airborne levels of airborne lead dust were measured during sanding or sawing on wood surfaces as compared to sanding or sawing on plaster surfaces. While outside of the scope of this study, informal discussions with coatings experts hypothesized that surface absorption of the paint differs between wood and plaster and may account for how much paint dust is generated during these activities. However, no published research on this issue was identified at the time this report was prepared.

7.0 REFERENCES

- ⁱ National Association of Home Builders, Request For Proposal Lead-Safe Work Practices Survey Project, November 2005.
- ⁱⁱ Federal Register: June 6, 2005 (Volume 70, Number 107)
- ⁱⁱⁱ “Air contaminants,” Code of Federal Regulations, Title 29, Part 1910.1000, 71 FR 16673, April 3, 2006.
- ^{iv} “Lead,” Code of Federal Regulations, Title 29, Part 1926.62, 71 FR 16674, April 3, 2006.
- ^v Provided by Andrew Teague, CIH, of Analytics Corporation (Analytics). Analytics is the AIHA accredited laboratory that analyzed the air samples for the Project.
- ^{vi} OSHA Technical Manual, Section II, Chapter 1, Appendix II:1-6. Sampling And Analytical Errors (SAE's)
- ^{vii} Mulhausen, J.R., and J. Damiano, Quantitative Exposure Data: Interpretation, Decision Making, and Statistical Tools. In *A Strategy for Assessing and Managing Occupational Exposures*, AIHA Press, Fairfax, VA, 1998.
- ^{viii} IBID.
- ^{ix} Wilson, J., et al, *Evaluation of HUD-funded Lead Hazard Control Treatments at 6 Years Post-intervention*, Environmental Research, pp 237-248, Volume 102, Issue 2, October 2006.
- ^x IBID
- ^{xi} “Air contaminants,” Code of Federal Regulations, Title 29, Part 1910.1000, 71 FR 16673, April 3, 2006.
- ^{xii} Jacobs, D.E., et al, *The Prevalence of Lead-Based Paint Hazards in U.S. Housing*, Environmental Health Perspectives, pp A599 – A606, Volume 110, No. 10, October 2002.
- ^{xiii} Wilson, J., et al, *Evaluation of HUD-funded Lead Hazard Control Treatments at 6 Years Post-intervention*, Environmental Research, pp 237-248, Volume 102, Issue 2, October 2006.
- ^{xiv} IBID

EXHIBIT A

FIELD DATA COLLECTION TOOL

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|----------|---------------|
|----------|-------|----|----------|---------------|

| | | |
|---------------------|------------------|--|
| Site Address | Street Address | |
| | City, State, Zip | |

| | | | | | |
|-----------------------|---------------|--|------------------|--------------------------------|--|
| Structure Type | Single Family | | Apartment | Approx. Construction Date (Yr) | |
| | Town House | | Other (describe) | Approx. Square Footage | |
| | Condomium | | | No. of Separate Rooms | |

Location of Work w/in structure

| Lead Content of Affected Surfaces | | | | Work Statistics | | | |
|-----------------------------------|------------|--------|--------|-----------------|------------|-----------|--|
| Surface | XRF Result | and/or | % Lead | No. of Workers | Start Time | Stop Time | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

Tools and Equipment Used
Use attached checklist

Pre-Work Sampling

| Air Sampling | | | | | | | | | | |
|--|----------------------------|---------|---------|----------|----------|----------|------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| | | | | | | | | | | |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Air Sampling | | | | | | | | | | |
|--|----------------------------|---------|---------|----------|----------|----------|------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| | | | | | | | | | | |

Post-Work Sampling

| Air Sampling | | | | | | | | | | |
|--|----------|---------|---------|----------|----------|----------|------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| | | | | | | | | | | |

Wipe Sampling

| Wipe Sampling | | | | | |
|---|----------|---------|--------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| | | | | | |

| Wipe Sampling | | | | | |
|---|----------|---------|--------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| | | | | | |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|--|
| Hygienist | |
| Activity | |
| Work Practice | |

| | |
|---|--|
| DATE | |
| LOCATION | |
| SCENARIO | |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | |
| Tape | |
| Utility Knife | |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | |
| N100 Respirator | |
| Gloves | |
| Disposable Shoe Covers | |
| Safety Glasses | |
| Disposable Towels | |

EXHIBIT B

PROJECT DATA SUMMARIES

Date 1/25/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|------------------------------------|---------------|
| | 1 | C1 | Window Replacement - jambs removed | Routine |

| | | |
|---------------------|------------------|-------------|
| Site Address | City, State, Zip | Roselle, IL |
|---------------------|------------------|-------------|

| | | | | | | |
|-----------------------|-------------------------------------|---------------|--------------------------|------------------|--------------------------------|------|
| Structure Type | <input checked="" type="checkbox"/> | Single Family | <input type="checkbox"/> | Apartment | Approx. Construction Date (Yr) | 1920 |
| | <input type="checkbox"/> | Town House | <input type="checkbox"/> | Other (describe) | Approx. Square Footage | 2000 |
| | <input type="checkbox"/> | Condomium | <input type="checkbox"/> | | No. of Separate Rooms | 8 |

| | |
|--|-------------|
| Location of Work w/in structure | Living Room |
|--|-------------|

| Lead Content of Affected Surfaces | | | Work Statistics | | |
|-----------------------------------|------------|--------|--------------------------|------------|-----------|
| Surface | XRF Result | % Lead | No. of Workers | Start Time | Stop Time |
| Window jamb LR | 17.837 | and/or | 2 | 9:00 | 12:30 |
| Window jamb LR | 20.125 | | Total Time (hrs) | 3.5 | |
| Window sash LR | 2 | | Tools and Equipment Used | | |
| Use attached checklist | | | | | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
|--|----------------------------|--------------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|----|
| P-C1-012406-001 | -A-Area | Kitchen | 20B | 3:05 | 3:01 | 5:20 | 2.958 | 135 | 2.958 | 399.33 | <5 |
| P-C1-012406-002 | -A-Area | Living Room | 21B | 3:15 | 3:01 | 5:30 | 2.998 | 135 | 2.998 | 404.73 | <5 |
| P-C1-012506-005 | -A-OS** | Stair Landing (Up) | 30B | 9:12 | 2 | 1:10 | 1.91 | 248 | 1.91 | 473.68 | <4 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
|--|----------------------------|-------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|----|
| D-C1-012506-003 | -A-Area | Living Room | 27B | 9:05 | 3:02 | 12:30 | 1.52 | 205 | 1.52 | 311.6 | <6 |
| D-C1-012506-00 | -A-Area | Kitchen | 20B | 9:10 | 3:01 | | | void | | | |
| D-C1-012506-00 | -A-PBZ | Worker 1 | 74B | 10:07 | 3:01 | | | void | | | |
| D-C1-012506-007 | -A-PBZ | Worker 2 | 29B | 10:07 | 3:03 | 12:28 | 3.47 | 141 | 3.03 | 427.23 | 20 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
|--|----------|-------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|----|
| C-C1-012506-016 | -A-Area | Living Room | 29B | 4:55 | 2:97 | 8:57 | 3:00 | 242 | 2.97 | 718.74 | <3 |

* - Post-work PBZ only required for scenarios where clean-up or other activities with exposures different than "during work" activities and that work will take at least 135 min (2-hrs, 15-min)

Wipe Sampling

Date 1/25/2016 Collected by

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
|---|----------|--------------------|--------------|---------------------------------|------------------------------|------|
| P-C1-012406-003 | -W-Area | Living Room | Window Well | Metal | 0.75 | 1640 |
| P-C1-012406-004 | -W-Area | Living Room | Window Sill | Wood | 1.00 | 836 |
| P-C1-012406-005 | -W-Area | Living Room | Floor | Wood | 1.00 | 258 |
| P-C1-012406-006 | -W-OS | Stair Landing (Up) | Floor | Wood | 1.00 | 117 |

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
|---|----------|--------------------|--------------|---------------------------------|------------------------------|------|
| C-C1-012506-020 | -W-Area | Living Room | Window Well | Metal | 0.75 | 22.4 |
| C-C1-012506-021 | -W-Area | Living Room | Window Sill | Wood | 1.00 | 79.4 |
| C-C1-012506-022 | -W-Area | Living Room | Floor | Wood | 1.00 | 80.6 |
| C-C1-012506-023 | -W-OS | Stair Landing (Up) | Floor | Wood | 1.00 | 113 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

WORK PRACTICE AND TOOL CHECKLIST

| | |
|------------------|------------------------|
| Hygienist | |
| Activity | WINDOW REMOVAL W/JAMBS |
| Work Prac | ROUTINE |

| | |
|--------------------------------------|-------------|
| DATE | 1/25/2006 |
| LOCATION | Roselle, IL |
| SCENARIO | C1 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and va | |
| Rope | |
| Barrier Tape | |
| Saw Horses | X |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | X |
| 4 or 6-mil Plastic Sheeting or | X |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power | |
| Heavy Duty Garbage Bags | X |
| Sawsall | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | |
| Wet Wipe Surfaces or Use | |
| Reusable Wet Mop w/ One | |
| Reusable Wet Mop w/ Two | |
| Use Swifter or Similar Disposable | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | X |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | |
| Safety Glasses | |
| Disposable Towels | X |

Date 1/25/2006

Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|---------------------------------------|---------------|
| | 2 | C3 | Window Replacement --jamb not removed | HUD/EPA LSWP |

| | | |
|--------------|------------------|-------------|
| Site Address | City, State, Zip | Roselle, IL |
|--------------|------------------|-------------|

| | | | | | |
|----------------|---|---------------|------------------|--------------------------------|------|
| Structure Type | x | Single Family | Apartment | Approx. Construction Date (Yr) | 1920 |
| | | Town House | Other (describe) | Approx. Square Footage | 2000 |
| | | Condomium | | No. of Separate Rooms | 8 |

| | | | | | |
|-----------------------------------|------------|-----------------------------|--------|-------------------------------|------|
| Location of Work w/in structure | | Bedroom # 1 and Bedroom # 3 | | | |
| Lead Content of Affected Surfaces | | | | Work Statistics | |
| Surface | XRF Result | and/or | % Lead | No. of Workers | 2 |
| window jamb BR #1 | 19.214 | | | Start Time | 2:00 |
| window jamb BR #1 | 22.717 | | | Stop Time | 5:30 |
| window sash BR #3 | 6.212 | | | Total Time (hrs) | 3.5 |
| window jamb BR #3 | 14.839 | | | Tools and Equipment Used | |
| window jamb BR #3 | 6.507 | | | Use attached checklist | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-##-A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|---|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P- C3-012506-001 -A-Area | Bedroom #1 | 26B | 9:08 | 3.01 | 11:27 | 2.97 | 135 | 2.97 | 400.95 | <5 |
| P- C3-012506-002 -A-Area | Bedroom #3 | 21B | 9:06 | 3.15 | 11:25 | 3.33 | 135 | 3.15 | 425.25 | <5 |
| P- C3-012506-008 -A-OS** | Top of stair landing | 30B | 1:12 | 2.02 | 4:40 | 2.04 | 308 | 2.02 | 622.16 | <3 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-##-A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|---|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D- C3-012506-009 -A-Area | Upstairs Hall | 27B | 1:59 | 3.01 | 4:36 | 3.11 | 155 | 3.01 | 466.55 | <4 |
| D- C3-012506-012 -A-Area | Bedroom # 1 | 26B | 1:58 | 3.04 | 4:35 | 3.07 | 153 | 3.04 | 465.12 | <4 |
| D- C3-012506-010 -A-PBZ | Worker 1 | 29B | 1:55 | 3.02 | 4:32 | 2.97 | 147 | 2.97 | 436.59 | <5 |
| D- C3-012506-011 -A-PBZ | Worker 2 | 19B | 1:55 | 3.03 | 4:25 | 2.95 | 140 | 2.95 | 413.00 | <5 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-##-A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|---|---------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C- C3-012506-014 -A-Area | Upstairs Hall | 27B | 4:45 | 3.11 | 9:04 | 2.99 | 259 | 2.99 | 774.41 | <3 |
| C- C3-012506-015 -A-Area | Bedroom #1 | 26B | 4:45 | 3.07 | 9:01 | 3.07 | 256 | 3.07 | 785.92 | <3 |

Wipe Sampling

Date 1/25/2016

Collected by

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|----------------------|-------------|--------------|---------------------------------|------------------------------|
| P- C3-012406-005 -W-Area | Bedroom #3 | Window Well | Metal | 0.611 | 8540 |
| P- C3-012406-006 -W-Area | Bedroom #2 | Window Sill | Wood | 0.64 | 1960 |
| P- C3-012406-007 -W-Area | Bedroom #1 | Floor | Tile | 1.00 | 202 |
| P- C3-012406-008 -W-OS | Top of stair landing | Floor | Wood | 0.96 | 141 |
| P- C3-012406-009 -W-Area | Bedroom #3 | Window Sill | Wood | 0.69 | 878 |

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|----------------------|-------------|--------------|---------------------------------|------------------------------|
| C- C3-012506-030 -W-Area | Bedroom #3 | Window Well | Wood | 0.50 | 108 |
| C- C3-012506-031 -W-Area | Bedroom #2 | Window Sill | Wood | 0.67 | 792 |
| C- C3-012506-032 -W-Area | Bedroom #1 | Floor | Tile | 1.00 | 36.2 |
| C- C3-012506-033 -W-OS | Top of Stair Landing | Floor | Wood | 0.96 | 254 |
| C- C3-012506-034 -W-Area | Bedroom #3 | Window Sill | Wood | 0.38 | 1140 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

WORK PRACTICE AND TOOL CHECKLIST

| | |
|------------------|--------------------------|
| Hygienist | |
| Activity | WINDOW REMOVAL W/O JAMBS |
| Work Prac | LSWP |

| | |
|--------------------------------------|-------------|
| DATE | 1/26/2006 |
| LOCATION | Roselle, IL |
| SCENARIO | C3 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and va | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | X |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or | X |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | X |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power | |
| Heavy Duty Garbage Bags | |
| Sawsall | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use | X |
| Reusable Wet Mop w/ One | |
| Reusable Wet Mop w/ Two | X |
| Use Swiffer or Similar Disposable | X |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | |
| Safety Glasses | |
| Disposable Towels | X |

Date 1/26/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|---------------------------------------|---------------|
| | 3 | C2 | Window Replacement --jamb not removed | modified LSWP |

Site Address

| | | | | | |
|----------------|-------------------------------------|---------------|------------------|--------------------------------|------|
| Structure Type | <input checked="" type="checkbox"/> | Single Family | Apartment | Approx. Construction Date (Yr) | 1920 |
| | <input type="checkbox"/> | Town House | Other (describe) | Approx. Square Footage | 2000 |
| | <input type="checkbox"/> | Condomium | | No. of Separate Rooms | 8 |

| Location of Work w/in structure | | Living Room/Dining Room | | | | |
|--|------------|-------------------------|--------|--------------------------|-------|--|
| Lead Content of Affected Surfaces | | | | | | |
| Surface | XRF Result | and/or | % Lead | Work Statistics | | |
| window jamb Dining Room | 13.597 | | | No. of Workers | 1 | |
| | | | | Start Time | 8:30 | |
| | | | | Stop Time | 10:48 | |
| | | | | Total Time (hrs) | 2.25 | |
| | | | | Tools and Equipment Used | | |
| <i>Use attached checklist</i> | | | | | | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C- C1012506-016 | Living Room | 29B | 4:55 | 2.97 | 8:57 | 3.00 | 242 | 2.97 | 718.74 | <3 |
| P- B2-012606-001 | Kitchen | 27B | 8:01 | 3.01 | 10:51 | 2.88 | 170 | 2.88 | 489.6 | <3 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D- C2-012606007 | -A-Area Dining Room | 30B | 8:35 | 3.04 | 11:25 | 2.97 | 170 | 2.97 | 504.9 | <4 |
| D- C2-012606006 | -A-PBZ* Worker 3 | 20B | 8:53 | 3.07 | 11:20 | 2.57 | 147 | 2.57 | 377.79 | <5 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|---------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C- C2-012606-020 | -A-Area Living Room | 30B | 11:30 | 2.97 | 1:50 | 2.92 | 135 | 2.92 | 394.2 | <5 |

Wipe Sampling

Date 1/25/2016 Collected by

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|---------------------|-------------|--------------|---------------------------------|------------------------------|
| P- C2-012606-002 | -W-Area Dining Room | Window Well | Metal | 0.56 | 36000 |
| P- C2-012606-003 | -W-Area Dining Room | Window Sill | Wood | 0.67 | 609 |
| P- C2-012606-004 | -W-Area Dining Room | Floor | Wood | 1.00 | 340 |
| P- C2-012606-005 | -W-OS Kitchen | Floor | Tile | 1.00 | 534 |

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|---------------------|-------------|--------------|---------------------------------|------------------------------|
| C- C2-012606-021 | -W-Area Dining Room | Window Well | Metal | 0.61 | 5380 |
| C- C2-012606-022 | -W-Area Dining Room | Window Sill | Wood | 0.40 | 326 |
| C- C2-012606-023 | -W-Area Dining Room | Floor | Wood | 1.00 | 42.6 |
| C- C2-012606-024 | -W-OS Kitchen | Floor | Tile | 1.00 | 77.6 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

WORK PRACTICE AND TOOL CHECKLIST

| | |
|------------------|--------------------------|
| Hygienist | |
| Activity | WINDOW REMOVAL W/O JAMBS |
| Work Prac | Modified LSWP |

| | |
|--------------------------------------|-------------|
| DATE | 1/26/2006 |
| LOCATION | Roselle, IL |
| SCENARIO | C2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and va | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power | |
| Sawzall | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use | X |
| Reusable Wet Mop w/ One | |
| Reusable Wet Mop w/ Two | |
| Use Swiffer or Similar Disposable | X |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | |
| Safety Glasses | |
| Disposable Towels | X |

Date Hygienist

| Scenario | Event ID | Activity | Work Practice |
|----------|----------|--|---------------|
| | 4 B2 | Install Recessed Lighting in Ceiling Plaster | modified LSWP |

Site Address City, State, Zip

| | | | | |
|----------------|---|------------------|--------------------------------|------|
| Structure Type | <input checked="" type="checkbox"/> Single Family | Apartment | Approx. Construction Date (Yr) | 1920 |
| | <input type="checkbox"/> Town House | Other (describe) | Approx. Square Footage | 2000 |
| | <input type="checkbox"/> Condominium | | No. of Separate Rooms | 8 |

| Location of Work w/in structure | | Kitchen Ceiling | | Work Statistics | |
|-----------------------------------|--|-----------------|--------|-------------------------------|-------|
| Lead Content of Affected Surfaces | | XRF Result | % Lead | No. of Workers | 1 |
| Surface | | 2.859 | | Start Time | 11:11 |
| Ceiling | | | | Stop Time | 1:45 |
| | | | | Total Time (hrs) | 2.75 |
| | | | | Tools and Equipment Used | |
| | | | | Use attached checklist | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P- B2-012606-001 -A-Area | Kitchen | 27B | 8:01 | 3.01 | 10:51 | 2.88 | 170 | 2.88 | 489.6 | <4 |
| C- C2-012606-020 -A-OS** | Living Room | 30B | 11:30 | 2.97 | 1:50 | 2.92 | 135 | 2.92 | 394.2 | <5 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D- B2-012606-019 -A-Area | Kitchen | 27B | 10:55 | 2.88 | 1:48 | 2.84 | 173 | 2.84 | 491.32 | <4 |
| D- B2-012606-018 -A-PBZ | Worker 3 | 74B | 11:21 | 3.05 | 1:45 | 2.82 | 144 | 2.82 | 406.08 | <5 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C- B2-012606-026 -A-Area | Kitchen | 27B | 1:55 | 2.84 | 4:20 | 2.84 | 145 | 2.84 | 411.8 | <5 |

* - Post-work PBZ only required for scenarios where clean-up or other activities with exposures different than "during work" activities and that work will take at least 135 min (2-hrs, 15-min)

Wipe Sampling

Date Collected by

| Pre-Work Wipe Sampling | | | | | |
|---|-------------|-------------|--------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| P- B2-012606-008 -W-Area | Kitchen | Window Sill | Wood | 0.61 | 252 |
| P- B2-012606-009 -W-Area | Kitchen | Counter Top | Formica | 1.00 | 60.3 |
| P- B2-012606-010 -W-Area | Kitchen | Floor | Tile | 1.00 | 95.1 |
| P- B2-012606-011 -W-Area | Kitchen | Floor | Tile | 1.00 | 824 |
| C- C2-012606-023 -W-Area | Dining Room | Floor | Wood | 1.00 | 42.6 |

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

| Post-Work Wipe Sampling | | | | | |
|---|-------------|-------------|--------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| C- B2-012606-028 -W-Area | Kitchen | Window Sill | Wood | 0.58 | 101 |
| C- B2-012606-029 -W-Area | Kitchen | Counter Top | Formica | 1.00 | 18.6 |
| C- B2-012606-030 -W-Area | Kitchen | Floor | Tile | 1.00 | 45.2 |
| C- B2-012606-031 -W-Area | Kitchen | Floor | Tile | 1.00 | 27 |
| C- B2-012606-032 -W-OS | Dining Room | Floor | Wood | 1.00 | 53.1 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

WORK PRACTICE AND TOOL CHECKLIST

| | |
|------------------|-------------------------------------|
| Hygienist | |
| Activity | INSTALLATION OF LIGHTING IN CEILING |
| Work Prac | Modified LSWP |

| | |
|--------------------------------------|-------------|
| DATE | 1/26/2006 |
| LOCATION | Roselle, IL |
| SCENARIO | B2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and va | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or | X |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe | |
| Work Practices/Tools | |
| Hammers/Prybars | |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power | |
| Hand Saw | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use | X |
| Reusable Wet Mop w/ One | |
| Reusable Wet Mop w/ Two | |
| Use Swiffer or Similar Disposable | X |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | |
| Safety Glasses | |
| Disposable Towels | X |

Date 1/26/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|-----------------------------|---------------|
| | 5 | G2 | Install Door In Closet Wall | Modified LSWP |

| | | |
|---------------------|------------------|-------------|
| Site Address | City, State, Zip | Roselle, IL |
|---------------------|------------------|-------------|

| | | | | |
|-----------------------|---|------------------|--------------------------------|------|
| Structure Type | <input checked="" type="checkbox"/> Single Family | Apartment | Approx. Construction Date (Yr) | 1920 |
| | <input type="checkbox"/> Town House | Other (describe) | Approx. Square Footage | 2000 |
| | <input type="checkbox"/> Condominium | | No. of Separate Rooms | 8 |

| Location of Work w/in structure | | Bedroom # 1 closet | |
|--|------------|--------------------|-------------------------------|
| Lead Content of Affected Surfaces | | | |
| Surface | XRF Result | and/or | Work Statistics |
| Closet Wall | 2.851 | | |
| | | | |
| | | | |
| | | % Lead | No. of Workers |
| | | | 1 |
| | | | Start Time |
| | | | 3:05 |
| | | | Stop Time |
| | | | 4:35 |
| | | | Total Time (hrs) |
| | | | 1.25 |
| | | | Tools and Equipment Used |
| | | | Use attached checklist |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P- -G2012606-012 -A-Area | BR #1 | 19B | 10:10 | 3.09 | 1:10 | 2.99 | 180 | 2.99 | 538.2 | <4 |
| P- -G2012606-013 -A-OS** | Upstairs Hall | 26B | 3:23 | 3.05 | 5:52 | 2.99 | 149 | 2.99 | 445.51 | <4 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D- -G2012606-025 -A-Area | BR #1 By Closet | 19B | 3:19 | 2.99 | 5:45 | 3.00 | 156 | 2.99 | 466.44 | <4 |
| D- -G2012606-027 -A-PBZ | Worker 3 | 74B | 3:15 | 3.03 | 5:35 | 3.05 | 140 | 3.03 | 424.20 | 7 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|-----------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C- -G2012606-041 -A-Area | BR #1 By Closet | 19B | 5:45 | 3.00 | 8:50 | 2.92 | 185 | 2.92 | 540.2 | <4 |

Wipe Sampling

Date 1/25/2016 Collected by

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|---------------|----------------|--------------|---------------------------------|------------------------------|
| P- -G2012606-014 -W-Area | Closet BR # 1 | Built In Shelf | Wood | 1.00 | 325 |
| P- -G2012606-015 -W-Area | Closet BR # 1 | Cabinet | Wood | 1.00 | 54.5 |
| P- -G2012606-016 -W-Area | Closet BR # 1 | Floor | Wood | 1.00 | 76.5 |
| P- -G2012606-017 -W-OS | Upstairs Hall | Floor | Tile | 1.00 | 26.1 |

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|---------------|----------------|--------------|---------------------------------|------------------------------|
| C- -G2012606-037 -W-Area | Closet BR # 1 | Built In Shelf | Wood | 1.00 | 15.2 |
| C- -G2012606-038 -W-Area | Closet BR # 1 | Cabinet | Wood | 1.00 | 14.9 |
| C- -G2012606-039 -W-Area | Closet BR # 1 | Floor | Wood | 1.00 | 111 |
| C- -G2012606-040 -W-OS | Upstairs Hall | Floor | Tile | 1.00 | 16.8 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

WORK PRACTICE AND TOOL CHECKLIST

| | |
|------------------|--------------------------------|
| Hygienist | |
| Activity | INSTALLATION OF DOOR IN CLOSET |
| Work Prac | MODIFIED LSWP |

| | |
|--------------------------------------|-------------|
| DATE | 1/26/2006 |
| LOCATION | Roselle, IL |
| SCENARIO | G2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and va | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power | |
| Heavy Duty Garbage Bags | |
| Sawsall | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use | X |
| Reusable Wet Mop w/ One | |
| Reusable Wet Mop w/ Two | |
| Use Swiffer or Similar Disposable | X |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | |
| Safety Glasses | |
| Disposable Towels | X |

Date: 4/19/2006 Hygienist: _____

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|-----------------------------|---------------|
| | 6 | A1 | CEILING AND WALL DEMOLITION | ROUTINE |

Site Address: City, State, Zip: WALLINGFORD, CT

| Structure Type | Single Family | Apartment | Approx. Construction Date (Yr) | 1910 |
|----------------|---------------|------------------|--------------------------------|------|
| | Town House | Other (describe) | Approx. Square Footage | 2300 |
| | Condomium | DUPLEX | No. of Separate Rooms | 16 |

| Location of Work w/in structure | | 2ND FLOOR REAR BATHROOM | | |
|-----------------------------------|------------|-------------------------|--------------------------|-----------------|
| Lead Content of Affected Surfaces | | | | Work Statistics |
| Surface | XRF Result | % Lead | No. of Workers | 1 |
| Wall A | 8.7 | | Start Time | 9:15 |
| Wall B | 7.0 | | Stop Time | 10:05 |
| Wall D | 5.6 | | Total Time (hrs) | 0.8 |
| Ceiling | 4.7 | | Tools and Equipment Used | |
| Use attached checklist | | | | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|------------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P-A1-041806-65 | -A-Area 2ND FL BATH - CENTER | 16666 | 17:02 | 2.63 | 17:39 | 2.67 | 37 | 2.63 | 97.3 | <21.0 |
| D-0-041806-55 | -A-Area 2ND FL KITCHEN | 16608 | 15:20 | 2.54 | 17:43 | 2.59 | 143 | 2.54 | 363.2 | <6 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| AREA SAMPLE VOIDED, CASSETTE BECAME DISCONNECTED FROM SAMPLING TRAIN | | | | | | | | | | |
| D-A1-041906-78 | -A-PBZ WORKER | 18105 | 9:12 | 2.57 | 10:05 | 2.53 | 53 | 2.53 | 134.1 | 17 |
| D-0-041906-69 | -A-OS** 2ND FL KITCHEN | 16608 | 8:42 | 2.51 | 11:14 | 2.34 | 173 | 2.51 | 434.2 | <5 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|------------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-A1-041906-79 | -A-Area 2ND FL BATH - CENTER | 18110 | 10:17 | 2.51 | 11:21 | 2.5 | 64 | 2.5 | 160 | <12.0 |

Wipe Sampling

Date: 4/19/2006 Collected by: _____

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|-------------------------------------|---------|--------------|---------------------------------|------------------------------|
| P-A1-041906-100 | -W-Area 2ND FL BATH | FLOOR | CERAMIC TILE | 1.00 | 1200 |
| P-A1-041906-102 | -W-Area 2ND FL BATH | SILL | WOOD | 0.25 | 44000 |
| C-D1-041806-62 | -W-Area* 2ND FLOOR KITCHEN - B WALL | FLOOR | LINOLEUM | 1.00 | 136 |
| C-D1-041806-63 | -W-Area* 2ND FLOOR KITCHEN - D WALL | FLOOR | LINOLEUM | 1.00 | 173 |
| C-D1-041806-64 | -W-Area* 2ND FLOOR KITCHEN - B WALL | SILL | WOOD | 0.25 | 2840 |

* - used as preliminary (background) outside samples for this scenario

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|----------------------------------|---------|--------------|---------------------------------|------------------------------|
| C-A1-041906-12 | -W-Area 2ND FL BATH | FLOOR | CERAMIC TILE | 1.00 | 503 |
| C-A1-041906-13 | -W-Area 2ND FL BATH | SILL | WOOD | 0.25 | 896 |
| C-0-041906-17 | -W-OS 2ND FLOOR KITCHEN - B WALL | FLOOR | LINOLEUM | 1.00 | 206 |
| C-0-041906-18 | -W-OS 2ND FLOOR KITCHEN - D WALL | FLOOR | LINOLEUM | 1.00 | 36.7 |
| C-0-041906-19 | -W-OS 2ND FLOOR KITCHEN - B WALL | SILL | WOOD | 0.25 | 520 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-----------------------------|
| Hygienist | |
| Activity | CEILING AND WALL DEMOLITION |
| Work Practice | ROUTINE |

| | |
|---|-----------------|
| DATE | 4/19/2006 |
| LOCATION | WALLINGFORD, CT |
| SCENARIO | A1a |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | X |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | X |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swifter or Similar Disposable Wet Mop | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

Date: 4/18/2006 Hygienist: _____

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|-----------------------------|---------------|
| | 7 | A2 | WALL AND CEILING DEMOLITION | MODIFIED LSWP |

Site Address: City, State, Zip: WALLINGFORD, CT

| Structure Type | Single Family | Apartment | Approx. Construction Date (Yr) |
|----------------|---------------|------------------|--------------------------------|
| | Town House | Other (describe) | 1910 |
| | Condomium | DUPLEX | Approx. Square Footage: 2300 |
| | | | No. of Separate Rooms: 16 |

| Location of Work w/in structure | | Lead Content of Affected Surfaces | | Work Statistics | |
|---------------------------------|--|-----------------------------------|------------|-----------------|-------------------------------|
| BASEMENT STAIRWELL | | Surface | XRF Result | % Lead | No. of Workers |
| | | Wall A | 1.3 | | 1 |
| | | Wall B | 1.0 | | Start Time: 1508 |
| | | Ceiling | 1.5 | | Stop Time: 1600 |
| | | | | | Total Time (hrs): 1 |
| | | | | | Tools and Equipment Used |
| | | | | | <i>Use attached checklist</i> |

Pre-Work Sampling

| Sample No. | Location/Employee/Activity | Pump ID | Time On | FR (ipm) | Time Off | FR (ipm) | Total Time (min) | Lowest FR (ipm) | Volume (L) | Result (ug/m ³) |
|----------------|----------------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P-A2-041806-02 | -A-Area BASEMENT STAIRWELL | 17185 | 7:45 | 2.60 | 8:37 | 2.58 | 52 | 2.58 | 134.2 | <15 |
| P-A2-041806-05 | -A-OS 1ST FL LIVING ROOM - NORTH | 17164 | 8:01 | 2.59 | 8:38 | 2.58 | 36 | 2.53 | 91.1 | <22 |
| P-A2-041806-06 | -A-OS 1ST FL LIVING ROOM - SOUTH | 16669 | 8:05 | 2.59 | 8:38 | 2.69 | 38 | 2.62 | 99.6 | <20 |
| D-U041806-23 | -A-OS 1ST FL KITCHEN | 17865 | 11:40 | 2.63 | 14:50 | 2.66 | 190 | 2.63 | 499.7 | <4 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. | Location/Employee/Activity | Pump ID | Time On | FR (ipm) | Time Off | FR (ipm) | Total Time (min) | Lowest FR (ipm) | Volume (L) | Result (ug/m ³) |
|----------------|----------------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-A2-041806-17 | -A-Area BASEMENT STAIRWELL | 17185 | 15:19 | 2.58 | 16:02 | 2.58 | 43 | 2.58 | 110.9 | 52 |
| D-A2-041806-49 | -A-PBZ WORKER | 18110 | 15:08 | 2.50 | 16:00 | 2.53 | 52 | 2.5 | 130.0 | 92 |
| D-A2-041806-43 | -A-OS 1ST FL LIVING ROOM - NORTH | 17184 | 15:08 | 2.57 | 16:10 | 2.56 | 62 | 2.56 | 158.7 | 37 |
| D-A2-041806-44 | -A-OS 1ST FL LIVING ROOM - SOUTH | 16669 | 15:09 | 2.54 | 16:10 | 2.50 | 61 | 2.5 | 152.5 | 38 |
| D-U041806-47 | -A-OS 1ST FL KITCHEN | 17856 | 15:12 | 2.64 | 17:23 | 2.58 | 133 | 2.58 | 343.1 | <6 |

Post-Work Sampling

| Sample No. | Location | Pump ID | Time On | FR (ipm) | Time Off | FR (ipm) | Total Time (min) | Lowest FR (ipm) | Volume (L) | Result (ug/m ³) |
|----------------|----------------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-A2-041806-57 | -A-Area BASEMENT STAIRWELL | 18110 | 17:04 | 2.65 | 18:04 | 2.66 | 60 | 2.65 | 159.0 | <13.0 |
| C-A2-041806-60 | -A-OS 1ST FL LIVING ROOM - NORTH | 17184 | 16:21 | 2.56 | 17:23 | 2.55 | 62 | 2.55 | 158.1 | <13.0 |
| C-A2-041806-59 | -A-OS 1ST FL LIVING ROOM - SOUTH | 16669 | 16:21 | 2.50 | 17:23 | 2.61 | 62 | 2.50 | 155.0 | <13.0 |

Wipe Sampling

Date: 4/18/2006 Collected by: _____

| Pre-Work Wipe Sampling | | | | | |
|------------------------|---|---------|--------------|---------------------------------|------------------------------|
| Sample No. | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| P-A2-041806-04 | -W-Area BASEMENT STAIRWELL | LEDGE | WOOD | 1.00 | 1430 |
| P-A2-041806-05 | -W-Area BASEMENT STAIRWELL | TREAD | WOOD | 0.67 | 3540 |
| P-D1-041806-01 | -W-Area* 1ST FL LIVING ROOM - NEAR B WALL | FLOOR | CARPET | 1.00 | 346 |
| P-D1-041806-02 | -W-Area* 1ST FL LIVING ROOM - NEAR D WALL | FLOOR | CARPET | 1.00 | 40.3 |

* - used as preliminary (background) outside samples for this scenario

| Post-Work Wipe Sampling | | | | | |
|-------------------------|---|---------------------------------|--------------|---------------------------------|------------------------------|
| Sample No. | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| C-A2-041806-76 | -W-Area BASEMENT STAIRWELL | LEDGE | WOOD | 1.00 | 469 |
| C-A2-041806-77 | -W-Area BASEMENT STAIRWELL | PLYWOOD (INSTALLED OVER STAIRS) | WOOD | 0.67 | 203 |
| C-U041806-85 | -W-Area* 1ST FL LIVING ROOM - NEAR B WALL | FLOOR | CARPET | 1.00 | 1590 |
| C-U041806-86 | -W-Area* 1ST FL LIVING ROOM - NEAR D WALL | FLOOR | CARPET | 1.00 | 74 |

* - used as outside samples for this scenario

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-----------------------------|
| Hygienist | |
| Activity | CEILING AND WALL DEMOLITION |
| Work Practice | MODIFIED LSWP |

| | |
|---|-----------------|
| DATE | 4/18/2006 |
| LOCATION | WALLINGFORD, CT |
| SCENARIO | A2a |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | X |
| Shovels | X |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-------------------------------|
| Hygienist | |
| Activity | WALL AND CEILING MODIFICATION |
| Work Practice | MODIFIED LSWP |

| | |
|---|-----------------|
| DATE | 4/18/2006 |
| LOCATION | WALLINGFORD, CT |
| SCENARIO | B2a |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swifter or Similar Disposable Wet Mop | |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | X |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

Date 4/18/2006 Hygienist

| Event | ID | Activity | Work Practice |
|----------|----|----------|----------------------|
| Scenario | 9 | C1 | REMOVING WINDOW SASH |
| | | | ROUTINE |

| | | |
|--------------|------------------|-----------------|
| Site Address | City, State, Zip | WALLINGFORD, CT |
|--------------|------------------|-----------------|

| | | | | |
|----------------|---------------|------------------|--------------------------------|------|
| Structure Type | Single Family | Apartment | Approx. Construction Date (Yr) | 1910 |
| | Town House | Other (describe) | Approx. Square Footage | 2300 |
| | Condomium | DUPLEX | No. of Separate Rooms | 16 |

| | | | | |
|-----------------------------------|------------|-----------------------|------------------|-------------------------------|
| Location of Work w/in structure | | 2ND FLOOR LIVING ROOM | | |
| Lead Content of Affected Surfaces | | | | |
| Surface | XRF Result | and/or | % Lead | Work Statistics |
| WINDOW CASING | >9.9 | | No. of Workers | 1 |
| WINDOW SASH | >9.9 | | Start Time | 15:20 |
| WINDOW SILL | >9.9 | | Stop Time | 16:20 |
| | | | Total Time (hrs) | 1 |
| | | | | Tools and Equipment Used |
| | | | | Use attached checklist |

Pre-Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
|--|----------------------------|------------------------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|-----|
| P-C1-041806-09 | -A-Area | 2ND FL - LIVING ROOM - NORTH | 18122 | 8:20 | 2.52 | 8:56 | 2:56 | 36 | 2.52 | 90.7 | <22 |
| P-C1-041806-10 | -A-Area | 2ND FL - LIVING ROOM - SOUTH | 18105 | 8:25 | 2.55 | 9:01 | 2:59 | 36 | 2.55 | 91.8 | <22 |
| P-D1-041806-11 | -A-Area* | 2ND FL KITCHEN | 16608 | 8:26 | 2.64 | 9:03 | 2:66 | 37 | 2.64 | 97.7 | <21 |

* - sample used as an outside work area sample for this scenario

During Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
|--|----------------------------|------------------------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|----|
| D-C1-141806-41 | -A-Area | 2ND FL - LIVING ROOM - NORTH | 18122 | 15:19 | 2.56 | 16:20 | 2:52 | 61 | 2.52 | 153.7 | 63 |
| D-C1-141806-42 | -A-Area | 2ND FL - LIVING ROOM - SOUTH | 18105 | 15:19 | 2.52 | 16:21 | 2:52 | 62 | 2.52 | 156.2 | 48 |
| D-C1-141806-54 | -A-PBZ | WORKER | 16666 | 15:17 | 2.58 | 16:20 | 2:49 | 63 | 2.49 | 156.9 | 78 |
| D-0-041806-55 | -A-Area | 2ND FL KITCHEN | 16608 | 15:21 | 2.54 | 17:44 | 2:59 | 143 | 2.54 | 363.2 | <6 |

Post-Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
|--|----------|------------------------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|-------|
| C-C1-141806-61 | -A-Area | 2ND FL - LIVING ROOM - SOUTH | 18105 | 16:28 | 2.52 | 17:30 | 2:52 | 62 | 2.52 | 156.2 | <13.0 |
| C-C1-141806-62 | -A-Area | 2ND FL - LIVING ROOM - NORTH | 18122 | 16:28 | 2.51 | 17:31 | 2:55 | 63 | 2.51 | 158.1 | <13.0 |

Wipe Sampling

Date 4/18/2006 Collected by:

| Sample No. (P-Scenario/D-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|----------|-----------------------------|--------------|---------------------------------|------------------------------|
| P-C1-041806-25 | -W-Area | 2ND FL LIVING ROOM - B WALL | FLOOR | CARPET | 1.00 155 |
| P-C1-041806-26 | -W-Area | 2ND FL LIVING ROOM - D WALL | FLOOR | CARPET | 1.00 152 |
| P-C1-041806-27 | -W-Area | 2ND FL LIVING ROOM - B WALL | SILL | WOOD | 0.25 16000 |

Post-Work Wipe Sampling

| Sample No. (P-Scenario/D-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|----------|-----------------------------|--------------|---------------------------------|------------------------------|
| C-C1-041806-91 | -W-Area | 2ND FL LIVING ROOM - B WALL | FLOOR | CARPET | 1.00 925 |
| C-C1-041806-92 | -W-Area | 2ND FL LIVING ROOM - D WALL | FLOOR | CARPET | 1.00 33.2 |
| C-C1-041806-93 | -W-Area | 2ND FL LIVING ROOM - B WALL | SILL | WOOD | 0.25 1360 |

OS - Outside of work area

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|----------------------|
| Hygienist | |
| Activity | REMOVING WINDOW SASH |
| Work Practice | ROUTINE |

| | |
|---|-----------------|
| DATE | 4/18/2006 |
| LOCATION | WALLINGFORD, CT |
| SCENARIO | C1b |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | X |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | X |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

Date: 4/18/2006 Hygienist: _____

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|---------------|---------------|
| | 10 | C1 | SANDING DOORS | Routine |

Site Address: City, State, Zip: WALLINGFORD, CT

| Structure Type | Single Family | Apartment | Approx. Construction Date (Yr) |
|----------------|---------------|------------------|--------------------------------|
| | Town House | Other (describe) | 1910 |
| | Condomium | DUPLEX | Approx. Square Footage: 2300 |
| | | | No. of Separate Rooms: 16 |

| Location of Work w/in structure | | Lead Content of Affected Surfaces | | Work Statistics | |
|----------------------------------|--|--|------------|-----------------|-------------------------------|
| 2ND FL FRONT BEDROOM (BEDROOM 4) | | Surface | XRF Result | % Lead | No. of Workers |
| | | DOORS FROM VARIOUS ROOMS (ALL >9.9 MG/CM2) | >9.9 | | 1 |
| | | | | | Start Time: 15:15 |
| | | | | | Stop Time: 16:15 |
| | | | | | Total Time (hrs): 1 |
| | | | | | Tools and Equipment Used |
| | | | | | <i>Use attached checklist</i> |

Pre-Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|----------------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-C1-041806-40 | -A-Area | CENTER OF BEDROOM 4 | 18107 | 13:25 | 2.63 | 14:40 | 75 | 2.62 | 196.5 | <10 |
| D-C1-041806-27 | -A-OS** | 2ND FLOOR REAR FOYER | 16608 | 11:37 | 2.64 | 14:58 | 201 | 2.54 | 510.5 | <4 |
| C-C1-041806-11 | -A-OS | UPSTAIRS KITCHEN | 16608 | 8:26 | 2.64 | 9:03 | 37 | 2.64 | 97.7 | <21 |

During Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-C1-041806-51 | -A-Area | CENTER OF BEDROOM 4 | 18107 | 15:00 | 2.62 | 16:15 | 75 | 2.61 | 195.8 | 613 |
| D-C1-041806-53 | -A-PBZ | WORKER | 16668 | 15:14 | 2.67 | 16:13 | 59 | 2.56 | 151.0 | 1050 |
| D-C1-041806-55 | -A-OS | UPSTAIRS KITCHEN | 16608 | 15:20 | 2.54 | 17:43 | 143 | 2.54 | 363.2 | <6.0 |

Post-Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------|---------------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-C1-041806-63 | -A-Area | CENTER OF BEDROOM 4 | 18107 | 16:30 | 2.61 | 17:32 | 62 | 2.61 | 161.8 | <13 |

Wipe Sampling

Date: 4/18/2006 Collected by: _____

| Sample No. (P-Scenario/D-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|----------|-------------------------|--------------|---------------------------------|------------------------------|
| C-C1-041806-56 | -W-Area | BEDROOM 4 - NEAR B WALL | FLOOR | 1.00 | 567 |
| C-C1-041806-57 | -W-Area | BEDROOM 4 - NEAR D WALL | FLOOR | 1.00 | 660 |
| C-C1-041806-58 | -W-Area | BEDROOM 4 - NEAR A WALL | SILL | 0.25 | 10200 |

Post-Work Wipe Sampling

| Sample No. (P-Scenario/D-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|----------|-------------------------|--------------|---------------------------------|------------------------------|
| C-C1-041806-88 | -W-Area | BEDROOM 4 - NEAR B WALL | FLOOR | 1.00 | 37.8 |
| C- | -W-Area | BEDROOM 4 - NEAR D WALL | FLOOR | 1.00 | 57.5 |
| C- | -W-Area | BEDROOM 4 - NEAR A WALL | SILL | 0.25 | 3310 |

OS - Outside of work area

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|---------------|
| Hygienist | |
| Activity | SANDING DOORS |
| Work Practice | ROUTINE |

| | |
|---|-----------------|
| DATE | 4/18/2006 |
| LOCATION | WALLINGFORD, CT |
| SCENARIO | C1 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | X |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | X |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

Date: 4/18/2006 Hygienist: []

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|-------------------------------------|---------------|
| | 11 | C1 | SANDING WINDOW STOPS W/ BELT SANDER | ROUTINE |

Site Address: City, State, Zip WALLINGFORD, CT

| Structure Type | Single Family | Apartment | Approx. Construction Date (Yr) | 1910 |
|----------------|---------------|------------------|--------------------------------|------|
| | Town House | Other (describe) | Approx. Square Footage | 2300 |
| | Condomium | DUPLEX | No. of Separate Rooms | 16 |

| Location of Work w/in structure | | 2ND FLOOR FRONT BEDROOM (BEDROOM 4) | | |
|-----------------------------------|------------|-------------------------------------|--------------------------|-------|
| Lead Content of Affected Surfaces | | Work Statistics | | |
| Surface | XRF Result | % Lead | No. of Workers | 1 |
| WINDOW CASINGS/SASH/STOPS | > 9.9 | | Start Time | 11:10 |
| | | | Stop Time | 13:00 |
| | | | Total Time (hrs) | 1.33 |
| | | | Tools and Equipment Used | |
| | | | Use attached checklist | |

Pre-Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (ppm) | Time Off | FR (ppm) | Total Time (min) | Lowest FR (ppm) | Volume (L) | Result (ug/m ³) |
|--|--------------------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P-CT-041806-13 | -A-Area CENTER OF BEDROOM 4 | 18107 | 8:31 | 2.63 | 9:10 | 2.67 | 39 | 2.63 | 102.6 | <19.5 |
| P-CT-041806-09 | -A-OS** 2ND FL - LIVING ROOM - NORTH | 18122 | 8:20 | 2.52 | 8:56 | 2.56 | 36 | 2.52 | 90.7 | <22 |
| P-CT-041806-10 | -A-OS** 2ND FL - LIVING ROOM - SOUTH | 18105 | 8:25 | 2.55 | 9:01 | 2.59 | 36 | 2.55 | 91.8 | <22 |
| P-CT-041806-12 | -A-OS** 2ND FLOOR REAR FOYER | 16608 | 8:29 | 2.64 | 9:06 | 2.64 | 37 | 2.64 | 97.7 | <21 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (ppm) | Time Off | FR (ppm) | Total Time (min) | Lowest FR (ppm) | Volume (L) | Result (ug/m ³) |
|--|--------------------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-CT-041806-28 | -A-Area CENTER OF BEDROOM 4 | 18107 | 11:31 | 2.67 | 12:59 | 2.63 | 88 | 2.63 | 231.4 | 310 |
| D-CT-041806-33 | -A-PBZ WORKER | 16608 | 11:41 | 2.61 | 12:59 | 2.67 | 78 | 2.61 | 203.6 | 545 |
| D-CT-041806-24 | -A-OS** 2ND FL - LIVING ROOM - NORTH | 18122 | 11:34 | 2.52 | 13:23 | 2.52 | 109 | 2.52 | 274.7 | 83 |
| D-CT-041806-25 | -A-OS** 2ND FL - LIVING ROOM - SOUTH | 18105 | 11:34 | 2.55 | 13:23 | 2.56 | 109 | 2.55 | 278.0 | 37 |
| D-CT-041806-27 | -A-OS** 2ND FLOOR REAR FOYER | 16608 | 11:37 | 2.64 | 14:58 | 2.54 | 201 | 2.54 | 510.5 | <4 |

Post-Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location | Pump ID | Time On | FR (ppm) | Time Off | FR (ppm) | Total Time (min) | Lowest FR (ppm) | Volume (L) | Result (ug/m ³) |
|--|-----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-CT-041806-40 | -A-Area CENTER OF BEDROOM 4 | 18107 | 13:25 | 2.63 | 14:40 | 2.62 | 75 | 2.62 | 196.5 | <10 |

Wipe Sampling

Date: 4/18/2006 Collected by: []

| Pre-Work Wipe Sampling | | | | | | |
|---|--|---------|--------------|---------------------------------|------------------------------|--|
| Sample No. (P-Scenario/D-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| P-CT-041806-22 | -W-Area BEDROOM 4 - NEAR B WALL | FLOOR | CARPET | 1.00 | 625 | |
| P-CT-041806-23 | -W-Area BEDROOM 4 - NEAR D WALL | FLOOR | CARPET | 1.00 | 755 | |
| P-CT-041806-24 | -W-Area BEDROOM 4 - NEAR A WALL | SILL | WOOD | 0.25 | 62000 | |
| P-CT-041806-35 | -W-OS 2ND FLOOR REAR FOYER - NEAR B WALL | FLOOR | WOOD | 1.00 | 2020 | |
| Post-Work Wipe Sampling | | | | | | |
| Sample No. (P-Scenario/D-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| C-CT-041806-56 | -W-Area BEDROOM 4 - NEAR B WALL | FLOOR | CARPET | 1.00 | 567 | |
| C-CT-041806-57 | -W-Area BEDROOM 4 - NEAR D WALL | FLOOR | CARPET | 1.00 | 660 | |
| C-CT-041806-58 | -W-Area BEDROOM 4 - NEAR A WALL | SILL | WOOD | 0.25 | 10200 | |
| C-CT-041806-69 | -W-OS 2ND FLOOR REAR FOYER - NEAR B WALL | FLOOR | WOOD | 1.00 | 2550 | |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-------------------------------------|
| Hygienist | |
| Activity | SANDING WINDOW STOPS W/ BELT SANDER |
| Work Practice | ROUTINE |

| | |
|---|-----------------|
| DATE | 4/18/2006 |
| LOCATION | WALLINGFORD, CT |
| SCENARIO | C1a |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | X |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | X |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swifter or Similar Disposable Wet Mop | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

Date 4/19/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|---------------|---------------|
| | 12 | C2 | SANDING DOORS | MODIFIED LSWP |

| | | |
|--------------|------------------|-----------------|
| Site Address | City, State, Zip | WALLINGFORD, CT |
|--------------|------------------|-----------------|

| | | | | |
|----------------|---------------|------------------|--------------------------------|------|
| Structure Type | Single Family | Apartment | Approx. Construction Date (Yr) | 1910 |
| | Town House | Other (describe) | Approx. Square Footage | 2300 |
| | Condomium | DUPLEX | No. of Separate Rooms | 16 |

| | | | | |
|--|------------|----------------------------------|-------------------------------|-------|
| Location of Work w/in structure | | 1ST FL FRONT BEDROOM (BEDROOM 1) | | |
| Lead Content of Affected Surfaces | | Work Statistics | | |
| Surface | XRF Result | % Lead | No. of Workers | 1 |
| DOORS FROM VARIOUS ROOMS (ALL >9.9 MG/CM2) | >9.9 | and/or | Start Time | 9:15 |
| | | | Stop Time | 10:25 |
| | | | Total Time (hrs) | 1.2 |
| | | | Tools and Equipment Used | |
| | | | Use attached checklist | |

Pre-Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|-------------------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-041806-58 | -A-Area 1ST FL FRONT BEDROOM (BED1) | 17179 | 17:02 | 2.65 | 18:02 | 2.64 | 60 | 2.64 | 158.4 | <13 |
| C-0-041806-59 | -A-OS 1ST FL LIVING ROOM - NORTH | 17184 | 16:21 | 2.56 | 17:51 | 2.58 | 62 | 2.55 | 158.1 | <13 |
| C-0-041806-60 | -A-OS 1ST FL LIVING ROOM - SOUTH | 16669 | 16:21 | 2.5 | 17:51 | 2.61 | 62 | 2.5 | 155.0 | <13 |

During Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|-------------------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-C2-041906-70 | -A-Area 1ST FL FRONT BEDROOM (BED1) | 16608 | 9:16 | 2.52 | 10:26 | 2.51 | 70 | 2.51 | 175.7 | 52 |
| D-C2-041906-75 | -A-PBZ WORKER | 17179 | 9:16 | 2.58 | 10:28 | 2.54 | 72 | 2.54 | 182.9 | 60 |
| D-0-041906-67 | -A-OS 1ST FL LIVING ROOM | 18104 | 8:31 | 2.57 | 11:24 | 2.64 | 173 | 2.57 | 444.6 | <4.0 |

Post-Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|-------------------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-C2-041906-83 | -A-Area 1ST FL FRONT BEDROOM (BED1) | 16608 | 10:27 | 2.51 | 11:29 | 2.55 | 62 | 2.51 | 155.6 | <13.0 |

Wipe Sampling

Date 4/19/2006 Collected by:

| Sample No. (P-Scenario/D-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|--------------------------------------|---------|--------------|---------------------------------|------------------------------|
| P-C2-041806-81 | -W-Area 1ST FL FRONT BEDROOM (BED 1) | FLOOR | CARPET | 1.00 | 198 |
| P-C2-041806-82 | -W-Area 1ST FL FRONT BEDROOM (BED 1) | FLOOR | CARPET | 1.00 | 2990 |
| P-C2-041806-83 | -W-Area 1ST FL FRONT BEDROOM (BED 1) | SILL | WOOD | 0.25 | 6720 |
| P-0-041806-49 | -W-OS 1ST FL KITCHEN | FLOOR | LINOLEUM | 1.00 | 475 |
| Sample No. (P-Scenario/D-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| C-C2-041906-1 | -W-Area 1ST FL FRONT BEDROOM (BED 1) | FLOOR | CARPET | 1.00 | 20.4 |
| C-C2-041906-2 | -W-Area 1ST FL FRONT BEDROOM (BED 1) | FLOOR | CARPET | 1.00 | 19.8 |
| C-C2-041906-3 | -W-Area 1ST FL FRONT BEDROOM (BED 1) | SILL | WOOD | 0.25 | 2320 |
| C-0-041906-7 | -W-OS 1ST FL LIVING ROOM | FLOOR | CARPET | 1.00 | 1290 |

OS - Outside of work area

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|---------------|
| Hygienist | |
| Activity | SANDING DOORS |
| Work Practice | mod LSWP |

| | |
|---|-----------------|
| DATE | 4/19/2006 |
| LOCATION | WALLINGFORD, CT |
| SCENARIO | C2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | X |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | X |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | X |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

Date Hygienist

| Event | ID | Activity | Work Practice |
|-------------|----|----------------------|---------------|
| Scenario 13 | C2 | SANDING WINDOW STOPS | MODIFIED LSWP |

Site Address City, State, Zip

| Structure Type | Single Family | Apartment | Approx. Construction Date (Yr) |
|----------------|---------------|------------------|--------------------------------|
| | Town House | Other (describe) | 1910 |
| | Condomium | DUPLEX | Approx. Square Footage 2300 |
| | | | No. of Separate Rooms 16 |

| Location of Work w/in structure | | 1ST FL FRONT BEDROOM (BEDROOM 1) | |
|---|------------|----------------------------------|-------------------------------|
| Lead Content of Affected Surfaces | | | |
| Surface | XRF Result | % Lead | Work Statistics |
| WINDOW STOPS FROM VARIOUS ROOMS (ALL >9.9 MG/CM2) | >9.9 | | No. of Workers 1 |
| | | | Start Time 15:06 |
| | | | Stop Time 16:08 |
| | | | Total Time (hrs) 1 |
| | | | Tools and Equipment Used |
| | | | <i>Use attached checklist</i> |

Pre-Work Sampling

| Sample No. (P-Scenario/D-Date-#-A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|-------------------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-C2-041806-03 | -A-Area 1ST FL FRONT BEDROOM (BED1) | 17179 | 7:48 | 2.54 | 8:24 | 2.58 | 36 | 2.54 | 91.4 | <22 |
| C-0-041806-07 | -A-OS 1ST FLOOR KITCHEN | 17865 | 8:01 | 2.59 | 8:38 | 2.63 | 37 | 2.59 | 95.8 | <21 |

During Work Sampling

| Sample No. (P-Scenario/D-Date-#-A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|-------------------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-C2-041806-20 | -A-Area 1ST FL FRONT BEDROOM (BED1) | 17179 | 15:06 | 2.58 | 16:08 | 2.65 | 62 | 2.58 | 160.0 | 68 |
| D-C2-041806-50 | -A-PBZ WORKER | 16612 | 15:06 | 2.66 | 16:08 | 2.62 | 62 | 2.62 | 162.4 | 91 |
| D-0-041806-47 | -A-OS 1ST FLOOR KITCHEN | 17865 | 15:12 | 2.64 | 17:23 | 2.58 | 133 | 2.58 | 343.1 | <6 |

Post-Work Sampling

| Sample No. (P-Scenario/D-Date-#-A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|-------------------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-C2-141806-58 | -A-Area 1ST FL FRONT BEDROOM (BED1) | 17179 | 17:02 | 2.65 | 18:02 | 2.64 | 60 | 2.64 | 158.4 | <13.0 |

Wipe Sampling

Date Collected by:

| Sample No. (P-Scenario/D-Date-#-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|--|---------|--------------|---------------------------------|------------------------------|
| P-C2-041806-06 | -W-Area 1ST FL FRONT BEDROOM (BED1) - B WALL | FLOOR | CARPET | 1.00 | 50.2 |
| P-C2-041806-07 | -W-Area 1ST FL FRONT BEDROOM (BED1) - D WALL | FLOOR | CARPET | 1.00 | 534 |
| P-C2-041806-08 | -W-Area 1ST FL FRONT BEDROOM (BED1) - A WALL | SILL | WOOD | 0.25 | 91200 |
| Post-Work Wipe Sampling | | | | | |
| Sample No. (P-Scenario/D-Date-#-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| C-C1-041806-81 | -W-Area 1ST FL FRONT BEDROOM (BED1) - B WALL | FLOOR | CARPET | 1.00 | 198 |
| C-C1-041806-82 | -W-Area 1ST FL FRONT BEDROOM (BED1) - D WALL | FLOOR | CARPET | 1.00 | 2990 |
| C-C1-041806-83 | -W-Area 1ST FL FRONT BEDROOM (BED1) - A WALL | SILL | WOOD | 0.25 | 6720 |

OS - Outside of work area

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|----------------------|
| Hygienist | |
| Activity | SANDING WINDOW STOPS |
| Work Practice | mod LSWP |

| | |
|---|-----------------|
| DATE | 4/18/2006 |
| LOCATION | WALLINGFORD, CT |
| SCENARIO | C2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | X |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | X |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | X |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

| | | | | | |
|-----------------------------------|----------------------------------|--------|-------------------|--------------------------------|------|
| Date | 4/18/2006 | | | Hygienist | |
| Scenario | Event | ID | Activity | Work Practice | |
| | 14 | D1 | Cabinet Removal | Routine | |
| Site Address | City, State, Zip WALLINGFORD, CT | | | | |
| Structure Type | Single Family | | Apartment | Approx. Construction Date (Yr) | |
| | Town House | X | Other (describe) | Approx. Square Footage | |
| | Condomium | | DUPLEX | No. of Separate Rooms | |
| | | | | 1910 | 2300 |
| | | | | 16 | |
| Location of Work w/in structure | | | 2nd Floor Kitchen | | |
| Lead Content of Affected Surfaces | | | Work Statistics | | |
| Surface | XRF Result | | % Lead | No. of Workers | 1 |
| cabinet door | 6.9 | and/or | | Start Time | 1135 |
| | | | | Stop Time | 1250 |
| | | | | Total Time (hrs) | 1.25 |
| | | | | Tools and Equipment Used | |
| | | | | Use attached checklist | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P-D1-041806-11 | -A-Area 2ND FLOOR KITCHEN | 17180 | 826 | 2.64 | 903 | 2.66 | 37 | 2.64 | 97.7 | <21.0 |
| P-D1-041806-12 | -A-OS** 2ND FL REAR FOYER | 16608 | 8:29 | 2.64 | 9:06 | 2.64 | 37 | 2.64 | 97.7 | <21.0 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-D1-041806-26 | -A-Area 2ND FLOOR KITCHEN | 17180 | 1135 | 2.66 | 1252 | 2.62 | 77 | 2.62 | 201.7 | 15 |
| D-D1-041806-34 | -A-PBZ WORKER | 16612 | 1138 | 2.62 | 1252 | 2.66 | 72 | 2.62 | 188.6 | 15 |
| D-D1-041806-27 | -A-OS 2ND FL REAR FOYER | 16608 | | | | | 201 | 2.54 | 510.5 | <4 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|---------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-D1-041806-38 | -A-Area 2ND FLOOR KITCHEN | 17180 | 1329 | 2.62 | 1445 | 2.59 | 77 | 2.59 | 199.4 | <10.0 |

Wipe Sampling

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|----------------------------------|---------|--------------|---------------------------------|------------------------------|
| P-D1-041806-31 | -W-Area 2nd FL Kitchen (B Wall) | Floor | Linoleum | 1 | 1440 |
| P-D1-041806-32 | -W-Area 2nd FL Kitchen (D Wall) | Floor | Linoleum | 1 | 1530 |
| P-D1-041806-33 | -W-Area 2nd FL Kitchen (B Wall) | Sill | Wood | 0.25 | 43600 |
| P-D1-041806-34 | -W-Area 2nd FL Kitchen (B Wall) | Counter | Formica | 1 | 679 |
| P-D1-041806-35 | -W-OS 2ND FL REAR FOYER - B WALL | Floor | Wood | 1 | 2020 |

Wipe Sampling

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Sampled (ft ²) | Result (ug/ft ²) |
|---|----------------------------------|---------|--------------|----------------------------|------------------------------|
| C-D1-041806-62 | -W-Area 2nd FL Kitchen (B Wall) | Floor | Linoleum | 1 | 136 |
| C-D1-041806-63 | -W-Area 2nd FL Kitchen (D Wall) | Floor | Linoleum | 1 | 173 |
| C-D1-041806-64 | -W-Area 2nd FL Kitchen (B Wall) | Sill | Wood | 0.25 | 2840 |
| C-D1-041806-65 | -W-Area 2nd FL Kitchen (B Wall) | Counter | Formica | 1 | 1270 |
| C-D1-041806-69 | -W-OS 2ND FL REAR FOYER - B WALL | Floor | Wood | 1 | 2550 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

Key for Scenario ID

| Activities | No Safe Work Practices Used | HUD/EPA Lead Safe Work Practices (LSWP) | A Variation of EPA/HUD Work Practices |
|--|-----------------------------|---|---------------------------------------|
| Key Activities | | | |
| Wall and ceiling removal (i.e. for an addition). | A1 | A2 | A3 |
| Wall and ceiling modification (i.e. for adding a door) | B1 | B2 | B3 |
| Window and door replacement which involves the removal or alteration of trims, moldings and jambs or anything else that may have LBP applied to the surface. | C1 | C2 | C3 |
| Kitchen and bath work (i.e. cabinet replacement, tile work, etc.) | D1 | D2 | D3 |
| Floor covering removal. This typically involves disturbing baseboards that may be coated with LBP. | E1 | E2 | E3 |
| Miscellaneous Activities | | | |
| Surface preparation. | F1 | F2 | F3 |
| Sawing into wood & plaster covered by LBP. | G1 | G2 | G3 |
| HVAC work | H1 | H2 | H3 |

Sample Numbering for Blanks

Samples (B-ScenarioID-Date-## -A)

Samples (P-ScenarioID-Date-## -W)

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-----------------|
| Hygienist | |
| Activity | CABINET REMOVAL |
| Work Practice | ROUTINE |

| | |
|---|-----------------|
| DATE | 4/18/2006 |
| LOCATION | WALLINGFORD, CT |
| SCENARIO | D1 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | X |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swifter or Similar Disposable Wet Mop | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 4/18/2006 Hygienist .

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|------------------|---------------|
| | 15 | E1 | REMOVE BASEBOARD | ROUTINE |

| | | |
|--------------|------------------|-----------------|
| Site Address | City, State, Zip | WALLINGFORD, CT |
|--------------|------------------|-----------------|

| | | | | | |
|----------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | | Apartment | Approx. Construction Date (Yr) | 1910 |
| | Town House | X | Other (describe) | Approx. Square Footage | 2300 |
| | Condomium | | DUPLEX | No. of Separate Rooms | 16 |

| | | | | | |
|-----------------------------------|------------|------------------------------------|--------|---|--|
| Location of Work w/in structure | | 2ND FLOOR REAR BEDROOM (BEDROOM 3) | | | |
| Lead Content of Affected Surfaces | | | | | |
| Surface | XRF Result | | % Lead | Work Statistics No. of Workers 1 Start Time 11:30 Stop Time 13:15 Total Time (hrs) 1.75 Tools and Equipment Used <i>Use attached checklist</i> | |
| BASEBOARD | > 9.9 | | | | |
| | | and/or | | | |
| | | | | | |
| | | | | | |

Pre-Work Sampling

| Sample No. <small>(P-ScenarioID-Date-## -A-Type)</small> | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|---|------------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P-CI-041806-14 -A-Area | CENTER OF BEDROOM 3 | 18104 | 8:34 | 2.58 | 9:11 | 2.59 | 37 | 2.58 | 95.5 | <21 |
| P-CI-041806-09 -A-OS** | 2ND FL - LIVING ROOM - NORTH | 18122 | 8:20 | 2.52 | 8:56 | 2.56 | 36 | 2.52 | 90.7 | <22 |
| P-CI-041806-10 -A-OS** | 2ND FL - LIVING ROOM - SOUTH | 18105 | 8:25 | 2.55 | 9:01 | 2.59 | 36 | 2.55 | 91.8 | <22 |
| P-CI-041806-12 -A-OS** | 2ND FLOOR REAR FOYER | 16608 | 8:29 | 2.64 | 9:06 | 2.64 | 37 | 2.64 | 97.7 | <21 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. <small>(P-ScenarioID-Date-## -A-Type)</small> | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|---|------------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-CI-041806-29 -A-Area | CENTER OF BEDROOM 3 | 18104 | 11:31 | 2.67 | 12:59 | 2.63 | 39 | 2.63 | 102.6 | 33 |
| D-CI-041806-32 -A-PBZ | WORKER | 16666 | 11:40 | 2.52 | 13:13 | 2.58 | 99 | 2.52 | 249.5 | 56 |
| D-CI-041806-24 -A-OS** | 2ND FL - LIVING ROOM - NORTH | 18122 | 11:34 | 2.52 | 13:23 | 2.52 | 109 | 2.52 | 274.7 | 83 |
| D-CI-041806-25 -A-OS** | 2ND FL - LIVING ROOM - SOUTH | 18105 | 11:34 | 2.55 | 13:23 | 2.56 | 109 | 2.55 | 278.0 | 37 |
| D-CI-041806-27 -A-OS** | 2ND FLOOR REAR FOYER | 16608 | 11:37 | 2.64 | 14:58 | 2.54 | 201 | 2.54 | 510.5 | <4 |

Post-Work Sampling

| Sample No. <small>(P-ScenarioID-Date-## -A-Type)</small> | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|---|---------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-CI-041806-39 -A-Area | CENTER OF BEDROOM 3 | 18104 | 13:27 | 2.54 | 14:41 | 2.52 | 74 | 2.52 | 186.5 | <11 |

Wipe Sampling

Date 4/18/2006 Collected by: .

| Pre-Work Wipe Sampling | | | | | | |
|--|------------------------------------|---------------|--------------|---------------------------------|------------------------------|--|
| Sample No. <small>(P-ScenarioID-Date-##-W-Location)</small> | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| P-CI-041806-28 -W-Area | BEDROOM 3 - NEAR B WALL | FLOOR | CARPET | 1.00 | 4700 | |
| P-CI-041806-29 -W-Area | BEDROOM 3 - NEAR D WALL | FLOOR | CARPET | 1.00 | 2810 | |
| P-CI-041806-30 -W-Area | BEDROOM 3 - NEAR B WALL | SILL | WOOD | 0.25 | 8760 | |
| P-CI-041806-35 -W-OS | 2ND FLOOR REAR FOYER - NEAR B WALL | FLOOR | WOOD | 1.00 | 2020 | |
| Post-Work Wipe Sampling | | | | | | |
| Sample No. <small>(P-ScenarioID-Date-##-W-Location)</small> | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| C-CI-041806-59 -W-Area | BEDROOM 3 - NEAR B WALL | FLOOR | CARPET | 1.00 | 218 | |
| C-CI-041806-60 -W-Area | BEDROOM 3 - NEAR D WALL | FLOOR | CARPET | 1.00 | 26.4 | |
| C-CI-041806-61 -W-Area | BEDROOM 3 - NEAR B WALL | SILL + TROUGH | WOOD | 0.42 | 39200 | |
| C-CI-041806-69 -W-OS | 2ND FLOOR REAR FOYER - NEAR B WALL | FLOOR | WOOD | 1.00 | 2550 | |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-------------------|
| Hygienist | |
| Activity | REMOVE BASEBOARDS |
| Work Practice | ROUTINE |

| | |
|---|-----------------|
| DATE | 4/18/2006 |
| LOCATION | WALLINGFORD, CT |
| SCENARIO | E1a |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | X |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | X |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swifter or Similar Disposable Wet Mop | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

Date **4/18/2006** Hygienist _____

| Event | ID | Activity | Work Practice |
|-------|----|-------------------|---------------|
| 16 | E2 | BASEBOARD REMOVAL | mod LSWP |

| | | |
|---------------------|------------------|-----------------|
| Site Address | City, State, Zip | WALLINGFORD, CT |
|---------------------|------------------|-----------------|

| | | | | |
|-----------------------|---------------|--------------------|--------------------------------|------|
| Structure Type | Single Family | Apartment | Approx. Construction Date (Yr) | 1910 |
| | Town House | X Other (describe) | Approx. Square Footage | 2300 |
| | Condomium | DUPLEX | No. of Separate Rooms | 16 |

| | | | |
|--|------------|------------------------|-------------------------------|
| Location of Work w/in structure | | | |
| Lead Content of Affected Surfaces | | Work Statistics | |
| Surface | XRF Result | % Lead | No. of Workers |
| BASEBOARDS | >9.9 | and/or | 1 |
| | | | Start Time |
| | | | 9:15 |
| | | | Stop Time |
| | | | 10:15 |
| | | | Total Time (hrs) |
| | | | 1 |
| | | | Tools and Equipment Used |
| | | | Use attached checklist |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------|-----------------|------------|-----------------------------|
| P-E2-041806-04 | -A-Area 1ST FL BR (BED 2) | | 7:48 | 2.54 | 8:24 | 2.59 | 36 | 2.57 | 92.5 | <22.0 |
| P-0-041806-07 | -A-OS** 1ST FL KITCHEN | 17865 | 8:01 | 2.59 | 8:38 | 2.63 | 37 | 2.59 | 95.8 | <21 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------|-----------------|------------|-----------------------------|
| D-E2-041906-71 | -A-Area 1ST FL BR #2 | 17180 | 9:15 | 2.58 | 10:21 | 2.58 | 66 | 2.58 | 170.3 | 29 |
| D-E2-041906-76 | -A-PBZ WORKER | 16612 | 9:15 | 2.59 | 10:16 | 2.55 | 61 | 2.55 | 155.6 | 38 |
| D-0-041906-67 | -A-OS 1ST FL KITCHEN | 18104 | 8:31 | 2.57 | 11:24 | 2.64 | 159 | 2.57 | 408.6 | <4 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------|---------|---------|----------|----------|----------|------------|-----------------|------------|-----------------------------|
| C-E2-041906-82 | -A-Area 1ST FL BR #2 | 17180 | 10:22 | 2.58 | 11:26 | 2.6 | 64 | 2.58 | 165.1 | <2.0 |

Wipe Sampling

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|-------------------------------|---------|--------------|---------------------------------|------------------------------|
| P-E2-041806-09 | -W-Area 1ST FL BR #2 (B Wall) | Floor | Carpet | 1 | 177 |
| P-E2-041806-10 | -W-Area 1ST FL BR #2 (D Wall) | Floor | Carpet | 1 | 1590 |
| P-E2-041806-11 | -W-Area 1ST FL BR #2 (D Wall) | Sill | Wood | 0.25 | 108000 |
| P-0-041806-12 | -W-OS 1ST FL KITCHEN (B WALL) | Floor | Linoleum | 1 | 1630 |

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|-------------------------------|---------|--------------|---------------------------------|------------------------------|
| C-E2-041906-4 | -W-Area 1ST FL BR #2 (B Wall) | Floor | Carpet | 1 | 39.4 |
| C-E2-041906-5 | -W-Area 1ST FL BR #2 (D Wall) | Floor | Carpet | 1 | 79.6 |
| C-E2-041906-6 | -W-Area 1ST FL BR #2 (D Wall) | Sill | Wood | 0.25 | 120 |
| C-0-041906-7 | -W-OS 1ST FL LR (B WALL) | Floor | Carpet | 1 | 1290 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-------------------|
| Hygienist | |
| Activity | BASEBOARD REMOVAL |
| Work Practice | mod LSWP |

| | |
|---|-----------------|
| DATE | 4/18/2006 |
| LOCATION | WALLINGFORD, CT |
| SCENARIO | E2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swifter or Similar Disposable Wet Mop | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

Date: 4/19/2006 Hygienist: _____

| Event | ID | Activity | Work Practice |
|-------|----|--|---------------|
| 17 | F1 | REMOVE & SAND MOLDING - ROUTINE - LIV RM 2 | ROUTINE |

| | | |
|--------------|------------------|-----------------|
| Site Address | City, State, Zip | Wallingford, CT |
|--------------|------------------|-----------------|

| | | | | |
|----------------|---------------|------------------|--------------------------------|------|
| Structure Type | Single Family | Apartment | Approx. Construction Date (Yr) | 1910 |
| | Town House | Other (describe) | Approx. Square Footage | 2300 |
| | Condomium | Duplex | No. of Separate Rooms | 14 |

Location of Work w/in structure: 2nd FL LIVING ROOM

| Lead Content of Affected Surfaces | | XRF Result | % Lead | Work Statistics | |
|-----------------------------------|--|------------|--------|-------------------------------|------|
| Surface | | | | No. of Workers | 1 |
| CROWN MOLDING | | 1.0 | | Start Time | 910 |
| | | | | Stop Time | 1009 |
| | | | | Total Time (hrs) | 1 |
| | | | | Tools and Equipment Used | |
| | | | | Use attached checklist | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
|--|----------------------------|------------------------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|----|
| D-CI-041806-24 | -A-Area | 2ND FL - LIVING ROOM - NORTH | 18122 | 11:34 | 2.52 | 13:23 | 2.52 | 109 | 2.52 | 274.7 | 83 |
| D-CI-041806-25 | -A-Area | 2ND FL - LIVING ROOM - SOUTH | 18105 | 11:34 | 2.55 | 13:23 | 2.56 | 109 | 2.55 | 278.0 | 37 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
|--|----------------------------|-----------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|-------|
| D-F1-041906-73 | -A-Area | 2nd FL LR North | 17865 | 9:23 | 2.58 | 10:11 | 2.61 | 48 | 2.58 | 123.8 | <16.0 |
| D-F1-041906-74 | -A-Area | 2nd FL LR South | 16670 | 9:23 | 2.58 | 10:13 | 2.58 | 50 | 2.58 | 129 | <16.0 |
| D-F1-041906-77 | -A-PBZ | WORKER | 16666 | 9:10 | 2.63 | 10:09 | 2.71 | 59 | 2.63 | 155.2 | <13.0 |
| D-0-041906-69 | -A-OS | 2nd FL KITCHEN | 16608 | 8:42 | 2.51 | 11:14 | 2.54 | 159 | 2.51 | 399.09 | <5.0 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
|--|----------|-----------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|-------|
| C-F1-041906-80 | -A-Area | 2nd FL LR North | 17865 | 10:15 | 2.61 | 11:18 | 2.56 | 63 | 2.56 | 161.3 | <12.0 |
| C-F1-041906-81 | -A-Area | 2ND FL LR South | 16670 | 10:14 | 2.58 | 11:16 | 2.54 | 62 | 2.54 | 157.5 | <13.0 |

Wipe Sampling

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|----------|-----------------------------|--------------|---------------------------------|------------------------------|
| C-C1-041806-91 | -W-Area | 2ND FL LIVING ROOM - B WALL | FLOOR | 1.00 | 925 |
| C-C1-041806-92 | -W-Area | 2ND FL LIVING ROOM - D WALL | FLOOR | 1.00 | 33.2 |
| C-C1-041806-93 | -W-Area | 2ND FL LIVING ROOM - B WALL | SILL | 0.25 | 1360 |

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|----------|-----------------------------|--------------|---------------------------------|------------------------------|
| C-F1-041906-14 | -W-Area | 2ND FL LIVING ROOM - B WALL | FLOOR | 1.00 | 64.1 |
| C-F1-041906-15 | -W-Area | 2ND FL LIVING ROOM - D WALL | FLOOR | 1.00 | 48.7 |
| C-F1-041906-16 | -W-Area | 2ND FL LIVING ROOM - B WALL | SILL | 0.25 | 824 |
| C-0-041906-17 | -W-OS | 2ND FL KITCHEN - B WALL | FLOOR | 1 | 206 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-------------------------|
| Hygienist | |
| Activity | REMOVE AND SAND MOLDING |
| Work Practice | ROUTINE |

| | |
|---|-----------------|
| DATE | 4/19/2006 |
| LOCATION | WALLINGFORD, CT |
| SCENARIO | F1 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | X |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swifter or Similar Disposable Wet Mop | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

Date 4/18/2006 Hygienist

| Event | ID | Activity | Work Practice |
|-------|----|---------------------------------|---------------|
| 18 | F1 | Belt Sand Stair Stringer (Wood) | Routine |

| | | |
|---------------------|------------------|-----------------|
| Site Address | City, State, Zip | Wallingford, CT |
|---------------------|------------------|-----------------|

| | | | | |
|-----------------------|---------------|--------------------|--------------------------------|------|
| Structure Type | Single Family | Apartment | Approx. Construction Date (Yr) | 1910 |
| | Town House | X Other (describe) | Approx. Square Footage | 2300 |
| | Condomium | Duplex | No. of Separate Rooms | 14 |

| | | | |
|--|------------|------------------------|-------------------------------|
| Location of Work w/in structure | | | |
| Lead Content of Affected Surfaces | | Work Statistics | |
| Surface | XRF Result | % Lead | No. of Workers |
| STAIR STRINGER | >9.9 | and/or | 1 |
| STAIR TREAD | >9.9 | | Start Time |
| STAIR RISER | >9.9 | | 1459 |
| | | | Stop Time |
| | | | 1552 |
| | | | Total Time (hrs) |
| | | | 1 |
| | | | Tools and Equipment Used |
| | | | Use attached checklist |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------|-----------------|------------|-----------------------------|
| C-F2-041806-36 -A-Area | Front Stairwell | 17863 | 13:05 | 2.55 | 14:46 | 2.55 | 101 | 2.55 | 257.6 | <8 |
| P-0-041806-23 -A-OS** | 1ST FL KITCHEN | 17865 | 11:40 | 2.63 | 14:50 | 2.61 | 190 | 2.61 | 495.9 | <4 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------|-----------------|------------|-----------------------------|
| D-F1-041806-46 -A-Area | Front Stairwell | 17863 | 1459 | 2.55 | 1552 | 2.56 | 53 | 2.55 | 135.2 | 1780 |
| D-F1-041806-48 -A-PBZ | WORKER | 16670 | 1459 | 2.56 | 1552 | 2.54 | 53 | 2.54 | 134.6 | 1700 |
| D-0-041806-47 -A-OS | 1ST FL KITCHEN | 17865 | 15:12 | 2.64 | 17:51 | 2.58 | 133 | 2.58 | 343.1 | <6 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|-----------------|---------|---------|----------|----------|----------|------------|-----------------|------------|-----------------------------|
| C-F1-041806-56 -A-Area | Front Stairwell | 17863 | 1703 | 2.56 | 1803 | 2.56 | 60 | 2.56 | 153.6 | <13.0 |

Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|-----------------|----------|--------------|---------------------------------|------------------------------|
| C-F2-041806-43 -W-Area | FRONT STAIRWELL | FLOOR | WOOD | 1 | 83.2 |
| C-F2-041806-44 -W-Area | FRONT STAIRWELL | TREAD | WOOD | 0.79 | 3680 |
| C-F2-041806-45 -W-Area | FRONT STAIRWELL | BANISTER | WOOD | 0.33 | 110 |
| P- | -W-OS | | | | |

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|--------------------|----------|--------------|---------------------------------|------------------------------|
| C-F1-041806-78 -W-Area | FRONT STAIRWELL | FLOOR | WOOD | 1 | 9700 |
| C-F1-041806-79 -W-Area | FRONT STAIRWELL | TREAD | WOOD | 0.79 | 14600 |
| C-F1-041806-80 -W-Area | FRONT STAIRWELL | BANISTER | WOOD | 0.33 | 809 |
| C-0-041806-86 -W-OS | 1ST FL LR (D WALL) | FLOOR | CARPET | 1 | 74 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|---------------------------------|
| Hygienist | |
| Activity | Belt Sand Stair Stringer (Wood) |
| Work Practice | ROUTINE |

| | |
|---|-----------------|
| DATE | 4/18/2006 |
| LOCATION | WALLINGFORD, CT |
| SCENARIO | F1 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | |
| Tape | |
| Utility Knife | |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | X |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swifter or Similar Disposable Wet Mop | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

Date: 4/18/2006 Hygienist: _____

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|-----------------------------------|---------------|
| | 19 | F2 | Sanding Stairwell (wood) (Treads) | Modified LSWP |

| | | |
|---------------------|------------------|-----------------|
| Site Address | City, State, Zip | Wallingford, CT |
|---------------------|------------------|-----------------|

| | | | | |
|-----------------------|---------------|------------------|--------------------------------|------|
| Structure Type | Single Family | Apartment | Approx. Construction Date (Yr) | 1910 |
| | Town House | Other (describe) | Approx. Square Footage | 2300 |
| | Condomium | Duplex | No. of Separate Rooms | 14 |

| | | | | |
|--|------------|-----------|------------------|-------------------------------|
| Location of Work w/in structure | | Stairwell | | |
| Lead Content of Affected Surfaces | | | | |
| Surface | XRF Result | and/or | % Lead | Work Statistics |
| STAIR STRINGER | >9.9 | | No. of Workers | 1 |
| STAIR TREAD | >9.9 | | Start Time | 1137 |
| STAIR RISER | >9.9 | | Stop Time | 1233 |
| | | | Total Time (hrs) | 1 |
| | | | | Tools and Equipment Used |
| | | | | Use attached checklist |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (ppm) | Time Off | FR (ppm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P-F2-041806-01 | -A-Area FRONT STAIRWELL | 17863 | 7:50 | 2.51 | 8:25 | 2.56 | 35 | 2.51 | 87.9 | <23.0 |
| P-0-041806-07 | -A-OS** 1ST FL KITCHEN | 17865 | 8:01 | 2.59 | 8:38 | 2.63 | 37 | 2.57 | 95.8 | <21.0 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (ppm) | Time Off | FR (ppm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-F2-041806-16 | -A-Area FRONT STAIRWELL | 17863 | 11:38 | 2.56 | 12:33 | 2.55 | 55 | 2.55 | 140.3 | 42 |
| D-F2-041806-31 | -A-PBZ WORKER | 16670 | 11:37 | 2.59 | 12:33 | 2.56 | 56 | 2.56 | 143.4 | 76 |
| D-0-041806-23 | -A-PBZ 1ST FL KITCHEN | 17865 | 11:40 | 2.63 | 14:50 | 2.64 | 190 | 2.63 | 499.7 | <4.0 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (ppm) | Time Off | FR (ppm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|-------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-F2-041806-36 | -A-Area FRONT STAIRWELL | 17863 | 13:05 | 2.55 | 14:46 | 2.55 | 101 | 2.55 | 257.6 | <8.0 |

Wipe Sampling

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|-------------------------|----------|--------------|---------------------------------|------------------------------|
| P-F2-041806-16 | -W-Area FRONT STAIRWELL | FLOOR | WOOD | 1 | 131 |
| P-F2-041806-17 | -W-Area FRONT STAIRWELL | TREAD | WOOD | 0.79 | 1050 |
| P-F2-041806-18 | -W-Area FRONT STAIRWELL | BANISTER | WOOD | 0.33 | 48.5 |
| P-0-041806-12 | -W-OS 1ST FL KITCHEN | FLOOR | LINOLEUM | 1 | 1630 |

Wipe Sampling

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|-------------------------|----------|--------------|---------------------------------|------------------------------|
| C-F2-041806-43 | -W-Area FRONT STAIRWELL | FLOOR | WOOD | 1 | 83.2 |
| C-F2-041806-44 | -W-Area FRONT STAIRWELL | TREAD | WOOD | 0.79 | 3680 |
| C-F2-041806-45 | -W-Area FRONT STAIRWELL | BANISTER | WOOD | 0.33 | 110 |
| C-0-041806-49 | -W-OS 1ST FL KITCHEN | FLOOR | LINOLEUM | 1 | 475 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-------------------|
| Hygienist | |
| Activity | SAND STAIR TREADS |
| Work Practice | mod LSWP |

| | |
|---|-----------------|
| DATE | 4/18/2006 |
| LOCATION | WALLINGFORD, CT |
| SCENARIO | F2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | X |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | |
| Tape | |
| Utility Knife | |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | X |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | X |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swifter or Similar Disposable Wet Mop | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 4/21/2006 Hygienist -

| Event | ID | Activity | Work Practice |
|-------|----|-------------------|---------------|
| 20 | B1 | WALL MODIFICATION | ROUTINE |

| | | |
|---------------------|------------------|--------------|
| Site Address | City, State, Zip | Cheshire, CT |
|---------------------|------------------|--------------|

| | | | | | |
|-----------------------|---|---------------|------------------|--------------------------------|------|
| Structure Type | x | Single Family | Apartment | Approx. Construction Date (Yr) | 1900 |
| | | Town House | Other (describe) | Approx. Square Footage | 6000 |
| | | Condomium | | No. of Separate Rooms | 34 |

Location of Work w/in structure BATHROOM 6

| Lead Content of Affected Surfaces | | | | Work Statistics | | |
|-----------------------------------|------------|--------|--------|--------------------------|------------|------|
| Surface | XRF Result | % Lead | | No. of Workers | | |
| A - WALL | 1.0 | | and/or | 1 | Start Time | 9:24 |
| | | | | Stop Time | 10:18 | |
| | | | | Total Time (hrs) | 0.9 | |
| | | | | Tools and Equipment Used | | |
| Use attached checklist | | | | | | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P-B1-041906-20 | -A-Area BATHROOM 6 | 18110 | 15:09 | 2.54 | 15:48 | 2.55 | 39 | 2.54 | 99.1 | <20 |
| P-041906-18 | -A-OS 2ND FL HALL | 17183 | 15:06 | 2.58 | 15:40 | 2.41 | 34 | 2.41 | 81.9 | <24 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-B1-042106-75 | -A-Area BATHROOM 6 | 17865 | 9:24 | 2.60 | 10:16 | 2.54 | 52 | 2.54 | 132.1 | <15 |
| D-B1-042106-76 | -A-PBZ WORKER | 16669 | 9:24 | 2.62 | 10:18 | 2.50 | 54 | 2.50 | 135.0 | <19 |
| D-042106-70 | -A-OS 2ND FL HALL | 18105 | 9:19 | 2.55 | 11:07 | 2.55 | 108 | 2.55 | 275.4 | <7 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|--------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-B1-042106-79 | -A-Area BATHROOM 6 | 17865 | 10:16 | 2.54 | 11:17 | 2.53 | 61 | 2.53 | 154.3 | <13 |

Wipe Sampling

Date 4/21/2006 Collected by

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|--------------------|----------------|--------------|---------------------------------|------------------------------|
| P-B1-041906-61 | -W-Area BATHROOM 6 | FLOOR - B WALL | TILE | 1.00 | 31.1 |
| P-B1-041906-62 | -W-Area BATHROOM 6 | FLOOR - D WALL | TILE | 1.00 | 17.8 |
| P-B1-041906-63 | -W-Area BATHROOM 6 | SILL - A WALL | WOOD | 1.00 | 766 |
| P-041906-64 | -W-OS 2ND FL HALL | FLOOR | STONE | 1.00 | NR |

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|--------------------|----------------|--------------|---------------------------------|------------------------------|
| C-B1-042106-8 | -W-Area BATHROOM 6 | FLOOR - B WALL | TILE | 1.00 | 30.1 |
| C-B1-042106-9 | -W-Area BATHROOM 6 | FLOOR - D WALL | TILE | 1.00 | 61.5 |
| C-B1-042106-10 | -W-Area BATHROOM 6 | SILL - A WALL | WOOD | 1.00 | 183 |
| C-042106-11 | -W-OS 2ND FL HALL | FLOOR | STONE | 1.00 | 40.8 |

OS - Outside of work area

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-------------------|
| Hygienist | |
| Activity | WALL MODIFICATION |
| Work Practice | ROUTINE |

| | |
|---|--------------|
| DATE | 4/21/2006 |
| LOCATION | Cheshire, CT |
| SCENARIO | B1 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | X |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | |
| Tape | |
| Utility Knife | |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | X |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 4/21/2006 Hygienist -

| Event | ID | Activity | Work Practice |
|-------|----|-------------------|---------------|
| 21 | B2 | WALL MODIFICATION | MOD LSWP |

| | | |
|--------------|------------------|--------------|
| Site Address | City, State, Zip | Cheshire, CT |
|--------------|------------------|--------------|

| | | | | | |
|----------------|---|---------------|------------------|--------------------------------|------|
| Structure Type | x | Single Family | Apartment | Approx. Construction Date (Yr) | 1900 |
| | | Town House | Other (describe) | Approx. Square Footage | 6000 |
| | | Condomium | | No. of Separate Rooms | 34 |

Location of Work w/in structure 1ST FLOOR BATHROOM

| Lead Content of Affected Surfaces | | | | Work Statistics | | |
|-----------------------------------|------------|--------|--------|--------------------------|-------|--|
| Surface | XRF Result | and/or | % Lead | No. of Workers | | |
| A - WALL | 1.4 | | | 1 | | |
| | | | | Start Time | 9:25 | |
| | | | | Stop Time | 10:14 | |
| | | | | Total Time (hrs) | 0.8 | |
| | | | | Tools and Equipment Used | | |
| Use attached checklist | | | | | | |

Pre-Work Sampling

| Air Sampling | | | | | | | | | | |
|---|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. <small>(P-ScenarioID-Date-## -A-Type)</small> | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| P-B2-041906-16 | -A-Area | 17179 | 15:06 | 2.63 | 15:42 | 2.62 | 36 | 2.62 | 94.3 | <21 |
| P-041906-17 | -A-OS | 16608 | 15:09 | 2.60 | 15:44 | 2.60 | 35 | 2.60 | 91.0 | <22 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Air Sampling | | | | | | | | | | |
|---|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. <small>(P-ScenarioID-Date-## -A-Type)</small> | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| D-B2-042106-69 | -A-Area | 17185 | 9:25 | 2.65 | 10:12 | 2.61 | 47 | 2.61 | 122.7 | <16 |
| D-B2-042106-72 | -A-PBZ | 18107 | 9:25 | 2.61 | 10:14 | 2.52 | 49 | 2.52 | 123.5 | <24 |
| D-042106-71 | -A-OS | 16608 | 9:25 | 2.58 | 11:13 | 2.59 | 108 | 2.58 | 278.6 | <7 |

Post-Work Sampling

| Air Sampling | | | | | | | | | | |
|---|----------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. <small>(P-ScenarioID-Date-## -A-Type)</small> | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| C-B2-042106-77 | -A-Area | 17185 | 10:13 | 2.61 | 11:11 | 2.58 | 58 | 2.58 | 149.6 | <13 |

Wipe Sampling

Date 4/21/2006 Collected by

| Pre-Work Wipe Sampling | | | | | |
|--|----------|-----------------|----------------|---------------------------------|------------------------------|
| Sample No. <small>(P-ScenarioID-Date-##-W-Location)</small> | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| P-B2-041906-51 | -W-Area | 1ST FL BATHROOM | FLOOR - A WALL | 1.00 | 124 |
| P-B2-041906-52 | -W-Area | 1ST FL BATHROOM | FLOOR - C WALL | 1.00 | 15 |
| P-B2-041906-53 | -W-Area | 1ST FL BATHROOM | SILL - A WALL | 0.46 | 898 |
| P-041906-57 | -W-OS | 1ST FL HALL | FLOOR | 1.00 | 42.5 |

| Post-Work Wipe Sampling | | | | | |
|--|----------|-----------------|----------------|---------------------------------|------------------------------|
| Sample No. <small>(P-ScenarioID-Date-##-W-Location)</small> | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| C-B2-042106-1 | -W-Area | 1ST FL BATHROOM | FLOOR - A WALL | 1.00 | 21.4 |
| C-B2-042106-2 | -W-Area | 1ST FL BATHROOM | FLOOR - C WALL | 1.00 | 18.2 |
| C-B2-042106-3 | -W-Area | 1ST FL BATHROOM | SILL - A WALL | 0.46 | 118 |
| C-042106-4 | -W-OS | 1ST FL HALL | FLOOR | 1.00 | 31.2 |

OS - Outside of work area

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-------------------|
| Hygienist | |
| Activity | WALL MODIFICATION |
| Work Practice | MOD LSWP |

| | |
|---|--------------|
| DATE | 4/21/2006 |
| LOCATION | Cheshire, CT |
| SCENARIO | B2a |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | |
| Utility Knife | |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 4/21/2006 Hygienist -

| Event | ID | Activity | Work Practice |
|-------|----|-------------------|---------------|
| 22 | B2 | WALL MODIFICATION | MOD LSWP |

| | |
|--------------------------------------|--------------|
| Site Address City, State, Zip | Cheshire, CT |
|--------------------------------------|--------------|

| | | | | | | |
|-----------------------|-------------------------------------|---------------|--------------------------|------------------|--------------------------------|------|
| Structure Type | <input checked="" type="checkbox"/> | Single Family | <input type="checkbox"/> | Apartment | Approx. Construction Date (Yr) | 1900 |
| | <input type="checkbox"/> | Town House | <input type="checkbox"/> | Other (describe) | Approx. Square Footage | 6000 |
| | <input type="checkbox"/> | Condomium | | | No. of Separate Rooms | 34 |

Location of Work w/in structure BATHROOM 5

| Lead Content of Affected Surfaces | | | | Work Statistics | | |
|-----------------------------------|------------|--------|--------|--------------------------|------------|-----------|
| Surface | XRF Result | and/or | % Lead | No. of Workers | Start Time | Stop Time |
| A - WALL | 1.0 | | | 1 | 9:22 | 10:07 |
| | | | | Total Time (hrs) | 0.8 | |
| | | | | Tools and Equipment Used | | |
| Use attached checklist | | | | | | |

Pre-Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------------------------|-------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|--|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| P-B2-041906-19 | -A-Area | BATHROOM 5 | 17451 | 15:09 | 2.55 | 15:47 | 38 | 2.55 | 96.9 | <21 | |
| P-041906-18 | -A-OS | 2ND FL HALL | 17183 | 15:06 | 2.58 | 15:40 | 34 | 2.41 | 81.9 | <24 | |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------------------------|-------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|--|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| D-B2-042106-73 | -A-Area | BATHROOM 5 | 17180 | 9:22 | 2.63 | 10:05 | 43 | 2.57 | 110.5 | <18 | |
| D-B2-042106-74 | -A-PBZ | WORKER | 18104 | 9:22 | 2.67 | 10:07 | 45 | 2.52 | 113.4 | <18 | |
| D-042106-70 | -A-OS | 2ND FL HALL | 18105 | 9:19 | 2.55 | 11:07 | 108 | 2.55 | 275.4 | <7 | |

Post-Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------|------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|--|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| C-B2-042106-78 | -A-Area | BATHROOM 5 | 17180 | 10:06 | 2.57 | 11:06 | 60 | 2.56 | 153.6 | <13 | |

Wipe Sampling

Date 4/21/2006 Collected by

| Pre-Work Wipe Sampling | | | | | | |
|---|----------|-------------|----------------|---------------------------------|------------------------------|------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| P-B2-041906-58 | -W-Area | BATHROOM 5 | FLOOR - A WALL | TILE | 1.00 | 231 |
| P-B2-041906-59 | -W-Area | BATHROOM 5 | FLOOR - C WALL | TILE | 1.00 | 13.4 |
| P-B2-041906-60 | -W-Area | BATHROOM 5 | SILL - A WALL | WOOD | 1.00 | 554 |
| P-041906-64 | -W-OS | 2ND FL HALL | FLOOR | STONE | 1.00 | NR |

| Post-Work Wipe Sampling | | | | | | |
|---|----------|-------------|----------------|---------------------------------|------------------------------|------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| C-B2-042106-5 | -W-Area | BATHROOM 5 | FLOOR - A WALL | TILE | 1.00 | 28.5 |
| C-B2-042106-6 | -W-Area | BATHROOM 5 | FLOOR - C WALL | TILE | 1.00 | 35 |
| C-B2-042106-7 | -W-Area | BATHROOM 5 | SILL - A WALL | TILE | 1.00 | 19.9 |
| C-042106-11 | -W-OS | 2ND FL HALL | FLOOR | STONE | 1.00 | 40.8 |

OS - Outside of work area

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-------------------|
| Hygienist | |
| Activity | WALL MODIFICATION |
| Work Practice | MOD LSWP |

| | |
|---|--------------|
| DATE | 4/21/2006 |
| LOCATION | Cheshire, CT |
| SCENARIO | B2b |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | |
| Utility Knife | |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 4/20/2006 Hygienist -

| Event | ID | Activity | Work Practice |
|-------|----|----------------------------|---------------|
| 23 | C1 | Window jamb removal (wood) | Routine |

| | |
|--------------------------------------|----------------|
| Site Address City, State, Zip | Farmington, CT |
|--------------------------------------|----------------|

| | | | | | | |
|-----------------------|-------------------------------------|---------------|--------------------------|------------------|--------------------------------|-----------|
| Structure Type | <input checked="" type="checkbox"/> | Single Family | <input type="checkbox"/> | Apartment | Approx. Construction Date (Yr) | 1800/1950 |
| | <input type="checkbox"/> | Town House | <input type="checkbox"/> | Other (describe) | Approx. Square Footage | 2000 |
| | <input type="checkbox"/> | Condomium | | | No. of Separate Rooms | 16 |

| | | | | | |
|--|------------|--|--------|--------------------------|-----|
| Location of Work w/in structure | BEDROOM 2 | | | | |
| Lead Content of Affected Surfaces | | | | Work Statistics | |
| Surface | XRF Result | | % | No. of Workers | 1 |
| WINDOW CASING | >9.9 | | and/or | Start Time | 851 |
| WINDOW SASH | 6.5 | | | Stop Time | 944 |
| WINDOW SILL | >9.9 | | | Total Time (hrs) | 1 |
| | | | | Tools and Equipment Used | |
| Use attached checklist | | | | | |

Pre-Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------------------------|----------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| P-C1-041906-11 | -A-Area | Bedroom 2 | 16668 | 13:33 | 2.62 | 14:07 | 2.60 | 34 | 2.60 | 88.4 | < 23 |
| P-041906-13 | -A-OS** | 2nd floor hall | 18105 | 13:35 | 2.55 | 14:11 | 2.55 | 36 | 2.55 | 91.8 | < 22 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------------------------|----------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| D-C1-042006-23 | -A-Area | Bedroom 2 | 16669 | 8:51 | 2.57 | 9:43 | 2.58 | 52 | 2.57 | 133.6 | 868 |
| D-C1-042006-25 | -A-PBZ | Worker | 17185 | 8:51 | 2.62 | 9:44 | 2.59 | 53 | 2.59 | 137.3 | 926 |
| D-042006-22 | -A-OS | 2nd floor hall | 16609 | 7:55 | 2.59 | 11:09 | 2.58 | 194 | 2.58 | 500.5 | 53 |

Post-Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------|-----------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. (C-ScenarioID-Date-## -A-Type) | Location | | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| C-C1-042006-34 | -A-Area | Bedroom 2 | 16669 | 10:04 | 2.58 | 11:06 | 2.56 | 62 | 2.56 | 158.7 | 190 |

Wipe Sampling

Date 4/20/2006 Collected by -

| Pre-Work Wipe Sampling | | | | | |
|---|----------|-------------|----------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| P-C1-041906-41 | -W-Area | BEDROOM 2 | FLOOR - A WALL | 1.00 | 983 |
| P-C1-041906-42 | -W-Area | BEDROOM 2 | FLOOR - C WALL | 1.00 | 90.6 |
| P-C1-041906-43 | -W-Area | BEDROOM 2 | SILL - D WALL | 0.25 | 812 |
| P-041906-47 | -W-OS | 2ND FL HALL | FLOOR | 1.00 | 54.2 |

| Post-Work Wipe Sampling | | | | | |
|---|----------|-------------|----------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| C-C1-042006-7 | -W-Area | BEDROOM 2 | FLOOR - A WALL | 1.00 | 1240 |
| C-C1-042006-8 | -W-Area | BEDROOM 2 | FLOOR - C WALL | 1.00 | 774 |
| C-C1-042006-9 | -W-Area | BEDROOM 2 | SILL - D WALL | 0.25 | 6440 |
| C-042006-14 | -W-OS | 2ND FL HALL | FLOOR | 1.00 | 108 |

OS - Outside of work area

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|---------------------|
| Hygienist | |
| Activity | WINDOW JAMB REMOVAL |
| Work Practice | ROUTINE |

| | |
|---|----------------|
| DATE | 4/20/2006 |
| LOCATION | Farmington, CT |
| SCENARIO | C1a |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | X |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | X |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | X |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 4/20/2006 Hygienist -

| Event | ID | Activity | Work Practice |
|-------|----|---------------------|---------------|
| 24 | C1 | WINDOW JAMB REMOVAL | ROUTINE |

| | |
|--------------------------------------|----------------|
| Site Address City, State, Zip | Farmington, CT |
|--------------------------------------|----------------|

| | | | | | | |
|-----------------------|-------------------------------------|---------------|--------------------------|------------------|--------------------------------|-----------|
| Structure Type | <input checked="" type="checkbox"/> | Single Family | <input type="checkbox"/> | Apartment | Approx. Construction Date (Yr) | 1800/1950 |
| | <input type="checkbox"/> | Town House | <input type="checkbox"/> | Other (describe) | Approx. Square Footage | 2000 |
| | <input type="checkbox"/> | Condomium | | | No. of Separate Rooms | 16 |

Location of Work w/in structure LIVING ROOM

| Lead Content of Affected Surfaces | | | | Work Statistics | | |
|-----------------------------------|------------|--------|------|--------------------------|------------|-----------|
| Surface | XRF Result | % | Lead | No. of Workers | Start Time | Stop Time |
| WINDOW CASING | >9.9 | and/or | | 1 | 8:58 | 9:53 |
| WINDOW SILL | 1.4 | | | | 107.8 | 0.9 |
| | | | | | | |
| | | | | Tools and Equipment Used | | |
| Use attached checklist | | | | | | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P-C1-041906-06 | -A-Area LIVING ROOM N | 17180 | 13:13 | 2.60 | 13:53 | 2.62 | 40 | 2.60 | 104.0 | < 19 |
| P-C1-041906-07 | -A-Area LIVING ROOM S | 18104 | 13:16 | 2.66 | 13:57 | 2.63 | 41 | 2.63 | 107.8 | < 19 |
| P-041906-01 | -A-OS KITCHEN | 16609 | 12:58 | 2.57 | 13:36 | 2.59 | 38 | 2.57 | 97.7 | < 21 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-C1-042006-30 | -A-Area LIVING ROOM N | 17865 | 8:58 | 2.56 | 9:54 | 2.62 | 56 | 2.56 | 143.4 | 165 |
| D-C1-042006-31 | -A-Area LIVING ROOM S | 18112 | 8:58 | 2.57 | 9:56 | 2.62 | 58 | 2.57 | 149.1 | 179 |
| D-C1-042006-32 | -A-PBZ WORKER | 17179 | 8:58 | 2.64 | 9:53 | 2.63 | 55 | 2.63 | 144.7 | 324 |
| D-042006-27 | -A-OS KITCHEN | 17183 | 8:20 | 2.59 | 10:58 | 2.68 | 158 | 2.59 | 409.2 | < 5 |

Post-Work Sampling

| Sample No. (C-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-C1-042006-35 | -A-Area LIVING ROOM N | 17865 | 9:57 | 2.62 | 11:00 | 2.60 | 63 | 2.60 | 163.8 | 32 |
| C-C1-042006-36 | -A-Area LIVING ROOM S | 18112 | 9:58 | 2.62 | 11:02 | 2.59 | 64 | 2.59 | 165.8 | 29 |

Wipe Sampling

Date 4/20/2006 Collected by -

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|---------------------|----------------|--------------|---------------------------------|------------------------------|
| P-C1-041906-35 | -W-Area LIVING ROOM | FLOOR - A WALL | WOOD | 1.00 | 33.6 |
| P-C1-041906-36 | -W-Area LIVING ROOM | FLOOR - C WALL | WOOD | 1.00 | 37.2 |
| P-C1-041906-37 | -W-Area LIVING ROOM | SILL - D WALL | WOOD | 0.25 | 366 |
| P-041906-31 | -W-OS KITCHEN | FLOOR | WOOD | 1.00 | 15 |

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|---------------------|----------------|--------------|---------------------------------|------------------------------|
| C-C1-042006-4 | -W-Area LIVING ROOM | FLOOR - A WALL | WOOD | 1.00 | 77.1 |
| C-C1-042006-5 | -W-Area LIVING ROOM | FLOOR - C WALL | WOOD | 1.00 | 205 |
| C-C1-042006-6 | -W-Area LIVING ROOM | SILL - D WALL | WOOD | 0.25 | 3080 |
| C-042006-13 | -W-OS KITCHEN | FLOOR | CARPET | 1.00 | 20.5 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|---------------------|
| Hygienist | |
| Activity | WINDOW JAMB REMOVAL |
| Work Practice | ROUTINE |

| | |
|---|----------------|
| DATE | 4/20/2006 |
| LOCATION | Farmington, CT |
| SCENARIO | C1b |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | X |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | X |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | X |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 4/20/2006 Hygienist -

| Event | ID | Activity | Work Practice |
|-------|----|----------------------------|---------------|
| 25 | C2 | Window jamb removal (wood) | Mod LSWP |

| | | |
|--------------|------------------|----------------|
| Site Address | City, State, Zip | Farmington, CT |
|--------------|------------------|----------------|

| | | | | | |
|----------------|---|---------------|------------------|--------------------------------|-----------|
| Structure Type | x | Single Family | Apartment | Approx. Construction Date (Yr) | 1800/1950 |
| | | Town House | Other (describe) | Approx. Square Footage | 2000 |
| | | Condomium | | No. of Separate Rooms | 16 |

| | | | | | |
|-----------------------------------|------------|--------|------|---|--|
| Location of Work w/in structure | BEDROOM 3 | | | | |
| Lead Content of Affected Surfaces | | | | | |
| Surface | XRF Result | | % | Work Statistics No. of Workers: 1 Start Time: 849 Stop Time: 1000 Total Time (hrs): 1 Tools and Equipment Used <i>Use attached checklist</i> | |
| WINDOW CASING | >9.9 | | Lead | | |
| WINDOW SASH | 1.7 | and/or | | | |
| WINDOW SILL | 7.2 | | | | |
| | | | | | |

Pre-Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|--|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| P-C2-041906-12 -A-Area | Bedroom 3 | 18107 | 13:35 | 2.55 | 14:11 | 2.55 | 36 | 2.55 | 91.8 | < 22 | |
| P-041906-13 -A-OS** | 2nd floor hall | 18105 | 13:35 | 2.55 | 14:11 | 2.55 | 36 | 2.55 | 91.8 | < 22 | |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|--|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| D-C2-042006-24 -A-Area | Bedroom 3 | 16612 | 8:49 | 2.61 | 10:02 | 2.60 | 73 | 2.60 | 189.8 | 428 | |
| D-C2-042006-26 -A-PBZ | Worker | 17184 | 8:49 | 2.59 | 10:00 | 2.60 | 71 | 2.59 | 183.9 | 805 | |
| D-042006-22 -A-OS | 2nd floor hall | 16609 | 7:55 | 2.59 | 11:09 | 2.58 | 194 | 2.58 | 500.5 | 53 | |

Post-Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|-----------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|--|
| Sample No. (C-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| C-C2-042006-37 -A-Area | Bedroom 3 | 16612 | 10:03 | 2.60 | 11:04 | 2.60 | 61 | 2.60 | 158.6 | 126 | |

Wipe Sampling

Date 4/20/2006 Collected by -

| Pre-Work Wipe Sampling | | | | | |
|---|-------------|----------------|--------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| P-C2-041906-44 -W-Area | BEDROOM 3 | FLOOR - A WALL | WOOD | 1.00 | NR |
| P-C2-041906-45 -W-Area | BEDROOM 3 | FLOOR - C WALL | WOOD | 1.00 | 106 |
| P-C2-041906-46 -W-Area | BEDROOM 3 | SILL - D WALL | WOOD | 0.25 | 370 |
| P-041906-47 -W-OS | 2ND FL HALL | FLOOR | WOOD | 1.00 | 54.2 |

| Post-Work Wipe Sampling | | | | | |
|---|-------------|----------------|--------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| C-C2-042006-10 -W-Area | BEDROOM 3 | FLOOR - A WALL | WOOD | 1.00 | 4320 |
| C-C2-042006-11 -W-Area | BEDROOM 3 | FLOOR - C WALL | WOOD | 1.00 | 2090 |
| C-C2-042006-12 -W-Area | BEDROOM 3 | SILL - D WALL | WOOD | 0.25 | 10800 |
| C-042006-14 -W-OS | 2ND FL HALL | FLOOR | WOOD | 1.00 | 108 |

OS - Outside of work area

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|---------------------|
| Hygienist | |
| Activity | WINDOW JAMB REMOVAL |
| Work Practice | MOD LSWP |

| | |
|---|----------------|
| DATE | 4/20/2006 |
| LOCATION | Farmington, CT |
| SCENARIO | C2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | X |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 4/20/2006 Hygienist -

| Event | ID | Activity | Work Practice |
|-------|----|-----------------|---------------|
| 26 | D1 | CABINET REMOVAL | ROUTINE |

| | | |
|--------------|------------------|----------------|
| Site Address | City, State, Zip | Farmington, CT |
|--------------|------------------|----------------|

| | | | | | |
|----------------|---|---------------|------------------|--------------------------------|-----------|
| Structure Type | x | Single Family | Apartment | Approx. Construction Date (Yr) | 1800/1950 |
| | | Town House | Other (describe) | Approx. Square Footage | 2000 |
| | | Condomium | | No. of Separate Rooms | 16 |

Location of Work w/in structure 1ST FLOOR BATHROOM

| Lead Content of Affected Surfaces | | | | Work Statistics | | |
|-----------------------------------|------------|---|--------|-------------------------------|------------|--|
| Surface | XRF Result | % | Lead | No. of Workers | Start Time | |
| CABINET SHELF | 2.1 | | | 1 | 11:24 | |
| | | | and/or | 12:10 | 0.8 | |
| | | | | Total Time (hrs) | | |
| | | | | Tools and Equipment Used | | |
| | | | | Use attached checklist | | |

Pre-Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------------------------|----------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| P-D1-041906-02 | -A-Area | BATHROOM | 17184 | 13:01 | 2.52 | 13:38 | 2.54 | 37 | 2.52 | 93.2 | < 21 |
| P-041906-01 | -A-OS | KITCHEN | 16609 | 12:58 | 2.57 | 13:36 | 2.59 | 38 | 2.57 | 97.7 | < 21 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------------------------|----------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| D-D1-042006-41 | -A-Area | BATHROOM | 18105 | 11:24 | 2.55 | 12:08 | 2.55 | 44 | 2.55 | 112.2 | < 18 |
| D-D1-042006-45 | -A-PBZ | WORKER | 17179 | 11:24 | 2.63 | 12:10 | 2.61 | 46 | 2.61 | 120.1 | 20 |
| D-042006-49 | -A-OS | KITCHEN | 17183 | 11:26 | 2.68 | 13:02 | 2.62 | 96 | 2.62 | 251.5 | < 8 |

Post-Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------|----------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| C-D1-042006-52 | -A-Area | BATHROOM | 18105 | 12:08 | 2.55 | 13:08 | 2.53 | 60 | 2.53 | 151.8 | < 13 |

Wipe Sampling

Date 4/20/2006 Collected by -

| Wipe Sampling | | | | | | |
|---|----------|----------|----------------|---------------------------------|------------------------------|------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| P-D1-041906-28 | -W-Area | BATHROOM | FLOOR - B WALL | LINOLEUM | 1.00 | 31.3 |
| P-D1-041906-29 | -W-Area | BATHROOM | FLOOR - D WALL | LINOLEUM | 1.00 | 18.9 |
| P-D1-041906-30 | -W-Area | BATHROOM | SILL - B WALL | WOOD | 0.21 | 543 |
| P-041906-31 | -W-OS | KITCHEN | FLOOR | CARPET | 1.00 | 15 |

| Wipe Sampling | | | | | | |
|---|----------|----------|----------------|----------------------------|------------------------------|------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Sampled (ft ²) | Result (ug/ft ²) | |
| C-D1-042006-15 | -W-Area | BATHROOM | FLOOR - B WALL | LINOLEUM | 1.00 | 93.9 |
| C-D1-042006-16 | -W-Area | BATHROOM | FLOOR - D WALL | LINOLEUM | 1.00 | 91.4 |
| C-D1-042006-17 | -W-Area | BATHROOM | SILL - B WALL | WOOD | 0.21 | 95.7 |
| C-042006-21 | -W-OS | KITCHEN | FLOOR | CARPET | 1.00 | 16.3 |

OS - Outside of work area

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-----------------|
| Hygienist | |
| Activity | CABINET REMOVAL |
| Work Practice | ROUTINE |

| | |
|---|----------------|
| DATE | 4/20/2006 |
| LOCATION | Farmington, CT |
| SCENARIO | D1 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Opening Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | X |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | X |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 4/20/2006 Hygienist -

| Event | ID | Activity | Work Practice |
|-------|----|-----------------|---------------|
| 27 | D2 | Cabinet Removal | Mod LSWP |

| Site Address | City, State, Zip |
|--------------|------------------|
| | Farmington, CT |

| Structure Type | x | Single Family | Apartment | Approx. Construction Date (Yr) |
|----------------|---|---------------|------------------|--------------------------------|
| | | Town House | Other (describe) | 1800/1950 |
| | | Condomium | | Approx. Square Footage |
| | | | | 2000 |
| | | | | No. of Separate Rooms |
| | | | | 16 |

Location of Work w/in structure DINING ROOM

| Lead Content of Affected Surfaces | | | | Work Statistics | | |
|-----------------------------------|------------|--------|------|-------------------------------|------------|-----------|
| Surface | XRF Result | % | Lead | No. of Workers | Start Time | Stop Time |
| CABINET DOOR | >9.9 | | | 1 | 8:59 | 10:12 |
| CABINET SHELF | 9.8 | | | | | |
| | | and/or | | Total Time (hrs) | 1.2 | |
| | | | | Tools and Equipment Used | | |
| | | | | Use attached checklist | | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P-D2-041906-08 -A-Area | DINING ROOM NW | 16608 | 13:19 | 2.60 | 14:00 | 2.60 | 41 | 2.60 | 106.6 | < 19 |
| P-D2-041906-09 -A-Area | DINING ROOM SE | 17179 | 13:21 | 2.60 | 14:02 | 2.62 | 41 | 2.60 | 106.6 | < 19 |
| P-041906-01 -A-OS | KITCHEN | 16609 | 12:58 | 2.57 | 13:36 | 2.59 | 38 | 2.57 | 97.7 | < 21 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-042006-29 -A-Area | DINING ROOM NW | 16608 | 9:00 | 2.56 | 10:15 | 2.57 | 75 | 2.56 | 192.0 | 14 |
| D-D2-042006-28 -A-Area | DINING ROOM SE | 16670 | 8:59 | 2.56 | 10:13 | 2.57 | 74 | 2.56 | 189.4 | 13 |
| D-D2-042006-33 -A-PBZ | WORKER | 18107 | 8:59 | 2.60 | 10:12 | 2.56 | 73 | 2.56 | 186.9 | 42 |
| D-042006-27 -A-OS | KITCHEN | 17183 | 8:20 | 2.59 | 10:58 | 2.68 | 158 | 2.59 | 409.2 | < 5 |

Post-Work Sampling

| Sample No. (C-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-D2-042006-39 -A-Area | DINING ROOM NW | 16608 | 10:16 | 2.57 | 11:13 | 2.58 | 57 | 2.57 | 146.5 | < 14 |
| C-D2-042006-38 -A-Area | DINING ROOM SE | 16670 | 10:14 | 2.57 | 11:15 | 2.59 | 61 | 2.57 | 156.8 | < 13 |

Wipe Sampling

Date 4/20/2006 Collected by -

| Pre-Work Wipe Sampling | | | | | |
|--|-------------|----------------|--------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| P-D2-041906-32 -W-Area | DINING ROOM | FLOOR - B WALL | WOOD | 1.00 | 15.4 |
| P-D2-041906-33 -W-Area | DINING ROOM | FLOOR - D WALL | WOOD | 1.00 | 22.5 |
| P-D2-041906-34 -W-Area | DINING ROOM | SILL - A WALL | WOOD | 0.25 | 820 |
| P-041906-31 -W-OS | KITCHEN | FLOOR | WOOD | 1.00 | 15 |

| Post-Work Wipe Sampling | | | | | |
|--|-------------|----------------|--------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| C-D2-042006-1 -W-Area | DINING ROOM | FLOOR - B WALL | WOOD | 1.00 | 84.4 |
| C-D2-042006-2 -W-Area | DINING ROOM | FLOOR - D WALL | WOOD | 1.00 | 170 |
| C-D2-042006-3 -W-Area | DINING ROOM | SILL - A WALL | WOOD | 1.00 | 328 |
| C-042006-13 -W-OS | KITCHEN | FLOOR | CARPET | 1.00 | 20.5 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-----------------|
| Hygienist | |
| Activity | CABINET REMOVAL |
| Work Practice | MOD LSWP |

| | |
|---|----------------|
| DATE | 4/20/2006 |
| LOCATION | Farmington, CT |
| SCENARIO | D2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Opening Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 4/20/2006 Hygienist -

| Event | ID | Activity | Work Practice |
|-------|----|-------------------|---------------|
| 28 | E1 | BASEBOARD REMOVAL | ROUTINE |

| Site Address | City, State, Zip | Farmington, CT | |
|--------------|------------------|----------------|--|
|--------------|------------------|----------------|--|

| Structure Type | x | Single Family | Apartment | Approx. Construction Date (Yr) | 1800/1950 |
|----------------|---|---------------|------------------|--------------------------------|-----------|
| | | Town House | Other (describe) | Approx. Square Footage | 2000 |
| | | Condomium | | No. of Separate Rooms | 16 |

Location of Work w/in structure FAMILY ROOM (NO LBP ON AFFECTED SURFACES)

| Lead Content of Affected Surfaces | | | | Work Statistics | | |
|-----------------------------------|------------|--------|------|--------------------------|-------|--|
| Surface | XRF Result | % | Lead | No. of Workers | 1 | |
| BASEBOARDS | <1.0 | and/or | | Start Time | 13:37 | |
| WALLS | <1.0 | | | Stop Time | 14:24 | |
| | | | | Total Time (hrs) | 0.8 | |
| | | | | Tools and Equipment Used | | |
| Use attached checklist | | | | | | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P-E1-041906-04 | -A-Area FAMILY ROOM E | 16669 | 13:07 | 2.58 | 13:47 | 2.55 | 40 | 2.55 | 102.0 | < 20 |
| P-E1-041906-05 | -A-Area FAMILY ROOM W | 16612 | 13:10 | 2.65 | 13:51 | 2.62 | 41 | 2.62 | 107.4 | < 19 |
| P-041906-01 | -A-OS KITCHEN | 16609 | 12:58 | 2.57 | 13:36 | 2.59 | 38 | 2.57 | 97.7 | < 21 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-E1-042006-55 | -A-Area FAMILY ROOM E | 166770 | 13:37 | 2.59 | 14:20 | 2.54 | 43 | 2.54 | 109.2 | < 18 |
| D-E1-042006-56 | -A-Area FAMILY ROOM W | 16608 | 13:37 | 2.58 | 14:22 | 2.55 | 45 | 2.55 | 114.8 | < 17 |
| D-E1-042006-59 | -A-PBZ WORKER | 17179 | 13:37 | 2.61 | 14:24 | 2.62 | 47 | 2.61 | 122.7 | < 16 |
| D-042006-61 | -A-OS KITCHEN | 17183 | 13:18 | 2.62 | 15:08 | 2.62 | 110 | 2.62 | 288.2 | < 7 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|-----------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-E1-042006-66 | -A-Area FAMILY ROOM W | 16608 | 14:22 | 2.55 | 15:22 | 2.57 | 60 | 2.55 | 153.0 | < 13 |
| C-E1-042006-67 | -A-Area FAMILY ROOM E | 16670 | 14:20 | 2.54 | 15:20 | 2.54 | 60 | 2.54 | 152.4 | < 13 |

Wipe Sampling

Date 4/20/2006 Collected by -

| Pre-Work Wipe Sampling | | | | | | |
|---|---------------------|------------------------|--------------|---------------------------------|------------------------------|--|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| P-E1-041906-25 | -W-Area FAMILY ROOM | FLOOR - B WALL | WOOD | 1.00 | 13 | |
| P-E1-041906-26 | -W-Area FAMILY ROOM | FLOOR - D WALL | WOOD | 1.00 | 75.4 | |
| P-E1-041906-27 | -W-Area FAMILY ROOM | SILL - C WALL - CENTER | WOOD | 0.21 | 643 | |
| P-041906-31 | -W-OS KITCHEN | FLOOR | WOOD | 1.00 | 15 | |

| Post-Work Wipe Sampling | | | | | | |
|---|---------------------|------------------------|--------------|---------------------------------|------------------------------|--|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| C-E1-042006-34 | -W-Area FAMILY ROOM | FLOOR - B WALL | WOOD | 1.00 | 75.5 | |
| C-E1-042006-35 | -W-Area FAMILY ROOM | FLOOR - D WALL | WOOD | 1.00 | 75.6 | |
| C-E1-042006-36 | -W-Area FAMILY ROOM | SILL - C WALL - CENTER | WOOD | 0.25 | 200 | |
| C-042006-37 | -W-OS KITCHEN | FLOOR | CARPET | 1.00 | 15.9 | |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-------------------|
| Hygienist | |
| Activity | BASEBOARD REMOVAL |
| Work Practice | ROUTINE |

| | |
|---|----------------|
| DATE | 4/20/2006 |
| LOCATION | Farmington, CT |
| SCENARIO | E1 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | X |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | X |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 4/20/2006 Hygienist -

| Event | ID | Activity | Work Practice |
|----------|----|----------|---------------|
| Scenario | 29 | F2 | DOOR SANDING |
| | | | MOD LSWP |

| | |
|--------------------------------------|----------------|
| Site Address City, State, Zip | Farmington, CT |
|--------------------------------------|----------------|

| | | | | | |
|-----------------------|---|---------------|------------------|--------------------------------|-----------|
| Structure Type | x | Single Family | Apartment | Approx. Construction Date (Yr) | 1800/1950 |
| | | Town House | Other (describe) | Approx. Square Footage | 2000 |
| | | Condomium | | No. of Separate Rooms | 16 |

| | | | | | |
|--|----------------|--------|--------|-------------------------------|-------|
| Location of Work w/in structure | BEDROOM 1 | | | | |
| Lead Content of Affected Surfaces | | | | Work Statistics | |
| Surface | XRF Result | and/or | % Lead | No. of Workers | 1 |
| FACE OF DOOR | >9.9 | | | Start Time | 13:26 |
| LEFT JAMB | 2.9 | | | Stop Time | 14:08 |
| RIGHT CASING | >9.9 | | | Total Time (hrs) | 0.7 |
| | | | | Tools and Equipment Used | |
| | | | | Use attached checklist | |

Pre-Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------------------------|-------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| P-F2-041906-10 | -A-Area | BEDROOM 1 | 17863 | 13:24 | 2.53 | 14:05 | 2.56 | 41 | 2.53 | 103.7 | <19 |
| P-041906-13 | -A-OS | 2ND FL HALL | 18105 | 13:35 | 2.55 | 14:11 | 2.55 | 36 | 2.55 | 91.8 | < 22 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------------------------|-------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|-----|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| D-F2-042006-58 | -A-Area | BEDROOM 1 | 17180 | 13:26 | 2.61 | 14:06 | 2.53 | 40 | 2.53 | 101.2 | 78 |
| D-F2-042006-57 | -A-PBZ | WORKER | 17865 | 13:26 | 2.60 | 14:08 | 2.50 | 42 | 2.50 | 105.0 | 47 |
| D-042006-63 | -A-OS | 2ND FL HALL | 16609 | 13:16 | 2.54 | 15:02 | 2.56 | 106 | 2.54 | 269.2 | < 7 |

Post-Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------|-----------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| C-F2-042006-64 | -A-Area | BEDROOM 1 | 17180 | 14:07 | 2.53 | 15:04 | 2.57 | 57 | 2.53 | 144.2 | < 14 |

Wipe Sampling

Date 4/20/2006 Collected by -

| Pre-Work Wipe Sampling | | | | | | |
|---|----------|-------------|----------------|---------------------------------|------------------------------|------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| P-F2-041906-38 | -W-Area | BEDROOM 1 | FLOOR - B WALL | WOOD | 1.00 | 236 |
| P-F2-041906-39 | -W-Area | BEDROOM 1 | FLOOR - D WALL | WOOD | 1.00 | 231 |
| P-F2-041906-40 | -W-Area | BEDROOM 1 | SILL - D WALL | WOOD | 0.25 | 1480 |
| P-041906-47 | -W-OS | 2ND FL HALL | FLOOR | WOOD | 1.00 | 54.2 |

| Post-Work Wipe Sampling | | | | | | |
|---|----------|-------------|----------------|---------------------------------|------------------------------|------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| C-F2-042006-38 | -W-Area | BEDROOM 1 | FLOOR - A WALL | WOOD | 1.00 | 443 |
| C-F2-042006-39 | -W-Area | BEDROOM 1 | FLOOR - C WALL | WOOD | 1.00 | 318 |
| C-F2-042006-40 | -W-Area | BEDROOM 1 | SILL - C WALL | WOOD | 1.00 | 58.7 |
| C-042006-41 | -W-OS | 2ND FL HALL | FLOOR | WOOD | 1.00 | 103 |

OS - Outside of work area

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|--------------|
| Hygienist | |
| Activity | DOOR SANDING |
| Work Practice | MOD LSWP |

| | |
|---|----------------|
| DATE | 4/20/2006 |
| LOCATION | Farmington, CT |
| SCENARIO | F2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Opening Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | X |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 4/20/2006 Hygienist -

| Event | ID | Activity | Work Practice |
|-------|----|----------------------------|---------------|
| 30 | G1 | CUT SHELVING - SAWING WOOD | ROUTINE |

| | |
|--------------------------------------|----------------|
| Site Address City, State, Zip | Farmington, CT |
|--------------------------------------|----------------|

| | | | | | | |
|-----------------------|-------------------------------------|---------------|--------------------------|------------------|--------------------------------|-----------|
| Structure Type | <input checked="" type="checkbox"/> | Single Family | <input type="checkbox"/> | Apartment | Approx. Construction Date (Yr) | 1800/1950 |
| | <input type="checkbox"/> | Town House | <input type="checkbox"/> | Other (describe) | Approx. Square Footage | 2000 |
| | <input type="checkbox"/> | Condomium | | | No. of Separate Rooms | 16 |

| | | | |
|--|------------|--------|--------------------------|
| Location of Work w/in structure | REAR FOYER | | |
| Lead Content of Affected Surfaces | | | |
| Surface | XRF Result | | |
| CLOSET SHELF | 1.6 | | |
| | | and/or | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | Work Statistics |
| | | | No. of Workers |
| | | | Start Time |
| | | | Stop Time |
| | | | Total Time (hrs) |
| | | | Tools and Equipment Used |
| Use attached checklist | | | |

Pre-Work Sampling

| Air Sampling | | | | | | | | | | |
|--|----------------------------|------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| P-G1-041906-03 | -A-Area | REAR FOYER | 17185 | 13:04 | 2.67 | 13:44 | 2.63 | 40 | 2.63 | 105.2 < 19 |
| P-041906-01 | -A-OS | KITCHEN | 16609 | 12:58 | 2.57 | 13:36 | 2.59 | 38 | 2.57 | 97.7 < 21 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Air Sampling | | | | | | | | | | |
|--|----------------------------|------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| D-G1-042006-40 | -A-Area | REAR FOYER | 17451 | 11:25 | 2.61 | 12:12 | 2.62 | 47 | 2.61 | 122.7 < 16 |
| D-G1-042006-44 | -A-PBZ | WORKER | 18107 | 11:25 | 2.56 | 12:15 | 2.60 | 50 | 2.56 | 128.0 < 16 |
| D-042006-49 | -A-OS | KITCHEN | 17183 | 11:26 | 2.68 | 13:02 | 2.62 | 96 | 2.62 | 251.5 < 8 |

Post-Work Sampling

| Air Sampling | | | | | | | | | | |
|--|----------|------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| C-G1-042006-53 | -A-Area | REAR FOYER | 17451 | 12:12 | 2.62 | 13:05 | 2.66 | 53 | 2.62 | 138.9 < 14 |

Wipe Sampling

Date 4/20/2006 Collected by -

| Pre-Work Wipe Sampling | | | | | |
|---|----------|------------|--------------------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| P-G1-041906-22 | -W-Area | REAR FOYER | FLOOR - B WALL | 1.00 | 18 |
| P-G1-041906-23 | -W-Area | REAR FOYER | FLOOR - D WALL | 1.00 | < 10.0 |
| P-G1-041906-24 | -W-Area | REAR FOYER | SHELF - BOTTOM OF CLOSET | 1.00 | 18.4 |
| P-041906-31 | -W-OS | KITCHEN | FLOOR | 1.00 | 15 |

| Post-Work Wipe Sampling | | | | | |
|---|----------|------------|--------------------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| C-G1-042006-18 | -W-Area | REAR FOYER | FLOOR - B WALL | 1.00 | 90.3 |
| C-G1-042006-19 | -W-Area | REAR FOYER | FLOOR - D WALL | 1.00 | 49.2 |
| C-G1-042006-20 | -W-Area | REAR FOYER | SHELF - BOTTOM OF CLOSET | 1.00 | 2880 |
| C-042006-21 | -W-OS | KITCHEN | FLOOR | 1.00 | 16.3 |

OS - Outside of work area

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|--------------|
| Hygienist | |
| Activity | CUT SHELVING |
| Work Practice | ROUTINE |

| | |
|---|----------------|
| DATE | 4/20/2006 |
| LOCATION | Farmington, CT |
| SCENARIO | G1b |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Opening Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | X |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | X |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 4/20/2006 Hygienist -

| Event | ID | Activity | Work Practice |
|-------|----|-------------------|---------------|
| 31 | E2 | BASEBOARD REMOVAL | MOD LSWP |

| | |
|--------------------------------------|----------------|
| Site Address City, State, Zip | Farmington, CT |
|--------------------------------------|----------------|

| | | | | | |
|-----------------------|---|---------------|------------------|--------------------------------|-----------|
| Structure Type | x | Single Family | Apartment | Approx. Construction Date (Yr) | 1800/1950 |
| | | Town House | Other (describe) | Approx. Square Footage | 2000 |
| | | Condomium | | No. of Separate Rooms | 16 |

| | | | | | |
|--|------------|--------|------|-------------------------------|-------|
| Location of Work w/in structure | REAR FOYER | | | | |
| Lead Content of Affected Surfaces | | | | | |
| Surface | XRF Result | % | Lead | Work Statistics | |
| BASEBOARD | >9.9 | | | | |
| | | and/or | | | |
| | | | | | |
| | | | | | |
| | | | | No. of Workers | 1 |
| | | | | Start Time | 13:36 |
| | | | | Stop Time | 14:17 |
| | | | | Total Time (hrs) | 0.7 |
| | | | | Tools and Equipment Used | |
| | | | | Use attached checklist | |

Pre-Work Sampling

| Air Sampling | | | | | | | | | | |
|--|----------------------------|------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| P-E2-042006-53 | -A-Area | REAR FOYER | 17451 | 12:12 | 2.62 | 13:05 | 2.66 | 53 | 2.62 | 138.9 < 14 |
| D-042006-49 | -A-OS | KITCHEN | 17183 | 11:26 | 2.62 | 13:02 | 2.62 | 96 | 2.62 | 251.5 < 8 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Air Sampling | | | | | | | | | | |
|--|----------------------------|------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| D-E2-042006-62 | -A-Area | REAR FOYER | 17451 | 13:36 | 2.66 | 14:18 | 2.64 | 42 | 2.64 | 110.9 < 18 |
| D-E2-042006-60 | -A-PBZ | WORKER | 18107 | 13:36 | 2.60 | 14:17 | 2.56 | 41 | 2.56 | 105.0 < 19 |
| D-042006-61 | -A-OS | KITCHEN | 17183 | 13:18 | 2.62 | 15:08 | 2.62 | 110 | 2.62 | 288.2 < 7 |

Post-Work Sampling

| Air Sampling | | | | | | | | | | |
|--|----------|------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| C-E2-042006-65 | -A-Area | REAR FOYER | 17451 | 14:18 | 2.64 | 15:17 | 2.64 | 59 | 2.64 | 155.8 < 13 |

* - Post-work PBZ only required for scenarios where clean-up or other activities with exposures different than "during work" activities and that work will take at least 135 min (2-hrs, 15-min)

Wipe Sampling

Date 4/20/2006 Collected by -

| Pre-Work Wipe Sampling | | | | | | |
|---|----------|------------|--------------------------|---------------------------------|------------------------------|--|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| P-E2-042006-18 | -W-Area | REAR FOYER | FLOOR - B WALL | WOOD | 1.00 90.3 | |
| P-E2-042006-19 | -W-Area | REAR FOYER | FLOOR - D WALL | WOOD | 1.00 49.2 | |
| P-E2-042006-20 | -W-Area | REAR FOYER | SHELF - BOTTOM OF CLOSET | WOOD | 1.00 2880 | |
| P-042006-21 | -W-OS | KITCHEN | FLOOR | CARPET | 1.00 16.3 | |
| Post-Work Wipe Sampling | | | | | | |
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| C-E2-042006-31 | -W-Area | REAR FOYER | FLOOR - D WALL | WOOD | 1.00 58.7 | |
| C-E2-042006-32 | -W-Area | REAR FOYER | FLOOR - B WALL | WOOD | 1.00 26.5 | |
| C-E2-042006-33 | -W-Area | REAR FOYER | FLOOR - A WALL | WOOD | 0.25 138 | |
| C-042006-37 | -W-OS | KITCHEN | FLOOR | CARPET | 1.00 15.9 | |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-------------------|
| Hygienist | |
| Activity | BASEBOARD REMOVAL |
| Work Practice | MOD LSWP |

| | |
|---|----------------|
| DATE | 4/20/2006 |
| LOCATION | Farmington, CT |
| SCENARIO | E2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date: 4/20/2006 Hygienist: -

| Event | ID | Activity | Work Practice |
|-------|----|---|---------------|
| 32 | G1 | CLOSET SHELF REMOVAL (WOOD) - SAWING WOOD | Routine |

| | | |
|--------------|------------------|----------------|
| Site Address | City, State, Zip | Farmington, CT |
|--------------|------------------|----------------|

| | | | | |
|----------------|---|---|--------------------------------|-----------|
| Structure Type | <input checked="" type="checkbox"/> Single Family | <input type="checkbox"/> Apartment | Approx. Construction Date (Yr) | 1800/1950 |
| | <input type="checkbox"/> Town House | <input type="checkbox"/> Other (describe) | Approx. Square Footage | 2000 |
| | <input type="checkbox"/> Condomium | | No. of Separate Rooms | 16 |

| | | | | |
|-----------------------------------|------------|-----------------|--------|-------------------------------|
| Location of Work w/in structure | | BEDROOM 2 | | |
| Lead Content of Affected Surfaces | | Work Statistics | | |
| Surface | XRF Result | and/or | % Lead | No. of Workers |
| CLOSET DOOR | 1.4 | | | 1 |
| | | | | Start Time |
| | | | | 11:21 |
| | | | | Stop Time |
| | | | | 12:03 |
| | | | | Total Time (hrs) |
| | | | | 0.7 |
| | | | | Tools and Equipment Used |
| | | | | Use attached checklist |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P-G1-042006-34 -A-Area | BEDROOM 2 | 16669 | 10:04 | 2.58 | 11:06 | 2.56 | 62 | 2.56 | 158.7 | 190 |
| P-042006-22 -A-OS | 2ND FLOOR HALL | 16609 | 7:55 | 2.59 | 11:09 | 2.58 | 194 | 2.58 | 500.5 | 53 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (D-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-G1-042006-46 -A-Area | BEDROOM 2 | 16669 | 11:20 | 2.56 | 12:03 | 2.57 | 43 | 2.56 | 110.1 | 69 |
| D-G1-042006-42 -A-PBZ | WORKER | 17185 | 11:21 | 2.59 | 12:03 | 2.58 | 42 | 2.58 | 108.4 | 111 |
| D-042006-48 -A-OS | 2ND FL HALL | 16609 | 11:19 | 2.58 | 13:14 | 2.54 | 115 | 2.54 | 292.1 | 24 |

Post-Work Sampling

| Sample No. (C-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|-----------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-G1-042006-50 -A-Area | BEDROOM 2 | 16669 | 12:04 | 2.57 | 13:12 | 2.54 | 68 | 2.54 | 172.7 | 25 |

Wipe Sampling

Date: 4/20/2006 Collected by:

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|-------------|----------------|--------------|---------------------------------|------------------------------|
| P-G1-042006-7 -W-Area | BEDROOM 2 | FLOOR - A WALL | WOOD | 1.00 | 1240 |
| P-G1-042006-8 -W-Area | BEDROOM 2 | FLOOR - C WALL | WOOD | 1.00 | 774 |
| P-G1-042006-9 -W-Area | BEDROOM 2 | SILL - D WALL | WOOD | 0.25 | 6440 |
| P-042006-14 -W-OS | 2ND FL HALL | FLOOR | WOOD | 1.00 | 108 |

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|-------------|-----------------|--------------|---------------------------------|------------------------------|
| C-G1-042006-22 -W-Area | BEDROOM 2 | FLOOR IN CLOSET | WOOD | 1.00 | 105 |
| C-G1-042006-23 -W-Area | BEDROOM 2 | FLOOR - C WALL | WOOD | 1.00 | 254 |
| C-G1-042006-24 -W-Area | BEDROOM 2 | SILL - D WALL | WOOD | 0.25 | 872 |
| C-042006-28 -W-OS | 2ND FL HALL | FLOOR | WOOD | 1.00 | 834 |

OS - Outside of work area

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|----------------------|
| Hygienist | |
| Activity | CLOSET SHELF REMOVAL |
| Work Practice | ROUTINE |

| | |
|---|----------------|
| DATE | 4/20/2006 |
| LOCATION | Farmington, CT |
| SCENARIO | G1a |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | X |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | X |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 4/20/2006 Hygienist -

| Event | ID | Activity | Work Practice |
|-------|----|---|---------------|
| 33 | G2 | CLOSET SHELF REMOVAL (WOOD) - SAWING WOOD | Mod LSWP |

| | | |
|---------------------|------------------|----------------|
| Site Address | City, State, Zip | Farmington, CT |
|---------------------|------------------|----------------|

| | | | | |
|-----------------------|---|------------------|--------------------------------|-----------|
| Structure Type | <input checked="" type="checkbox"/> Single Family | Apartment | Approx. Construction Date (Yr) | 1800/1950 |
| | <input type="checkbox"/> Town House | Other (describe) | Approx. Square Footage | 2000 |
| | <input type="checkbox"/> Condomium | | No. of Separate Rooms | 16 |

| | | | | |
|--|------------|------------------------|-------------------------------|----------------|
| Location of Work w/in structure | | BEDROOM 3 | | |
| Lead Content of Affected Surfaces | | Work Statistics | | |
| Surface | XRF Result | and/or | % Lead | No. of Workers |
| SHELF SUPPORT | >9.9 | | | 1 |
| | | | | Start Time |
| | | | | 11:23 |
| | | | | Stop Time |
| | | | 12:05 | |
| | | | Total Time (hrs) | 0.7 |
| | | | Tools and Equipment Used | |
| | | | <i>Use attached checklist</i> | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P-G2-042006-37 -A-Area | BEDROOM 3 | 16612 | 10:03 | 2.60 | 11:04 | 2.60 | 61 | 2.60 | 158.6 | 126 |
| P-042006-48 -A-OS | 2ND FL HALL | 16609 | 11:19 | 2.58 | 13:14 | 2.54 | 115 | 2.54 | 292.1 | 24 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-G2-042006-47 -A-Area | BEDROOM 3 | 16612 | 11:23 | 2.60 | 12:05 | 2.58 | 42 | 2.58 | 108.4 | 38 |
| D-G2-042006-43 -A-PBZ | WORKER | 17184 | 11:23 | 2.60 | 12:05 | 2.58 | 42 | 2.58 | 108.4 | 45 |
| D-042006-48 -A-OS | 2ND FL HALL | 16609 | 11:19 | 2.58 | 13:14 | 2.54 | 115 | 2.54 | 292.1 | 24 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|-----------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-G2-042006-51 -A-Area | BEDROOM 3 | 16612 | 12:06 | 2.58 | 13:11 | 2.58 | 65 | 2.58 | 167.7 | 13 |

Wipe Sampling

Date 4/20/2006 Collected by -

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|-------------|----------------|--------------|---------------------------------|------------------------------|
| P-G2-042006-10 -W-Area | BEDROOM 3 | FLOOR - A WALL | WOOD | 1.00 | 4320 |
| P-G2-042006-11 -W-Area | BEDROOM 3 | FLOOR - C WALL | WOOD | 1.00 | 2090 |
| P-G2-042006-12 -W-Area | BEDROOM 3 | SILL - D WALL | WOOD | 0.25 | 10800 |
| P-042006-14 -W-OS | 2ND FL HALL | FLOOR | WOOD | 1.00 | 108 |

| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|-------------|-----------------|--------------|---------------------------------|------------------------------|
| C-G2-042006-25 -W-Area | BEDROOM 3 | FLOOR IN CLOSET | WOOD | 1.00 | 56.7 |
| C-G2-042006-26 -W-Area | BEDROOM 3 | FLOOR - A WALL | WOOD | 1.00 | 1040 |
| C-G2-042006-27 -W-Area | BEDROOM 3 | SILL - D WALL | WOOD | 1.00 | 133 |
| C-042006-28 -W-OS | 2ND FL HALL | FLOOR | WOOD | 1.00 | 834 |

OS - Outside of work area

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|----------------------|
| Hygienist | |
| Activity | CLOSET SHELF REMOVAL |
| Work Practice | MOD LSWP |

| | |
|---|----------------|
| DATE | 4/20/2006 |
| LOCATION | Farmington, CT |
| SCENARIO | G2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Opening Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/2/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|----------------------|---------------|
| | 34 | B1 | CEILING MODIFICATION | ROUTINE |

| | |
|--------------------------------------|---------------|
| Site Address City, State, Zip | Milwaukee, WI |
|--------------------------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

| | | | | | |
|--|--|-------------|--------|--------|--|
| Location of Work w/in structure | | 3RD FL BR 1 | | | |
| Lead Content of Affected Surfaces | | | | | |
| Surface | | XRF Result | | % Lead | |
| CEILING | | 2.8 | | | |
| | | | and/or | | |
| | | | | | |
| | | | | | |
| | | | | | Work Statistics No. of Workers 1 Start Time 940 Stop Time 1005 Total Time (hrs) 0.3 Tools and Equipment Used <i>Use attached checklist</i> |

Pre-Work Sampling

| Air Sampling | | | | | | | | | | | |
|---|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|--|
| Sample No. <small>(P-ScenarioID-Date-## -A-Type)</small> | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| P-B1-050106-003 -A-Area | 3RD FL BR 1 | 17865 | 14:59 | 2.63 | 15:52 | 2.61 | 53 | 2.61 | 138.3 | <14 | |
| P-B1-050106-001 -A-OS | 3RD FL BR 3 | 17180 | 14:55 | 2.65 | 15:48 | 2.63 | 53 | 2.63 | 139.4 | <14 | |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Air Sampling | | | | | | | | | | | |
|---|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|--|
| Sample No. <small>(P-ScenarioID-Date-## -A-Type)</small> | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| D-B1-050206-020 -A-Area | 3RD FL BR 1 | 18105 | 9:39 | 2.59 | 10:52 | 2.54 | 73 | 2.54 | 185.4 | 54 | |
| D-B1-050206-019 -A-PBZ | WORKER | 17183 | 9:39 | 2.64 | 10:50 | 2.64 | 71 | 2.64 | 187.4 | 68 | |
| D-B1-050206-021 -A-OS | 3RD FL BR 3 | 18112 | 9:38 | 2.64 | 12:21 | 2.59 | 163 | 2.59 | 422.2 | 7 | |

Post-Work Sampling

| Air Sampling | | | | | | | | | | | |
|---|-------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|--|
| Sample No. <small>(P-ScenarioID-Date-## -A-Type)</small> | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| C-B1-050206-027 -A-Area | 3RD FL BR 1 | 18105 | 10:53 | 2.54 | 12:19 | 2.54 | 86 | 2.54 | 218.4 | <9 | |

Pre-work Wipe Sampling

| Wipe Sampling | | | | | | |
|---|-------------|-----------|--------------|---------------------------------|------------------------------|--|
| Sample No. <small>(P-ScenarioID-Date-## -W-Location)</small> | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| P-B1-050106-201 -W-Area | 3RD FL BR 1 | HAND RAIL | WOOD | 0.58 | 464 | |
| P-B1-050106-202 -W-Area | 3RD FL BR 1 | FLOOR N | WOOD | 1.00 | 124 | |
| P-B1-050106-203 -W-Area | 3RD FL BR 1 | FLOOR S | WOOD | 1.00 | 94 | |
| P-B1-050106-207 -W-OS | 3RD FL BR 3 | FLOOR | WOOD | 1.00 | 126 | |

Clearance Wipe Sampling

| Wipe Sampling | | | | | | |
|---|-------------|-----------|--------------|---------------------------------|------------------------------|--|
| Sample No. <small>(P-ScenarioID-Date-## -W-Location)</small> | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| C-B1-050206-242 -W-Area | 3RD FL BR 1 | FLOOR N | WOOD | 1.00 | 139 | |
| C-B1-050206-243 -W-Area | 3RD FL BR 1 | FLOOR S | WOOD | 1.00 | 523 | |
| C-B1-050206-244 -W-Area | 3RD FL BR 1 | HAND RAIL | WOOD | 0.50 | 513 | |
| C-B1-050206-241 -W-OS | 3RD FL BR 3 | FLOOR W | WOOD | 1.00 | 657 | |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|----------------------|
| Hygienist | |
| Activity | CEILING MODIFICATION |
| Work Practice | ROUTINE |

| | |
|---|---------------|
| DATE | 5/2/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | B1a |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | |
| Brooms | X |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | X |
| Disposable Towels | |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/2/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|-------------------|---------------|
| | 35 | B1 | WALL MODIFICATION | ROUTINE |

| | |
|--------------------------------------|---------------|
| Site Address City, State, Zip | Milwaukee, WI |
|--------------------------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

| | | | | | |
|--|-------------|-------------|------|--------------------------|------|
| Location of Work w/in structure | | 2ND FL BR 2 | | | |
| Lead Content of Affected Surfaces | | | | | |
| Surface | XRF Result | | % | Work Statistics | |
| BR 1 Wall (assumed same) | 13.4 | | Lead | | |
| | | and/or | | | |
| | | | | | |
| | | | | | |
| | | | | No. of Workers | 1 |
| | | | | Start Time | 1247 |
| | | | | Stop Time | 1320 |
| | | | | Total Time (hrs) | 0.5 |
| | | | | Tools and Equipment Used | |
| Use attached checklist | | | | | |

Pre-Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------------------------|-------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|-----|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| P-B1-050106-008 | -A-Area | 2ND FL BR 2 | 16609 | 15:26 | 2.61 | 16:07 | 2.62 | 41 | 2.61 | 107.0 | <19 |
| P-C3-050106-004 | -A-OS | GRND FL | 17184 | 15:10 | 2.66 | 15:56 | 2.66 | 46 | 2.66 | 122.4 | <16 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------------------------|-------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|-----|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| D-B1-050206-033 | -A-Area | 2ND FL BR 2 | 17184 | 12:47 | 2.66 | 13:46 | 2.57 | 59 | 2.57 | 151.6 | <13 |
| D-B1-050206-032 | -A-PBZ | WORKER | 17185 | 12:47 | 2.62 | 13:47 | 2.59 | 60 | 2.59 | 155.4 | <13 |
| D-C2-050206-040 | -A-OS | KITCHEN | 18110 | 12:34 | 2.53 | 15:22 | 2.53 | 168 | 2.53 | 425.0 | <5 |
| D-C2-050206-041 | -A-OS | GRND FL | 17451 | 12:38 | 2.68 | 15:06 | 2.67 | 148 | 2.67 | 395.2 | <5 |

Post-Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------|-------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|-----|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| C-B1-050206-048 | -A-Area | 2ND FL BR 2 | 17184 | 13:47 | 2.57 | 14:50 | 2.61 | 63 | 2.57 | 161.9 | <12 |

Pre-work Wipe Sampling

| Wipe Sampling | | | | | |
|---|----------|-------------|--------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| P-B1-050206-221 | -W-Area | 2ND FL BR 2 | FLOOR N | 1.00 | 550 |
| P-B1-050206-222 | -W-Area | 2ND FL BR 2 | FLOOR S | 1.00 | 593 |
| P-B1-050206-223 | -W-Area | 2ND FL BR 2 | W-SILL | 0.46 | 1300 |
| P-C3-050206-211 | -W-OS | GROUND FL | FLOOR | 1.00 | 800 |

Clearance Wipe Sampling

| Wipe Sampling | | | | | |
|---|----------|-------------|--------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| C-B1-050206-257 | -W-Area | 2ND FL BR 2 | FLOOR N | 1.00 | 1070 |
| C-B1-050206-258 | -W-Area | 2ND FL BR 2 | FLOOR S | 1.00 | 150 |
| C-B1-050206-256 | -W-Area | 2ND FL BR 2 | W-SILL | 0.42 | 411 |
| C-C3-050206-251 | -W-OS | GROUND FL | FLOOR | 1.00 | 535 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-------------------|
| Hygienist | |
| Activity | WALL MODIFICATION |
| Work Practice | ROUTINE |

| | |
|---|---------------|
| DATE | 5/2/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | B1 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | X |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/2/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|---------------------|---------------|
| | 36 | C2 | WINDOW INSTALLATION | mod LSWP |

| | | |
|---------------------|------------------|---------------|
| Site Address | City, State, Zip | Milwaukee, WI |
|---------------------|------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

| | | | | | | |
|--|------------|-------------|--------------------------|------------------------|-------------------------------|------|
| Location of Work w/in structure | | LIVING ROOM | | | | |
| Lead Content of Affected Surfaces | | | | | | |
| Surface | XRF Result | and/or | % Lead | Work Statistics | | |
| WINDOW SILL | 3.7 | | No. of Workers | 1 | Start Time | 1305 |
| WINDOW SASH | 18.9 | | Stop Time | 1402 | Total Time (hrs) | 1 |
| WINDOW | 22.5 | | Tools and Equipment Used | | <i>Use attached checklist</i> | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-C3-050206-029 -A-Area | LR S | 16609 | 11:03 | 2.56 | 12:29 | 2.57 | 86 | 2.56 | 220.2 | <9 |
| C-C3-050206-030 -A-Area | LR N | 16666 | 11:03 | 2.63 | 12:31 | 2.61 | 88 | 2.61 | 229.7 | <9 |
| D-C3-050206-026 -A-OS | KITCHEN | 18110 | 8:53 | 2.65 | 12:24 | 2.53 | 211 | 2.53 | 533.8 | <4 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-C2-050206-038 -A-Area | LR S | 16609 | 13:03 | 2.50 | 13:57 | 2.58 | 54 | 2.50 | 135.0 | <15 |
| D-C2-050206-039 -A-Area | LR N | 16666 | 13:03 | 2.61 | 13:58 | 2.61 | 55 | 2.61 | 143.6 | <14 |
| D-C2-050206-044 -A-PBZ | WORKER | 17180 | 13:05 | 2.65 | 14:02 | 2.55 | 57 | 2.55 | 145.4 | <14 |
| D-C2-050206-040 -A-OS | KITCHEN | 18110 | 12:34 | 2.53 | 15:22 | 2.53 | 168 | 2.53 | 425.0 | <5 |
| D-C2-050206-041 -A-OS | GRND FL | 17451 | 12:38 | 2.68 | 15:06 | 2.67 | 148 | 2.67 | 395.2 | <5 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-C2-050206-050 -A-Area | LR S | 16609 | 13:58 | 2.58 | 15:00 | 2.58 | 62 | 2.58 | 160.0 | <13 |
| C-C2-050206-051 -A-Area | LR N | 16666 | 13:59 | 2.61 | 15:02 | 2.61 | 63 | 2.61 | 164.4 | <12 |

Pre-work Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|-----------|---------|--------------|---------------------------------|------------------------------|
| C-C3-050206-250 -W-Area | LR | W-SILL | WOOD | 0.29 | 452 |
| C-C3-050206-248 -W-Area | LR | FLOOR N | WOOD | 1.00 | 1320 |
| C-C3-050206-249 -W-Area | LR | FLOOR S | WOOD | 1.00 | 402 |
| C-C3-050206-251 -W-OS | GROUND FL | FLOOR | WOOD | 1.00 | 535 |

Clearance Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|-----------|---------|--------------|---------------------------------|------------------------------|
| C-C2-050206-264 -W-Area | LR | W-SILL | WOOD | 0.29 | 642 |
| C-C2-050206-265 -W-Area | LR | FLOOR N | WOOD | 1.00 | 11400 |
| C-C2-050206-266 -W-Area | LR | FLOOR S | WOOD | 1.00 | 306 |
| C-C2-050206-263 -W-OS | GROUND FL | FLOOR W | WOOD | 1.00 | 1050 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|---------------------|
| Hygienist | |
| Activity | WONDOW INSTALLATION |
| Work Practice | mod LSWP |

| | |
|---|---------------|
| DATE | 5/2/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | C2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | X |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | X |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | X |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | X |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/2/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|---------------------|---------------|
| | 37 | B3 | OUTLET INSTALLATION | HUD/EPA LSWP |

| | |
|--------------------------------------|---------------|
| Site Address City, State, Zip | Milwaukee, WI |
|--------------------------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

| | | | | | |
|--|-------------|-------------|------|-------------------------------|------|
| Location of Work w/in structure | | 2ND FL BR 1 | | | |
| Lead Content of Affected Surfaces | | | | | |
| Surface | XRF Result | | % | Work Statistics | |
| WALL | 13.4 | | Lead | | |
| | | and/or | | | |
| | | | | | |
| | | | | | |
| | | | | No. of Workers | 1 |
| | | | | Start Time | 940 |
| | | | | Stop Time | 1020 |
| | | | | Total Time (hrs) | 0.6 |
| | | | | Tools and Equipment Used | |
| | | | | Use attached checklist | |

Pre-Work Sampling

| Air Sampling | | | | | | | | | | |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| P-B3-050106-007 -A-Area | 2ND FL BR 1 | 16608 | 15:24 | 2.59 | 16:05 | 2.58 | 41 | 2.58 | 105.8 | <19 |
| P-C3-050106-004 -A-OS | GRND FL | 17184 | 15:10 | 2.66 | 15:56 | 2.66 | 46 | 2.66 | 122.4 | <16 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Air Sampling | | | | | | | | | | |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| D-B3-050206-022 -A-Area | 2ND FL BR 1 | 16608 | 9:34 | 2.60 | 10:58 | 2.57 | 84 | 2.57 | 215.9 | <9 |
| D-B3-050206-017 -A-PBZ | WORKER | 17185 | 9:19 | 2.65 | 10:56 | 2.62 | 97 | 2.62 | 254.1 | <8 |
| D-C3-050206-026 -A-OS | KITCHEN | 18110 | 8:53 | 2.65 | 12:24 | 2.53 | 211 | 2.53 | 533.8 | <4 |

Post-Work Sampling

| Air Sampling | | | | | | | | | | |
|--|-------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| C-B3-050206-028 -A-Area | 2ND FL BR 1 | 16608 | 10:59 | 2.57 | 12:26 | 2.55 | 87 | 2.55 | 221.9 | <9 |

Pre-work Wipe Sampling

| Wipe Sampling | | | | | |
|--|-------------|---------|--------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| P-B3-050206-218 -W-Area | 2ND FL BR 1 | W-SILL | WOOD | 0.46 | 2090 |
| P-B3-050206-219 -W-Area | 2ND FL BR 1 | FLOOR W | WOOD | 1.00 | 891 |
| P-B3-050206-220 -W-Area | 2ND FL BR 1 | FLOOR E | WOOD | 1.00 | 210 |
| P-C3-050206-211 -W-OS | GROUND FL | FLOOR | WOOD | 1.00 | 800 |

Clearance Wipe Sampling

| Wipe Sampling | | | | | |
|--|-------------|---------|--------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| C-B3-050206-247 -W-Area | 2ND FL BR 1 | W-SILL | WOOD | 0.42 | 476 |
| C-B3-050206-245 -W-Area | 2ND FL BR 1 | FLOOR N | WOOD | 1.00 | 402 |
| C-B3-050206-246 -W-Area | 2ND FL BR 1 | FLOOR S | WOOD | 1.00 | 423 |
| C-C3-050206-251 -W-OS | GROUND FL | FLOOR | WOOD | 1.00 | 535 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|--------------------------------|
| Hygienist | |
| Activity | WALL MOD - OUTLET INSTALLATION |
| Work Practice | LSWP |

| | |
|---|---------------|
| DATE | 5/2/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | B3 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | X |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | NA |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | |
| Tack Pad | |
| Disposable Towels for Wipe Down | X |
| Work Practices/Tools | |
| Hammers/Prybars | |
| Misting Bottle | X |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | |
| Wet Wipe Surfaces or Use Detergent | X |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | X |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | X |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/2/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|--|---------------|
| | 38 | C3 | WINDOW MODIFICATION (SASHES AND STOPS) | HUD/EPA LSWP |

| | | |
|---------------------|------------------|---------------|
| Site Address | City, State, Zip | Milwaukee, WI |
|---------------------|------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

Location of Work w/in structure LIVING ROOM

| Lead Content of Affected Surfaces | | | XRF Result | % | Lead | Work Statistics | | |
|-----------------------------------|--|--|------------|--------|------|-------------------------------|------------|-----------|
| Surface | | | | | | No. of Workers | Start Time | Stop Time |
| WINDOW SASH | | | 18.9 | and/or | | | 1 | 940 |
| WINDOW SILL | | | 3.7 | | | 1023 | | |
| | | | | | | | 0.6 | |
| | | | | | | Tools and Equipment Used | | |
| | | | | | | Use attached checklist | | |

Pre-Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P-C3-050106-005 -A-Area | LR N | 16666 | 15:17 | 2.68 | 16:02 | 2.68 | 45 | 2.68 | 120.6 | <17 |
| P-C3-050106-006 -A-Area | LR S | 16668 | 15:20 | 2.65 | 16:04 | 2.68 | 44 | 2.65 | 116.6 | <17 |
| P-C3-050106-004 -A-OS | GRND FL | 17184 | 15:10 | 2.66 | 15:56 | 2.66 | 46 | 2.66 | 122.4 | <16 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-C3-050206-023 -A-Area | LR S | 16609 | 9:34 | 2.60 | 11:02 | 2.56 | 88 | 2.56 | 225.3 | <9 |
| D-C3-050206-024 -A-Area | LR N | 16666 | 9:34 | 2.70 | 11:03 | 2.63 | 89 | 2.63 | 234.1 | <9 |
| D-C3-050206-018 -A-PBZ | WORKER | 16669 | 9:14 | 2.59 | 11:05 | 2.58 | 111 | 2.58 | 286.4 | <7 |
| D-C3-050206-025 -A-OS | GRND FL | 17451 | 8:49 | 2.68 | 12:36 | 2.67 | 227 | 2.67 | 606.1 | <3 |
| D-C3-050206-026 -A-OS | KITCHEN | 18110 | 8:53 | 2.65 | 12:24 | 2.53 | 211 | 2.53 | 533.8 | <4 |

Post-Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-C3-050206-029 -A-Area | LR S | 16609 | 11:03 | 2.56 | 12:29 | 2.57 | 86 | 2.56 | 220.2 | <9 |
| C-C3-050206-030 -A-Area | LR N | 16666 | 11:03 | 2.63 | 12:31 | 2.61 | 88 | 2.61 | 229.7 | <9 |

Pre-work Wipe Sampling

| Sample No. (P-Scenario/D-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|-----------|---------|--------------|---------------------------------|------------------------------|
| P-C3-050206-212 -W-Area | LR | FLOOR N | WOOD | 1.00 | 437 |
| P-C3-050206-213 -W-Area | LR | FLOOR S | WOOD | 1.00 | 324 |
| P-C3-050206-214 -W-Area | LR | W-SILL | WOOD | 0.29 | 680 |
| P-C3-050206-211 -W-OS | GROUND FL | FLOOR | WOOD | 1.00 | 800 |

Clearance Wipe Sampling

| Sample No. (P-Scenario/D-Date-##-W-Location) | Location | Surface | Surface Type | Sampled (ft ²) | Result (ug/ft ²) |
|---|-----------|---------|--------------|----------------------------|------------------------------|
| C-C3-050206-248 -W-Area | LR | FLOOR N | WOOD | 1.00 | 1320 |
| C-C3-050206-249 -W-Area | LR | FLOOR S | WOOD | 1.00 | 402 |
| C-C3-050206-250 -W-Area | LR | W-SILL | WOOD | 0.29 | 452 |
| C-C3-050206-251 -W-OS | GROUND FL | FLOOR | WOOD | 1.00 | 535 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|---------------------|
| Hygienist | |
| Activity | WINDOW MODIFICATION |
| Work Practice | LSWP |

| | |
|---|---------------|
| DATE | 5/2/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | C3 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | X |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | X |
| Work Practices/Tools | |
| Hammers/Prybars | |
| Misting Bottle | X |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | X |
| Disposable Hand Towels | |
| Pump Sprayer | X |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | X |
| Disposable Towels | |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/2/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|-----------------------|---------------|
| | 39 | C1 | WINDOW WORK - SANDING | ROUTINE |

| | | |
|---------------------|------------------|---------------|
| Site Address | City, State, Zip | Milwaukee, WI |
|---------------------|------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

Location of Work w/in structure 2ND FL BR 1

| Lead Content of Affected Surfaces | | | | Work Statistics | | |
|-----------------------------------|------------|--------|--|--------------------------|-------------------------------|-----------|
| Surface | XRF Result | % Lead | | No. of Workers | Start Time | Stop Time |
| WINDOW SASH | 13.8 | and/or | | Total Time (hrs) | 1342 | 1400 |
| WINDOW SILL | 12.7 | | | | 0.3 | |
| | | | | Tools and Equipment Used | <i>Use attached checklist</i> | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-B3-050206-028 -A-Area | 2ND FL BR 1 | 16608 | 10:59 | 2.57 | 12:26 | 2.55 | 87 | 2.55 | 221.9 | <9 |
| D-C3-050206-025 -A-OS | GRND FL | 17451 | 8:49 | 2.68 | 12:36 | 2.67 | 227 | 2.67 | 606.1 | <3 |
| D-C3-050206-026 -A-OS | KITCHEN | 18110 | 8:53 | 2.65 | 12:24 | 2.53 | 211 | 2.53 | 533.8 | <4 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-C1-050206-047 -A-Area | 2ND FL BR 1 | 16608 | 13:43 | 2.55 | 14:28 | 2.55 | 45 | 2.55 | 114.8 | 161 |
| D-C1-050206-047 -A-Area | 2ND FL BR 1 | 16608 | 13:43 | 2.55 | 14:28 | 2.55 | 45 | 2.55 | 114.8 | 161 |
| D-C1-050206-046 -A-PBZ | WORKER | 17183 | 13:42 | 2.63 | 14:29 | 2.63 | 47 | 2.63 | 123.6 | 184 |
| D-C2-050206-040 -A-OS | KITCHEN | 18110 | 12:34 | 2.53 | 15:22 | 2.53 | 168 | 2.53 | 425.0 | <5 |
| D-C2-050206-041 -A-OS | GRND FL | 17451 | 12:38 | 2.68 | 15:06 | 2.67 | 148 | 2.67 | 395.2 | <5 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|-------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-C1-050206-052 -A-Area | 2ND FL BR 1 | 16608 | 14:28 | 2.55 | 15:29 | 2.59 | 61 | 2.55 | 155.6 | <13 |

Pre-work Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|-------------|---------|--------------|---------------------------------|------------------------------|
| C-B3-050206-245 -W-Area | 2ND FL BR 1 | FLOOR N | WOOD | 1.00 | 402 |
| C-B3-050206-246 -W-Area | 2ND FL BR 1 | FLOOR S | WOOD | 1.00 | 423 |
| C-B3-050206-247 -W-Area | 2ND FL BR 1 | W-SILL | WOOD | 0.42 | 476 |
| C-B1-050206-240 -W-OS | KITCHEN | FLOOR S | WOOD | 1.00 | 293 |

Clearance Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|-------------|---------|--------------|---------------------------------|------------------------------|
| C-C1-050206-268 -W-Area | 2ND FL BR 1 | FLOOR N | WOOD | 1.00 | 779 |
| C-C1-050206-269 -W-Area | 2ND FL BR 1 | FLOOR S | WOOD | 1.00 | 481 |
| C-C1-050206-267 -W-Area | 2ND FL BR 1 | W-SILL | WOOD | 0.42 | 315 |
| C-F2-050206-262 -W-OS | KITCHEN | FLOOR S | WOOD | 1.00 | 683 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-------------|
| Hygienist | |
| Activity | WINDOW WORK |
| Work Practice | ROUTINE |

| | |
|---|---------------|
| DATE | 5/2/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | C1 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | X |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | X |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | |
| Brooms | X |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | X |
| Disposable Towels | |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/3/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|-----------------------------------|---------------|
| 40 | A2 | | BANISTER REMOVAL AND INSTALLATION | mod LSWP |

| | | |
|--------------|------------------|---------------|
| Site Address | City, State, Zip | Milwaukee, WI |
|--------------|------------------|---------------|

| | | | | | |
|----------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

| | | | | | |
|-----------------------------------|--|-------------|--------|--------|---|
| Location of Work w/in structure | | 3RD FL BR 1 | | | |
| Lead Content of Affected Surfaces | | | | | |
| Surface | | XRF Result | | % Lead | |
| STAIR HANDRAIL | | 4.4 | | | |
| | | | and/or | | |
| | | | | | |
| | | | | | |
| | | | | | Work Statistics No. of Workers 2 Start Time 1315 Stop Time 1551 Total Time (hrs) 2.5 Tools and Equipment Used <i>Use attached checklist</i> |

Pre-Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------------------------|-------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|-----|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| C-B1-050306-073 | -A-Area | 3RD FL BR 1 | 16669 | 11:36 | 2.59 | 12:50 | 2.58 | 74 | 2.58 | 190.9 | <11 |
| D-F2-050306-060 | -A-OS | 3RD FL BR 3 | 18110 | 10:06 | 2.57 | 13:06 | 2.54 | 180 | 2.54 | 457.2 | <4 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------------------------|-------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|----|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| D-A2-050306-081 | -A-Area | 3RD FL BR 1 | 16669 | 13:13 | 2.58 | 16:08 | 2.53 | 175 | 2.53 | 442.8 | <5 |
| D-A2-050306-082 | -A-PBZ | WORKER | 17863 | 13:15 | 2.51 | 15:54 | 2.54 | 159 | 2.51 | 399.1 | <5 |
| D-A2-050306-083 | -A-PBZ | WORKER | 18104 | 13:14 | 2.57 | 16:10 | 2.53 | 176 | 2.53 | 445.3 | <4 |
| D-A2-050306-084 | -A-OS | 3RD FL BR 3 | 18110 | 13:07 | 2.54 | 15:09 | 2.49 | 122 | 2.49 | 303.8 | <7 |

Post-Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------|-------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|-----|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| C-A2-050306-097 | -A-Area | 3RD FL BR 1 | 16669 | 16:08 | 2.53 | 17:08 | 2.57 | 60 | 2.53 | 151.8 | <13 |

Pre-work Wipe Sampling

| Wipe Sampling | | | | | |
|---|----------|-------------|--------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| C-B1-050306-270 | -W-Area | 3RD FL BR 1 | HAND RAIL | 0.58 | 779 |
| C-B1-050306-271 | -W-Area | 3RD FL BR 1 | FLOOR S | 1.00 | 481 |
| C-B1-050306-272 | -W-Area | 3RD FL BR 1 | FLOOR N | 1.00 | 653 |
| C-B1-050306-276 | -W-OS | 3RD FL BR 3 | FLOOR W | 1.00 | 245 |

Clearance Wipe Sampling

| Wipe Sampling | | | | | |
|---|----------|-------------|--------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| C-A2-050306-306 | -W-Area | 3RD FL BR 1 | FLOOR E | 1.00 | 163 |
| C-A2-050306-307 | -W-Area | 3RD FL BR 1 | FLOOR N | 1.00 | 151 |
| C-A2-050306-308 | -W-Area | 3RD FL BR 1 | FLOOR S | 1.00 | 3800 |
| C-A2-050306-309 | -W-OS | 3RD FL BR 3 | FLOOR E | 1.00 | 165 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-----------------------------------|
| Hygienist | |
| Activity | BANISTER REMOVAL AND INSTALLATION |
| Work Practice | mod LSWP |

| | |
|---|---------------|
| DATE | 5/3/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | A2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | X |
| Rope | |
| Barrier Tape | |
| Saw Horses | X |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | NA |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | X |
| Sandpaper/Sanding Sponge | X |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | X |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | X |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/2/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|-------------------|---------------|
| | 41 | E1 | BASEBOARD REMOVAL | ROUTINE |

| | |
|--------------------------------------|---------------|
| Site Address City, State, Zip | Milwaukee, WI |
|--------------------------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

| | | | | | | |
|--|--|------------|-------------|--------|--------------------------|------|
| Location of Work w/in structure | | | 3RD FL BR 1 | | | |
| Lead Content of Affected Surfaces | | | | | | |
| Surface | | XRF Result | | % Lead | | |
| BASEBOARD | | 9.9 | | | | |
| | | | and/or | | | |
| | | | | | | |
| | | | | | | |
| | | | | | Work Statistics | |
| | | | | | No. of Workers | 1 |
| | | | | | Start Time | 1241 |
| | | | | | Stop Time | 1300 |
| | | | | | Total Time (hrs) | 0.3 |
| | | | | | Tools and Equipment Used | |
| Use attached checklist | | | | | | |

Pre-Work Sampling

| Air Sampling | | | | | | | | | | | |
|---|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|--|
| Sample No. <small>(P-ScenarioID-Date-## -A-Type)</small> | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| C-B1-050206-027 -A-Area | 3RD FL BR 1 | 18105 | 10:53 | 2.54 | 12:19 | 2.54 | 86 | 2.54 | 218.4 | <9 | |
| D-B1-050206-021 -A-OS | 3RD FL BR 3 | 18112 | 9:38 | 2.64 | 12:21 | 2.59 | 163 | 2.59 | 422.2 | 7 | |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Air Sampling | | | | | | | | | | | |
|---|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|--|
| Sample No. <small>(P-ScenarioID-Date-## -A-Type)</small> | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| D-E1-050206-036 -A-Area | 3RD FL BR 1 | 18105 | 12:41 | 2.51 | 13:35 | 2.52 | 54 | 2.51 | 135.5 | <15 | |
| D-E1-050206-035 -A-PBZ | WORKER | 17183 | 12:41 | 2.64 | 13:36 | 2.63 | 55 | 2.63 | 144.7 | <14 | |
| D-E1-050206-037 -A-OS | 3RD FL BR 3 | 18112 | 12:22 | 2.59 | 14:35 | 2.60 | 133 | 2.59 | 344.5 | <6 | |

Post-Work Sampling

| Air Sampling | | | | | | | | | | | |
|---|-------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|--|
| Sample No. <small>(P-ScenarioID-Date-## -A-Type)</small> | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| C-E1-050206-045 -A-Area | 3RD FL BR 1 | 18105 | 13:36 | 2.52 | 14:37 | 2.52 | 61 | 2.52 | 153.7 | <13 | |

Pre-work Wipe Sampling

| Wipe Sampling | | | | | | |
|---|-------------|-----------|--------------|---------------------------------|------------------------------|--|
| Sample No. <small>(P-ScenarioID-Date-## -W-Location)</small> | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| C-B1-050206-244 -W-Area | 3RD FL BR 1 | HAND RAIL | WOOD | 0.50 | 513 | |
| C-B1-050206-242 -W-Area | 3RD FL BR 1 | FLOOR N | WOOD | 1.00 | 139 | |
| C-B1-050206-243 -W-Area | 3RD FL BR 1 | FLOOR S | WOOD | 1.00 | 523 | |
| C-B1-050206-241 -W-OS | 3RD FL BR 3 | FLOOR W | WOOD | 1.00 | 657 | |

Clearance Wipe Sampling

| Wipe Sampling | | | | | | |
|---|-------------|-----------|--------------|---------------------------------|------------------------------|--|
| Sample No. <small>(P-ScenarioID-Date-## -W-Location)</small> | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| C-E1-050206-252 -W-Area | 3RD FL BR 1 | HAND RAIL | WOOD | 0.33 | 1050 | |
| C-E1-050206-253 -W-Area | 3RD FL BR 1 | FLOOR N | WOOD | 1.00 | 158 | |
| C-E1-050206-254 -W-Area | 3RD FL BR 1 | FLOOR S | WOOD | 1.00 | 312 | |
| C-E1-050206-255 -W-OS | 3RD FL BR 3 | FLOOR W | WOOD | 1.00 | 431 | |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-------------------|
| Hygienist | |
| Activity | BASEBOARD REMOVAL |
| Work Practice | ROUTINE |

| | |
|---|---------------|
| DATE | 5/2/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | E1 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | X |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | |
| Brooms | X |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/2/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|---------------|---------------|
| | 42 | F2 | FLOOR SANDING | mod LSWP |

| | | |
|---------------------|------------------|---------------|
| Site Address | City, State, Zip | Milwaukee, WI |
|---------------------|------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

| | | | | | | |
|--|-------|------------|--------|--------|--------------------------|------|
| Location of Work w/in structure | | PANTRY | | | | |
| Lead Content of Affected Surfaces | | | | | | |
| Surface | | XRF Result | | % Lead | Work Statistics | |
| | FLOOR | 2.3 | and/or | | | |
| | FLOOR | 1.7 | | | | |
| | FLOOR | 1.3 | | | | |
| | | | | | No. of Workers | 1 |
| | | | | | Start Time | 1242 |
| | | | | | Stop Time | 1349 |
| | | | | | Total Time (hrs) | 1 |
| | | | | | Tools and Equipment Used | |
| Use attached checklist | | | | | | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P-F2-050106-010 -A-Area | PANTRY | 18107 | 15:33 | 2.67 | 16:13 | 2.68 | 40 | 2.67 | 106.8 | <19 |
| P-C3-050106-004 -A-OS | GRND FL | 17184 | 15:10 | 2.66 | 15:56 | 2.66 | 46 | 2.66 | 122.4 | <16 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-F2-050206-034 -A-Area | PANTRY | 17179 | 12:42 | 2.63 | 13:52 | 2.66 | 70 | 2.63 | 184.1 | 411 |
| D-F2-050206-031 -A-PBZ | WORKER | 16669 | 12:42 | 2.58 | 13:49 | 2.54 | 67 | 2.54 | 170.2 | 420 |
| D-C3-050206-025 -A-OS | GRND FL | 17451 | 8:49 | 2.68 | 12:36 | 2.67 | 227 | 2.67 | 606.1 | <3 |
| D-C3-050206-026 -A-OS | KITCHEN | 18110 | 8:53 | 2.65 | 12:24 | 2.53 | 211 | 2.53 | 533.8 | <4 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-F2-050206-049 -A-Area | PANTRY | 17179 | 13:53 | 2.66 | 14:55 | 2.62 | 62 | 2.62 | 162.4 | <12 |

Pre-work Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|-----------|---------|--------------|---------------------------------|------------------------------|
| P-F2-050206-227 -W-Area | PANTRY | W-SILL | WOOD | 0.42 | 1700 |
| P-F2-050206-228 -W-Area | PANTRY | FLOOR E | WOOD | 1.00 | 1090 |
| P-F2-050206-229 -W-Area | PANTRY | FLOOR W | WOOD | 1.00 | 6080 |
| P-C3-050206-211 -W-OS | GROUND FL | FLOOR | WOOD | 1.00 | 800 |

Clearance Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|-----------|---------|--------------|---------------------------------|------------------------------|
| C-F2-050206-259 -W-Area | PANTRY | W-SILL | WOOD | 0.42 | 208 |
| C-F2-050206-260 -W-Area | PANTRY | FLOOR E | WOOD | 1.00 | 5440 |
| C-F2-050206-261 -W-Area | PANTRY | FLOOR W | WOOD | 1.00 | 603 |
| C-C2-050206-263 -W-OS | GROUND FL | FLOOR W | WOOD | 1.00 | 1050 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|---------------|
| Hygienist | |
| Activity | FLOOR SANDING |
| Work Practice | mod LSWP |

| | |
|---|---------------|
| DATE | 5/2/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | F2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | X |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | |
| Wet Wipe Surfaces or Use Detergent | X |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | X |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/3/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|-------------------|---------------|
| | 43 | E3 | BASEBOARD REMOVAL | HUD/EPA LSWP |

| | |
|--------------------------------------|---------------|
| Site Address City, State, Zip | Milwaukee, WI |
|--------------------------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

| | | | | | |
|--|--|-------------|--------|--------|---|
| Location of Work w/in structure | | PANTRY | | | |
| Lead Content of Affected Surfaces | | | | | |
| Surface | | XRF Result | | % Lead | |
| BASEBOARD | | 19.2 | | | |
| | | | and/or | | |
| | | | | | |
| | | | | | |
| | | | | | Work Statistics No. of Workers 1 Start Time 1355 Stop Time 1505 Total Time (hrs) 1.1 Tools and Equipment Used <i>Use attached checklist</i> |

Pre-Work Sampling

| Air Sampling | | | | | | | | | | |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| C-F2-050206-049 -A-Area | PANTRY | 17179 | 13:53 | 2.66 | 14:55 | 2.62 | 62 | 2.62 | 162.4 | <12 |
| D-C2-050206-040 -A-OS | KITCHEN | 18110 | 12:34 | 2.53 | 15:22 | 2.53 | 168 | 2.53 | 425.0 | <5 |
| D-C2-050206-041 -A-OS | GRND FL | 17451 | 12:38 | 2.68 | 15:06 | 2.67 | 148 | 2.67 | 395.2 | <5 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Air Sampling | | | | | | | | | | |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| D-E3-050306-085 -A-Area | PANTRY | 16608 | 13:54 | 2.53 | 15:10 | 2.56 | 76 | 2.53 | 192.3 | 28 |
| D-E3-050306-086 -A-PBZ | WORKER | 18107 | 13:54 | 2.67 | 15:12 | 2.58 | 78 | 2.58 | 201.2 | 52 |
| D-B1-050306-090 -A-OS | KITCHEN | 18112 | 13:52 | 2.63 | 16:43 | 2.63 | 171 | 2.63 | 449.7 | <4 |
| D-B1-050306-091 -A-OS | DINING ROOM | 17180 | 13:50 | 2.56 | 16:44 | 2.59 | 174 | 2.56 | 445.4 | <10 |

Post-Work Sampling

| Air Sampling | | | | | | | | | | |
|--|----------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| C-E3-050306-094 -A-Area | PANTRY | 16608 | 15:11 | 2.56 | 16:23 | 2.54 | 72 | 2.54 | 182.9 | <11 |

Pre-work Wipe Sampling

| Wipe Sampling | | | | | |
|--|----------|---------|--------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| C-F2-050206-259 -W-Area | PANTRY | W-SILL | WOOD | 0.42 | 1070 |
| C-F2-050206-260 -W-Area | PANTRY | FLOOR E | WOOD | 1.00 | 150 |
| C-F2-050206-261 -W-Area | PANTRY | FLOOR W | WOOD | 1.00 | 208 |
| C-F2-050206-262 -W-OS | KITCHEN | FLOOR S | WOOD | 1.00 | 5440 |

Clearance Wipe Sampling

| Wipe Sampling | | | | | |
|--|----------|---------|--------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| C-E3-050306-298 -W-Area | PANTRY | W-SILL | WOOD | 0.29 | 862 |
| C-E3-050306-299 -W-Area | PANTRY | FLOOR E | WOOD | 1.00 | 231 |
| C-E3-050306-300 -W-Area | PANTRY | FLOOR W | WOOD | 1.00 | 352 |
| C-B1-050306-304 -W-OS | KITCHEN | FLOOR W | WOOD | 1.00 | 888 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-------------------|
| Hygienist | |
| Activity | BASEBOARD REMOVAL |
| Work Practice | LSWP |

| | |
|---|---------------|
| DATE | 5/3/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | E3 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | X |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | X |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | X |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | X |
| Disposable Hand Towels | X |
| Pump Sprayer | X |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | X |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/3/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|--|---------------|
| | 44 | B1 | CEILING MODIFICATION (RECESSED LIGHTS) | ROUTINE |

| | | |
|---------------------|------------------|---------------|
| Site Address | City, State, Zip | Milwaukee, WI |
|---------------------|------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

Location of Work w/in structure 3RD FL BR 1

| Lead Content of Affected Surfaces | | | Work Statistics | | |
|-----------------------------------|------------|--------|-------------------------------|------------|-----------|
| Surface | XRF Result | % Lead | No. of Workers | Start Time | Stop Time |
| CEILING | 2.8 | and/or | 1 | 1030 | 1110 |
| | | | Total Time (hrs) | 0.6 | |
| | | | Tools and Equipment Used | | |
| | | | Use attached checklist | | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-E1-050206-045 | -A-Area 3RD FL BR 1 | 18105 | 13:36 | 2.52 | 14:37 | 2.52 | 61 | 2.52 | 153.7 | <13 |
| D-E1-050206-037 | -A-OS 3RD FL BR 3 | 18112 | 12:22 | 2.59 | 14:35 | 2.60 | 133 | 2.59 | 344.5 | <6 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-B1-050306-058 | -A-Area 3RD FL BR 1 | 16669 | 10:27 | 2.60 | 11:35 | 2.59 | 68 | 2.59 | 176.1 | 14 |
| D-B1-050306-059 | -A-PBZ WORKER | 17863 | 10:28 | 2.53 | 11:36 | 2.51 | 68 | 2.51 | 170.7 | 12 |
| D-F2-050306-060 | -A-OS 3RD FL BR 3 | 18110 | 10:06 | 2.57 | 13:06 | 2.54 | 180 | 2.54 | 457.2 | <4 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|---------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-B1-050306-073 | -A-Area 3RD FL BR 1 | 16669 | 11:36 | 2.59 | 12:50 | 2.58 | 74 | 2.58 | 190.9 | <11 |

Pre-work Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|---------------------|-----------|--------------|---------------------------------|------------------------------|
| C-E1-050206-252 | -W-Area 3RD FL BR 1 | HAND RAIL | WOOD | 0.33 | 452 |
| C-E1-050206-254 | -W-Area 3RD FL BR 1 | FLOOR S | WOOD | 1.00 | 1050 |
| C-E1-050206-253 | -W-Area 3RD FL BR 1 | FLOOR N | WOOD | 1.00 | 535 |
| C-E1-050206-255 | -W-OS 3RD FL BR 3 | FLOOR W | WOOD | 1.00 | 158 |

Clearance Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|---------------------|-----------|--------------|---------------------------------|------------------------------|
| C-B1-050306-270 | -W-Area 3RD FL BR 1 | HAND RAIL | WOOD | 0.58 | 779 |
| C-B1-050306-271 | -W-Area 3RD FL BR 1 | FLOOR S | WOOD | 1.00 | 481 |
| C-B1-050306-272 | -W-Area 3RD FL BR 1 | FLOOR N | WOOD | 1.00 | 653 |
| C-B1-050306-276 | -W-OS 3RD FL BR 3 | FLOOR W | WOOD | 1.00 | 245 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|--|
| Hygienist | |
| Activity | CEILING MODIFICATION (RECESSED LIGHTS) |
| Work Practice | ROUTINE |

| | |
|---|---------------|
| DATE | 5/3/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | B1 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | X |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | X |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/3/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|-----------------|---------------|
| | 45 | F2 | CEILING SANDING | mod LSWP |

| | | |
|---------------------|------------------|---------------|
| Site Address | City, State, Zip | Milwaukee, WI |
|---------------------|------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

| | | | | | |
|--|-------------|------------------|----------------|-------------------------------|--|
| Location of Work w/in structure | | LIVING ROOM | | | |
| Lead Content of Affected Surfaces | | | | | |
| Surface | XRF Result | and/or | % Lead | Work Statistics | |
| CEILING | 16.5 | | No. of Workers | 1 | |
| | | | Start Time | 1402 | |
| | | | Stop Time | 1506 | |
| | | Total Time (hrs) | 1 | Tools and Equipment Used | |
| | | | | Use attached checklist | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-C2-050206-050 -A-Area | LR S | 16609 | 13:58 | 2.58 | 15:00 | 2.58 | 62 | 2.58 | 160.0 | <13 |
| C-C2-050206-051 -A-Area | LR N | 16666 | 13:59 | 2.61 | 15:02 | 2.61 | 63 | 2.61 | 164.4 | <12 |
| D-C2-050206-040 -A-OS | KITCHEN | 18110 | 12:34 | 2.53 | 15:22 | 2.53 | 168 | 2.53 | 425.0 | <5 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-F2-050306-076 -A-Area | LR S | 16666 | 14:02 | 2.63 | 15:03 | 2.61 | 61 | 2.61 | 159.2 | <13 |
| D-F2-050306-077 -A-Area | LR N | 16609 | 14:00 | 2.65 | 15:05 | 2.55 | 65 | 2.55 | 165.8 | <12 |
| D-F2-050306-078 -A-PBZ | WORKER | 17185 | 14:02 | 2.63 | 15:06 | 2.57 | 64 | 2.57 | 164.5 | <12 |
| D-B1-050306-090 -A-OS | KITCHEN | 18112 | 13:52 | 2.63 | 16:43 | 2.63 | 171 | 2.63 | 449.7 | <4 |
| D-B1-050306-091 -A-OS | DINING ROOM | 17180 | 13:50 | 2.56 | 16:44 | 2.59 | 174 | 2.56 | 445.4 | <10 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-F2-050306-092 -A-Area | LR S | 16666 | 15:03 | 2.61 | 16:19 | 2.60 | 76 | 2.60 | 197.6 | <10 |
| C-F2-050306-093 -A-Area | LR N | 16609 | 15:05 | 2.55 | 16:21 | 2.58 | 76 | 2.55 | 193.8 | <10 |

Pre-work Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|----------|---------|--------------|---------------------------------|------------------------------|
| C-C2-050206-264 -W-Area | LR | W-SILL | WOOD | 0.29 | 683 |
| C-C2-050206-265 -W-Area | LR | FLOOR N | WOOD | 1.00 | 1050 |
| C-C2-050206-266 -W-Area | LR | FLOOR S | WOOD | 1.00 | 642 |
| C-F2-050206-262 -W-OS | KITCHEN | FLOOR S | WOOD | 1.00 | 5440 |

Clearance Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|----------|---------|--------------|---------------------------------|------------------------------|
| C-F2-050306-295 -W-Area | LR | W-SILL | WOOD | 0.29 | 253 |
| C-F2-050306-296 -W-Area | LR | FLOOR N | WOOD | 1.00 | 391 |
| C-F2-050306-297 -W-Area | LR | FLOOR S | WOOD | 1.00 | 370 |
| C-B1-050306-304 -W-OS | KITCHEN | FLOOR W | WOOD | 1.00 | 888 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-----------------|
| Hygienist | |
| Activity | CEILING SANDING |
| Work Practice | mod LSWP |

| | |
|---|---------------|
| DATE | 5/3/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | F2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | X |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | X |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | X |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | X |
| Disposable Towels | |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/3/2006 Hygienist

| Event | ID | Activity | Work Practice |
|-------|----|---------------------------------------|---------------|
| 46 | B1 | WALL MODIFICATION (DOOR INSTALLATION) | ROUTINE |

| | | |
|---------------------|------------------|---------------|
| Site Address | City, State, Zip | Milwaukee, WI |
|---------------------|------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

Location of Work w/in structure 2ND FL BR 1

| Lead Content of Affected Surfaces | | | Work Statistics | | |
|-----------------------------------|------------|--------|-------------------------------|------------|-----------|
| Surface | XRF Result | % Lead | No. of Workers | Start Time | Stop Time |
| BR 1 WALL | 13.4 | and/or | 1 | 1005 | 1145 |
| | | | Total Time (hrs) | 1.6 | |
| | | | Tools and Equipment Used | | |
| | | | <i>Use attached checklist</i> | | |
| | | | | | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C- C1-050206-052 -A-Area | 2ND FL BR 1 | 16608 | 14:28 | 2.55 | 15:29 | 2.59 | 61 | 2.55 | 155.6 | <13 |
| D- C2-050206-040 -A-OS | KITCHEN | 18110 | 12:34 | 2.53 | 15:22 | 2.53 | 168 | 2.53 | 425.0 | <5 |
| D- C2-050206-041 -A-OS | GRND FL | 17451 | 12:38 | 2.68 | 15:06 | 2.67 | 148 | 2.67 | 395.2 | <5 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D- B1-050306-066 -A-Area | 2ND FL BR 1 | 17184 | 10:03 | 2.67 | 11:54 | 2.61 | 111 | 2.61 | 289.7 | <7 |
| D- B1-050306-067 -A-PBZ | WORKER | 18107 | 10:02 | 2.62 | 11:47 | 2.67 | 105 | 2.62 | 275.1 | 12 |
| D- 050306-068 -A-OS | KITCHEN | 18112 | 10:05 | 2.64 | 13:51 | 2.63 | 226 | 2.63 | 594.4 | <3 |
| D- 050306-069 -A-OS | DINING ROOM | 17180 | 10:05 | 2.65 | 13:49 | 2.65 | 224 | 2.65 | 593.6 | <3 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|-------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C- B1-050306-074 -A-Area | 2ND FL BR 1 | 17184 | 11:55 | 2.61 | 13:28 | 2.61 | 93 | 2.61 | 242.7 | <8 |
| C- B1-050306-070 -A-Area | 2ND FL BR 2 | 18105 | 11:56 | 2.57 | 13:26 | 2.53 | 90 | 2.53 | 227.7 | <9 |

Pre-work Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|-------------|---------|--------------|---------------------------------|------------------------------|
| C- C1-050206-267 -W-Area | 2ND FL BR 1 | W-SILL | WOOD | 0.42 | 11400 |
| C- C1-050206-268 -W-Area | 2ND FL BR 1 | FLOOR N | WOOD | 1.00 | 306 |
| C- C1-050206-269 -W-Area | 2ND FL BR 1 | FLOOR S | WOOD | 1.00 | 315 |
| C- F2-050206-262 -W-OS | KITCHEN | FLOOR S | WOOD | 1.00 | 5440 |

Clearance Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|-------------|---------|--------------|---------------------------------|------------------------------|
| C- B1-050306-277 -W-Area | 2ND FL BR 1 | W-SILL | WOOD | 0.42 | 890 |
| C- B1-050306-278 -W-Area | 2ND FL BR 1 | FLOOR E | WOOD | 1.00 | 240 |
| C- B1-050306-279 -W-Area | 2ND FL BR 1 | FLOOR W | WOOD | 1.00 | 214 |
| C- D3-050306-283 -W-OS | KITCHEN | FLOOR S | WOOD | 1.00 | 1470 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|---------------------------------------|
| Hygienist | |
| Activity | WALL MODIFICATION (DOOR INSTALLATION) |
| Work Practice | ROUTINE |

| | |
|---|---------------|
| DATE | 5/3/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | B1 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | X |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | X |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/3/2006 Hygienist

| Event | ID | Activity | Work Practice |
|----------|----|--|---------------|
| Scenario | 47 | B1 WALL MODIFICATION (WINDOW INSTALLATION) | ROUTINE |

| | |
|--------------------------------------|---------------|
| Site Address City, State, Zip | Milwaukee, WI |
|--------------------------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

Location of Work w/in structure 2ND FL BR 1

| Lead Content of Affected Surfaces | | | | Work Statistics | | |
|-----------------------------------|-------------|---|------|-------------------------------|--------|--|
| Surface | XRF Result | % | Lead | No. of Workers | Result | |
| BR 1 WALL | 13.4 | | | 1 | | |
| | | | | Start Time | 1358 | |
| | | | | Stop Time | 1539 | |
| | | | | Total Time (hrs) | 1.6 | |
| | | | | Tools and Equipment Used | | |
| | | | | <i>Use attached checklist</i> | | |

Pre-Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-B1-050306-074 | -A-Area 2ND FL BR 1 | 17184 | 11:55 | 2.61 | 13:28 | 2.61 | 93 | 2.61 | 242.7 | <8 |
| C-B1-050306-070 | -A-Area 2ND FL BR 2 | 18105 | 11:56 | 2.57 | 13:26 | 2.53 | 90 | 2.53 | 227.7 | <9 |
| D-050306-068 | -A-OS KITCHEN | 18112 | 10:05 | 2.64 | 13:51 | 2.63 | 226 | 2.63 | 594.4 | <3 |
| D-050306-069 | -A-OS DINING ROOM | 17180 | 10:05 | 2.65 | 13:49 | 2.65 | 224 | 2.65 | 593.6 | <3 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-B1-050306-087 | -A-Area 2ND FL BR 1 | 17184 | 13:59 | 2.61 | 15:34 | 2.63 | 95 | 2.61 | 248.0 | 9 |
| D-B1-050306-088 | -A-Area 2ND FL BR 2 | 18105 | 13:58 | 2.53 | 15:36 | 2.58 | 98 | 2.53 | 247.9 | 28 |
| D-B1-050306-089 | -A-PBZ WORKER | 16612 | 13:58 | 2.57 | 15:39 | 2.59 | 101 | 2.57 | 259.6 | 63 |
| D-B1-050306-090 | -A-OS KITCHEN | 18112 | 13:52 | 2.63 | 16:43 | 2.63 | 171 | 2.63 | 449.7 | <4 |
| D-B1-050306-091 | -A-OS DINING ROOM | 17180 | 13:50 | 2.56 | 16:44 | 2.59 | 174 | 2.56 | 445.4 | <10 |

Post-Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|---------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-B1-050306-095 | -A-Area 2ND FL BR 1 | 17184 | 15:35 | 2.63 | 16:38 | 2.63 | 63 | 2.63 | 165.7 | <12 |
| C-B1-050306-096 | -A-Area 2ND FL BR 2 | 18105 | 15:36 | 2.61 | 16:39 | 2.60 | 63 | 2.60 | 163.8 | <12 |

Pre-work Wipe Sampling

| Sample No. (P-Scenario/D-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|---------------------|---------|--------------|---------------------------------|------------------------------|
| C-B1-050306-277 | -W-Area 2ND FL BR 1 | W-SILL | WOOD | 0.42 | 890 |
| C-B1-050306-278 | -W-Area 2ND FL BR 1 | FLOOR E | WOOD | 1.00 | 240 |
| C-B1-050306-279 | -W-Area 2ND FL BR 1 | FLOOR W | WOOD | 1.00 | 214 |
| C-D3-050306-283 | -W-OS KITCHEN | FLOOR S | WOOD | 1.00 | 1470 |

Clearance Wipe Sampling

| Sample No. (P-Scenario/D-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|---------------------|---------|--------------|---------------------------------|------------------------------|
| C-B1-050306-301 | -W-Area 2ND FL BR 1 | W-SILL | WOOD | 0.42 | 979 |
| C-B1-050306-302 | -W-Area 2ND FL BR 1 | FLOOR N | WOOD | 1.00 | 350 |
| C-B1-050306-303 | -W-Area 2ND FL BR 2 | FLOOR S | WOOD | 1.00 | 153 |
| C-B1-050306-304 | -W-OS KITCHEN | FLOOR W | WOOD | 1.00 | 888 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|---|
| Hygienist | |
| Activity | WALL MODIFICATION (WINDOW INSTALLATION) |
| Work Practice | ROUTINE |

| | |
|---|---------------|
| DATE | 5/3/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | B1 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | X |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | X |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | X |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/3/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|-----------------|---------------|
| | 48 | D2 | CABINET REMOVAL | HUD/EPA LSWP |

| | | |
|---------------------|------------------|---------------|
| Site Address | City, State, Zip | Milwaukee, WI |
|---------------------|------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1905 |
| | Town House | | Other (describe) | Approx. Square Footage | |
| | Condomium | | | No. of Separate Rooms | 15 |

| | | | | | |
|--|------------|--------|----------------|-------------------------------|------------|
| Location of Work w/in structure | | BATH | | | |
| Lead Content of Affected Surfaces | | | | | |
| Surface | XRF Result | and/or | % Lead | Work Statistics | |
| CABINET | 9.6 | | No. of Workers | 1 | Start Time |
| | | | | Stop Time | 1240 |
| | | | | Total Time (hrs) | 2.5 |
| | | | | Tools and Equipment Used | |
| | | | | Use attached checklist | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P-D3-050106-011 -A-Area | BATH | 17183 | 15:37 | 2.67 | 16:15 | 2.69 | 38 | 2.67 | 101.5 | <20 |
| P-C3-050106-004 -A-OS | GRND FL | 17184 | 15:10 | 2.66 | 15:56 | 2.66 | 46 | 2.66 | 122.4 | <16 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-D3-050306-064 -A-Area | BATH | 17179 | 10:15 | 2.64 | 12:41 | 2.63 | 146 | 2.63 | 384.0 | <5 |
| D-D3-050306-065 -A-PBZ | WORKER | 16608 | 10:15 | 2.57 | 12:43 | 2.53 | 148 | 2.53 | 374.4 | 6 |
| D-050306-069 -A-OS | DINING ROOM | 17180 | 10:05 | 2.65 | 13:49 | 2.65 | 224 | 2.65 | 593.6 | <3 |
| D-050306-068 -A-OS | KITCHEN | 18112 | 10:05 | 2.64 | 13:51 | 2.63 | 226 | 2.63 | 594.4 | <3 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-D3-050306-080 -A-Area | BATH | 17179 | 12:43 | 2.63 | 13:48 | 2.63 | 65 | 2.63 | 171.0 | <12 |

Pre-work Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|-----------|---------|--------------|---------------------------------|------------------------------|
| P-D3-050206-215 -W-Area | BATH | W-SILL | WOOD | 0.42 | 213 |
| P-D3-050206-216 -W-Area | BATH | FLOOR S | LINOLEUM | 1.00 | 996 |
| P-D3-050206-217 -W-Area | BATH | FLOOR N | LINOLEUM | 1.00 | 1210 |
| P-C3-050206-211 -W-OS | GROUND FL | FLOOR | WOOD | 1.00 | 800 |

Clearance Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|----------|---------|--------------|---------------------------------|------------------------------|
| C-D3-050306-280 -W-Area | BATH | W-SILL | WOOD | 0.42 | 354 |
| C-D3-050306-281 -W-Area | BATH | FLOOR W | LINOLEUM | 1.00 | 1470 |
| C-D3-050306-282 -W-Area | BATH | FLOOR E | LINOLEUM | 1.00 | 571 |
| C-D3-050306-283 -W-OS | KITCHEN | FLOOR S | WOOD | 1.00 | 1470 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-----------------|
| Hygienist | |
| Activity | CABINET REMOVAL |
| Work Practice | LSWP |

| | |
|---|---------------|
| DATE | 5/3/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | D3 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | X |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | X |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | X |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | X |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | X |
| Disposable Hand Towels | X |
| Pump Sprayer | X |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | X |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/3/2006 Hygienist

| Event | ID | Activity | Work Practice |
|----------|----|---------------------------------------|---------------|
| Scenario | 49 | F2 SURFACE PREPARATION (WINDOW FRAME) | mod LSWP |

| | | |
|--------------|------------------|---------------|
| Site Address | City, State, Zip | Milwaukee, WI |
|--------------|------------------|---------------|

| | | | | | |
|----------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

Location of Work w/in structure 3RD FL BR 2

| Lead Content of Affected Surfaces | | | | Work Statistics | | |
|-----------------------------------|------------|--------|--------|-----------------|-------------------------------|--|
| Surface | XRF Result | and/or | % Lead | No. of Workers | | |
| WINDOW SASH | 6 | | | 1 | Start Time 1058 | |
| WINDOW SILL | 5.6 | | | 1205 | Stop Time | |
| | | | | 1 | Total Time (hrs) | |
| | | | | | Tools and Equipment Used | |
| | | | | | Use attached checklist | |

Pre-Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|--|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| P-F2-050106-002 | -A-Area 3RD FL BR 2 | 18105 | 14:56 | 2.58 | 15:50 | 2.57 | 54 | 2.57 | 138.8 | <14 | |
| P-B1-050106-001 | -A-OS 3RD FL BR 3 | 17180 | 14:55 | 2.65 | 15:48 | 2.63 | 53 | 2.63 | 139.4 | <14 | |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|--|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| D-F2-050306-056 | -A-Area 3RD FL BR 2 | 16670 | 10:58 | 2.55 | 12:04 | 2.54 | 66 | 2.54 | 167.6 | 73 | |
| D-F2-050306-057 | -A-PBZ WORKER | 18104 | 10:58 | 2.52 | 12:05 | 2.57 | 67 | 2.52 | 168.8 | 140 | |
| D-F2-050306-060 | -A-OS 3RD FL BR 3 | 18110 | 10:06 | 2.57 | 13:06 | 2.54 | 180 | 2.54 | 457.2 | <4 | |

Post-Work Sampling

| Air Sampling | | | | | | | | | | | |
|--|---------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|--|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| C-F2-050306-075 | -A-Area 3RD FL BR 2 | 16670 | 12:04 | 2.54 | 13:05 | 2.50 | 61 | 2.50 | 152.5 | <13 | |

Pre-work Wipe Sampling

| Wipe Sampling | | | | | | |
|--|---------------------|---------|--------------|---------------------------------|------------------------------|--|
| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| P-B1-050106-204 | -W-Area 3RD FL BR 2 | FLOOR S | WOOD | 1.00 | 236 | |
| P-B1-050106-205 | -W-Area 3RD FL BR 2 | FLOOR N | WOOD | 1.00 | 54.3 | |
| P-B1-050106-206 | -W-Area 3RD FL BR 2 | W-SILL | WOOD | 0.75 | 2590 | |
| P-B1-050106-207 | -W-OS 3RD FL BR 3 | FLOOR | WOOD | 1.00 | 126 | |

Clearance Wipe Sampling

| Wipe Sampling | | | | | | |
|--|---------------------|---------|--------------|---------------------------------|------------------------------|--|
| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| C-F2-050306-273 | -W-Area 3RD FL BR 2 | W-SILL | WOOD | 0.67 | 734 | |
| C-F2-050306-274 | -W-Area 3RD FL BR 2 | FLOOR N | WOOD | 1.00 | 81.2 | |
| C-F2-050306-275 | -W-Area 3RD FL BR 2 | FLOOR S | WOOD | 1.00 | 1210 | |
| C-B1-050306-276 | -W-OS 3RD FL BR 3 | FLOOR W | WOOD | 1.00 | 245 | |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|------------------------------------|
| Hygienist | |
| Activity | SURFACE PREPARATION (WINDOW FRAME) |
| Work Practice | mod LSWP |

| | |
|---|---------------|
| DATE | 5/3/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | F2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | X |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | X |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | X |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | X |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/4/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|-----------------|---------------|
| 50 | A2 | | WALL DEMOLITION | mod LSWP |

| | |
|--------------------------------------|---------------|
| Site Address City, State, Zip | Milwaukee, WI |
|--------------------------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1905 |
| | Town House | | Other (describe) | Approx. Square Footage | |
| | Condomium | | | No. of Separate Rooms | 15 |

| | | | | | |
|--|--|-------------|--------|--------|------|
| Location of Work w/in structure | | 2ND FL BR 1 | | | |
| Lead Content of Affected Surfaces | | | | | |
| Surface | | XRF Result | | % Lead | |
| BR 1 WALL | | 13.4 | | | |
| BR 2 CEILING | | 12.7 | and/or | | |
| | | | | | |
| | | | | | |
| Work Statistics | | | | | |
| No. of Workers | | | | | 2 |
| Start Time | | | | | 950 |
| Stop Time | | | | | 1405 |
| Total Time (hrs) | | | | | 4.25 |
| Tools and Equipment Used | | | | | |
| Use attached checklist | | | | | |

Pre-Work Sampling

| Air Sampling | | | | | | | | | | |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| C-B1-050306-095 -A-Area | 2ND FL BR 1 | 17184 | 15:35 | 2.63 | 16:38 | 2.63 | 63 | 2.63 | 165.7 | <12 |
| C-B1-050306-096 -A-Area | 2ND FL BR 2 | 18105 | 15:36 | 2.61 | 16:39 | 2.60 | 63 | 2.60 | 163.8 | <12 |
| D-B1-050306-091 -A-OS | DINING ROOM | 17180 | 13:50 | 2.56 | 16:44 | 2.59 | 174 | 2.56 | 445.4 | <10 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Air Sampling | | | | | | | | | | |
|--|----------------------------|---------|---------|----------|-----------------------------------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| D-A2-050406-103 -A-Area | 2ND FL BR 1 | 18107 | 9:47 | 2.59 | 14:12 | 2.65 | 265 | 2.59 | 686.4 | <3 |
| D-A2-050406-104 -A-Area | 2ND FL BR 2 | 16666 | 9:50 | 2.65 | 14:11 | 2.63 | 261 | 2.63 | 686.4 | <3 |
| D-A2-050406-105 -A-PBZ | WORKER | 16612 | 9:48 | 2.63 | 14:07 | 2.60 | 259 | 2.60 | 673.4 | 4 |
| D-A2-050406-106 -A-PBZ | WORKER | 16608 | 9:48 | 2.57 | VOIDED, SAMPLE DETACHED FROM PUMP | | | | | |
| D-A2-050406-107 -A-OS | LR | 17451 | 9:52 | 2.62 | 16:35 | 2.60 | 403 | 2.60 | 1047.8 | <2 |

Post-Work Sampling

| Air Sampling | | | | | | | | | | |
|--|-------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
| C-A2-050406-116 -A-Area | 2ND FL BR 1 | 18107 | 14:14 | 2.65 | 15:34 | 2.65 | 80 | 2.65 | 212.0 | <9 |
| C-A2-050406-117 -A-Area | 2ND FL BR 2 | 16666 | 14:15 | 2.63 | 15:36 | 2.63 | 81 | 2.63 | 213.0 | <9 |

Pre-work Wipe Sampling

| Wipe Sampling | | | | | |
|--|-------------|---------|--------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| P-A2-050406-276 -W-Area | 2ND FL BR 2 | FLOOR | WOOD | 1.00 | 227 |
| P-A2-050406-277 -W-Area | 2ND FL BR 1 | FLOOR | WOOD | 1.00 | 334 |
| P-A2-050406-278 -W-Area | 2ND FL BR 1 | W-SILL | WOOD | 0.88 | 263 |
| C-B2-050406-282 -W-OS | 3RD FL BR 3 | FLOOR | WOOD | 1.00 | 226 |

Clearance Wipe Sampling

| Wipe Sampling | | | | | |
|--|-------------|---------|--------------|---------------------------------|------------------------------|
| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
| C-A2-050406-284 -W-Area | 2ND FL BR 2 | FLOOR | WOOD | 1.00 | 242 |
| C-A2-050406-285 -W-Area | 2ND FL BR 1 | FLOOR | WOOD | 1.00 | 271 |
| C-A2-050406-286 -W-Area | 2ND FL BR 1 | W-SILL | WOOD | 0.75 | 200 |
| C-F1-050406-287 -W-OS | 3RD FL BR 3 | FLOOR | WOOD | 1.00 | 219 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-----------------|
| Hygienist | |
| Activity | WALL DEMOLITION |
| Work Practice | mod LSWP |

| | |
|---|---------------|
| DATE | 5/4/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | A2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | X |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | X |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | X |
| Reusable Wet Mop w/ One Bucket | X |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | X |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | X |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/4/2006 Hygienist

| Event | ID | Activity | Work Practice |
|-------|----|---|---------------|
| 51 | B2 | WALL MODIFICATION (OUTLET INSTALLATION) | mod LSWP |

Site Address City, State, Zip Milwaukee, WI

| | | | | | |
|----------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

Location of Work w/in structure 3RD FL BR 1

| Lead Content of Affected Surfaces | | | XRF Result | % Lead | and/or | Work Statistics | |
|-----------------------------------|--|--|------------|--------|--------|-------------------------------|------|
| Surface | | | | | | No. of Workers | |
| WALL 4 | | | 4.4 | | | No. of Workers | 1 |
| WALL 3 | | | 4.5 | | | Start Time | 955 |
| | | | | | | Stop Time | 1045 |
| | | | | | | Total Time (hrs) | 0.8 |
| | | | | | | Tools and Equipment Used | |
| | | | | | | Use attached checklist | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-A2-050306-097 | -A-Area 3RD FL BR 1 | 16669 | 16:08 | 2.53 | 17:08 | 2.57 | 60 | 2.53 | 151.8 | <13 |
| D-A2-050306-084 | -A-OS 3RD FL BR 3 | 18110 | 13:07 | 2.54 | 15:09 | 2.49 | 122 | 2.49 | 303.8 | <7 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-B2-050406-108 | -A-Area 3RD FL BR 1 | 17180 | 9:58 | 2.60 | 10:49 | 2.59 | 51 | 2.59 | 132.1 | <15 |
| D-B2-050406-109 | -A-PBZ WORKER | 18110 | 9:58 | 2.60 | 10:49 | 2.59 | 51 | 2.59 | 132.1 | <15 |
| D-B2-050406-110 | -A-OS 3RD FL BR 3 | 18104 | 10:00 | 2.59 | 11:51 | 2.63 | 111 | 2.59 | 287.5 | <7 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|---------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-B2-050406-111 | -A-Area 3RD FL BR 1 | 17180 | 10:48 | 2.59 | 11:50 | 2.59 | 62 | 2.59 | 160.6 | <12 |

Pre-work Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|---------------------|---------|--------------|---------------------------------|------------------------------|
| C-A2-050306-306 | -W-Area 3RD FL BR 1 | FLOOR E | WOOD | 1.00 | 163 |
| C-A2-050306-307 | -W-Area 3RD FL BR 1 | FLOOR N | WOOD | 1.00 | 151 |
| C-A2-050306-308 | -W-Area 3RD FL BR 1 | FLOOR S | WOOD | 1.00 | 3800 |
| C-A2-050306-309 | -W-OS 3RD FL BR 3 | FLOOR E | WOOD | 1.00 | 165 |

Clearance Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|---------------------|----------|--------------|---------------------------------|------------------------------|
| C-B2-050406-279 | -W-Area 3RD FL BR 1 | FLOOR | WOOD | 1.00 | 68.7 |
| C-B2-050406-280 | -W-Area 3RD FL BR 1 | FLOOR | WOOD | 1.00 | 314 |
| C-B2-050406-281 | -W-Area 3RD FL BR 1 | BANISTER | WOOD | 0.37 | <27 |
| C-B2-050406-282 | -W-OS 3RD FL BR 3 | FLOOR | WOOD | 1.00 | 226 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|--------------------------------|
| Hygienist | |
| Activity | WALL MOD - OUTLET INSTALLATION |
| Work Practice | mod LSWP |

| | |
|---|---------------|
| DATE | 5/4/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | B2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | X |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | X |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | X |
| Disposable Towels | |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/4/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|----------------|---------------|
| | 52 | C2 | WINDOW REMOVAL | mod LSWP |

| | |
|--------------------------------------|---------------|
| Site Address City, State, Zip | Milwaukee, WI |
|--------------------------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

| | | | | | |
|--|------------|-------------|------|--------------------------|------|
| Location of Work w/in structure | | DINING ROOM | | | |
| Lead Content of Affected Surfaces | | | | | |
| Surface | XRF Result | | % | Work Statistics | |
| WINDOW SASH | 11 | | Lead | | |
| WINDOW SASH | 7.5 | and/or | | | |
| | | | | | |
| | | | | | |
| | | | | No. of Workers | 1 |
| | | | | Start Time | 1130 |
| | | | | Stop Time | 1503 |
| | | | | Total Time (hrs) | 3.5 |
| | | | | Tools and Equipment Used | |
| Use attached checklist | | | | | |

Pre-Work Sampling

| Air Sampling | | | | | | | | | | | |
|---|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|--|
| Sample No. <small>(P-ScenarioID-Date-## -A-Type)</small> | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| P-C2-050106-013 -A-Area | DINING ROOM | 16669 | 15:42 | 2.63 | 16:21 | 2.64 | 39 | 2.63 | 102.6 | <20 | |
| P-C3-050106-004 -A-OS | GRND FL | 17184 | 15:10 | 2.66 | 15:56 | 2.66 | 46 | 2.66 | 122.4 | <16 | |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Air Sampling | | | | | | | | | | | |
|---|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|--|
| Sample No. <small>(P-ScenarioID-Date-## -A-Type)</small> | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| D-C2-050406-101 -A-Area | DINING ROOM | 17179 | 11:30 | 2.66 | 15:29 | 2.67 | 239 | 2.66 | 635.7 | <3 | |
| D-C2-050406-102 -A-PBZ | WORKER | 16669 | 11:31 | 2.59 | 15:27 | 2.60 | 236 | 2.59 | 611.2 | 7 | |
| D-A2-050406-107 -A-OS | LR | 17451 | 9:52 | 2.62 | 16:35 | 2.60 | 403 | 2.60 | 1047.8 | <2 | |

Post-Work Sampling

| Air Sampling | | | | | | | | | | | |
|---|-------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|--|
| Sample No. <small>(P-ScenarioID-Date-## -A-Type)</small> | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| C-C2-050406-120 -A-Area | DINING ROOM | 17179 | 15:30 | 2.67 | 16:32 | 2.66 | 62 | 2.66 | 164.9 | <12 | |

Pre-work Wipe Sampling

| Wipe Sampling | | | | | | |
|---|-------------|---------|--------------|---------------------------------|------------------------------|--|
| Sample No. <small>(P-ScenarioID-Date-## -W-Location)</small> | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| P-C2-050206-233 -W-Area | DINING ROOM | FLOOR N | WOOD | 1.00 | 681 | |
| P-C2-050206-234 -W-Area | DINING ROOM | FLOOR S | WOOD | 1.00 | 720 | |
| P-C2-050206-235 -W-Area | DINING ROOM | W-SILL | WOOD | 0.50 | 5120 | |
| P-C3-050206-211 -W-OS | GROUND FL | FLOOR | WOOD | 1.00 | 800 | |

Clearance Wipe Sampling

| Wipe Sampling | | | | | | |
|---|-------------|---------|--------------|---------------------------------|------------------------------|--|
| Sample No. <small>(P-ScenarioID-Date-## -W-Location)</small> | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| C-C2-050406-295 -W-Area | DINING ROOM | FLOOR | WOOD | 1.00 | 180 | |
| C-C2-050406-296 -W-Area | DINING ROOM | W-SILL | WOOD | 0.57 | 523 | |
| C-C2-050406-297 -W-Area | DINING ROOM | FLOOR | WOOD | 1.00 | 239 | |
| C-C2-050406-298 -W-OS | LR | FLOOR | WOOD | 1.00 | 1210 | |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|----------------|
| Hygienist | |
| Activity | WINDOW REMOVAL |
| Work Practice | mod LSWP |

| | |
|---|---------------|
| DATE | 5/4/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | C2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | X |
| Orange Cones | |
| Signs | |
| Doorways/Opening Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | X |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | X |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | X |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/4/2006 Hygienist

| Event | ID | Activity | Work Practice |
|-------|----|----------------------------------|---------------|
| 53 | F1 | SURFACE PREP (SAND STAIR TREADS) | ROUTINE |

| | | |
|---------------------|------------------|---------------|
| Site Address | City, State, Zip | Milwaukee, WI |
|---------------------|------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

| | | | | | |
|--|------------|--------|------------------------|--------------------------|------|
| Location of Work w/in structure | STAIRWELL | | | | |
| Lead Content of Affected Surfaces | | | Work Statistics | | |
| Surface | XRF Result | and/or | % Lead | No. of Workers | 1 |
| STAIR TREADS | 13 | | | Start Time | 1405 |
| | | | | Stop Time | 1455 |
| | | | | Total Time (hrs) | 0.8 |
| | | | | Tools and Equipment Used | |
| <i>Use attached checklist</i> | | | | | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P-F1-050106-009 | -A-Area STAIRWELL | 17185 | 15:30 | 2.68 | 16:10 | 2.67 | 40 | 2.67 | 106.8 | <19 |
| P-B1-050106-001 | -A-OS 3RD FL BR 3 | 17180 | 14:55 | 2.65 | 15:48 | 2.63 | 53 | 2.63 | 139.4 | <14 |
| P-C3-050106-004 | -A-OS GRND FL | 17184 | 15:10 | 2.66 | 15:56 | 2.66 | 46 | 2.66 | 122.4 | <16 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-F1-050406-112 | -A-Area STAIRWELL | 17185 | 14:05 | 2.67 | 14:57 | 2.61 | 52 | 2.61 | 135.7 | 45 |
| C-B2-050406-111 | -A-Area 3RD FL BR 1 | 17180 | 10:48 | 2.59 | 11:50 | 2.59 | 62 | 2.59 | 160.6 | <12 |
| D-F1-050406-113 | -A-PBZ WORKER | 17863 | 14:04 | 2.60 | 14:55 | 2.53 | 51 | 2.53 | 129.0 | 145 |
| D-F1-050406-114 | -A-OS 3RD FL BR 3 | 18104 | 14:01 | 2.66 | 16:17 | 2.62 | 136 | 2.62 | 356.3 | <6 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|---------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-F1-050406-118 | -A-Area STAIRWELL | 17185 | 14:59 | 2.61 | 16:14 | 2.68 | 75 | 2.61 | 195.8 | <10 |
| C-F1-050406-119 | -A-Area 3RD FL BR 1 | 17180 | 15:00 | 2.56 | 16:16 | 2.63 | 76 | 2.56 | 194.6 | <10 |

Pre-work Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|---------------------|--------------|--------------|---------------------------------|------------------------------|
| C-B2-050406-281 | -W-Area 3RD FL BR 1 | BANISTER | WOOD | 0.37 | <27 |
| C-B2-050406-279 | -W-Area 3RD FL BR 1 | FLOOR | WOOD | 1.00 | 68.7 |
| C-B2-050406-280 | -W-Area 3RD FL BR 1 | FLOOR | WOOD | 1.00 | 314 |
| P-F1-050106-208 | -W-Area STAIRWELL | TOP TREAD | WOOD | 0.63 | 645 |
| P-F1-050106-209 | -W-Area STAIRWELL | BOTTOM TREAD | WOOD | 0.63 | 1630 |
| P-F1-050106-210 | -W-Area STAIRWELL | LANDING | LINOLEUM | 1.00 | 341 |
| P-B1-050106-207 | -W-OS 3RD FL BR 3 | FLOOR | WOOD | 1.00 | 126 |

Clearance Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|---------------------|----------|--------------|---------------------------------|------------------------------|
| C-F1-050406-288 | -W-Area 3RD FL BR 1 | BANISTER | WOOD | 0.26 | 1100 |
| C-F1-050406-289 | -W-Area 3RD FL BR 1 | FLOOR | WOOD | 1.00 | 707 |
| C-F1-050406-290 | -W-Area 3RD FL BR 1 | FLOOR | WOOD | 1.00 | 2020 |
| C-F1-050406-291 | -W-Area STAIRWELL | TREAD | WOOD | 0.71 | 476 |
| C-F1-050406-292 | -W-Area STAIRWELL | W-SILL | WOOD | 0.46 | 3200 |
| C-F1-050406-293 | -W-Area STAIRWELL | FLOOR | LINOLEUM | 1.00 | 1520 |
| C-F1-050406-287 | -W-OS 3RD FL BR 3 | FLOOR | WOOD | 1.00 | 219 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|----------------------------------|
| Hygienist | |
| Activity | SURFACE PREP (SAND STAIR TREADS) |
| Work Practice | ROUTINE |

| | |
|---|---------------|
| DATE | 5/4/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | F1 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | |
| Tape | |
| Utility Knife | |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | X |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/5/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|-----------------------|---------------|
| | 54 | B2 | REMOVE SHELF SUPPORTS | mod LSWP |

| | | |
|---------------------|------------------|---------------|
| Site Address | City, State, Zip | Milwaukee, WI |
|---------------------|------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

| | | | | | |
|--|--|------------|--------|--------|--|
| Location of Work w/in structure | | CLOSET | | | |
| Lead Content of Affected Surfaces | | | | | |
| Surface | | XRF Result | | % Lead | |
| Wall | | 25.3 | | | |
| | | | and/or | | |
| | | | | | |
| | | | | | |
| | | | | | Work Statistics No. of Workers 1 Start Time 901 Stop Time 952 Total Time (hrs) 0.8 Tools and Equipment Used <i>Use attached checklist</i> |

Pre-Work Sampling

| Air Sampling | | | | | | | | | | | |
|---|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|-----|
| Sample No. <small>(P-ScenarioID-Date-## -A-Type)</small> | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| P-B2-050206-015 | -A-Area | CLOSET | 16612 | 7:35 | 2.61 | 8:31 | 2.66 | 56 | 2.61 | 146.2 | <14 |
| P-C3-050206-016 | -A-OS | GRND FL | 17451 | 7:39 | 2.63 | 8:48 | 2.68 | 69 | 2.63 | 181.5 | <11 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Air Sampling | | | | | | | | | | | |
|---|----------------------------|-------------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|-----|
| Sample No. <small>(P-ScenarioID-Date-## -A-Type)</small> | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| D-B2-050506-126 | -A-Area | CLOSET | 18104 | 9:00 | 2.63 | 9:50 | 2.66 | 50 | 2.63 | 131.5 | <15 |
| D-B2-050506-127 | -A-PBZ | WORKER | 17863 | 9:01 | 2.58 | 9:52 | 2.53 | 51 | 2.53 | 129.0 | <16 |
| D-C1-050506-125 | -A-OS | 2ND FL BR 2 | 16612 | 9:06 | 2.61 | 11:38 | 2.61 | 152 | 2.61 | 396.7 | <5 |

Post-Work Sampling

| Air Sampling | | | | | | | | | | | |
|---|----------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|----|
| Sample No. <small>(P-ScenarioID-Date-## -A-Type)</small> | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) | |
| C-B2-050506-134 | -A-Area | CLOSET | 18104 | 9:51 | 2.66 | 11:27 | 2.64 | 96 | 2.64 | 253.4 | <8 |

Pre-work Wipe Sampling

| Wipe Sampling | | | | | | |
|---|----------|-----------------|--------------|---------------------------------|------------------------------|------|
| Sample No. <small>(P-ScenarioID-Date-## -W-Location)</small> | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| P-B2-050206-230 | -W-Area | CLOSET | FLOOR W | WOOD | 1.00 | 1320 |
| P-B2-050206-237 | -W-Area | 2ND FL STAIRWAY | W-SILL | WOOD | 0.33 | 3090 |
| P-B2-050206-231 | -W-Area | CLOSET | FLOOR E | WOOD | 1.00 | 4710 |
| C-F1-050406-287 | -W-OS | 3RD FL BR 3 | FLOOR | WOOD | 1.00 | 219 |

Clearance Wipe Sampling

| Wipe Sampling | | | | | | |
|---|----------|-----------------|--------------|---------------------------------|------------------------------|------|
| Sample No. <small>(P-ScenarioID-Date-## -W-Location)</small> | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) | |
| C-B2-050506-302 | -W-Area | CLOSET | FLOOR | WOOD | 1.00 | 2670 |
| C-B2-050506-303 | -W-Area | 2ND FL STAIRWAY | W-SILL | WOOD | 0.73 | 2700 |
| C-B2-050506-304 | -W-Area | CLOSET | FLOOR | WOOD | 1.00 | 1530 |
| C-B2-050506-329 | -W-OS | 2ND FL BR 2 | FLOOR | WOOD | 1.00 | 186 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-----------------------|
| Hygienist | |
| Activity | REMOVE SHELF SUPPORTS |
| Work Practice | mod LSWP |

| | |
|---|---------------|
| DATE | 5/5/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | B2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | X |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/5/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|--|---------------|
| | 55 | B2 | CEILING MODIFICATION (RECESSED LIGHTING) | mod LSWP |

| | | |
|---------------------|------------------|---------------|
| Site Address | City, State, Zip | Milwaukee, WI |
|---------------------|------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

Location of Work w/in structure 3RD FL BR 1

| Lead Content of Affected Surfaces | | XRF Result | and/or | % Lead | Work Statistics | |
|-----------------------------------|--|------------|--------|--------|-------------------------------|------|
| Surface | | | | | No. of Workers | |
| CEILING | | 2.9 | | | No. of Workers | 2 |
| | | | | | Start Time | 1220 |
| | | | | | Stop Time | 1311 |
| | | | | | Total Time (hrs) | 0.8 |
| | | | | | Tools and Equipment Used | |
| | | | | | Use attached checklist | |

Pre-Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-E2-050506-138 -A-Area | 3RD FL BR 1 | 16609 | 10:41 | 2.61 | 11:44 | 2.58 | 63 | 2.58 | 162.5 | <12 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-B2-050506-145 -A-Area | 3RD FL BR 1 | 16609 | 12:19 | 2.58 | 13:10 | 2.56 | 51 | 2.56 | 130.6 | <15 |
| D-B2-050506-146 -A-PBZ | WORKER | 16669 | 12:20 | 2.57 | 13:11 | 2.60 | 51 | 2.57 | 131.1 | 26 |
| D-B2-050506-147 -A-PBZ | WORKER | 16670 | 12:20 | 2.68 | 13:12 | 2.65 | 52 | 2.65 | 137.8 | 23 |
| D-B2-050506-148 -A-OS | 3RD FL BR 3 | 17180 | 12:04 | 2.62 | 14:08 | 2.59 | 124 | 2.59 | 321.2 | <6 |

Post-Work Sampling

| Sample No. (P-Scenario/D-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|-------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-B2-050506-153 -A-Area | 3RD FL BR 1 | 16609 | 13:10 | 2.56 | 14:11 | 2.56 | 61 | 2.56 | 156.2 | <13 |

Pre-work Wipe Sampling

| Sample No. (P-Scenario/D-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|-------------|----------|--------------|---------------------------------|------------------------------|
| C-E2-050506-310 -W-Area | 3RD FL BR 1 | FLOOR | WOOD | 1.00 | 5020 |
| C-E2-050506-311 -W-Area | 3RD FL BR 1 | FLOOR | WOOD | 1.00 | 368 |
| C-E2-050506-309 -W-Area | 3RD FL BR 1 | BANISTER | WOOD | 0.36 | 733 |
| C-F1-050406-287 -W-OS | 3RD FL BR 3 | FLOOR | WOOD | 1.00 | 219 |

Clearance Wipe Sampling

| Sample No. (P-Scenario/D-Date-##-W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|---|-------------|----------|--------------|---------------------------------|------------------------------|
| C-B2-050506-320 -W-Area | 3RD FL BR 1 | FLOOR | WOOD | 1.00 | 295 |
| C-B2-050506-321 -W-Area | 3RD FL BR 1 | FLOOR | WOOD | 1.00 | 72.9 |
| C-B2-050506-322 -W-Area | 3RD FL BR 1 | BANISTER | WOOD | 0.24 | 342 |
| C-B2-050506-319 -W-OS | 3RD FL BR 3 | FLOOR | WOOD | 1.00 | 197 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|--|
| Hygienist | |
| Activity | CEILING MODIFICATION (RECESSED LIGHTS) |
| Work Practice | mod LSWP |

| | |
|---|---------------|
| DATE | 5/5/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | B2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | X |
| Disposable Hand Towels | X |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | X |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/5/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|---------------------|---------------|
| | 56 | C1 | WINDOW MODIFICATION | ROUTINE |

| | | |
|---------------------|------------------|---------------|
| Site Address | City, State, Zip | Milwaukee, WI |
|---------------------|------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

Location of Work w/in structure LIVING ROOM

| Lead Content of Affected Surfaces | | | | Work Statistics | | |
|-----------------------------------|------------|--------|--|--------------------------|------|--|
| Surface | XRF Result | % Lead | | No. of Workers | | |
| WINDOW SILL | 3.7 | and/or | | Start Time | 905 | |
| WINDOW SASH | 18.9 | | | Stop Time | 1030 | |
| WINDOW | 22.5 | | | Total Time (hrs) | 1.5 | |
| | | | | Tools and Equipment Used | | |
| Use attached checklist | | | | | | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-F2-050306-092 -A-Area | LR S | 16666 | 15:03 | 2.61 | 16:19 | 2.60 | 76 | 2.60 | 197.6 | <10 |
| C-F2-050306-093 -A-Area | LR N | 16609 | 15:05 | 2.55 | 16:21 | 2.58 | 76 | 2.55 | 193.8 | <10 |
| D-B1-050306-091 -A-OS | DINING ROOM | 17180 | 13:50 | 2.56 | 16:44 | 2.59 | 174 | 2.56 | 445.4 | <10 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-C1-050506-121 -A-Area | LR S | 16666 | 9:02 | 2.64 | 10:25 | 2.67 | 83 | 2.64 | 219.1 | 32 |
| D-C1-050506-122 -A-Area | LR N | 17451 | 9:02 | 2.66 | 10:30 | 2.63 | 88 | 2.63 | 231.4 | 56 |
| D-C1-050506-123 -A-PBZ | WORKER | 16608 | 9:05 | 2.55 | 10:29 | 2.53 | 84 | 2.53 | 212.5 | 147 |
| D-C1-050506-124 -A-PBZ | WORKER | 17185 | 9:04 | 2.64 | 10:27 | 2.60 | 83 | 2.60 | 215.8 | 8 |
| D-C1-050506-125 -A-OS | 2ND FL BR 2 | 16612 | 9:06 | 2.61 | 11:38 | 2.61 | 152 | 2.61 | 396.7 | <5 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-C1-050506-135 -A-Area | LR S | 16666 | 10:26 | 2.67 | 11:30 | 2.64 | 64 | 2.64 | 169.0 | <12 |
| C-C1-050506-136 -A-Area | LR N | 17451 | 10:31 | 2.63 | 11:32 | 2.62 | 61 | 2.62 | 159.8 | <13 |

Pre-work Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|----------|---------|--------------|---------------------------------|------------------------------|
| P-C1-050406-299 -W-Area | LR | W-SILL | WOOD | 0.63 | 1030 |
| P-C1-050406-300 -W-Area | LR | FLOOR | WOOD | 1.00 | 402 |
| P-C1-050406-301 -W-Area | LR | FLOOR | WOOD | 1.00 | 411 |
| C-C2-050406-298 -W-OS | LR | FLOOR | WOOD | 1.00 | 1210 |

Clearance Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|-------------|---------|--------------|---------------------------------|------------------------------|
| C-C1-050506-305 -W-Area | LR | FLOOR | WOOD | 1.00 | 4560 |
| C-C1-050506-306 -W-Area | LR | W-SILL | WOOD | 0.64 | 3300 |
| C-C1-050506-307 -W-Area | LR | FLOOR | WOOD | 1.00 | 3500 |
| C-B2-050506-329 -W-OS | 2ND FL BR 2 | FLOOR | WOOD | 1.00 | 186 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|---------------------|
| Hygienist | |
| Activity | WINDOW MODIFICATION |
| Work Practice | ROUTINE |

| | |
|---|---------------|
| DATE | 5/5/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | C1 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | X |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | |
| Tape | X |
| Utility Knife | |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | X |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | |
| Brooms | X |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | X |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/5/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|-----------------|---------------|
| | 57 | D2 | CABINET REMOVAL | mod LSWP |

| | | |
|---------------------|------------------|---------------|
| Site Address | City, State, Zip | Milwaukee, WI |
|---------------------|------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

| | | | | | |
|--|----------|------------|--------|-------------------------------|------|
| Location of Work w/in structure | | KITCHEN | | | |
| Lead Content of Affected Surfaces | | | | | |
| Surface | | XRF Result | % Lead | Work Statistics | |
| | CABINETS | 9.4 | and/or | No. of Workers | 1 |
| | CABINETS | 5.2 | | Start Time | 856 |
| | | | | Stop Time | 1050 |
| | | | | Total Time (hrs) | 2 |
| | | | | Tools and Equipment Used | |
| | | | | Use attached checklist | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| P-D2-050106-012 -A-Area | KITCHEN | 18104 | 15:40 | 2.67 | 16:19 | 2.66 | 39 | 2.66 | 103.7 | <19 |
| P-C3-050206-016 -A-OS | GRND FL | 17451 | 7:39 | 2.63 | 8:48 | 2.68 | 69 | 2.63 | 181.5 | <11 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-D2-050506-128 -A-Area | KITCHEN | 18105 | 8:53 | 2.60 | 10:49 | 2.64 | 116 | 2.60 | 301.6 | 21 |
| D-D2-050506-129 -A-PBZ | WORKER | 17184 | 8:56 | 2.63 | 10:50 | 2.58 | 114 | 2.58 | 294.1 | 49 |
| D-C1-050506-125 -A-OS | 2ND FL BR 2 | 16612 | 9:06 | 2.61 | 11:38 | 2.61 | 152 | 2.61 | 396.7 | <5 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-D2-050506-139 -A-Area | KITCHEN | 18105 | 10:49 | 2.64 | 12:10 | 2.63 | 81 | 2.63 | 213.0 | <9 |

Pre-work Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|-----------|---------|--------------|---------------------------------|------------------------------|
| P-D2-050206-224 -W-Area | KITCHEN | FLOOR S | WOOD | 1.00 | 3520 |
| P-D2-050206-225 -W-Area | KITCHEN | FLOOR N | WOOD | 1.00 | 4060 |
| P-D2-050206-226 -W-Area | KITCHEN | W-SILL | WOOD | 0.46 | 19600 |
| P-C3-050206-211 -W-OS | GROUND FL | FLOOR | WOOD | 1.00 | 800 |

Clearance Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|-------------|---------|--------------|---------------------------------|------------------------------|
| C-D2-050506-315 -W-Area | KITCHEN | FLOOR | WOOD | 1.00 | 1490 |
| C-D2-050506-316 -W-Area | KITCHEN | FLOOR | WOOD | 1.00 | 403 |
| C-D2-050506-317 -W-Area | KITCHEN | W-SILL | WOOD | 0.88 | 1400 |
| C-B2-050506-329 -W-OS | 2ND FL BR 2 | FLOOR | WOOD | 1.00 | 186 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-----------------|
| Hygienist | |
| Activity | CABINET REMOVAL |
| Work Practice | mod LSWP |

| | |
|---|---------------|
| DATE | 5/5/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | D2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | |
| Tack Pad | |
| Disposable Towels for Wipe Down | X |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | X |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | X |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | X |
| Disposable Towels | X |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/5/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|-------------------|---------------|
| | 58 | E2 | BASEBOARD REMOVAL | mod LSWP |

| | | |
|---------------------|------------------|---------------|
| Site Address | City, State, Zip | Milwaukee, WI |
|---------------------|------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

| | | | | | |
|--|-----------|------------|--------|-------------------------------|------|
| Location of Work w/in structure | | BATH | | | |
| Lead Content of Affected Surfaces | | | | | |
| Surface | | XRF Result | % Lead | Work Statistics | |
| | BASEBOARD | 7.4 | | No. of Workers | 1 |
| | | | and/or | Start Time | 1226 |
| | | | | Stop Time | 1325 |
| | | | | Total Time (hrs) | 1 |
| | | | | Tools and Equipment Used | |
| | | | | Use attached checklist | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-D3-050306-080 -A-Area | BATH | 17179 | 12:43 | 2.63 | 13:48 | 2.63 | 65 | 2.63 | 171.0 | <12 |
| D-050306-068 -A-OS | KITCHEN | 18112 | 10:05 | 2.64 | 13:51 | 2.63 | 226 | 2.63 | 594.4 | <3 |
| D-050306-069 -A-OS | DINING ROOM | 17180 | 10:05 | 2.65 | 13:49 | 2.65 | 224 | 2.65 | 593.6 | <3 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-E2-050506-149 -A-Area | BATH | 18104 | 12:26 | 2.64 | 13:21 | 2.63 | 55 | 2.63 | 144.7 | <14 |
| D-E2-050506-150 -A-PBZ | WORKER | 17184 | 12:26 | 2.58 | 13:25 | 2.59 | 59 | 2.58 | 152.2 | <13 |
| D-E2-050506-144 -A-OS | 2ND FL BR 2 | 16612 | 12:05 | 2.61 | 14:20 | 2.62 | 135 | 2.61 | 352.4 | <6 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-E2-050506-154 -A-Area | BATH | 18104 | 13:21 | 2.63 | 14:23 | 2.65 | 62 | 2.63 | 163.1 | <12 |

Pre-work Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|----------|---------|--------------|---------------------------------|------------------------------|
| C-D3-050306-280 -W-Area | BATH | W-SILL | WOOD | 0.42 | 136 |
| C-D3-050306-281 -W-Area | BATH | FLOOR W | LINOLEUM | 1.00 | 401 |
| C-D3-050306-282 -W-Area | BATH | FLOOR E | LINOLEUM | 1.00 | 354 |
| C-D3-050306-283 -W-OS | KITCHEN | FLOOR S | WOOD | 1.00 | 1470 |

Clearance Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Sampled (ft ²) | Result (ug/ft ²) |
|--|-------------|---------|--------------|----------------------------|------------------------------|
| C-E2-050506-326 -W-Area | BATH | W-SILL | WOOD | 0.65 | 81.8 |
| C-E2-050506-327 -W-Area | BATH | FLOOR | LINOLEUM | 1.00 | 347 |
| C-E2-050506-328 -W-Area | BATH | FLOOR | LINOLEUM | 1.00 | 164 |
| C-B2-050506-329 -W-OS | 2ND FL BR 2 | FLOOR | WOOD | 1.00 | 186 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-------------------|
| Hygienist | |
| Activity | BASEBOARD REMOVAL |
| Work Practice | mod LSWP |

| | |
|---|---------------|
| DATE | 5/5/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | E2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | X |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | X |
| Disposable Towels | |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/5/2006 Hygienist

| Event | ID | Activity | Work Practice |
|-------|----|-------------------|---------------|
| 59 | E2 | STAIR REPLACEMENT | mod LSWP |

| | | |
|---------------------|------------------|---------------|
| Site Address | City, State, Zip | Milwaukee, WI |
|---------------------|------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

| | | | | | |
|--|------------|--------|--------------------------|-------------------------------|--|
| Location of Work w/in structure | STAIRWELL | | | | |
| Lead Content of Affected Surfaces | | | | | |
| Surface | XRF Result | and/or | % Lead | Work Statistics | |
| TREAD | 13 | | No. of Workers | 2 | |
| RISER | 11.8 | | Start Time | 858 | |
| STRINGER | 11.3 | | Stop Time | 1028 | |
| | | | Total Time (hrs) | 1.5 | |
| | | | Tools and Equipment Used | <i>Use attached checklist</i> | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-F1-050406-118 | -A-Area STAIRWELL | 17185 | 14:59 | 2.61 | 16:14 | 2.68 | 75 | 2.61 | 195.8 | <10 |
| D-F1-050406-114 | -A-OS 3RD FL BR 3 | 18104 | 14:01 | 2.66 | 16:17 | 2.62 | 136 | 2.62 | 356.3 | <6 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-E2-050506-130 | -A-Area STAIRWELL | 16670 | 8:58 | 2.67 | 10:36 | 2.68 | 98 | 2.67 | 261.7 | 140 |
| D-E2-050506-132 | -A-Area 3RD FL BR 1 | 16609 | 8:59 | 2.60 | 10:40 | 2.61 | 101 | 2.60 | 262.6 | 19 |
| D-E2-050506-131 | -A-PBZ WORKER | 16669 | 8:57 | 2.63 | 10:37 | 2.57 | 100 | 2.57 | 257.0 | 31 |
| D-E2-050506-133 | -A-OS 3RD FL BR 3 | 17180 | 8:46 | 2.61 | 11:47 | 2.62 | 181 | 2.61 | 472.4 | <4 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|---------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-E2-050506-137 | -A-Area STAIRWELL | 16670 | 10:36 | 2.68 | 11:41 | 2.68 | 65 | 2.68 | 174.2 | <12 |
| C-E2-050506-138 | -A-Area 3RD FL BR 1 | 16609 | 10:41 | 2.61 | 11:44 | 2.58 | 63 | 2.58 | 162.5 | <12 |

Pre-work Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|---------------------|----------|--------------|---------------------------------|------------------------------|
| C-F1-050406-288 | -W-Area 3RD FL BR 1 | BANISTER | WOOD | 0.26 | 1100 |
| C-F1-050406-289 | -W-Area 3RD FL BR 1 | FLOOR | WOOD | 1.00 | 707 |
| C-F1-050406-290 | -W-Area 3RD FL BR 1 | FLOOR | WOOD | 1.00 | 2020 |
| C-F1-050406-291 | -W-Area STAIRWELL | TREAD | WOOD | 0.71 | 476 |
| C-F1-050406-292 | -W-Area STAIRWELL | W-SILL | WOOD | 0.46 | 3200 |
| C-F1-050406-293 | -W-Area STAIRWELL | FLOOR | LINOLEUM | 1.00 | 1520 |
| C-F1-050406-287 | -W-OS 3RD FL BR 3 | FLOOR | WOOD | 1.00 | 219 |

Clearance Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|---------------------|----------|--------------|---------------------------------|------------------------------|
| C-E2-050506-309 | -W-Area 3RD FL BR 1 | BANISTER | WOOD | 0.36 | 733 |
| C-E2-050506-310 | -W-Area 3RD FL BR 1 | FLOOR | WOOD | 1.00 | 5020 |
| C-E2-050506-311 | -W-Area 3RD FL BR 1 | FLOOR | WOOD | 1.00 | 368 |
| C-E2-050506-312 | -W-Area STAIRWELL | TREAD | WOOD | 1.06 | 937 |
| C-E2-050506-313 | -W-Area STAIRWELL | W-SILL | WOOD | 0.45 | 873 |
| C-E2-050506-314 | -W-Area STAIRWELL | FLOOR | LINOLEUM | 1.00 | 3140 |
| C-B2-050506-319 | -W-OS 3RD FL BR 3 | FLOOR | WOOD | 1.00 | 197 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-------------------|
| Hygienist | |
| Activity | STAIR REPLACEMENT |
| Work Practice | mod LSWP |

| | |
|---|---------------|
| DATE | 5/5/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | E2 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | X |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | X |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | X |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | X |
| Orbital Sander | |
| Other Non-ventilated Power Tools | X |
| Heavy Duty Garbage Bags | X |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | X |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | X |
| Shop or Industrial Vacuum | |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | |
| Disposable Towels | |

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

Date 5/5/2006 Hygienist

| Scenario | Event | ID | Activity | Work Practice |
|----------|-------|----|-----------------|---------------|
| | 60 | F1 | CEILING SANDING | ROUTINE |

| | | |
|---------------------|------------------|---------------|
| Site Address | City, State, Zip | Milwaukee, WI |
|---------------------|------------------|---------------|

| | | | | | |
|-----------------------|---------------|---|------------------|--------------------------------|------|
| Structure Type | Single Family | X | Apartment | Approx. Construction Date (Yr) | 1890 |
| | Town House | | Other (describe) | Approx. Square Footage | 5000 |
| | Condomium | | | No. of Separate Rooms | 18 |

| | | | | | |
|--|---------|-------------|--------|-------------------------------|------|
| Location of Work w/in structure | | LIVING ROOM | | | |
| Lead Content of Affected Surfaces | | | | | |
| Surface | | XRF Result | % Lead | Work Statistics | |
| | CEILING | 16.5 | | No. of Workers | 2 |
| | | | and/or | Start Time | 1156 |
| | | | | Stop Time | 1248 |
| | | | | Total Time (hrs) | 0.9 |
| | | | | Tools and Equipment Used | |
| | | | | Use attached checklist | |

Pre-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-C1-050506-135 -A-Area | LR S | 16666 | 10:26 | 2.67 | 11:30 | 2.64 | 64 | 2.64 | 169.0 | <12 |
| C-C1-050506-136 -A-Area | LR N | 17451 | 10:31 | 2.63 | 11:32 | 2.62 | 61 | 2.62 | 159.8 | <13 |
| D-C1-050506-125 -A-OS | 2ND FL BR 2 | 16612 | 9:06 | 2.61 | 11:38 | 2.61 | 152 | 2.61 | 396.7 | <5 |

** OS - Outside of work area - run air sample for the duration of the scenario

During Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location/Employee/Activity | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------------------------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| D-F1-050506-140 -A-Area | LR S | 16666 | 11:55 | 2.64 | 12:46 | 2.61 | 51 | 2.61 | 133.1 | 23 |
| D-F1-050506-141 -A-Area | LR N | 17451 | 11:55 | 2.62 | 12:48 | 2.60 | 53 | 2.60 | 137.8 | 30 |
| D-F1-050506-142 -A-PBZ | WORKER | 17185 | 11:56 | 2.60 | 12:49 | 2.59 | 53 | 2.59 | 137.3 | 51 |
| D-F1-050506-143 -A-PBZ | WORKER | 16608 | 11:57 | 2.53 | 12:51 | 2.54 | 54 | 2.53 | 136.6 | 95 |
| D-E2-050506-144 -A-OS | 2ND FL BR 2 | 16612 | 12:05 | 2.61 | 14:20 | 2.62 | 135 | 2.61 | 352.4 | <6 |

Post-Work Sampling

| Sample No. (P-ScenarioID-Date-## -A-Type) | Location | Pump ID | Time On | FR (lpm) | Time Off | FR (lpm) | Total Time (min) | Lowest FR (lpm) | Volume (L) | Result (ug/m ³) |
|--|----------|---------|---------|----------|----------|----------|------------------|-----------------|------------|-----------------------------|
| C-F1-050506-151 -A-Area | LR S | 16666 | 12:47 | 2.61 | 13:55 | 2.62 | 68 | 2.61 | 177.5 | <11 |
| C-F1-050506-152 -A-Area | LR N | 17451 | 12:48 | 2.60 | 13:56 | 2.61 | 68 | 2.60 | 176.8 | <11 |

Wipe Sampling

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|----------|---------|--------------|---------------------------------|------------------------------|
| C-C1-050506-306 -W-Area | LR | W-SILL | WOOD | 0.64 | 3300 |
| C-C1-050506-305 -W-Area | LR | FLOOR | WOOD | 1.00 | 4560 |
| C-C1-050506-307 -W-Area | LR | FLOOR | WOOD | 1.00 | 3500 |

| Sample No. (P-ScenarioID-Date-## -W-Location) | Location | Surface | Surface Type | Area Sampled (ft ²) | Result (ug/ft ²) |
|--|-------------|---------|--------------|---------------------------------|------------------------------|
| C-F1-050506-323 -W-Area | LR | W-SILL | WOOD | 0.62 | 2350 |
| C-F1-050506-324 -W-Area | LR | FLOOR | WOOD | 1.00 | 1520 |
| C-F1-050506-325 -W-Area | LR | FLOOR | WOOD | 1.00 | 1600 |
| C-B2-050506-329 -W-OS | 2ND FL BR 2 | FLOOR | WOOD | 1.00 | 186 |

OS - Outside of work area

Surface type - wood, tile, linoleum, concrete, carpet, metal, etc.

**ATRIUM ENVIRONMENTAL HEALTH SAFETY, LLC
LEAD SAFE WORK PRACTICES STUDY FIELD DATA SHEET**

WORK PRACTICE AND TOOL CHECKLIST

| | |
|----------------------|-----------------|
| Hygienist | |
| Activity | CEILING SANDING |
| Work Practice | ROUTINE |

| | |
|---|---------------|
| DATE | 5/5/2006 |
| LOCATION | MILWAUKEE, WI |
| SCENARIO | F1 |
| Work Area Preparation | |
| Pre-cleaning w/ wet wiping and vac | |
| Rope | |
| Barrier Tape | |
| Saw Horses | |
| Orange Cones | |
| Signs | |
| Doorways/Openings Covered | X |
| HVAC Openings Sealed | |
| Reusable Drop Cloth | |
| 4 or 6-mil Plastic Sheeting or Disposable Drop Cloth | X |
| Disposable Mesh | |
| Staple Gun | X |
| Tape | X |
| Utility Knife | |
| Tack Pad | |
| Disposable Towels for Wipe Down | |
| Work Practices/Tools | |
| Hammers/Prybars | X |
| Misting Bottle | |
| Sandpaper/Sanding Sponge | X |
| Chemical Stripper | |
| Heat Gun | |
| Shop or Industrial Vacuum | |
| HEPA-equipped Vacuum | |
| HEPA-rated Vacuum | |
| Shrouded Sander/Grinder/Planer connected to HEPA Vacuum | |
| Power Washing Equipment | |
| Needle Gun connected to HEPA Vacuum | |
| Belt Sander | |
| Orbital Sander | |
| Other Non-ventilated Power Tools | |
| Heavy Duty Garbage Bags | |
| Work Area/Personnel Clean-up | |
| Roll Dropcloths Inward | X |
| Wet Wipe Surfaces or Use Detergent | |
| Reusable Wet Mop w/ One Bucket | |
| Reusable Wet Mop w/ Two Buckets | |
| Use Swiffer or Similar Disposable Wet Mop | X |
| Disposable Hand Towels | |
| Pump Sprayer | |
| HEPA-equipped Vacuum | |
| Shop or Industrial Vacuum | X |
| Brooms | |
| Shovels | |
| Personal Protective Equipment | |
| Full Body Disposable Coveralls | X |
| N100 Respirator | X |
| Gloves | X |
| Disposable Shoe Covers | X |
| Safety Glasses | X |
| Disposable Towels | X |

JANUARY 23, 2007

**DRAFT FINAL REPORT
ON
CHARACTERIZATION OF DUST LEAD LEVELS AFTER RENOVATION, REPAIR, AND
PAINTING ACTIVITIES**

Prepared By

**BATTELLE
505 King Avenue
Columbus, Ohio 43201**

EPA Contract No. EP-W-04-021

Prepared For

**Sineta Wooten, Project Officer
John Schwemberger, Work Assignment Manager
Samuel Brown, Deputy Work Assignment Manager**

**Program Assessment and Outreach Branch
National Program Chemicals Division
Office of Pollution Prevention and Toxics
U.S. Environmental Protection Agency
1200 Pennsylvania Avenue NW (7404T)
Washington, D.C. 20460**

Acknowledgements

Many people contributed to the completion of this study. At EPA, Mr. John Schwemberger served as the EPA Work Assignment Manager assisted by Mr. Samuel Brown. At Battelle, Mr. Tim Pivetz served as the project manager supported by a large team of people. In alphabetical order, those who contributed significantly include Mr. Wesley Baxter, Ms. Rona Boehm, Mr. Peter Bujnak, Dr. Cynthia Cooper, Mr. Steven Gomori, Mr. Brad Goodwin, Mr. Pernell Horton, Ms. Nicole-Iroz Elardo, Mr. Darrell Joseph, Ms. Michelle Lobdell, Ms. Kathya Mahadevan, Mr. Ian MacGregor, Mr. Mark Misita, Ms. Susan Morriss, Ms. Jyothi Nagaraja, Mr. Henry Pham, Ms. Cyndi Reese, Mr. Adam Ridenbaugh, Dr. Jessica Sanford, Dr. Ketra Schmitt, Ms. Elizabeth Slone, Mr. Warren Strauss, Mr. Joseph Tabor, Ms. Rena Thomas, Ms. Stephanie Weber, Mr. Zachary Willenberg, and Ms. Jennifer Zewatsky.

The study team expresses sincere thanks to the many property owners who made their houses available for renovation work under this study, as well as to Columbus Public Schools who provided access to one of their vacant buildings. The study team also thanks the many subcontractors who supported the study including police officers in Columbus and Pittsburgh, renovation firms and the renovation workers who implemented the study protocols, abatement cleaning firms, environmental testing firms who provided XRF testing and clearance testing services, the analytical laboratory, and staff at Healthy Housing Solutions, Inc. who supported the search for potential units. The study also thanks those staff at the Ohio Department of Health, Columbus Health Department, Pennsylvania Department of Health, and Allegheny County Health Department who provided guidance and assistance along the way.

Thanks also to other staff and subcontractors who provided support to the study but are not named above. The study could not have been completed without the full effort of everyone on the team.

TABLE OF CONTENTS

| | <u>Page</u> |
|--|-------------|
| GLOSSARY OF TERMS..... | vi |
| 1.0 INTRODUCTION..... | 1-1 |
| 1.1 BACKGROUND AND PURPOSE OF STUDY..... | 1-1 |
| 1.2 PROPOSED RULE SUMMARY..... | 1-1 |
| 1.3 STUDY OBJECTIVES..... | 1-2 |
| 2.0 SUMMARY OF CONCLUSIONS AND PEER REVIEWS..... | 2-1 |
| 2.1 CONCLUSIONS SUMMARY..... | 2-1 |
| 2.2 PEER REVIEW OF STUDY DESIGN..... | 2-2 |
| 2.3 HUMAN SUBJECTS REVIEW..... | 2-3 |
| 3.0 STUDY DESIGN..... | 3-1 |
| 3.1 SITE SELECTION PROCESS AND REQUIREMENTS..... | 3-1 |
| 3.2 SAMPLING METHODS..... | 3-2 |
| 3.3 LABORATORY ANALYSIS METHODS..... | 3-2 |
| 3.4 FIELD SAMPLING PROTOCOLS..... | 3-4 |
| 3.4.1 Interior Jobs..... | 3-4 |
| 3.4.2 Exterior Jobs..... | 3-7 |
| 3.5 PARTICIPATING CONTRACTORS (RRP WORKERS, CLEANING, CLEARANCE TECHNICIANS)..... | 3-8 |
| 3.6 ENVIRONMENTAL SAFETY AND HEALTH PLAN..... | 3-8 |
| 4.0 FIELD WORK SUMMARY..... | 4-1 |
| 4.1 OVERVIEW OF SITE SELECTION/SCREENING PROCESS..... | 4-1 |
| 4.2 NUMBER AND TYPE OF EXPERIMENTS COMPLETED..... | 4-2 |
| 4.3 PROTECTION AND CLEANING ROUTINES..... | 4-3 |
| 4.4 ENVIRONMENTAL SAMPLES COLLECTED..... | 4-5 |
| 4.5 PROTOCOL/SAMPLING ISSUES AND RESOLUTIONS..... | 4-6 |
| 4.6 ADHERENCE TO ENVIRONMENTAL SAFETY AND HEALTH PROTOCOLS..... | 4-8 |
| 4.7 RECORDKEEPING..... | 4-10 |
| 5.0 STATISTICAL ANALYSIS PLAN..... | 5-1 |
| 5.1 DATA ORGANIZATION..... | 5-1 |
| 5.2 DESCRIPTIVE ANALYSES..... | 5-1 |
| 5.3 STATISTICAL MODELS..... | 5-2 |
| 6.0 DESCRIPTIVE ANALYSES..... | 6-1 |
| 6.1 HOUSING UNIT/EXPERIMENT SUMMARY INFORMATION..... | 6-1 |
| 6.2 PAINT LEAD LEVELS..... | 6-5 |
| 6.3 PRE-WORK CLEARANCE LEVELS..... | 6-6 |
| 6.4 BULK DEBRIS SAMPLES..... | 6-10 |
| 6.5 INTERIOR DUST SAMPLES..... | 6-11 |
| 6.5.1 Interior Floor Samples..... | 6-11 |
| 6.5.2 Interior Sill Samples..... | 6-15 |
| 6.5.3 Hallway/Exit Samples..... | 6-20 |
| 6.5.4 Exterior Post-Work Tray Samples During Window Replacement Jobs..... | 6-21 |
| 6.6 INTERIOR AIR SAMPLES..... | 6-22 |
| 6.7 EXTERIOR DUST SAMPLES..... | 6-24 |

| | <u>Page</u> |
|--------|--|
| 6.8 | SOIL SAMPLES 6-27 |
| 6.8.1 | Soil Sampling Interior Jobs 6-27 |
| 6.8.2 | Soil Sampling Exterior Jobs 6-30 |
| 6.9 | LENGTH OF ACTIVITY DATA 6-32 |
| 6.9.1 | Duration of Post-work Cleaning 6-32 |
| 6.9.2 | Duration of Cleaning Verification 6-33 |
| 6.9.3 | Duration of Pre-Work Set Up 6-34 |
| 6.9.4 | Duration of Interior RRP Work 6-35 |
| 6.10 | CLEANING VERIFICATION DATA 6-36 |
| 6.10.1 | Verification of Floor Zones 6-36 |
| 6.10.2 | Verification of Window Sills 6-45 |
| 7.0 | STATISTICAL MODELING RESULTS 7-1 |
| 7.1 | POST-WORK DUST LEAD LEVELS 7-2 |
| 7.1.1 | POST-WORK WORK ROOM DUST LEAD LEVELS 7-2 |
| 7.1.2 | POST-CLEANING WORK ROOM DUST LEAD LEVELS 7-4 |
| 7.1.3 | POST VERIFICATION WORK ROOM DUST LEAD LEVELS 7-6 |
| 7.2 | POST CLEANING STAGE – DUST LEAD LEVELS 7-7 |
| 7.2.1 | POST-WORK WORK ROOM DUST LEAD LEVELS 7-7 |
| 7.2.2 | POST-CLEANING TOOL ROOM DUST LEAD LEVELS 7-10 |
| 7.2.3 | POST-CLEANING OBSERVATION ROOM DUST LEAD LEVELS 7-13 |
| 7.3 | POST-VERIFICATION STAGE DUST LEAD LEVELS 7-16 |
| 7.3.1 | POST-VERIFICATION WORK ROOM DUST LEAD LEVELS 7-16 |
| 7.3.2 | POST-VERIFICATION TOOL ROOM DUST LEAD LEVELS 7-18 |
| 7.3.3 | POST-VERIFICATION OBSERVATION ROOM DUST LEAD LEVELS 7-20 |
| 7.4 | COMPARISON OF RULE PRACTICES AND BASELINE PRACTICES-POST-JOB DUST LEAD LEVELS 7-22 |
| 7.4.1 | POST-JOB WORK ROOM DUST LEAD LEVELS 7-22 |
| 7.4.2 | POST-JOB TOOL ROOM DUST LEAD LEVELS 7-23 |
| 7.4.3 | POST-JOB OBSERVATION ROOM DUST LEAD LEVELS 7-24 |
| 7.5 | EXTERIOR DUST LEAD LEVELS 7-26 |
| 8.0 | QUALITY ASSURANCE AND QUALITY CONTROL RESULTS 8-1 |
| 8.1 | FIELD AUDIT RESULTS 8-1 |
| 8.1.1 | Site Selection Audit 8-1 |
| 8.1.2 | Field Implementation 8-1 |
| 8.1.3 | EPA Site Visits 8-2 |
| 8.2 | LABORATORY AUDIT RESULTS 8-2 |
| 8.3 | QC SAMPLE RESULTS, ISSUES, AND RESOLUTIONS 8-2 |
| 8.4 | DATA AUDIT PROCESS AND RESULTS 8-4 |
| 8.5 | SOFTWARE REVIEWS 8-4 |
| 9.0 | CONCLUSIONS 9-1 |
| 9.1 | BENEFITS OF PROPOSED RULE PACKAGE 9-1 |
| 9.2 | BENEFITS OF PLASTIC PROTECTIVE SHEETING 9-5 |
| 9.3 | BENEFITS OF RULE CLEANING WITH HEPA VACUUM AND WET MOPPING WITH CLEANING SOLUTION 9-6 |
| 9.4 | BENEFITS OF CLEANING VERIFICATION 9-6 |

| | | |
|-------------|--|-----|
| APPENDIX A: | EXPERIMENT-SPECIFIC REPORTS | A-1 |
| APPENDIX B: | DETAILED DESCRIPTIVE ANALYSES OF EXTERIOR DUST LEAD LOADINGS (INCLUDING BULK DEBRIS SAMPLES)..... | B-1 |
| APPENDIX C: | DETAILED DESCRIPTIVE ANALYSES OF INTERIOR FLOOR DUST LEAD LOADINGS | C-1 |
| APPENDIX D: | DETAILED DESCRIPTIVE ANALYSES OF INTERIOR WINDOW SILL DUST LEAD LOADINGS | D-1 |
| APPENDIX E: | DETAILED DESCRIPTIVE ANALYSES OF EXTERIOR DUST LEAD LOADINGS (WITHOUT BULK DEBRIS SAMPLES)..... | E-1 |
| APPENDIX F: | DETAILED DESCRIPTIVE ANALYSES OF INTERIOR AIR LEAD CONCENTRATIONS..... | F-1 |
| APPENDIX G: | DETAILED DESCRIPTIVE ANALYSES OF AVERAGE POST-WORK WORK ROOM FLOOR DUST LEAD LOADING, AVERAGE PAINT LEAD LOADING, AND AREA DISTURBED | G-1 |
| APPENDIX H: | DETAILED DESCRIPTIVE ANALYSES OF INTERIOR HALLWAY DUST LEAD LOADINGS | H-1 |
| APPENDIX I: | DETAILED STATISTICAL MODELING RESULTS OF RESIDENTIAL FLOOR LEAD LEVELS | I-1 |
| APPENDIX J: | DETAILED STATISTICAL MODELING RESULTS OF RESIDENTIAL WINDOW SILL LEAD LEVELS..... | J-1 |
| APPENDIX K: | DETAILED STATISTICAL MODELING RESULTS OF COF FLOOR LEAD LEVELS | K-1 |
| APPENDIX L: | DETAILED STATISTICAL MODELING RESULTS OF COMBINED HOUSING UNIT/COF FLOOR LEAD LEVELS..... | L-1 |
| APPENDIX M: | DETAILED STATISTICAL MODELING RESULTS OF COMBINED HOUSING UNIT/COF WINDOW SILL LEAD LEVELS..... | M-1 |
| APPENDIX N: | DETAILED STATISTICAL MODELING RESULTS OF EXTERIOR DUST LEAD LEVELS FOR COMBINED RESIDENTIAL AND COF DATA | N-1 |
| APPENDIX O: | HISTOGRAMS OF RESIDUALS OF BEST FITTING MODELS | O-1 |

LIST OF TABLES

| | | |
|------------|---|-----|
| Table 4-1. | Housing Unit Distribution by City | 4-1 |
| Table 4-2. | Interior RRP Jobs Across Three Levels of RRP Work..... | 4-3 |
| Table 4-3. | Exterior RRP Jobs Across Three Levels of RRP Work | 4-3 |
| Table 4-4. | Interior Jobs and Associated Approaches for Conducting Experiment | 4-4 |
| Table 4-5. | Exterior Jobs Conducted in Each City | 4-5 |
| Table 4-6. | Total Number of Environmental Samples Collected | 4-6 |
| Table 6-1 | Housing Unit Information | 6-1 |
| Table 6-2 | Interior Experiment Summary Table | 6-2 |

| | | |
|------------|--|------|
| Table 6-3 | Exterior Experiment Summary Table | 6-4 |
| Table 6-4 | Summary of the Pre-work Clearance Information..... | 6-8 |
| Table 6-5 | Interior Bulk Samples by Job Type | 6-10 |
| Table 6-6 | Exterior Bulk Samples by Job Type | 6-10 |
| Table 6-7 | Exterior Dust Wipe Samples During Window Replacement | 6-22 |
| Table 6-8 | Number (and Percentage) of Interior Air Dust Lead Concentration Measurements ($\mu\text{g}/\text{m}^3$) Below Detection Limit Measurements by Room and Stage..... | 6-23 |
| Table 6-9 | Distance of Exterior Trays from Work..... | 6-24 |
| Table 6-10 | Average Background Dust Loading for Exterior Experiments, by Job Type..... | 6-27 |
| Table 6-11 | Pre- and Post-Work Soil Sample Results ($\mu\text{g}/\text{g}$) by Interior Experiment | 6-28 |
| Table 6-12 | Average Post-work/Pre-work Ratios for Interior Work Soil Samples by Job Type | 6-30 |
| Table 6-13 | Pre- and Post-Work Soil Sample Results ($\mu\text{g}/\text{g}$) for Exterior Experiments..... | 6-31 |
| Table 6-14 | Ratio of Post-work to Pre-work Soil Lead Level in Exterior Soil Samples by Job Type..... | 6-32 |
| Table 6-15 | Summary of Post-work Cleaning Times, by Phase (in minutes) | 6-32 |
| Table 6-16 | Summary of Post-work Cleaning Times, by Job (in minutes)..... | 6-33 |
| Table 6-17 | Summary of Post-work Cleaning Times, by Contractor (in minutes)..... | 6-33 |
| Table 6-18 | Duration of Post-work Cleaning Verification Stages, by Phase (in minutes)..... | 6-33 |
| Table 6-19 | Duration of Post-work Cleaning Verification Stages, by Job (in minutes) | 6-34 |
| Table 6-20 | Duration of Post-work Cleaning Verification Stages, by Contractor (in minutes) | 6-34 |
| Table 6-21 | Duration of Interior Pre-work Set-up (in minutes) | 6-34 |
| Table 6-22 | Duration of Interior Pre-work Set-up, by Contractor | 6-34 |
| Table 6-23 | Duration of Interior Pre-work Set-up, by Building Type (in minutes) | 6-35 |
| Table 6-24 | Duration of Interior Work, by Job (in minutes) | 6-35 |
| Table 6-25 | Duration of Exterior Work, by Job (in minutes)..... | 6-36 |
| Table 6-26 | Floor Verification Information by Phase | 6-38 |
| Table 6-27 | Post-cleaning and Post-verification Floor Lead Levels for Experiments with Zero and ≥ 1 Verification Failures by Phase..... | 6-38 |
| Table 6-28 | Floor Verification Information by Job Type | 6-39 |
| Table 6-29 | Floor Verification Information by Contractor | 6-40 |
| Table 6-30 | Floor Verification Information by Floor Type..... | 6-40 |
| Table 6-31 | Floor Verification Information by Floor Condition..... | 6-40 |
| Table 6-32 | Floor Verification Information by Job Type, Floor Type, and Floor Condition | 6-41 |
| Table 6-33 | Floor Zones That Failed Second Wet Cloth Verification..... | 6-41 |
| Table 6-34 | Verification Information for Interior Experiments..... | 6-43 |
| Table 6-35 | Window Sill Verification Information by Phase | 6-45 |
| Table 6-36 | Window Sill Verification Information by Intensity Level..... | 6-45 |
| Table 6-37 | Verification Information for Interior Experiments..... | 6-45 |
| Table 6-38 | Post-cleaning and Post-verification Sill Lead Levels for Experiments with Zero and ≥ 1 Verification Failures by Phase..... | 6-46 |
| Table 6-39 | Window Sill Verification Information for Interior Experiments..... | 6-47 |
| Table 7-1 | Post-Work Work Room Modeling Results..... | 7-4 |
| Table 7-2 | Post-Work Tool Room Modeling Results | 7-5 |
| Table 7-3 | Post-Work Observation Room Modeling Results | 7-7 |
| Table 7-4 | Post-cleaning Work Room Modeling Results | 7-9 |
| Table 7-5 | Post-cleaning Tool Room Modeling Results | 7-12 |
| Table 7-6 | Post-cleaning Observation Room Modeling Results | 7-14 |
| Table 7-7 | Post-verification Work Room Modeling Results..... | 7-17 |
| Table 7-8 | Post-verification Tool Room Modeling Results | 7-19 |
| Table 7-9 | Post-verification Observation Room Modeling Results..... | 7-21 |
| Table 7-10 | Post-job Work Room Rule vs. Non-Rule Modeling Results..... | 7-23 |
| Table 7-11 | Post-job Tool Room Rule vs. Non-Rule Modeling Results | 7-23 |
| Table 7-12 | Post-job Observation Room Rule vs. Non-Rule Modeling Results..... | 7-25 |
| Table 7-13 | Comparison Exterior Dust Pan Levels Within Each Job with Bulk Debris Samples Included (Model Based Estimate Differences and Ratios) | 7-26 |

| | <u>Page</u> |
|------------|---|
| Table 7-14 | Comparison Exterior Dust Pan Levels Within Each Job Excluding Bulk Debris Samples (Model Based Estimate Differences and Ratios)..... 7-27 |
| Table 8-1 | Summary of External QC Results 8-3 |
| Table 8-2 | Schneider Laboratories Quality Control Data 8-3 |
| Table 9-1 | Post-Job Average Floor Lead Levels and Failed Samples by Job Type 9-3 |
| Table 9-2 | Post-job Window Sill Average Lead Levels and Failed Samples by Job Type 9-4 |
| Table 9-2 | Post-Job Floor Lead Levels And Number Of Samples Failing Clearance (Excluding Door Planing And High Heat Gun Jobs)..... 9-3 |
| Table 9-3 | Post-Job Floor Lead Levels And Number Of Samples Failing Clearance 9-7 |
| Table 9-4 | Post-Job Floor Lead Levels and Number of Samples Failing Clearance (Excluding Door Planing and High Heat Gun) 9-7 |
| Table 9-5 | Post-Job Floor Lead Levels and Number of Samples Failing Clearance (Door Planing and High Heat Gun Jobs Only)..... 9-8 |
| Table 9-6 | Post-job Window Sill Lead Levels and Number of Samples Failing Clearance 9-8 |
| Table 9-7 | Post-job Window Sill Lead Levels and Number of Samples Failing Clearance For Sampled Window Sills 9-8 |
| Table 9-8 | Post-job Window Sill Lead Levels and Number of Samples Failing Clearance Sampled Dust Collection Trays..... 9-9 |

LIST OF FIGURES

| | |
|-------------|---|
| Figure 6-1 | Scatter Plot of Area Disturbed vs. Average Post-work Work Room Floor Lead Loading 6-6 |
| Figure 6-2 | Post-work Work Room Floor Lead Levels, by Job..... 6-11 |
| Figure 6-3 | Post-Cleaning Work Room Floor Lead Levels, by Job and Plastic Use..... 6-12 |
| Figure 6-4 | Post-Cleaning Work Room Floor Lead Levels, by Job and Cleaning Method..... 6-12 |
| Figure 6-5 | Post-Job Work Room Floor Lead Levels, by Job and Phase 6-13 |
| Figure 6-6 | Post-Job Tool Room Floor Lead Levels, by Job and Phase..... 6-14 |
| Figure 6-7 | Post-Job Observation Room Floor Lead Levels, by Job and Phase 6-15 |
| Figure 6-8 | Post-Cleaning Work Room Sill Lead Levels, by Job and Plastic Use 6-17 |
| Figure 6-9 | Post-Cleaning Work Room Sill Lead Levels, by Job and Cleaning Method 6-17 |
| Figure 6-10 | Post-Job Work Room Sill Lead Levels, by Job and Rule Use 6-18 |
| Figure 6-11 | Post-Job Work Room Sill Lead Levels, by Job and Phase..... 6-18 |
| Figure 6-12 | Post-Job Tool Room Sill Lead Levels, by Job and Rule Use 6-19 |
| Figure 6-13 | Post-Job Observation Room Sill Lead Levels, by Job and Rule Use..... 6-20 |
| Figure 6-14 | Post-work Air Lead Concentrations in the Work Room, by Job..... 6-23 |
| Figure 6-15 | Exterior Dust Lead Levels on and Under Rule Plastic, by Job (w/bulk samples) 6-26 |
| Figure 6-16 | Exterior Dust Lead Levels on and Under Rule Plastic, by Job (w/bulk samples) 6-26 |
| Figure 6-17 | Time Series of Soil Samples Near the Front Porch at H09 6-29 |
| Figure 6-18 | Post-verification Floor Lead Loadings by Phase 6-37 |
| Figure 6-19 | Post-verification Floor Lead Loadings by Job Type..... 6-39 |
| Figure 6-20 | Number of Experiments by Post-cleaning and Post-verification Floor Lead Loadings.. 6-42 |
| Figure 6-21 | Number of Experiments by Post-cleaning and Post-verification Sill Lead Loadings 6-46 |
| Figure 9-1 | Post-Job Work Room Floor Lead Levels, by Job and Rule Use 9-1 |
| Figure 9-2 | Post-Job Work Room Sill Lead Levels, by Job and Rule Use 9-1 |

**Glossary of Terms
for the
Field Study to Characterize Dust Lead Levels
After Renovation, Repair, and Painting**

Baseline Cleaning – a series of steps to remove dust that are representative of standard cleaning practices used by RRP contractors without a final EPA rule for Renovation, Repair, and Painting. These include sweeping and vacuuming with a non-HEPA vacuum.

Baseline Practices – the set of protection and clean-up practices (no use of protective plastic during work and use of baseline cleaning following work) representing typical work practices utilized for a renovation job without a final EPA rule for Renovation, Repair, and Painting.

Child-Occupied Facility (COF) – a building, or portion of a vacant building, constructed before 1978 that could be used by children under six years old, such as a daycare center or early year kindergarten at a school, and that could conceivably meet the formal definition of a Child-Occupied Facility in 40 CFR part 745.223.

Experiment – full implementation of a single phase of one job, including all work, cleaning, and environmental sampling.

Housing Unit – a structure or portion of a structure that is typically occupied by one or more persons as living quarters.

Job – a specific renovation, repair, or painting activity that is of interest for the risk assessment and economic cost-benefit analysis, such as installing a new window.

Lead-based paint – paint or other coating with lead content at or above 1.0 mg/cm² or at or above 0.5% by weight (5,000 µg/g).

Level or Intensity-level – one of three job categories (low, medium, or high), determined based on pre-study expectations of the amount of dust expected to be generated by each activity; because analysis of post-work lead levels indicated that these pre-assigned levels were not entirely consistent with actual dust generated, the primary analyses presented in the report summarize the renovation activities by individual job.

Observation Room – an interior room adjacent to the Tool Room but not the Work Room that represents other areas of a house impacted by interior RRP work.

Phase – one of four iterations of a job specified by the use or non-use of containment and a particular cleaning method (Phase I=plastic sheeting with specialized cleaning, Phase II=plastic sheeting with baseline cleaning, Phase III=no plastic sheeting with specialized cleaning, and Phase IV=no plastic sheeting with baseline cleaning), each implemented under comparable conditions so the effect of containment and cleaning method can each be assessed.

Replicate – a repetition of a specific job, including all four phases or iterations associated with the job (e.g., a second set of window replacements).

RRP – an acronym that stands for Renovation, Repair, and Painting.

Rule Practices – the set of protection and clean-up methods (use protective plastic during work, specialized cleaning following work, and cleaning verification) representing work practices under EPA’s Proposed Rule for Renovation, Repair, and Painting.

Sites - housing units or COFs where one or more study experiments were conducted.

Specialized (Rule) Cleaning – cleaning required by the EPA Proposed Rule for Renovation, Repair, and Painting; comprised of HEPA vacuuming and wet-mopping with two-bucket method.

Stage (of Sampling) – the four different points of time within an experiment at which environmental samples were collected (after completion of the RRP job, after completion of cleaning, after completion of the last wet cloth in the cleaning verification, and after completion of the last dry cloth in the cleaning verification).

Study Location – a city or other geographic area participating in the study through identification, recruitment, and participation of housing units and COFs.

Tool Room – an interior room immediately adjacent to the work room where workers might place equipment and materials needed for a job.

Work Area – the location within the work room or on the exterior perimeter where the actual RRP work was performed. Note that the interior work area could cross the boundaries of the work room, e.g. if a window was being replaced from the inside, the work area might have included portions of the exterior.

Work Room – the room in the housing unit or COF where the RRP work was to be performed.

1. Introduction

1.1. Background and Purpose of Study

Many residences built prior to 1978 contain lead-based paint that, if disturbed, is likely to create lead hazards for residents of the home. Data from the National Survey of Lead and Allergens in Housing indicate that lead-based paint was used in 24% of the housing constructed between 1960 and 1978, in 69% of housing constructed between 1940 and 1959, and in 87% of housing constructed prior to 1940.¹ Actions that involve the disturbance or removal of lead-based paint, including many renovation and repair activities, can result in high localized concentrations of lead dust in the air and on exposed surfaces within the home, as well as in surrounding soils.²

In support of the Federal government's goal of eliminating childhood lead poisoning by 2010, EPA proposed a rule establishing requirements to protect residents of pre-1978 housing units from lead hazards due to Renovation, Repair, and Painting (RRP) activities. The proposed rule, issued under the authority of §402(c)(3) of the Toxic Substances Control Act (TSCA), was published in the Federal Register on January 10, 2006.³

In an effort to support a thorough risk assessment and cost-benefit analysis of the proposed rule, a field study was designed and conducted to characterize dust lead levels during various stages of RRP activities. Results of that field study are presented in this report.

1.2. Proposed Rule Summary

EPA's proposed rule establishes training, certification, and accreditation requirements, as well as work practice standards, for contractors performing RRP work in housing built prior to 1978. Specifically, the proposal would establish requirements for training renovators and dust sampling technicians; certifying renovators, dust sampling technicians, and renovation firms; and accrediting providers of renovation and dust sampling technician training. The proposal would also require renovation professionals to follow certain lead-safe work practice standards. EPA developed these requirements, in part, based on conclusions drawn from a previous renovation and remodeling field study that identified relationships between certain renovation activities and elevated blood-lead levels.⁴ The requirements address EPA's concern that RRP work conducted by untrained and uncertified contractors may create new lead hazards, increasing the risk of lead exposure to the residents of homes containing lead-based paint.

EPA has proposed a phased approach for implementation of this rule. Initially, the rule would apply only to RRP work performed in target housing built before 1960 – both rental and owner-occupied – where a child with an elevated blood-lead level resides, unless, with respect to owner-occupied target housing, the renovation professional obtains a signed statement from the

¹ U.S. Department of Housing and Urban Development (HUD). 2002. National Survey of Lead and Allergens in Housing, Volume I: Analysis of Lead Hazards, Final Report, Revision 7.1.

² U.S. EPA. 2006. Air Quality Criteria for Lead (Second External Review Draft), Volume I of II. EPA/600/R-5/144aB.

³ U.S. EPA. 40 CFR 745, Lead; Renovation, Repair, and Painting Program; Proposed Rule. Federal Register (71 FR 1588, January 10, 2006).

⁴ U.S. EPA. 1999. Lead Exposure Associated with Renovation and Remodeling Activities: Phase III, Wisconsin Childhood Blood-Lead Study. EPA 747-R-99-002.

owner-occupant indicating that the renovation will occur in the owner's residence and that no child under age 6 resides there. By the end of the phase-in period, the applicability of the rule would be expanded to include all rental and owner-occupied target housing built between 1960 and 1977 and occupied by a child under age six. "Target housing" is defined in §401 of TSCA as "any housing constructed before 1978, except housing for the elderly or persons with disabilities (unless any child under age 6 resides or is expected to reside in such housing) or any 0-bedroom dwelling." EPA is also proposing to authorize interested states, U.S. Territories, and Indian Tribes to administer and enforce all elements of the new renovation provisions.

1.3. Study Objectives

The study was designed to compare environmental lead levels at appropriate stages after various types of RRP activities were conducted on the interior and exterior of residential housing units and child-occupied facilities (COFs). All jobs disturbed more than 2 square feet of lead based paint, which is the de minimus amount of disturbed area, to which the proposed rule applies. Of particular interest was the impact of using specific work practices that renovation contractors would be required to follow under the proposed rule (e.g., the use of plastic containment in the work area and a multi-step cleaning protocol). The RRP activities conducted represented the range of activities permitted under the proposed rule, including work practices that are restricted or prohibited under 40 CFR part 745.227(e)(6). These restricted or prohibited work practices included:

- Open-flame burning or torching of lead-based paint;
- Machine sanding or grinding or abrasive blasting or sandblasting of lead-based paint without a High Efficiency Particulate Air (HEPA) exhaust control;
- Dry scraping of more than 2 square feet of interior lead-based paint in any one room and dry scraping totaling more than 20 square feet on exterior surfaces; and
- Operating a heat gun on lead-based paint at temperatures above 1100 degrees Fahrenheit.

The study design was tailored to generate data that would permit evaluation of the following six study objectives:

Objective 1: What is the effect of low-, medium-, and high-level RRP work on post-work, post-cleaning, and post-verification dust-lead levels (interior and exterior)?

Objective 2: Are there significant differences in lead levels at the post-cleaning and/or post-verification phases from the use of heavy-duty polyethylene plastic sheeting during the work activity? Is there an interaction between level of RRP work and the use of plastic?

Objective 3: Are there significant differences in post-cleaning and/or post-verification lead levels between surfaces cleaned with the proposed rule cleaning method and surfaces cleaned with baseline cleaning methods? Is there an interaction between level of RRP work and cleaning method used?

Objective 4: Are there differences in the amount of lead dust migration from the Work Room to adjacent rooms between different levels of RRP work, use and non-use of plastic, and use and non-use of proposed rule cleaning methods?

Objective 5: Does the use of plastic ground coverings during exterior work reduce the amount of dust lead falling onto the ground?

Objective 6: Are there significant differences in the lead levels remaining after the two steps of the cleaning verification process, i.e., the wet cloth step and the dry cloth step?

Objective X: Are there significant differences between post-job lead levels between jobs conducted using proposed rule practices (use of plastic, specialized cleaning, and cleaning verification) and those conducted using baseline practices (no plastic and baseline cleaning)?

2. Summary of Conclusions and Peer Reviews

2.1. Conclusions Summary

Interior

Application of the package of plastic protective sheeting, HEPA vacuuming and wet mopping, and cleaning verification practices in EPA's proposed rule did result in lower lead levels at the end of a job than were achieved using baseline practices (no plastic protective sheeting and cleaning with broom and a shop-vacuum vacuum). Descriptive analyses in this report display the lower geometric mean levels achieved consistently across jobs on work room floors and sills. Statistical modeling presented in the report confirms a statistically significant difference between proposed rule and baseline practices for work room floors and sills.

Exterior

The use of plastic as a ground covering during exterior jobs captured large amounts of leaded dust. Analyses in the report compare the amount of lead on top of the rule plastic to the amount under the rule plastic, both with and without samples of bulk debris. For most job types, there is a substantial difference between the amount of lead captured by the rule plastic and the amount under the rule plastic. One notable special case is Torching. Without the bulk debris samples, the amount of lead under the plastic for Torching exceeded the amount on top. For all 8 job types, the ratio of the amount of lead on top of the rule plastic to the amount underneath was statistically significant when bulk debris samples were included. This changed to 6 out of the 8 job types when bulk debris samples were excluded. In addition, for some job types, substantial amounts of lead were measured in collection trays just outside the rule plastic.

The study also examined the specific components of the rule package in comparison to baseline practices. Results for the specific components of the rule package are summarized in Sections 9.2, 9.3, and 9.4.

2.2. Peer Review of the Study Design

The design and quality assurance project plan of this study were peer reviewed. The peer review was conducted from May 24, 2006 to June 11, 2006. Experts in fields related to the study reviewed the design and quality assurance plan independently and provided written comments to EPA. The major comments of the reviewers as a group are summarized below.

Overall, most reviewers commented favorably on the study design. In response to a charge question asking for recommendations for alternative approaches, most reviewers indicated the design as proposed was satisfactory. Nevertheless, a number of reviewers recommended that more samples be collected. In response, more dust samples were added in the Work Room, more exterior soil samples were included for both interior and exterior renovation jobs, and background samples for exterior dust collection tray sampling were added.

Some reviewers suggested adding more intensive jobs to the study, and some reviewers questioned whether the less intensive jobs in the study would result in a sufficient amount of lead dust. In response, more intensive jobs, such as power sanding without a HEPA attachment and open flame burning, were added to the study. Less intensive jobs remained in the study, however, because the goal of the study was to examine the range of activities expected to be covered by the EPA rule. Approximate square footage of lead-based paint disturbed by each job was measured in each experiment, and all jobs in the study disturbed more than the de minimus 2 square feet in the proposed Renovation, Repair, and Painting rule.

A number of reviewers commented that the impact of “real world” renovation conditions, such as the presence of furniture, occupants, pets, pre-existing lead dust, and so on, would not be captured by the study. For health and safety reasons, the study was conducted in vacant housing units and other vacant units. The study results may underestimate the levels of dust that would result from a renovation job due to the absence of these “real world” factors, but the study will achieve its goal of providing comparative data on the difference in lead dust levels when lead-based paint is disturbed under proposed rule versus baseline work practices.

A reviewer questioned the use of the phrase “normal cleaning” in the design documentation to describe dry broom sweeping and shop vacuuming. Dry broom sweeping and shop vacuuming were included in the study for comparative purposes as the cleaning that would likely be done if there were no EPA rule for Renovation, Repair, and Painting. The phrase “normal cleaning” was changed to “baseline cleaning.”

Some reviewers recommended the use of ASTM standards. ASTM standards were adopted for dust and soil sampling. An ASTM standard for paint chip collection was included in the design at the time of the peer review.

EPA has established an electronic record of the peer review of the study design. This record includes the comments from the reviewers and EPA’s responses to those comments. The peer review record for the review of the study design can be found in the public docket for the final rule.

2.3. Human Subjects Review

The study was assessed by EPA as to whether it met the definition of a Human Subjects study as defined by 40 CFR Part 26 – Protection of Human Subjects. EPA made the determination that the study was not a Human Subjects study because; (1) the only human subjects monitoring in the study, via the collection of personal air monitoring samples and the collection of blood samples from the RRP workers, was conducted solely to ensure compliance with all OSHA requirements in 29 CFR Part 1926.62 – Lead Exposure in Construction, and (2) the ensuing personal air monitoring data and blood lead data were not to be analyzed or generalized as part of the study analysis. The personal air monitoring data and blood lead data were reported to appropriate parties as required by 29 CFR Part 1926.62.

Representatives of the Battelle Institutional Review Board (IRB) reviewed the study design and data collection plans early in the design stage and again once the study protocols were fully

established. From both reviews, they determined that the study did not meet the regulatory definition of “human subjects research” according to the definitions at 45 CFR 102 (f)(2) (Common Rule) and 40 CFR 26.102 (f)(2) (EPA specific regulation). As such, the study was not subject to the Human Subjects Protections regulations.

Personal exposure monitoring was performed in accordance with health and safety requirements and was not used for *purposes of research*, but rather to determine the amount of airborne lead dust, if any, to which workers might be exposed and to confirm that the appropriate personal protective equipment (PPE) was used for the RRP workers. Thus, the IRB’s opinion was that the personal exposure monitoring was not related to the research objectives and, therefore, did not invoke human subjects protections, but, rather, was a personnel protection activity. In addition, the IRB did not determine the RPP field study to be an “intentional exposure” study in accordance with the provisions of 40 CFR Part 26.1102(1), “*Research involving intentional exposure of a human subject means a study of a substance in which the exposure to the substance experienced by a human subject participating in the study would not have occurred but for the human subject's participation in the study.*”.

3. Study Design

3.1. Site Selection Process and Requirements

As noted previously, the project was conducted to characterize the dust lead levels after various types and intensity of renovation, repair, or painting jobs in vacant housing units and vacant child-occupied facilities with lead-based paint (LBP). Both interior and exterior jobs were considered when evaluating sites for selection.

Potential sites were evaluated for the 60 interior experiments (48 at housing units and 12 at COFs) and 15 exterior experiments (12 at housing units and 3 at COFs) for a total of 75 experiments. Since multiple experiments could be performed at a single site, 75 individual sites were not required. To allow for multiple experiments at a site, however, there needed to be lead-based paint in sufficient quantities on the desired building components, ability to conduct the experiments in the available timeframe, and ability to avoid cross-contamination through cleaning and verification between experiments conducted at the same site.

The following characteristics summarize the requirements of potential sites for inclusion in the study:

- Built before 1978;
- Cleanable before work began, in between, and at the completion of all study activities;
- Vacant and accessible during the study data collection period and available to schedule work according to the study's needs;
- Presence of lead based paint at the required levels (defined as dried paint film that has a lead content at or exceeding 1.0 mg/cm² or 0.5 percent by weight) and of sufficient size [2 square feet (ft²) or more] within a single room or on specific desired components of the prospective site;
- Ability of potential interior sites to meet the desired three room study layout by containing three sequentially adjacent rooms to allow sampling in a Work Room, a Tool Room, and an Observation Room; and
- Adequate space at potential exterior sites in the yard or around the exterior of the building to allow desired sample collection and containment of dust and debris.

Additional characteristics were also desirable but not required in potential sites, including:

- Availability of electricity;
- Selection of a cross section of building ages (e.g., 2 pre-1920, 2 built between 1920 and 1950, and 2 built between 1950-1978) was ideal, but this desire was balanced by other study considerations; and
- Sites within close proximity to each other so as to maximize site coordination efforts.

3.2. Sampling Methods

For interior work, the study-impacted areas of participating housing units or COFs was defined as a set of three rooms – one undergoing the RRP activity, an adjacent room for tool storage, and an observation room adjacent to the tool storage room. In addition, post-experiment samples were obtained from a hallway running between these areas and the entrance of the unit used for conducting and exiting the job.

Paint Chip Samples – Following initial identification of lead-based paint using an X-ray fluorescence instrument, paint chip samples were collected from prospective components for laboratory analysis in order to obtain an accurate measurement of the lead in the paint that was potentially going to be disturbed by the RRP work. The method used to collect paint samples was the cold-scraping method described in ASTM E1729, “Standard Practice for Field Collection of Dried Paint Samples for Subsequent Lead Determination.” The size of the samples obtained was approximately two square inches and included all paint down to the substrate, minimizing the amount of substrate material in the sample. Lead-based paint is defined by EPA as paint or other surface coatings that contain lead greater than or equal to 0.5 percent by weight or greater than or equal to 1.0 mg/cm².

Interior Dust Wipe Samples – The interior sampling protocol involved collecting four floor dust wipe samples and one window sill dust wipe sample from the Work Room and two floor dust wipe samples and one window sill dust wipe sample from the other two study rooms (Tool and Observation rooms) at each stage of the experiment – post-work, post-cleaning, and post-cleaning verification. In addition, if a floor verification zone in the Work Room failed two wet cloth verifications, an additional post-wet cloth verification sample was collected for that floor zone before proceeding with the dry verification process. All dust wipes were collected in accordance with ASTM 1728, “Standard Practice for Collection of Settled Dust Samples Using Wipe Sampling Methods for Subsequent Lead Determination.”

The locations of the floor and window sill dust wipe samples in all three study rooms were randomly selected prior to the experiment and specified in experiment-specific sampling plans. This ensured that the locations of the samples were not biased by the field technician, and that no two samples were collected from the same area. The randomized sample selection in each room was stratified as necessary, to ensure samples were obtained from different sections of a room. If window sills were badly damaged, inadequately sized, or missing, a dust collection tray was placed in the study room, and all window sill samples were collected from the tray. Dust collection trays also replaced actual window sills when sills could not be cleaned below 250 µg/ft². For the window replacement experiments, a dust collection tray was placed on the horizontal surface directly below the outside of the window and sampled after the work was completed.

Exterior Dust Wipe Samples – For exterior work, nine dust collection trays were set up prior to the RRP work – three on top of the Rule plastic coverings, three in corresponding positions underneath the Rule plastic coverings, and three near the Rule plastic and on top of the protection plastic. Dust wipe samples were taken from each tray following completion of the

work. Background lead levels in the air at exterior job sites were measured by setting out a dust collection tray for a number of hours and subsequently taking a dust wipe of the tray.

Bulk Debris Samples – Where necessary, field technicians were instructed to collect excess debris that could not be collected with a dust wipe from each sampling location during the post-work sampling stage. The debris was collected by glove-covered hands and tools such as chisels that could scoop up material and placed in a plastic bag or centrifuge tube for further processing and laboratory analysis. For jobs that generated such large amounts of dust that it could not all be picked up using a dust wipe (such as the door planing job), technicians also used glove-covered hands to collect and place the excessive dust in a plastic bag.

Ambient Air Samples – Air samples were collected as part of this study following NIOSH Method 7082. For interior work, air samplers were placed in all three study rooms on tripods approximately five feet off the ground, so as to approximate levels of dust lead available to be inhaled.

Soil Samples – Soil samples were collected according to ASTM E1727-05, “Standard Practice for Field Collection of Soil Samples for Subsequent Lead Determination,” before and after both interior and exterior work. The soil samples served to measure potential track-in contamination during work (interior) and background lead contamination of the property (exterior), as well as potential contamination of the property by study activities.

3.3. Laboratory Analysis Methods

Paint Chip Samples – Laboratory sample preparation was performed according to EPA Method 3050B, and the subsequent atomic absorption analysis of the determination of lead followed EPA Method 7420. The analysis provided measurements of lead concentrations in $\mu\text{g/g}$, with a minimum detection limit of 20 μg total lead per sample.

Dust Wipe Samples – All interior and exterior dust wipe samples were prepared according to EPA Method 3050B and analyzed for lead content using EPA Method 7420 (atomic absorption). The analysis provided measurements of lead concentrations in $\mu\text{g}/\text{ft}^2$, with a minimum detection limit of 10 μg total lead per sample, which was requested to provide more specificity at lower levels of lead.

Bulk Debris Samples – Battelle technicians recorded the total mass of each bulk debris sample. Subsequently, any non-paint chip/dust debris was removed (screws, nails, pieces of wood, etc.), the samples were homogenized (paint, dust, and other material crushed and mixed with a clean mortar and pestle), and two subsamples of at least 1 g each were obtained. Each was labeled appropriately and sent to the laboratory for analysis as paint chip samples. The laboratory reported percentage of lead by mass in each of the two subsamples. The mean lead mass percent was calculated; this mean multiplied by the total bulk mass gives the total lead in the bulk sample. The total lead mass in the bulk sample is added to the total lead mass measured in the associated dust wipe sample to obtain total mass per square foot ($\mu\text{g}/\text{ft}^2$) in the sampled area.

Ambient Air Samples – Air filter samples were analyzed using NIOSH Method 7082 (flame atomic absorption spectrophotometry). The analysis provided measurements of lead concentrations in $\mu\text{g}/\text{m}^3$, with a minimum detection limit of 2 μg total lead per filter.

Soil Samples – EPA Method 3050B was used to prepare the soil samples for analysis. EPA Method 7420 (atomic absorption) was used to analyze the samples for lead. The analysis of soil lead concentrations was reported in $\mu\text{g}/\text{g}$, with a minimum detection limit of 20 μg total lead per sample.

3.4. Field Sampling Protocols

3.4.1. Interior Jobs

Prior to the start of an experiment, paint chip samples were collected from building components that would potentially be disturbed during RRP activities to evaluate the lead concentrations in the paint. In addition, three composite soil samples were collected, where applicable, from bare soil nearest to (1) the entryway to the building used by the workers, (2) the walkway from the entryway to the street, and (3) a window closest to the work area. If the unit was used for multiple interior experiments, the post-experiment soil samples of the previous experiment were used as the pre-experiment soil samples for the next interior experiment, where appropriate.

All areas of the unit not being used in the study were barricaded using plastic coverings. All air vents in floors, walls, and ceilings in any of the areas impacted by the study were also covered with plastic. A thorough cleaning was conducted by a lead abatement firm with experience cleaning after lead abatement activities in accordance with the U.S. Department of Housing and Urban Development (HUD) Guidelines on abatement cleaning and clearance. An independent licensed clearance technician then collected five dust wipes (4 floor, 1 sill) from the Work Room and three dust wipes (2 floor and 1 sill) each from the Tool and Observation Rooms, plus up to three additional samples in hallways or other areas impacted by the study. If the lead loading on the clearance wipes was no greater than 40 $\mu\text{g}/\text{ft}^2$ on floors and 250 $\mu\text{g}/\text{ft}^2$ on window sills, the unit was declared clean. If one or more samples failed to meet these clearance standards, then the room in which that sample was collected was re-cleaned and re-sampled.

Deviations from this plan did occur in order to maintain progress. There were some cases where one or more samples in a room were measured above 40 $\mu\text{g}/\text{ft}^2$, but because the room average was below 40, the decision was made to proceed with work. There were a few cases where the room average was above 40 $\mu\text{g}/\text{ft}^2$, but work occurred because of schedule constraints. When floors in Tool and Observations were unable to achieve clearance, they were covered with clean plastic, which provided a clean surface with which to start the experiment. When window sills were in poor condition and/or could not be cleaned below 250 $\mu\text{g}/\text{ft}^2$, clean dust collection trays were used in place of the actual window sill in almost all cases.

If the interior protection/clean-up (P/CU) phase to be implemented involved containment, plastic coverings were set up in the Work Room by the RRP contractor according to the proposed rule. This included closing and sealing all doors into the Work Room; covering all doors within the work area that had to be used while the job was being performed with plastic sheeting in a manner that allowed workers to pass through, while confining dust and debris to the work area;

covering the entire floor surface with taped-down plastic sheeting in the Work Room; and taping plastic to the outside of the window frame, if a window was being replaced as part of the job, so that no debris could fall to the ground outside the window.

An area just outside of the Work Room (either in the hallway or the Tool Room) was identified to serve as the primary decontamination area where workers removed all dust and debris from their person, their equipment, and the exterior of any waste containers using a HEPA vacuum. The floor of the primary decontamination area was securely covered with plastic.

A secondary decontamination area was set up just inside or outside of the main entrance to the unit. This area was used to remove and dispose of the Tyvek suits and booties worn for worker protection while inside the unit. Respirators were also removed in the secondary decontamination area. Personnel also cleaned off any debris remaining on equipment, clothing, or the exterior of waste containers prior to leaving the study site. A tack pad was set up to remove any remaining dust from street shoes before leaving the property.

The hired RRP contractors conducted their job as they normally would, within the specifications of the study. Following job completion, study personnel waited for one hour before collecting post-work dust wipe and air samples. In instances where significant debris covered the pre-designated sampling location, the debris was collected in a plastic bag prior to wiping the area with a dust wipe. The bulk samples were sent separately to the lab for analysis.

Once post-work environmental samples were collected, the RRP contractor misted and picked up the plastic sheeting covering the floor, if present. The sheeting isolating the Work Room from the other areas of the unit remained in place until all cleaning activities were completed. RRP contractors were instructed to follow one of two cleaning methods – a baseline cleaning or the proposed rule cleaning. For a baseline cleaning effort, the RRP contractor swept the entire Work Room with a broom and dustpan to collect large amounts of debris. Subsequently, the RRP contractor vacuumed the work area with a Shop Vac-type vacuum. For the rule cleaning, the RRP contractor followed the guidelines detailed in the proposed rule to clean the entire Work Room. Large pieces of debris were collected and disposed of prior to cleaning. All walls were vacuumed with a HEPA vacuum starting from the ceiling and working down to the floor. The remaining surfaces and objects in the work area, including floors and any fixtures, were then vacuumed with a HEPA vacuum. The floors were then thoroughly mopped using a 2-bucket mopping method. If containment was used in the experiment, [after completion of all appropriate cleaning activities], the plastic covering the door separating the Work Room from the other areas of the unit was taken down. This was performed by first misting and, then removing the plastic carefully folding it up, and placing it in a heavy duty garbage bag.

After the cleaning was complete, all study personnel waited for one hour before collecting post-cleaning dust wipe and air samples. Once all post-cleaning samples were collected, the RRP contractor began the cleaning verification process described in detail in the proposed rule. For both the window sills and floor zones, each area was wiped with a wet cleaning verification cloth and compared to the verification card provided as guidance for determining the cleanliness of the cloth. If that cloth failed, then the component was re-cleaned following the proposed rule cleaning method (i.e., using a HEPA vacuum and wet mop) and wiped again with a new wet

cloth. Any re-cleanings were done with the proposed rule cleaning method in order to get more information regarding the cleaning cloth performance under proposed rule methods.

If the second wet cloth failed verification, then the component was re-cleaned and allowed to dry. The component was then wiped with a dry verification cloth, which was compared to the verification card provided. If the first dry cloth failed, then the component was wiped with a second dry verification cloth. The process was repeated for a maximum of four dry verification cloths. All windowsills were verified as clean before moving on to the floor verification. The floor was separated into zones approximately 40 ft² in area for the verification process. In the cases where a window sill or floor zone failed two wet verification tests, a post-wet verification sample was collected from that zone before proceeding with re-cleaning the component and dry cloth verification. The collection of post-verification dust wipe and air samples took place immediately following the cleaning verification.

After collection of the cleaning verification samples from the three study rooms, up to three additional 1 ft² floor dust wipe samples from a hallway connecting the study rooms to the unit's entrance were collected. In addition, three composite soil samples were collected in locations near those taken during pre-experiment sampling.

Following completion of an experiment, the areas of the unit impacted by the study were re-cleaned. If the unit was to be used in a subsequent experiment, the plastic sheeting protecting the parts of a housing unit not impacted by the study were left in place. A licensed clearance technician then collected five dust wipes (4 floor, 1 sill) from the Work Room and three dust wipes (2 floor and 1 sill) from the Tool and Observation Rooms, plus up to three additional samples in hallways or other areas impacted by the study. If the lead in the clearance wipes met the study's clearance standards, the unit was declared clean. If not, then each room that failed was re-cleaned and re-sampled.

If all interior work at the unit was complete, the plastic sheeting protecting the parts of the housing unit not impacted by the study was taken down, and the entire unit underwent an abatement style cleaning. A certified inspector/risk assessor or clearance technician then collected samples from one floor, one window sill, and one window trough, where accessible, from four rooms in the unit, in accordance with state procedures for clearance testing after lead abatement. If one or more samples were measured with dust lead levels over the clearance level, the area from which that sample was taken underwent re-cleaning. Following re-cleaning, another clearance sample was obtained and re-analyzed. Clearance levels were achieved in all study housing units, with the exception of some window troughs. Some window troughs did not get below 400 µg/ft², but these were either unimpacted by study activities or were in a deteriorated condition pointed out to the property owner. Final clearance results were provided to all property owners.

3.4.2. Exterior Jobs

Prior to the start of an experiment, paint chip samples were collected from building components that were potentially going to be disturbed during RRP activities to evaluate the lead concentrations in the paint. In addition, three composite soil samples were collected, where applicable, from bare soil (1) near the foundation of the housing unit/COF and within the area to be covered by the Rule plastic, (2) at the back edge (farthest from the housing unit/COF) of the Rule plastic, and (3) at the back edge (farthest from the housing unit/COF) of the containment plastic. If the unit was used in multiple exterior experiments, the post-experiment soil samples from the previous experiment were used as the pre-experiment soil samples for the next interior experiment, where appropriate. One or more dust collection trays were set out prior to work commencing to evaluate the background level of dust lead in the air at a housing unit.

The approximate size and location of the “Rule containment” was estimated in advance by the study team in order to identify pre-work soil sample locations. The exact size and location of the “Rule containment” was determined by the site supervisor in consultation with the RRP contractor, taking into account any physical constraints such as property lines, fences, nearby houses and the placement of the vertical containment structure. Before exterior work began, the RRP contractor set up “protection containment,” which included a large area of plastic covering the ground and vertical containment spanning the entire distance between ground level and the maximum height of the component undergoing RRP work.

The Rule containment was set up subsequently by the RRP contractor in accordance with the proposed rule. This included lying securely taped- or weighed-down plastic on top of the containment plastic extending out from the edge of the building a reasonable distance to collect falling paint debris. All doors and windows within 20 feet of and below the work area were closed. Dust collection pans were placed by study technicians under, on top of, and near the Rule plastic covering.

A decontamination area was set up immediately outside of the work area, where all study personnel removed and disposed of their protective suits and booties, and removed all dust and debris from tools and supplies.

The hired RRP contractors conducted their job as they normally would, within the specifications of the study. Following an up to one-hour wait after job completion, field technicians obtained dust-wipe samples from the dust collection pans on top of the Rule plastic sheeting. Subsequently, the RRP contractor misted and folded the plastic sheeting inward to trap dust and debris inside. The dust wipe samples from the pans under the Rule plastic were sampled after the plastic was removed. The trays placed near the rule plastic were also sampled at this time. Technicians collected three composite soil samples, consisting of three sub-samples each, in locations similar to those used for the pre-experiment soil sampling. Once all study-related activities were complete, the RRP contractor removed the vertical containment.

3.5. Participating Contractors (RRP Workers, Cleaning, Clearance Technicians)

Study implementation required the participation of multiple contractors in both Columbus, Ohio, and Pittsburgh, Pennsylvania. In Columbus, the study utilized two licensed firms to conduct initial cleanings, recleanings, and final cleanings of the Columbus housing units and child-occupied facility. All XRF inspections and dust lead clearance tests were performed by ATC Associates, Inc. (ATC), also licensed by the state of Ohio to conduct these activities. Three separate contractors provided the renovation work support for the field operations at the Columbus housing units and school. All had at least one person who had received training in the EPA/HUD course in Lead Safety for Remodeling, Repair, and Painting. In some cases, property owners worked with study personnel to identify preferred contractors who would conduct the renovation work on their properties.

In Pittsburgh, the study utilized services of one abatement cleaning firm, one certified environmental firm to conduct XRF inspections and dust lead clearance tests, and one renovation contractor. The renovation workers in Pittsburgh received training in the EPA/HUD course in Lead Safety for Remodeling, Repair, and Painting prior to starting work.

All participating renovation workers underwent study-specific training that reviewed the study health and safety plan, reviewed study protocols, and introduced and demonstrated the cleaning verification process. In addition, the study arranged for respirator training and fit testing for those renovation workers who were not equipped with the necessary respirator protection.

Site security during working hours was provided by special-duty police officers in Pittsburgh and off-duty police officers in Columbus.

3.6. Environmental Safety and Health Plan

The health and safety requirements for the study were applicable to all RRP workers and study personnel. A Health and Safety Plan was drafted to specify the precautions required to comply with the OSHA Lead in Construction standard (29 CFR 1926.62); to prevent study personnel from injuring themselves, their families, or neighbors; and to protect the study property and surrounding properties. During study activities, standard safe work practices were followed to avoid falls, burns, lacerations, and other injuries.

All RRP contractors were trained in accordance with the Lead in Construction standard, as well as the HAZCOM standard (29 CFR 1910.1200) with regard to lead. In addition, at least one member of the RRP work crew present on site was required to have Lead Safe Renovation training. Half- or full-face respirators were worn during all work activities in accordance with the observed personal exposure results for each type of study-related activity performed. To ensure that workers had adequate respiratory protection prior to job-specific data being available, the study conservatively assigned respirator types to each job at the beginning of the study so that for many jobs a higher degree of protection was utilized beyond what might typically be used. For the experiments where paint was removed by open-flame torching, the RRP workers and study personnel wore supplied air respirators for increased protection against lead inhalation.

A blood lead surveillance program was implemented to monitor the pre- and post- study blood lead content of all RRP workers and study personnel.

For both interior and exterior work, personal air samples were collected to ensure compliance with OSHA requirements; however, the results are not analyzed as part of the study. Personal air sampling results were monitored closely to ensure that respirators used for each job were adequate to provide sufficient protection. All personal air monitoring and blood lead results were provided to the workers.

Great effort was taken to limit the potential for lead contamination outside of the study area. Workers and study personnel were required to wear hooded protective clothing made of Tyvek, or another appropriate material, while performing study activities. Upon exiting the work area, all protective clothing and equipment were cleaned with a HEPA vacuum, and, in some cases, a wet cloth. Protective booties were worn to protect against contamination of the study areas from the outside, as well as to protect the property from contamination due to the work-generated dust. Before exiting the property, the protective clothing was vacuumed, again, and discarded. A tack pad was used to remove any residual dust from the bottoms of shoes. Workers and study personnel were required to wash exposed skin with soap and water immediately after exiting the property. All waste generated during study activities was removed from the properties and transported to a municipal or construction landfill to be disposed of as household waste.

4. Field Work Summary

4.1. Overview of Site Selection/Screening Process

The study team developed a list of potential locations and contacts for identifying prospective housing units and COFs to enroll in the study. Initially, the study sought to identify locations in or around Columbus, Ohio because of their proximity to Battelle and because Columbus is home to a large scale effort by various housing agencies, neighborhood associations, non-profit agencies, and private developers to rehabilitate older, low-income housing. The study team thought such organizations would likely have vacant housing and would be open to collaborating on the study to have work done that is beneficial to their ongoing efforts in housing renovation and remodeling activities. Leads identified through various sources in other cities were explored including Milwaukee, Detroit, Los Angeles, Birmingham, Philadelphia, Chicago, Baltimore, Arlington (VA), and Washington, DC.

The site selection process involved contacting organizations thought to have information on ongoing RRP activities. During the initial contact, study representatives explained the study to the contact, offered to provide them with a Fact Sheet summarizing the study, and asked whether they knew of RRP activities planned for housing in their area or of housing fitting the study requirements that would be a good candidate for participation in the study. If they were interested in supporting the study, detailed discussions about potential candidate housing units were held. If phone conversations concerning potential sites seemed to satisfy all the necessary study requirements and the owner was amenable to working within the study requirements for available experiments and study schedule, then a site visit was scheduled to inspect the property.

Permission to inspect and test units or buildings was obtained from site owners or managers prior to any inspection or testing taking place. The permission included an agreement as to whether and how the results of the inspection and testing would be transmitted to the site owner or manager. The required study form was used to obtain formal permission of the property owner to conduct the XRF inspection and visual assessment of a property. Each prospective housing unit or COF underwent a visual inspection to ensure that it met the study requirements beyond the presence of LBP – three sequential rooms, vacant, cleanable, etc. If the visual inspection confirmed that a prospective housing unit met the study requirements, a full lead screening inspection was scheduled with a portable XRF device to measure lead content of various painted components in the house – walls, window sills, trim, doors, etc. Inspectors obtained a large number of XRF measurements throughout a house, which were recorded by the field operations coordinator for the area, or their representative, on the appropriate data collection forms. As the study progressed and experiments were assigned to prospective units to begin work, subsequent site inspections were targeted to the components for experiments that still needed to be assigned.

Following review of the XRF measurements at a prospective housing unit, study planners determined whether there were one or more rooms that could serve as the Work Room for an interior job or whether there was more than one exterior side of the house that could serve as the work area for an exterior job. Permission to collect paint chip samples was obtained from the property owner using the proper form. Paint samples were then collected from components in prospective rooms and exterior sides for laboratory analysis, as necessary. Based on

confirmation of sufficient levels of lead based paint in the prospective housing site components, matching experiments were assigned and the housing owners were informed of their inclusion in the study and of the intended schedule of renovation activities to be performed at their housing unit.

In Columbus, Ohio and Pittsburgh, Pennsylvania, the study was able to conduct experiments in vacant housing owned by local non-profit agencies that own older housing needing renovation. Additionally, private citizens in Columbus who owned vacant housing containing lead-based paint also made their homes available to the study. A suitable COF was identified through the Columbus Public Schools system. A vacant school that contained sufficient amounts of lead-based paint was utilized for all COF experiments. Therefore, the study was able to use housing units in both Columbus and Pittsburgh and a COF in Columbus to provide some measure of geographic diversity while still being able to allow economy of site coordination efforts.

A total of 35 housing units were sufficient candidates to warrant a visual inspection of the properties. Of these 35 units, 27 properties were in good enough condition and satisfied the study requirements to warrant having an XRF screening performed. Based on the XRF measurements, the subsequent paint chip sampling, and a matching of the units to the study experiments, the study ultimately identified 15 housing units that met the selection criteria for use in the characterization of environmental lead levels associated with low, medium, and high levels of interior and exterior RRP activity. Table 4-1 summarizes the distribution of housing units among the two cities and interior/exterior experiments. As mentioned above, in addition to the housing units, one school was utilized to conduct 12 interior and 3 exterior experiments.

Table 4-1. Housing Unit Distribution by City.

| | Columbus | Pittsburgh |
|--------------------------|-----------------|-------------------|
| Interior Only | 3 | 4 |
| Exterior Only | 3 | 1 |
| Interior/Exterior | 1 | 3 |
| TOTAL | 7 | 8 |

4.2. Number and Type of Experiments Completed

The study conducted 12 interior jobs at housing units and 3 interior jobs at a COF and, similarly, 12 exterior jobs at housing units and 3 exterior jobs at a COF. Table 4-2 identifies each of the interior and exterior jobs performed at housing units across three work intensity levels specified prior to work taking place, while Table 4-3 lists the interior and exterior work performed at the COF. In parentheses at the end of each job description is the number of times each job was conducted. For interior jobs, each replicate of a job was to be done four times under each phase of plastic protection and cleaning method. Thus, interior housing unit jobs actually were conducted eight times to achieve the two full job replicates. As noted in Section 1.3, practices restricted by 40 CFR 745.227(e)(6) were included among the jobs conducted as part of the study. These are noted with roman numerals within the table corresponding to the four prohibited activities specified in 40 CFR 745.227(e)(6).

Table 4-2. Interior RRP Jobs Across Three Levels of RRP Work.

| Type | Low Level Work | Medium Level Work | High Level Work |
|---------------|---|---|--|
| HOUSING UNITS | Make up to three cut-outs, each of a 2 foot or more section of wall with LBP disturbing approximately 6 ft ² of LBP. (2) Replace window from inside unit, disturbing at least 2 ft ² of LBP. (2) | Scrape deteriorating LBP from interior walls, scraping 50-75 ft ² of painted surfaces [iii]. (2) Plane 20-40 ft ² of LBP from an interior door [ii]. (2) | Remove paint from 75-100 ft ² of lead-based painted components by using a heat gun over 1100° Fahrenheit held at one inch or the distance specified from paint [iv]. (2) Gut out a kitchen, disturbing 100 ft ² or more of LBP. (2) |
| COF | Make three cut-outs, each of a 2 foot or more section of wall with LBP disturbing approximately 6 ft ² of lead-based paint. (1) | Remove paint from 50 ft ² of lead-based painted components by using a heat gun UNDER 1100° Fahrenheit held at one inch or the distance specified from paint [iv]. (1) | Remove paint from 75 ft ² of lead-based painted components by using a heat gun OVER 1100° Fahrenheit held at one inch or the distance specified from paint [iv]. (1) |

Table 4-3. Exterior RRP Jobs Across Three Levels of RRP Work.

| Type | Low Level Work | Medium Level Work | High Level Work |
|---------------|---|---|--|
| HOUSING UNITS | Replace an exterior door and doorway, disturbing 25-50 ft ² of lead-based paint. (2) Replace fascia boards, soffits, and other exterior trim on one side of the structure, disturbing approximately 50 ft ² of lead-based paint. (2) | Remove lead-based paint from exterior components by dry scraping, disturbing approximately 100 ft ² of lead-based paint [iii]. (4) | Remove paint by power sanding or grinding at least 100 ft ² of lead-based paint on exterior wood components on one side of the structure [ii]. (2) Remove lead-based paint by torching or open-flame burning on at least 100 ft ² of lead-based paint from wood porch ceilings [i]. (2) |
| COF | Remove approximately 50 ft ² of LBP from an exterior component using a needle gun. (1) | Remove paint from 50-75 ft ² of lead-based painted components by using a heat gun UNDER 1100° Fahrenheit held at one inch or the distance specified from paint. (1) | Remove paint from 75-100 ft ² of lead-based painted components by using a heat gun OVER 1100° Fahrenheit held at one inch or the distance specified from paint [iv]. (1) |

4.3. Protection and Cleaning Routines

Interior Jobs – For each interior job, the study evaluated four work area protection/clean-up (P/CU) routines or phases – the four combinations of (1) use of plastic coverings/no use of plastic coverings and (2) baseline cleaning after work completion/cleaning per the proposed rule after work completion. Thus, the four P/CU routines were:

- Phase I - Use of plastic coverings and rule cleaning after work completion;
- Phase II - Use of plastic coverings and baseline cleaning after work completion;
- Phase III - No plastic coverings and rule cleaning after work completion; and
- Phase IV - No plastic coverings and baseline cleaning after work completion.

Within each job, the study attempted to characterize the amount and spread of dust under each of the four P/CU routines. The preferred method for achieving this was to split the job into four phases of equal activity to be performed in one room – the 1 Unit/1 Room Approach – and conduct the experiment independently four times so that each experiment corresponded to one of the four P/CU routines. In the instances where the job was unable to be replicated four times in the same room, the next alternative was to conduct the work across two rooms – applying two of the four P/CU routines in one room and the other two routines in another room. For jobs that could not be replicated in one or two rooms, such as the kitchen gutting job, the study used a 4 Room approach where each P/CU routine was conducted in a different room. These rooms could be in the same unit or different units. The approaches requiring multiple rooms or units to complete a full job produced data for which comparability depends on the degree to which similar room layouts with lead-based paint on the same components could be found. Table 4-4 lists the jobs performed with the approach used to complete that job.

Table 4-4. Interior Jobs and Associated Approaches for Conducting Experiment.

| Activity Level | Job | Job # | Columbus | Pittsburgh |
|----------------|--|-------|------------------|------------------|
| Low | Cut outs | 1 | | 2 Units, 2 Rooms |
| | | 2 | 2 Units, 2 Rooms | |
| | Replace window from inside house | 1 | | 2 Units, 2 Rooms |
| | | 2 | 1 Unit, 3 Rooms | |
| Medium | Scrape deteriorating lead-based paint from a flat interior component | 1 | 1 Unit, 1 Room | |
| | | 2 | | 1 Unit, 1 Room |
| | Scrape or plane 20-40 ft ² of lead-based paint from an interior door | 1 | 2 Units, 3 Rooms | |
| | | 2 | 2 Units, 2 Rooms | |
| High | Remove paint from 75-100 ft ² of lead-based painted components in a room by using a heat gun at or over 1100 degrees Fahrenheit | 1 | | 1 Unit, 1 Room |
| | | 2 | 1 Unit, 4 Rooms | |
| | Gut out a kitchen | 1 | | 4 Units, 4 Rooms |
| | | 2 | 2 Units, 2 Rooms | 2 Units, 2 Rooms |

The window replacement job in Columbus was conducted in one housing unit, but the windows were spread across three rooms with one room having two windows replaced. The other job that required three rooms, one door planing job, used two doors from a room in one house and two doors from another house, but the doors in the second house were in different rooms.

At the school, the three jobs were conducted in two separate classrooms, with six experiments conducted in each classroom. All four Cut-out experiments were conducted in one room, while the four low heat gun jobs were conducted in the second classroom. The high heat gun job was split between the two classrooms with two experiments conducted in each room. These assignments were made based on wall space available to have paint removed.

Exterior Jobs – For exterior jobs, the primary protection technique under evaluation was the use of plastic ground covering. To investigate this, plastic coverings were set up under an exterior job, as required by the proposed rule, with dust collection trays under, on top of, and near the plastic coverings. After completion of the exterior work, dust wipe samples were obtained from the dust collection trays. Thus, the exterior work and associated sampling were performed in one phase. Table 4-5 shows the distribution of the exterior jobs across city and the number of housing units required. The three exterior jobs at the COF were all conducted at the school in Columbus.

Table 4-5. Exterior Jobs Conducted in Each City.

| Activity Level | Job (# Jobs) | Columbus | Pittsburgh |
|----------------|--|----------|------------|
| Low | Replace exterior door (2) | | 2 Units |
| | Replace soffit, fascia and trim (2) | 1 Unit | 1 Unit |
| Medium | Scrape deteriorating lead-based paint from a flat exterior component (4) | 3 Units | |
| High | Remove paint from 100 ft ² of lead-based painted components by power sanding (2) | 1 Unit | |
| | Remove paint from 100 ft ² of lead-based painted components by open flame burning (2) | | 2 Units |

4.4. Environmental Samples Collected

Dust wipe and air samples were collected during each stage of the interior experiments. In addition, dust clearance samples were gathered following the pre-experiment (initial clearance) and post-experiment (final clearance) cleanings for interior jobs to ensure (1) that each phase of work began in a clean environment and (2) that housing units and buildings did not contain any residual lead hazards when work was completed. Table 4-6 summarizes the total number of environmental samples that were collected, including those collected for clearance purposes. The quality control samples included in the table include field spike and field blank samples inserted into the sample stream for quality assurance purposes.

Table 4-6. Total Number of Environmental Samples Collected

| Experiment Type | Sample Type | Housing Units (12) | COF (3) | TOTAL |
|-----------------|--------------------------|--------------------|--------------|--------------|
| | | # of Samples | # of Samples | |
| Interior | Dust Lead Clearance Wipe | 806 | 132 | 938 |
| | Dust Wipe | 1,699 | 469 | 2,168 |
| | Air | 576 | 146 | 722 |
| | Bulk | 120 | 37 | 157 |
| | Soil | 170 | 0 | 170 |
| | Paint Chip | 187 | 22 | 209 |
| Exterior | Dust Wipe | 137 | 28 | 165 |
| | Air | 13 | 4 | 17 |
| | Bulk | 24 | 11 | 35 |
| | Soil | 72 | 0 | 72 |
| | Paint Chip | 29 | 4 | 33 |
| Quality Control | Wipe QC | 201 | 51 | 252 |
| | Air QC | 96 | 25 | 121 |
| TOTAL | | 4,130 | 929 | 5,059 |

4.5. Protocol/Sampling Issues and Resolutions

Throughout the duration of field work, various circumstances impacted the performance of study protocols. Such circumstances generally resulted in minor adaptations to field activities or sampling procedures. Any adaptations were planned by field personnel, in consultation with study organizers whenever possible, to preserve the validity of each experiment. Summarized below are various protocol variations and sampling issues noted by field personnel over the course of the field study.

Protocol Variations

Obstructed floor samples – All sampling plans were prepared prior to sampling without access to detailed photographs of the study rooms. As a result, sampling plans sometimes included floor samples in areas occupied by air vents and other obstructions. When this occurred, field technicians moved the affected floor sample to an adjacent location not already used or designated for sampling.

Reduced wait times – The study design called for field personnel to wait for one hour following completion of the RRP work and cleaning stages before collecting dust wipe and air samples from the study rooms. Some RRP jobs took significantly longer than anticipated to complete, pushing the first one-hour wait period well into the afternoon. On several such occasions, site

supervisors opted to reduce the post-cleaning wait time in an effort to finish the experiment before dark or before site security personnel left for the day (typically at 5:00 pm). When this occurred, wait times were reduced by as short a duration as possible to allow a settling time of 30 to 40 minutes. During exterior work, one hour post-work wait times also were planned to allow dust to settle before sampling. In a few cases, anticipated bad weather or increasing winds led site supervisors to shorten wait times in order to collect samples before weather conditions might lead to loss of samples.

Extreme weather conditions (during interior experiments) – In general, field personnel used a front porch or other non-study area of a housing unit to set up a staging area for all study-related equipment and supplies. Several experiments were conducted in Columbus on extremely cold or rainy days at housing units with no available interior space, aside from the study rooms, to set up a staging area. To protect study equipment and personnel from the elements, field technicians used a portion of the housing unit’s Observation Room to hold study equipment. In these cases, which are noted in the experiment-level reports (see Appendix A), technicians first ensured that adequate space was available in the Observation Room to serve as a staging area and satisfy sampling requirements for that room. All equipment and cleaning supplies were protected under plastic whenever necessary to prevent contamination from RRP work and other study-related activities. Floor samples were moved, when necessary, to the open area nearest the planned sampling location to avoid sampling from areas partially or fully covered by study equipment.

Vacuuuming protocol (Baseline cleaning) – Early in the study, field personnel in Pittsburgh were confused as to whether contractors should be using the Shop-Vac to vacuum the Work Room walls during baseline cleaning. In some experiments the walls had been vacuumed, and in others they had not. Field personnel consulted with study organizers in Columbus and determined that the walls should not be vacuumed during baseline cleaning, since the baseline scenario was intended to represent a less intensive cleaning effort than Rule cleaning. For all subsequent experiments, contractors were directed to vacuum the walls only during Rule cleaning.

Mopping protocol (Rule cleaning) – The application of the two bucket mopping method differed across the RRP contractors. Some contractors preferred to mop the entire Work Room with soapy water first, then remove the soapy bucket from the room and mop the entire floor again with the rinse water. Other contractors used both buckets simultaneously – mopping several square feet with soapy water and then going over the same area with rinse water. Since both approaches are consistent with the text in the proposed rule and as RRP contractors were expected to perform the job as they would under normal conditions, both approaches were represented in the study.

Sampling Issues

Use of sampling trays in place of window sills – During many experiments, sampling trays were used in place of actual window sills. This was done for a number of reasons including poor condition of a sill, inability to clean a sill so it would pass clearance, or insufficient sill surface area for repeated sampling. On a small number of occasions in Pittsburgh, sampling trays were not put into position before RRP work began, when they were supposed to be used. In these instances, field technicians taped off a rectangular section of floor in an area where no floor

samples were supposed to be taken and sampled directly from the floor instead of the tray. On several other occasions when sampling trays should have been used in place of the unit's original window sills, field technicians inadvertently sampled from the sills instead of sampling trays. All such instances are noted in the experiment-level reports (see Appendix A).

Soil sample locations – Soil samples were intended to be taken from the same general locations before and after each experiment to facilitate a comparative analysis of soil-lead levels. In practice, field technicians occasionally took post-work samples from areas that were not sampled prior to work. A variety of field personnel was used in Columbus, and the same individuals did not always work at the same housing units. As a result, the individuals collecting the samples were occasionally uncertain about the location of pre-work samples and/or the most appropriate location of post-work samples.

Use of Plastic to cover tool and observation floors – The design of the study called for sampling to occur on actual floor surfaces, which had been cleaned prior to a renovation job occurring. Because of floors that were in poor condition and proved difficult to clean to a level at which they would pass clearance testing, during some experiments plastic sheeting was used to cover tool and observation room floors in order to provide a clean surface at the beginning of the experiment. No work room floors were ever covered because of the desire to have a realistic surface that had to be cleaned following work.

Cleaning Verification - Some RRP contractors appeared more likely than others to consider discolored wet verification cloths to be “clean,” attributing discolorations to factors other than residual paint dust (with no apparent basis for such conclusions). The impact of this on the study is that there may have been fewer cleaning verifications than there should have been, and potentially higher post-verification lead levels than would have been achieved if re-cleaning was performed and additional verification cloths used.

Field personnel also observed that the use of Simple Green detergent could contribute to discoloration of the verification cloths, as on multiple occasions verification cloths used on zones that were re-cleaned with Simple Green appeared progressively more soiled after each re-cleaning. Field personnel eventually concluded that the cleaning solution itself was causing the grayish discoloration. Subsequent analysis of floor samples taken from these zones confirmed that the discoloration was not caused by lead-based paint particulates.

4.6. Adherence to Environmental Safety and Health Protocols

As described in Section 3, a site-specific health and safety plan was prepared for each housing unit and COF used for field work. The field work crews in Columbus and Pittsburgh kept copies of these plans on-site at all times. Each plan contained detailed health and safety protocols to be followed by contractors and field technicians. The site supervisor at each job site was responsible for ensuring that all crew members adhered to these guidelines, which could be grouped into the general categories described below.

Study unit containment (to prevent lead contamination of non-study areas) – Contractors were directed to seal off non-study areas of each housing unit/COF with plastic sheeting and tape prior to beginning work. If cuts, holes, or gaps were observed in the containment at any time, contractors or field technicians quickly took action to re-tape or otherwise re-seal the plastic so that non-study areas would continue to be protected from lead dust and other potential hazards.

Personal safety during all stages of field work and sampling – On each day of field work, prior to beginning the RRP activity, the site supervisor held a safety meeting to communicate potential hazards associated with the job (e.g., lead exposure, physical hazards) and remind the crew members about the personal protective equipment that would be required for the day's work. During work, contractors were routinely reminded to inform the site supervisor if they needed a break. Field crews had access to a fire extinguisher, first-aid kit, and emergency air horn at all times during the study.

Respiratory protection and monitoring – All crew members were required to wear NIOSH/MSHA-approved respirators when inside the work areas. The type of respirator initially required for each job was based on the OSHA requirements and an assessment of the air monitoring data available for the jobs in the study. Half-mask, air-purifying respirators were required for activities expected to generate relatively small amounts of lead dust. Full-mask, air-purifying respirators or half-mask, supplied-air respirators were required for activities expected to generate significant dust or lead vapors. Air sampling for personal exposure to lead was performed during each of the three stages of the study – renovation work, post-work cleaning, and cleaning verification. Personal air sampling results were reviewed after each job and used to modify respirator requirements for subsequent jobs. For example, personal air samples collected during the cleaning verification stage were consistently below the analyzing laboratory's detection limits; therefore, contractors and field technicians in Pittsburgh and Columbus were not required to wear respiratory protection during the cleaning verification stage after the first two weeks of field work.

Hygiene – Site-specific health and safety plans called for handwashing facilities to include hot water, soap, and towels. Contractors in Columbus in Pittsburgh were responsible for providing these facilities, which typically consisted of two handheld pressure sprayers (one filled with soapy water, one with clear water) and a bucket to collect used water. Workers in the COF had access to a sink with running water and often elected to use hand soap at the sink instead of the pressure sprayers. Because much of the field work was conducted in cold weather, it was not always possible to use hot water for the handwashing stations set up at the housing units. Contractors had no way of heating the water or maintaining its temperature in the field. On days when outdoor temperatures were below freezing, some crew members elected to use baby wipes to clean their hands and faces in lieu of the cold water in the pressure sprayers.

Medical Surveillance – Medical surveillance was conducted on all field personnel and renovation workers. Each worker's blood lead level was measured before field work began and was or will be measured again following completion of work on the study.

4.7. Recordkeeping

Detailed records were kept of all field data collection activities. The information recorded by site supervisors and field technicians on data collection forms included:

- Clearance sampling locations and chain of custody records;
- Site wind speed and direction data for each day of exterior work;
- Precipitation activity during exterior work;
- P/CU phase of each experiment;
- Description of RRP work and duration of all RRP activities, including setting up plastic coverings, conducting cleaning, and conducting cleaning verification;
- Unit ID, location of study rooms or exterior work area, and specific location of samples obtained;
- Surface type and size of dust wipe samples;
- Air sampling locations and air flow rates for each sampler;
- Soil sample locations and associated sample IDs
- Location of the decontamination area where booties and other protective gear were removed upon exiting the work area;
- Paint lead levels on components undergoing work activity;
- Regular sample and QC sample identification information;
- Chain-of-custody records; and
- Signatures and initials of sample collectors.

When data collectors made or discovered errors on their data collection forms, they crossed out the incorrect information, inserted the correct information, and added their initials and the date next to the change.

In addition to written records, site supervisors obtained digital photographs and video recordings of various activities during the study across a subset of the housing units and experiments performed. Activities photographed or recorded include:

- initial inspection of the properties,
- RRP contractors conducting the work,
- plastic coverings being set up as containment,
- post-work cleaning,
- collection of environmental samples, and
- cleaning verification.

All digital photographs and video recordings were downloaded to computers for electronic storage.

Laboratory results were returned from the laboratory in electronic spreadsheet and Portable Document Format (PDF) files. All laboratory results were entered into a Microsoft (MS) Access 2003 database and exported into MS Excel 2003 and SAS v9.1 for statistical analyses. Data collection forms were archived for use in verifying the results entered in the database and in checking the electronic files received from the laboratory. These forms are not included in this final report in order to maintain the privacy of individual property owners.

5. Statistical Analysis Plan

5.1. Data Organization

A MS Access database was developed to manage the various types of data generated by the study. Throughout the study, paint chip, initial and final soil, initial and final dust clearance, dust wipe, air and bulk samples were collected, with respective collection information recorded on data collection forms (see Section 4). In addition to the environmental samples, property information, room designations and XRF results were recorded. The information recorded on the forms was entered by a data entry specialist or other professional into a customized interface that mirrored the look of the actual forms so that the information could be entered exactly as it was seen on the individual forms, thus reducing the potential for data entry errors. Laboratory analysis results were submitted electronically by the laboratory in MS Excel format. After review, they were directly uploaded into the database. The two sources of information could be linked by the unique sample ID. The information from the data collection sheets provided supplemental information to the lab results, including the collection date, location of the sample, and any issues encountered when collecting the sample.

5.2. Descriptive Analyses

The descriptive analysis section presents summary results for each type of data collected in the order listed below:

- Housing unit/experiment summary data,
- Paint lead levels,
- Pre-work clearance levels,
- Bulk debris samples,
- Interior dust samples,
- Interior air samples,
- Exterior dust samples with and without bulk debris samples included,
- Soil samples,
- Activity duration data, and
- Cleaning verification information.

For the environmental sample data, exploratory descriptive analyses were generated to summarize sampling results summarized by a variety of covariates of interest. The study was performed in multiple housing units in two different cities by four different renovation contractors, providing multiple sources of variance; thus, results are summarized by Unit, City, and Contractor. Results are also presented with respect to the type of job performed and the expected intensity level of the work. Jobs are further aggregated into those that did and did not use restricted practices. For interior experiments, the effect of the P/CU phase used during the experiment is investigated. The P/CU analysis is further broken down into the use or non-use of plastic coverings and whether the RRP contractors followed the rule cleaning or baseline cleaning guidelines. Additionally, floor and sill wipe results are summarized by work room floor type and condition.

For the various categorical variables investigated, detailed descriptive analyses in Appendices B-E contain box plots and summary tables, which illustrate and summarize the distribution of the data across the various factors. A box plot displays the median (represented by the center horizontal line), the 25th percentile (represented by the bottom of the box), and the 75th percentile (represented by the top of the box). The vertical lines, or whiskers, are drawn from the box to the most extreme point within 1.5 * interquartile range. (An interquartile range is the distance between the 25th and the 75th percentiles.) Any value more extreme than this, is identified individually with stars. The data are plotted using a log-base 10 scale. The summary statistics provided in the tables are sample size, arithmetic average, geometric average, minimum, 25th percentile, median, 75th percentile, maximum, and, for interior wipe data, the percentage of measurements exceeding the federal clearance standard.

Continuous variables investigated in the exploratory analyses include the paint lead concentration and size of the disturbed area for both interior and exterior work; pre- and post-work soil lead concentrations for both interior and exterior work; and floor dust lead loadings at clearance and average post-work work room floor lead level for interior work. For these variables, scatter plots of dust lead loadings are presented to illustrate the distribution of the data as a function of the various characteristics. Fitted linear regression lines are included on those scatter plots with associated r-square values to provide information on the correlation between the data and the characteristic of interest.

The detailed descriptive analyses (Appendices B-E) also present analysis of the distribution of the various types of data before and after transformation.

Due to laboratory limitations, some environmental samples were reported as having levels below the detection limit, which was 10 µg for dust wipes and 2 µg for air samples. In order to include these values in summary analyses, the lead level for all sample types was set to one half of the reporting limit of the laboratory.

The dust wipes in the descriptive analyses are presented as both wipe only and wipe plus bulk results. The wipe only results represent the amount of lead dust remaining on the floor after RRP work was performed and larger pieces of debris and excessive amounts of dust were picked up; a probable scenario for real-world RRP work. The inclusion of bulk samples provides a value of the total lead in the dust and debris, and thus total lead contamination, resulting from the work.

5.3. Statistical Models

Effectiveness of the proposed cleaning and interior plastic and exterior plastic protocols was analyzed using general linear models with mixed (fixed and random) effects. The response (\log_e -concentrations) was modeled to be linearly related to combinations of categorical and continuous covariates. The lead concentrations were \log_e -transformed prior to modeling so that residuals were approximately normally-distributed. Key fixed effects included indicators for rule- or baseline cleaning and use of containment plastic on interior jobs. On exterior jobs, the key fixed effects included tray position on, under or near a sheet of plastic.

A random effect was included for experiment number (grouped by Work-room number nested within housing unit) in order to model covariance among the multiple sub-samples to correctly assess significance and confidence limits. That is, floor-wipes within an experiment are treated as sub-samples (exchangeable repeated measures) on the experimental unit. Dustpan loadings in each exterior experiment are also treated as sub-samples on the experimental unit.

Besides key fixed effects, other covariates (both categorical and continuous) were analyzed to assess the extent that different factors explain differences in \log_e lead concentrations in the samples. More detailed descriptions follow. Detailed model results across all objectives is available in Appendices I through N.

The first objective is assessed using only Work-room wipes at the Post-work (PW) stages. The effects of plastic and cleaning (the second and third objectives) on reduction of \log_e lead levels subsequent to cleaning are assessed using Work-room wipes from Post-cleaning (PC) and Post-verification (PV) stages. The effects of plastic and cleaning on migration (the fourth objective) are assessed on wipes from Post-cleaning (PC) and Post-verification (PV) stages from the Observation and Tool rooms. Objective 5 addresses exterior plastic and involves only the exterior dust pan \log_e loadings.

6. Descriptive Analyses

6.1. Housing Unit/Experiment Summary Information

Table 6-1 summarizes the 15 housing units and one COF utilized to complete the 75 experiments. The four apartments (H31-H33, H35) were located in two attached buildings and the two duplex units (H16-H17) were both halves of the same building. Thus, 12 separate buildings were used for the study, with most of the buildings built between approximately 1900 and 1925. The only exception was the COF school building, which was built in 1967.

Table 6-1. Housing Unit Information

| Unit ID | City | Year Built | Building Type | Approximate Interior Square Footage |
|---------|--------------------------|-----------------|---------------|-------------------------------------|
| H01 | Columbus, Ohio | 1918 | Single Family | Exterior Only |
| H02 | Columbus, Ohio | OLD* (Pre-1920) | Single Family | Exterior Only |
| H03 | Columbus, Ohio | OLD* (Pre-1920) | Single Family | 1,500 |
| H08 | Columbus, Ohio | 1910 | Single Family | 1,744 |
| H09 | Columbus, Ohio | OLD* (Pre-1920) | Single Family | 2,404 |
| H10 | Pittsburgh, Pennsylvania | 1920 | Single Family | 2,508 |
| H13 | Pittsburgh, Pennsylvania | 1900 | Single Family | Exterior Only |
| H16 | Pittsburgh, Pennsylvania | 1925 | Duplex | 1,472 |
| H17 | Pittsburgh, Pennsylvania | 1925 | Duplex | 1,472 |
| H19 | Columbus, Ohio | 1920 | Garage | Exterior Only |
| H31 | Pittsburgh, Pennsylvania | 1925 | Apartment | 550 |
| H32 | Pittsburgh, Pennsylvania | 1925 | Apartment | 550 |
| H33 | Pittsburgh, Pennsylvania | 1925 | Apartment | 550 |
| H35 | Columbus, Ohio | 1900 | Single Family | 1,538 |
| H36 | Pittsburgh, Pennsylvania | 1925 | Apartment | 550 |
| C01 | Columbus, Ohio | 1967 | School | Not available |

* Only information on Year Built from tax assessor records is "OLD." Nearby properties indicate that these houses were likely built between 1900 and 1920.

Tables 6-2 and 6-3 summarize various characteristics of the interior and exterior experiments, respectively. For the interior experiments, Table 6-2 contains the average paint lead, amount of surface disturbed and type of surface disturbed. Average paint lead ranged from 0.8 to 13.0 percent by weight across the 60 interior experiments. For the work room, floor type and condition and size are presented. The size of the tool and observation rooms is also included, as well as the distance from the observation room to the work room. This was calculated as the distance from the observation room entrance to the work room entrance. In some cases, these distances are relatively small, such as four and five feet. In those cases, the work room was a second floor bedroom and the observation room was another second floor bedroom. The hallway separating the bedrooms served as the tool room.

Table 6-2. Interior Experiment Summary Table

| Job-Related Information | | | | | | | Work Room | | | | Tool Room | | Observation Room | | |
|-------------------------|---------|--------------|-------|----------------------------|------------------------------------|------------------------|-----------|------------|-----------------|-------------------------|-----------|-------------------------|------------------|-------------------------|----------------------------|
| Exp. # | Unit ID | Job | Phase | Avg. Paint Lead (% by wt.) | Disturbed Paint (ft ²) | Substrate Behind Paint | Room # | Floor Type | Floor Condition | Size (ft ²) | Room # | Size (ft ²) | Room # | Size (ft ²) | Distance to Work Room (ft) |
| 5 | H03 | Dry Scrape | I | 1.6 | 90 | Plaster | 201 | Wood | Poor | 160 | 205 | 70 | 203 | 100 | 15 |
| 6 | H03 | Dry Scrape | II | 2.7 | 90 | Plaster | 201 | Wood | Poor | 160 | 205 | 70 | 203 | 100 | 15 |
| 7 | H03 | Dry Scrape | IV | 1.7 | 70 | Plaster | 201 | Wood | Poor | 160 | 205 | 70 | 203 | 100 | 15 |
| 8 | H03 | Dry Scrape | III | 1.7 | 110 | Plaster | 201 | Wood | Poor | 160 | 205 | 70 | 203 | 100 | 15 |
| 9 | H09 | Window Repl. | III | 7.3 | 9 | Wood | 201 | Wood | Poor | 180 | 204 | 100 | 203 | 200 | 5 |
| 10 | H09 | Window Repl. | IV | 3.3 | 9 | Wood | 201 | Wood | Poor | 180 | 204 | 100 | 203 | 200 | 5 |
| 11 | H09 | Window Repl. | II | 10.1 | 18 | Wood | 203 | Wood | Poor | 200 | 204 | 100 | 201 | 180 | 5 |
| 12 | H09 | Window Repl. | I | 7.2 | 11 | Wood | 206 | Wood | Poor | 150 | 204 | 100 | 203 | 200 | 15 |
| 13 | H09 | Heat Gun | II | 8.1 | 53 | Wood/Stone | 201 | Wood | Poor | 180 | 204 | 100 | 203 | 200 | 5 |
| 14 | H09 | Heat Gun | III | 2.0 | 75 | Wood | 202 | Wood | Poor | 140 | 204 | 100 | 203 | 200 | 5 |
| 15 | H09 | Heat Gun | IV | 10.2 | 75 | Wood/Stone | 203 | Wood | Poor | 200 | 204 | 100 | 206 | 150 | 15 |
| 16 | H09 | Heat Gun | I | 4.0 | 75 | Wood | 206 | Wood | Poor | 150 | 204 | 100 | 203 | 200 | 15 |
| 22 | H16 | Cut-outs | IV | 3.6 | 13 | Plaster | 103 | Vinyl Tile | Good | 190 | 102 | 215 | 101 | 230 | 14 |
| 23 | H16 | Cut-outs | I | 3.6 | 14 | Plaster | 103 | Vinyl Tile | Good | 190 | 102 | 215 | 101 | 230 | 14 |
| 24 | H17 | Cut-outs | III | 5.0 | 40 | Plaster | 103 | Vinyl Tile | Good | 190 | 102 | 215 | 101 | 230 | 14 |
| 25 | H16 | Cut-outs | II | 3.6 | 14 | Plaster | 103 | Vinyl Tile | Good | 190 | 102 | 215 | 101 | 230 | 14 |
| 26 | H17 | Dry Scrape | III | 2.1 | 60 | Plaster | 103 | Vinyl Tile | Good | 190 | 102 | 215 | 101 | 230 | 14 |
| 27 | H17 | Dry Scrape | IV | 2.5 | 64 | Plaster | 103 | Vinyl Tile | Good | 190 | 102 | 215 | 101 | 230 | 14 |
| 28 | H17 | Dry Scrape | I | 2.5 | 65 | Plaster | 103 | Vinyl Tile | Good | 190 | 102 | 215 | 101 | 230 | 14 |
| 29 | H17 | Dry Scrape | II | 2.6 | 72 | Plaster | 103 | Vinyl Tile | Good | 190 | 102 | 215 | 101 | 230 | 14 |
| 30 | H10 | Heat Gun | IV | 10 | 65 | Wood | 201 | Wood | Poor | 150 | 206 | 50 | 202 | 105 | 4 |
| 31 | H10 | Heat Gun | II | 5.1 | 65 | Wood | 201 | Wood | Poor | 150 | 206 | 50 | 202 | 105 | 4 |
| 32 | H10 | Heat Gun | III | 8.5 | 69 | Wood | 201 | Wood | Poor | 150 | 206 | 50 | 202 | 105 | 4 |
| 33 | H10 | Heat Gun | I | 3.5 | 60 | Wood | 201 | Wood | Poor | 150 | 206 | 50 | 202 | 105 | 4 |
| 41 | H16 | Window Repl. | I | 0.9 | 10 | Wood | 101 | Wood | Poor | 230 | 102 | 215 | 103 | 190 | 14 |
| 42 | H16 | Window Repl. | II | 1.9 | 10 | Wood | 101 | Wood | Poor | 230 | 102 | 215 | 103 | 190 | 14 |
| 43 | H17 | Window Repl. | IV | 1.9 | 10 | Wood | 101 | Wood | Fair | 230 | 102 | 215 | 103 | 190 | 14 |
| 44 | H17 | Window Repl. | III | 4.1 | 10 | Wood | 101 | Wood | Fair | 230 | 102 | 215 | 103 | 190 | 14 |
| 45 | H08 | Cut-outs | IV | 1.8 | 6 | Plaster | 103 | Vinyl Tile | Poor | 180 | 102 | 220 | 101 | 200 | 15 |
| 46 | H08 | Cut-outs | III | 1.8 | 7 | Plaster | 103 | Vinyl Tile | Poor | 180 | 102 | 220 | 101 | 200 | 15 |
| 47 | H08 | Door Plane | IV | 3.9 | 40 | Wood | 103 | Vinyl Tile | Poor | 180 | 102 | 220 | 101 | 200 | 15 |
| 48 | H08 | Door Plane | I | 7.8 | 40 | Wood | 103 | Vinyl Tile | Poor | 180 | 102 | 220 | 101 | 200 | 15 |
| 49 | H31 | Kitchen Gut | II | 1.7 | 55 | Plaster | 101 | Vinyl Tile | Fair | 80 | 106 | 80 | 102 | 110 | 10 |
| 50 | H32 | Kitchen Gut | IV | 2.3 | 40 | Plaster | 101 | Vinyl Tile | Fair | 80 | 106 | 80 | 102 | 110 | 10 |

Table 6-2. (continued) Interior Experiment Summary Table

| Job-Related Information | | | | | | | Work Room | | | | Tool Room | | Observation Room | | |
|-------------------------|---------|--------------|-------|----------------------------|------------------------------------|------------------------|-----------|------------|-----------------|-------------------------|-----------|-------------------------|------------------|-------------------------|----------------------------|
| Exp. # | Unit ID | Job | Phase | Avg. Paint Lead (% by wt.) | Disturbed Paint (ft ²) | Substrate Behind Paint | Room # | Floor Type | Floor Condition | Size (ft ²) | Room # | Size (ft ²) | Room # | Size (ft ²) | Distance to Work Room (ft) |
| 51 | H33 | Kitchen Gut | I | 3.5 | 66 | Plaster | 101 | Vinyl Tile | Fair | 80 | 106 | 80 | 102 | 110 | 10 |
| 52 | C01 | Cut-outs | III | 9.5 | 6 | Plaster | 102 | Tile | Good | 120 | 112 | 560 | 120 | 50 | 25 |
| 53 | C01 | Cut-outs | II | 7.4 | 6 | Plaster | 102 | Tile | Good | 120 | 112 | 560 | 120 | 50 | 20 |
| 54 | C01 | Cut-outs | IV | 7.4 | 6 | Plaster | 102 | Tile | Good | 120 | 112 | 560 | 120 | 50 | 15 |
| 55 | C01 | Cut-outs | I | 7.4 | 6 | Plaster | 102 | Tile | Good | 120 | 112 | 560 | 120 | 50 | 15 |
| 56 | C01 | Low Heat Gun | II | 2.2 | 50 | Plaster | 105 | Tile | Good | 190 | 115 | 550 | 125 | 120 | 20 |
| 57 | C01 | Low Heat Gun | IV | 2.4 | 50 | Plaster | 105 | Tile | Good | 190 | 115 | 550 | 125 | 120 | 15 |
| 58 | C01 | Low Heat Gun | III | 2.8 | 50 | Plaster | 105 | Tile | Good | 145 | 115 | 600 | 125 | 120 | 15 |
| 59 | C01 | Low Heat Gun | I | 13.0 | 50 | Plaster | 105 | Tile | Good | 240 | 115 | 500 | 125 | 120 | 25 |
| 60 | C01 | Heat Gun | II | 2.9 | 75 | Plaster | 105 | Tile | Good | 160 | 115 | 580 | 125 | 120 | 25 |
| 61 | C01 | Heat Gun | III | 2.2 | 75 | Plaster | 105 | Tile | Good | 160 | 115 | 580 | 125 | 120 | 25 |
| 62 | C01 | Heat Gun | IV | 2.2 | 73 | Plaster | 102 | Tile | Good | 160 | 112 | 520 | 120 | 50 | 25 |
| 63 | C01 | Heat Gun | I | 2.6 | 75 | Plaster | 102 | Tile | Good | 160 | 112 | 520 | 120 | 50 | 25 |
| 67 | H16 | Kitchen Gut | I | 1.2 | 40 | Plaster | 103 | Vinyl Tile | Good | 190 | 102 | 215 | 101 | 230 | 14 |
| 68 | H17 | Kitchen Gut | III | 2.5 | 34 | Plaster | 103 | Vinyl Tile | Good | 190 | 102 | 215 | 101 | 230 | 14 |
| 69 | H08 | Kitchen Gut | IV | 5.2 | 69 | Plaster | 103 | Vinyl Tile | Poor | 180 | 102 | 220 | 101 | 200 | 15 |
| 70 | H35 | Kitchen Gut | II | 0.8 | 61 | Plaster | 101 | Tile | Fair | 115 | 110 | 50 | 104 | 180 | 10 |
| 71 | H35 | Cut-outs | II | 0.8 | 6 | Plaster | 101 | Tile | Fair | 115 | 110 | 50 | 104 | 180 | 10 |
| 72 | H35 | Cut-outs | I | 1.0 | 7 | Plaster | 101 | Tile | Fair | 115 | 110 | 50 | 104 | 180 | 10 |
| 73 | H35 | Door Plane | II | 1.2 | 31 | Wood | 101 | Tile | Fair | 115 | 110 | 50 | 104 | 180 | 10 |
| 74 | H35 | Door Plane | III | 3.2 | 26 | Wood | 101 | Tile | Fair | 115 | 110 | 50 | 104 | 180 | 10 |
| 76 | H36 | Kitchen Gut | III | 1.6 | 60 | Plaster | 101 | Vinyl Tile | Fair | 80 | 106 | 80 | 102 | 110 | 10 |
| 77 | H08 | Door Plane | II | 1.7 | 26 | Wood | 103 | Vinyl Tile | Poor | 180 | 102 | 220 | 101 | 200 | 15 |
| 78 | H08 | Door Plane | IV | 2.0 | 25 | Wood | 103 | Vinyl Tile | Poor | 180 | 102 | 220 | 101 | 200 | 15 |
| 79 | H09 | Door Plane | I | 2.1 | 32 | Wood | 202 | Wood | Poor | 140 | 204 | 100 | 203 | 200 | 5 |
| 80 | H09 | Door Plane | III | 5.9 | 40 | Wood | 201 | Wood | Poor | 180 | 204 | 100 | 203 | 200 | 5 |

Table 6-3. Exterior Experiment Summary Table

| Exp. # | Job | Unit ID | Work Location | Painted Material | Average Paint Lead (% by wt.) | Disturbed Paint (ft ²) | Length of Rule Plastic from Work Location (ft) | Width of Rule Plastic (ft) | Length of Containment Plastic Beyond Rule Plastic (ft) |
|--------|-----------------------|---------|------------------------|------------------|-------------------------------|------------------------------------|--|----------------------------|--|
| 1 | Dry Scrape | H01 | North Wall | Wood | 13.5 | 90 | 7 | 12 | 10 |
| 2 | Power Sanding | H01 | North Wall | Wood | 11.7 | 100 | 12 | 35 | 5 |
| 3 | Power Sanding | H01 | North Wall | Wood | 13.1 | 100 | 12 | 25 | 5 |
| 4 | Trim Replacement | H02 | Rear Porch | Wood | 15.3 | 40 | 5 | 20 | 2 |
| 21 | Dry Scrape | H09 | North Wall | Wood | 1.3 | 150 | 12 | 25 | 6 |
| 34 | Replace Exterior Door | H16 | South Wall | Wood | 10.5 | 25 | 4 | 8 | 4 |
| 35 | Replace Exterior Door | H17 | North Wall | Wood | 11.2 | 25 | 4 | 8 | 4 |
| 36 | Trim Replacement | H10 | Front Porch | Wood | 16.8 | 60 | 13 | 24 | 4 |
| 37 | Torching | H10 | Porch Ceiling | Wood | 2.7 | 98 | 13 | 20 | 4 |
| 38 | Torching | H13 | Porch Ceiling | Wood | 11.4 | 80 | 10 | 15 | 4 |
| 40 | Dry Scrape | H19 | North Wall | Wood | 15.7 | 250 | 6 | 20 | 6 |
| 64 | Low Heat Gun | C01 | Door Trim in Courtyard | Wood | 31.5 | 75 | 5 | 10 | 3 |
| 65 | Needle Gun | C01 | Railing in Courtyard | Metal | 5.3 | 30 | 5 | 30 | Varied* |
| 66 | High Heat Gun | C01 | Awning in Courtyard | Metal | 18.3 | 30 | 8 | 12 | 8 |
| 75 | Dry Scrape | H09 | North Wall | Wood | 1.3 | 100 | 6 | 25 | 10 |

* The containment plastic did not extend an identical amount in all directions around the railing. The railing was bordered on one side by a staircase and a vertical wall, which limited the size of the rule and containment plastic on that side.

6.2. Paint Lead Levels

Once the presence of lead-based paint was established based on XRF measurements, paint chips were obtained from each building component that would be disturbed by the renovation work. In all cases, the laboratory reported lead levels in the paint chips consistent with the definition of LBP. In general, higher levels of lead were found on exterior surfaces with average paint lead levels ranging from 1 percent to 32 percent by weight across the 15 exterior experiments with an overall average of approximately 12 percent. Across the 60 interior experiments, overall average paint lead levels ranged from 1 to 13 percent with an average of approximately 4 percent.

The lead content of the paint in a particular experiment could affect the resulting dust lead levels. To investigate this within Appendix G, Section G2 contains detailed summaries of the average paint lead levels by intensity level, city, job, use of plastic and cleaning method, and other experimental characteristics. The bullets below summarize some findings of interest from those analyses:

- Average paint lead levels were similar across the three intensity levels for both interior and exterior work. Average interior levels were 3 or 4 percent across the three levels for interior work and 11 to 13 percent across the three levels for exterior work (see Figure/Table G2.1a).
- Average paint lead levels differed a bit across jobs (see Figure/Table G2.3a). Average paint lead levels ranged from 2 to 5 percent across different interior jobs with dry scraping and kitchen gut/cabinet replacement having the lowest average levels. Average paint lead levels ranged from 5 to 32 percent across different exterior jobs with the needle gun, torching, and dry scraping being the only jobs averaging less than 10 percent. The low heat gun job on an exterior door and doorway at the school was the job with a paint lead average of 32 percent lead, much higher than the next highest single job average of 18 percent.
- Average paint lead level did not differ based on plastic use, cleaning method, or phase (see Figures/Tables G2.5a-2.7a).
- There appeared to be only a slight association between paint lead levels and average post-work floor lead loadings in the work room (see Figure G2.11).
- Paint lead levels and post-work soil lead levels after interior work appeared to have some association with an r-square of 0.11 (see Figure G2.14).

In addition to the average paint lead level, the amount of paint disturbed during the work was another factor that might influence the lead levels resulting from the job. Following work, field technicians recorded the approximate number of square feet that were disturbed by each job. Area disturbed ranged from 25 to 250 ft² across exterior jobs and 6 to 110 ft² across interior jobs. Appendix G, Section G3 explores the association of square footage disturbed with the various other study characteristics of interest. Findings of interest are listed below:

- Low level interior and exterior jobs disturbed significantly less area than the medium and high intensity jobs, which is consistent with the study design (see Figure/Table G3.1a)

- Of the interior jobs, the cut outs and window replacement jobs disturbed the least amount of paint (see Figure/Table G3.2a).
- Average area disturbed did not differ much based on plastic use, cleaning method, or phase (see Figures/Tables G3.5a-2.7a).
- For interior restricted jobs, average area disturbed was 61 ft² compared to 26 ft² for non-restricted jobs (see Figure/Table G3.8a).
- As seen in Figure 6-1 below, average area disturbed did appear to be associated with average post-work floor lead levels in the work room with an r-square of 0.28 (see also Figure G3.11). Average area disturbed may be associated with job intensity, since the disturbed area increased as the (initial) job intensity increased.




Figure 6-1. Scatter Plot of Area Disturbed Versus Average Post-work Work Room Floor Lead Loading

6.3. Pre-work Clearance Levels

The goal at the beginning of each experiment was to obtain values of <math><10 \mu\text{g}/\text{ft}^2</math> for all pre-work floor clearance samples and <math><62.5 \mu\text{g}/\text{ft}^2</math> for all pre-work window sill clearance samples. Because of study implementation issues such as some floors and sills that were difficult to clean and in poor condition, the pre-work clearance standards were changed to target an average of <math><40 \mu\text{g}/\text{ft}^2</math> for floors and <math><250 \mu\text{g}/\text{ft}^2</math> for sills, the current EPA clearance levels for lead in dust. For most experiments these targets were achieved; however, there were a few cases where they were not.

As seen in Table 6-4, which presents the average clearance levels for all experiments, there were three experiments that started with average work room floor lead levels above $40 \mu\text{g}/\text{ft}^2$, ranging from 44 to 151 $\mu\text{g}/\text{ft}^2$. Tool room and observation room floor lead levels started above $40 \mu\text{g}/\text{ft}^2$ once in each room type. Additionally, exit hallways started above $40 \mu\text{g}/\text{ft}^2$ four times. There were also a handful of cases where a window sill was used for sampling after failing to get below

clearance levels. For most experiments, dust collection trays replaced window sills when they were in poor condition or could not pass clearance.

Pre-work clearance levels did not appear to be associated with other endpoints. Within Appendix G, pre-work clearance levels are compared to average post-work lead levels and little or no correlation is evident with an r-square of 0.03 (see Figure G1.12). Figures C3.2a-c within Appendix C explore the correlation between pre-work clearance levels and post-work, post-cleaning, and post-verification floor lead levels. No correlation was apparent in any of the three rooms at any of the three sampling stages. Figures D3.2a-c within Appendix D present these analyses for sill lead levels with similar results.

Table 6-4. Summary of Pre-Work Clearance Information

| Exp. # | Job | Phase | Final Pre-work Floor Lead Levels | | | | | | | | Final Pre-work Sill Lead Levels ** | | | | | |
|--------|--------------|-------|----------------------------------|--------------------------|----------------------------|-------------|----------------------------|-------------|----------------------------|-------------|------------------------------------|-------------|----------------------------|-------------|----------------------------|-------------|
| | | | Work Room | | Tool Room | | Observ. Room | | Hallway | | Work Room | | Tool Room | | Observ. Room | |
| | | | Avg. (µg/ft ²) | # of Cleans [^] | Avg. (µg/ft ²) | # of Cleans | Avg. (µg/ft ²) | # of Cleans | Avg. (µg/ft ²) | # of Cleans | Avg. (µg/ft ²) | # of Cleans | Avg. (µg/ft ²) | # of Cleans | Avg. (µg/ft ²) | # of Cleans |
| 5 | Dry Scrape | I | 28.4 | 1 | 29.8 | 1 | 25.7 | 1 | <10 | 1 | 323.1 ^T | 1 | n/a | | 1,980 ^T | 1 |
| 6 | Dry Scrape | II | 27.4 | 2 | 15.3 | 1 | 22.1 | 1 | <10 | 1 | - | - | - | - | - | - |
| 7 | Dry Scrape | IV | 35.0 | 1 | 32.3 | 1 | 17.8 | 1 | <10 | 1 | - | - | - | - | - | - |
| 8 | Dry Scrape | III | 7.1 | 2 | 8.3 | 1 | <10 | 1 | <10 | 1 | - | - | - | - | - | - |
| 9 | Window Repl. | III | 30.0 | 2 | 10.5 | 1 | 19.6 | 1 | 20.6 | 1 | 120.8 | 2 | <10 | 1 | 58.5 | 2 |
| 10 | Window Repl. | IV | <10 | 1 | 55.8* | 1 | 44.7* | 1 | 8.4 | 1 | 30.9 | 1 | 756.9 ^T | 1 | 44 | 1 |
| 11 | Window Repl. | II | 6.8 | 3 | <10 | 1 | <10 | 2 | 4.1 | 1 | 46.3 | 1 | 7,737.4 ^T | 1 | 228.8 | 1 |
| 12 | Window Repl. | I | 43.9 | 2 | <10 | 1 | <10 | 1 | <10 | 1 | 346.9 ^T | 2 | 172.0 ^T | 1 | 404.7 ^T | 1 |
| 13 | Heat Gun | II | 10.4 | 1 | <10 | 1 | 8.7 | 1 | 57.6 | 1 | 18.3 ^T | 1 | 481.3 ^T | 1 | 80.5 ^T | 1 |
| 14 | Heat Gun | III | <10 | 2 | 28.2 | 1 | 32.5 | 1 | 9.9 | 1 | 1684.4 ^T | 1 | 1096.6 ^T | 1 | 74.7 ^T | 1 |
| 15 | Heat Gun | IV | <10 | 1 | <10 | 1 | <10 | 1 | 45.7 | 1 | 89.7 ^T | 1 | 453.3 ^T | 1 | 552.3 ^T | 1 |
| 16 | Heat Gun | I | <10 | 1 | <10 | 1 | <10 | 1 | 6.0 | 1 | 374.3 ^T | 1 | 1,828.1 ^T | 1 | 7.3 ^T | 1 |
| 22 | Cut-outs | IV | <10 | 1 | <10 | 1 | <10 | 1 | - | - | 61.1 | 1 | 960.6 ^T | 1 | 35.8 | 1 |
| 23 | Cut-outs | I | <10 | 1 | <10 | 1 | <10 | 1 | - | - | <15.9 | 1 | 73.3 | 1 | <20.0 | 1 |
| 24 | Cut-outs | III | <10 | 2 | 12.7 | 1 | 21.4 | 1 | - | - | <76.9 | 1 | 88.3 | 1 | 94 | 1 |
| 25 | Cut-outs | II | <10 | 1 | <10 | 1 | <10 | 1 | - | - | <15.9 | 1 | 63.2 | 1 | <20.0 | 1 |
| 26 | Dry Scrape | III | <10 | 1 | <10 | 1 | 8.7 | 1 | - | - | <20 | 1 | 143.7 | 1 | 24.4 | 1 |
| 27 | Dry Scrape | IV | <10 | 1 | <10 | 1 | <10 | 1 | - | - | 25.9 | 1 | 78.8 | 1 | 19.7 | 1 |
| 28 | Dry Scrape | I | <10 | 1 | <10 | 1 | <10 | 1 | - | - | <20 | 1 | 18.9 | 1 | 29.4 | 1 |
| 29 | Dry Scrape | II | <10 | 1 | <10 | 1 | <10 | 1 | - | - | <20 | 1 | <20 | 1 | 16.5 | 1 |
| 30 | Heat Gun | IV | 11.0 | 2 | <10 | 2 | <10 | 2 | 29.3 | 2 | - | - | - | - | - | - |
| 31 | Heat Gun | II | 17.8 | 2 | <10 | 2 | <10 | 2 | <10 | 2 | - | - | - | - | - | - |
| 32 | Heat Gun | III | 18.3 | 1 | <10 | 1 | <10 | 1 | 12.0 | 1 | - | - | - | - | - | - |
| 33 | Heat Gun | I | <10 | 1 | <10 | 1 | <10 | 1 | 10.0 | 1 | - | - | - | - | - | - |
| 41 | Window Repl. | I | <10 | 1 | <10 | 1 | <10 | 1 | - | - | <16.1 | 1 | 45.4 | 1 | <16.1 | 1 |
| 42 | Window Repl. | II | <10 | 1 | <10 | 1 | <10 | 1 | - | - | <16.1 | 1 | <16.1 | 1 | 13 | 1 |
| 43 | Window Repl. | IV | <10 | 1 | <10 | 1 | <10 | 1 | - | - | 20.2 | 1 | 65.3 | 1 | <16.1 | 1 |
| 44 | Window Repl. | III | <10 | 1 | <10 | 1 | <10 | 1 | - | - | 18.3 | 1 | <16.1 | 1 | <16.1 | 1 |
| 45 | Cut-outs | IV | 95.0 | 2 | 20.7 | 2 | 18.8 | 2 | - | - | 1,217.50 | 2 | 29.6 | 1 | <20.8 | 1 |
| 46 | Cut-outs | III | 19.0 | 2 | 39.3* | 1 | 146.1* | 1 | - | - | 336.8 ^T | 2 | 45.0 ^T | 1 | <20.8 ^T | 1 |
| 47 | Door Plane | IV | <10 | 1 | <10 | 1 | <10 | 1 | - | - | 107.1 | 1 | <10.9 | 1 | <1.8 | 1 |

Table 6-4. (continued) Summary of Pre-Work Clearance Information

| Exp. # | Job | Phase | Final Pre-work Floor Lead Levels | | | | | | | | Final Pre-work Sill Lead Levels ** | | | | | |
|--------|--------------|-------|----------------------------------|--------------------------|----------------------------|-------------|----------------------------|-------------|----------------------------|-------------|------------------------------------|-------------|----------------------------|-------------|----------------------------|-------------|
| | | | Work Room | | Tool Room | | Observ. Room | | Hallway | | Work Room | | Tool Room | | Observ. Room | |
| | | | Avg. (µg/ft ²) | # of Cleans [^] | Avg. (µg/ft ²) | # of Cleans | Avg. (µg/ft ²) | # of Cleans | Avg. (µg/ft ²) | # of Cleans | Avg. (µg/ft ²) | # of Cleans | Avg. (µg/ft ²) | # of Cleans | Avg. (µg/ft ²) | # of Cleans |
| 48 | Door Plane | I | 150.7 | 1 | 708.7* | 1 | 250.3* | 1 | - | - | 516.8 | 1 | 599.7 | 1 | 55.7 | 1 |
| 49 | Kitchen Gut | II | < 10 | 1 | < 10 | 1 | < 10 | 1 | - | - | <30.3 | 1 | - | - | <13.3 | 1 |
| 50 | Kitchen Gut | IV | < 10 | 1 | < 10 | 1 | < 10 | 1 | - | - | <30.3 | 1 | - | - | < 10 | 1 |
| 51 | Kitchen Gut | I | < 10 | 1 | < 10 | 1 | < 10 | 1 | - | - | <30.3 | 1 | - | - | 154.2 | 1 |
| 52 | Cut-outs | III | < 10 | 1 | < 10 | 1 | 19.3 | 1 | < 10 | 1 | - | - | - | - | - | - |
| 53 | Cut-outs | II | < 10 | 1 | < 10 | 1 | < 10 | 1 | 8.9 | 1 | - | - | - | - | - | - |
| 54 | Cut-outs | IV | < 10 | 1 | < 10 | 1 | < 10 | 1 | < 10 | 1 | - | - | - | - | - | - |
| 55 | Cut-outs | I | 6.8 | 1 | < 10 | 1 | < 10 | 1 | < 10 | 1 | - | - | - | - | - | - |
| 56 | Low Heat Gun | II | 7.9 | 1 | 10.8 | 1 | < 10 | 1 | < 10 | 1 | - | - | - | - | - | - |
| 57 | Low Heat Gun | IV | 6.8 | 1 | 8.6 | 1 | 8.6 | 1 | 12.3 | 1 | - | - | - | - | - | - |
| 58 | Low Heat Gun | III | 18.4 | 1 | 12.5 | 1 | 9.1 | 1 | < 10 | 1 | - | - | - | - | - | - |
| 59 | Low Heat Gun | I | 9.4 | 1 | 14.4 | 1 | < 10 | 1 | < 10 | 1 | - | - | - | - | - | - |
| 60 | Heat Gun | II | 14.1 | 1 | 82.0 | 1 | < 10 | 1 | < 10 | 1 | - | - | - | - | - | - |
| 61 | Heat Gun | III | 12.5 | 1 | 11.2 | 1 | < 10 | 1 | < 10 | 1 | - | - | - | - | - | - |
| 62 | Heat Gun | IV | < 10 | 1 | < 10 | 1 | < 10 | 1 | < 10 | 1 | - | - | - | - | - | - |
| 63 | Heat Gun | I | < 10 | 1 | < 10 | 1 | < 10 | 1 | < 10 | 1 | - | - | - | - | - | - |
| 67 | Kitchen Gut | I | < 10 | 1 | < 10 | 1 | < 10 | 1 | - | - | < 16.1 | 1 | 131.3 | 1 | < 16.1 | 1 |
| 68 | Kitchen Gut | III | < 10 | 1 | < 10 | 1 | <10 | 1 | - | - | 152.1 | 1 | 19.2 | 1 | 66.1 | 1 |
| 69 | Kitchen Gut | IV | < 10 | 1 | < 10 | 1 | <10 | 1 | - | - | 264.8 | 1 | 55.1 | 1 | < 15.4 | 1 |
| 70 | Kitchen Gut | II | 8.4 | 1 | < 10 | 1 | <10 | 1 | 69.2 | 1 | < 30.3 | 1 | - | - | 27.4 | 1 |
| 71 | Cut-outs | II | < 10 | 1 | 8.0 | 1 | < 10 | 1 | 141.1 | 1 | 22.4 | 1 | - | - | 28.9 | 1 |
| 72 | Cut-outs | I | < 10 | 1 | < 10 | 1 | < 10 | 1 | 17.2 | 1 | < 18.5 | 1 | - | - | < 13.2 | 1 |
| 73 | Door Plane | II | < 10 | 1 | < 10 | 1 | < 10 | 1 | <10 | 1 | <18.9 | 1 | - | - | 13.4 | 1 |
| 74 | Door Plane | III | < 10 | 1 | < 10 | 1 | < 10 | 1 | <10 | 1 | <14.5 | 1 | - | - | 23.2 | 1 |
| 76 | Kitchen Gut | III | < 10 | 1 | < 10 | 1 | < 10 | 1 | - | - | <30.3 | 1 | - | - | 404.6 ^T | 1 |
| 77 | Door Plane | II | 7.5 | 1 | < 10 | 1 | < 10 | 1 | - | - | 3,304.9 ^T | 1 | 25.4 | 1 | 25.1 | 1 |
| 78 | Door Plane | IV | 18.0 | 1 | < 10 | 1 | < 10 | 1 | - | - | 1,161.1 ^T | 1 | 90.5 | 1 | 10.4 | 1 |
| 79 | Door Plane | I | < 10 | 1 | < 10 | 1 | 48.9 | 1 | 8.2 | 1 | 1,691.9 ^T | 1 | 1,078.8 ^T | 1 | 104.7 | 1 |
| 80 | Door Plane | III | 9.6 | 1 | < 10 | 1 | 38.6 | 1 | 37.0 | 1 | 417.9 ^T | 1 | 7.8 | 1 | 7.4 | 1 |

* Clean plastic was put over the floor prior to the start of work

** Where the window sill clearance sample is missing (-), or has a 'T' (^T), a dust collection tray was used instead of the window sill

[^] # of Cleans represents the number of times that a unit was cleaned prior to an experiment. If one or more rooms did not pass clearance, re-cleaning and additional clearance testing was required.

6.4. Bulk Debris Samples

Many of the intensive renovation jobs generated large amounts of debris and dust. When larger pieces of debris and/or excessive dust were present, technicians collected it in a sample bag or container prior to collecting the dust wipe. For interior work, all these samples were taken in the work room during the post-work stage. For exterior work, all bulk samples were taken on top of the rule plastic. In later analyses, the bulk sample results are largely excluded from interior data analyses based on the concept that renovators would typically pick up larger debris and excessive dust. Table 6-5 contains a summary of the bulk debris samples collected on each interior job. Each bulk sample was collected from a specific sampling area, and the average lead in the wipes that correspond to those sampling areas is presented, as well. For the exterior analyses, descriptive analyses of the exterior dust results are presented both with and without the bulk debris samples. Table 6-6 contains summary data by job for the exterior jobs. Similar to the interior experiments, the average lead in the wipes represents the trays from which the bulk samples were collected.

Table 6-5. Interior Bulk Samples by Job Type

| Interior Job | # of Bulk Samples | Average Lead in Corresponding Wipes ($\mu\text{g}/\text{ft}^2$) | Average Lead in Bulk Sample ($\mu\text{g}/\text{ft}^2$) | Average Total Lead in Sample Area ($\mu\text{g}/\text{ft}^2$) |
|--------------------|-------------------|---|---|---|
| Cut-outs | 17 | 1,809.9 | 255,734.2 | 257,544.1 |
| Window Replacement | 8 | 10,771.1 | 84,976.4 | 95,747.5 |
| Dry Scrape | 19 | 7,659.4 | 1,946,557.5 | 1,954,216.9 |
| Door Plane | 19 | 59,802.2 | 1,685,459.9 | 1,745,262.0 |
| Low Heat Gun | 8 | 20,509.9 | 630,303.9 | 650,813.8 |
| Kitchen Gut | 9 | 3,362.7 | 74,610.1 | 77,972.8 |
| Heat Gun | 34 | 32,780.4 | 1,558,268.2 | 1,591,048.6 |
| TOTAL | 114 | 23,750.7 | 1,164,304.1 | 1,188,054.8 |

Table 6-6. Exterior Bulk Samples by Job Type

| Exterior Job | # Bulk Samples | Average Lead in Corresponding Wipes ($\mu\text{g}/\text{ft}^2$) | Average Lead in Bulk Sample ($\mu\text{g}/\text{ft}^2$) | Average Total Lead in Sample Area ($\mu\text{g}/\text{ft}^2$) |
|-----------------------|----------------|---|---|---|
| Replace Exterior Door | 1 | 5,285.9 | 212,025.0 | 217,310.9 |
| Trim Replacement | 3 | 58,423.5 | 2,087,562.2 | 2,145,985.6 |
| Needle Gun | 2 | 21,466.4 | 613,410.1 | 634,876.4 |
| Dry Scrape | 5 | 58,974.6 | 5,479,144.3 | 5,538,118.9 |
| Low Heat Gun | 4 | 65,883.5 | 34,193,430.5 | 34,259,314.0 |
| Power Sanding | 2 | 46,608.0 | 6,431,385.6 | 6,477,993.6 |
| High Heat Gun | 3 | 17,383.9 | 490,164.1 | 507,548.0 |
| Torching | 5 | 25,297.3 | 6,827,905.1 | 6,853,202.4 |
| TOTAL | 25 | 42,150.0 | 8,813,750.6 | 8,855,900.6 |

6.5. Interior Dust Samples

The exploratory analyses of the interior dust samples include data for both the housing units and COF combined. The bulk debris samples, which all were in the work room at the post-work stage, are not included in these analyses.

6.5.1. Interior Floor Samples

Appendix C contains numerous box plots, summary tables, and scatter plots of the interior floor dust lead loadings across the three study room. The bullets below list highlights of those analyses separately for the Work room and the Tool/Observation rooms.

Work Room

- Figure and Table C2.1a summarize the work room data by intensity level. The geometric means (GM) and medians for the medium intensity job are higher than the high intensity jobs at all three sampling stages. The low intensity jobs do have lower GMs and median floor lead levels compared to the other two intensity levels.
- Floor lead levels are similar between the work in Columbus and Pittsburgh, as seen in Figures and Tables C2.2a to C2.2c.
- The door planing and heat gun jobs >1100 degrees Fahrenheit jobs generated the highest amounts of post-work lead dust in the work room, as seen in Table C2.3.a and Figure 6-2 below.




Figure 6-2. Post-work Floor Lead Levels in the Work Room, by Job

- There are differences in work room floor lead levels across the three contractors that performed interior work with post-cleaning GMs ranging from 27 µg/ft² to 90 µg/ft² and post-verification GMs ranging 18 µg/ft² to 53 µg/ft². (Figure/Table C2.4a)
- When plastic protective sheeting was used as required in the proposed EPA rule, GM post-cleaning floor lead levels in the work room are 41 µg/ft² compared to 62 µg/ft² when

plastic was not used. Figure 6-3 compares work room post-cleaning floor lead levels by use of plastic and by job. Use of plastic did not lead to lower post-cleaning floor lead levels in the Work Room for all jobs.




Figure 6-3. Post-Cleaning Work Room Floor Lead Levels, By Job And Plastic Use

- When rule cleaning was performed following work, post-cleaning GM and median floor lead levels in the work room were lower (see Figure/Table C2.7a). Across all jobs, the GM post-cleaning lead level was 34 µg/ft² with rule cleaning and 75 µg/ft² with baseline cleaning. There is variability in this difference by job, as seen in Figure 6-4, but except for the door planing job, rule cleaning consistently achieved lower post-cleaning levels.




Figure 6-4. Post-Cleaning Work Room Floor Lead Levels, By Job And Cleaning Method

- Table C2.8a reports that the phases using rule cleaning (I and III) led to lower GM floor lead levels in the work room following post-work cleaning, with Phase IV (no plastic and baseline cleaning) having a GM nearly twice that of the nearest phase – 105 $\mu\text{g}/\text{ft}^2$ compared to 54 $\mu\text{g}/\text{ft}^2$ for baseline cleaning with plastic. When analyzing how the four phases compare, it is appropriate to use post-cleaning data for the baseline cleaning phases and post-verification data for the rule cleaning phases, since under the proposed rule the rule cleaning would be followed by the cleaning verification process. These data are referred to as “post-job” levels throughout this and subsequent analyses. Figure 6-5 compares those data for each job, illustrating the consistently lower levels achieved by the proposed rule practices compared to the baseline practices. Regarding the phases that combined rule and baseline practices, in five of seven jobs no plastic/rule cleaning achieved noticeably lower GM floor lead levels than plastic/baseline cleaning, indicating that rule cleaning may be more important than the use of plastic sheeting for lowering lead levels on floors in the Work Room. Large differences are evident for a few jobs such as heat gun over 1100 degrees with GM post-job floor lead levels of 36 $\mu\text{g}/\text{ft}^2$ using proposed rule methods and 445 $\mu\text{g}/\text{ft}^2$ using baseline methods.




Figure 6-5. Post-Job Work Room Floor Lead Levels, By Job And Phase

- When grouping jobs together by whether a restricted practice was used, the non-restricted practice jobs achieved significantly lower GM and median work room floor lead levels at each of the post-work, post-cleaning, and post-verification phases (see Figure/Table C2.9a).
- Higher lead levels were measured on wood floors compared to tile floors (see Figure/Table C2.10a); however, because the post-work levels are measurably higher on

wood floors, this may be correlated with the types of jobs done on wood floors and the paint lead level and square footage disturbed in those rooms.

- Similarly, floor in poor condition also had higher floor lead levels across the three sampling stages; however, because post-work levels are measurably higher, the differences at the subsequent two stages may be caused by higher intensity work (see Figure/Table C2.11a).
- There is some correlation between the average paint lead concentration of the components worked on and the work room floor lead levels measured at the three main sampling stages (see Figure C3.1a). R-square values range from 0.10 to 0.15 across the post-work to post-verification stages. Work room floor lead levels also appear to be correlated with average post-work work room floor lead levels (including bulk debris samples) with r-square values of 0.24 at post-cleaning and 0.16 at post-verification (see Figure C3.6a).
- Work room floor lead levels do not appear to be correlated with pre-work clearance levels, initial and final soil lead levels, and area disturbed.

Tool/Observation Rooms

- Similar to the Work room, the Medium intensity jobs led to a higher GM floor lead level in both the Tool and Observation rooms at all three sampling stages – post-work, post-cleaning, and post-verification (see Figure/Table C2.1b-c).
- Tool and Observation room floor lead levels vary by job performed, with the jobs leading to higher work room levels (Door planing and high heat gun) also having higher levels in the non-work rooms (see Figure/Table C2.3b-c).
- Lower GM floor lead levels were achieved with plastic than without plastic across the three sampling stages (see Figures/Tables C2.6b-c). On the other hand, the levels measured in the non-work rooms did not vary much based on cleaning method used (see Figures/Tables C2.7b-c). Thus, for Tool and Observation rooms, use of plastic sheeting for the Work Room as required by the Proposed Rule appears to be more important than the cleaning method used in the Work Room.
- Comparing proposed rule practices to baseline practices in the Tool room, post-job (post-cleaning for baseline cleaning phases and post-verification for rule cleaning phases) GM floor lead levels are 36 $\mu\text{g}/\text{ft}^2$ using proposed rule practices and 66 $\mu\text{g}/\text{ft}^2$ using baseline practices (see Table C2.8b). In the Observation room, post-job floor lead levels are 20 $\mu\text{g}/\text{ft}^2$ using proposed rule practices and 34 $\mu\text{g}/\text{ft}^2$ using baseline practices (see Table C2.8c).
- Figures 6-6 and 6-7 plot the post-job (post-cleaning for baseline cleaning phases and post-verification for rule cleaning phases) floor lead levels for Phase I and Phase IV by job. The differences in the non-work rooms become more pronounced in the higher intensity jobs. Further evidence of this is seen when comparing restricted practice jobs to non-restricted practice jobs (see Figure/Table C2.9b-c). The restricted practice jobs have higher GM floor lead levels across the three sampling stages in both non-work rooms, although the difference is larger in the Tool room.




Figure 6-6. Post-Job Tool Room Floor Lead Levels, By Job And Phase




Figure 6-7. Post-Job Observation Room Floor Lead Levels, By Job And Phase

- Tool and Observation room floor lead levels are not correlated with most of the continuous covariates considered (soil lead levels, paint lead levels, square footage); however they do appear to be correlated with post-work work room floor lead levels, i.e., the more lead dust stirred up by the work, the more lead dust escapes to nearby rooms (see Figures C3.6b-c).

6.5.2. Interior Sill Samples

Appendix D contains an identical set of exploratory analyses to that generated for the floor dust data. As seen in Table D1.1, a higher percentage of non-detect measurements was obtained for

the window sill data. For example, over 70 percent of Observation Room samples were below the detection limit at the post-cleaning and post-observation stages. Note that the sample sizes for most of the window sill samples were less than 1 square foot. With less surface area to work with on actual window sills and dust collection trays serving as window sills, the size of some sill samples is around 0.25-0.35 ft². With a reporting limit of 10 µg of lead and a sample size of .2 ft², the reported measurement would be <50 µg/ft². As noted earlier, half the detection limit was used for analysis purposes. Thus, a <50 µg/ft² sample was reported as 25 µg/ft² for the following analyses.

The bullets below contain selected results of interest from the detailed Appendix D analyses.

- The window sill data are much closer to a normal distribution following the log transformation (see Figures D1.1a-D1.3b). The large number of non-detects still skews the distribution, but use of the log-transformed data should be acceptable.
- The post-work sill samples in the Work room do not have a consistent relationship across sampling stages when analyzed by intensity level. At post-work, medium intensity jobs yielded higher sill levels; however at post-cleaning, the high level jobs yielded higher GM sill lead levels (see Figure/Table D2.1a).
- Jobs in Pittsburgh appear to have yielded higher sill lead levels across the three study rooms and all sampling stages than jobs in Columbus (see Figures/Tables D2.2a-D2.2c).
- The door planing job generated higher lead dust on window sills as measured at each sampling stage in all three study rooms (Figure/Tables D2.3a-D2.3c). Generally, the high heat gun job and window replacement job also led to somewhat higher levels than the other jobs.
- Contractor C2's jobs led to lower sill lead levels at all sampling stages across the three rooms (see Figure/Tables D2.4a-D2.4c). This may be correlated with the job types conducted by each contractor.
- The sill lead levels are highly variable across housing units. Unit H10 yielded much higher post-cleaning and post-verification sill lead levels in the work room with GMs of 4,067 µg/ft² and 1,367 µg/ft² at the two stages, respectively (see Figure/Tables D2.5a-D2.5c). The next highest GM at both stages in the Work room belonged to H08 at 367 µg/ft² and 196 µg/ft², respectively.
- Use of plastic is associated with lower post-cleaning and post-verification GM and median sill lead levels across all three rooms (see Figure/Tables D2.6a-D2.6c). Sill lead levels in the Tool room are also lower when plastic was used with a post-cleaning GM of 67 µg/ft² with plastic and 124 µg/ft² without plastic. When focused on post-cleaning levels by job in the Work room, five of seven jobs yielded similar or lower sill lead levels when plastic was used, as illustrated in Figure 6-8.



Figure 6-8. Post-Cleaning Work Room Sill Lead Levels, By Job And Plastic Use

- Use of rule cleaning appears to be associated with lower post-cleaning and post-verification sill lead levels in the Work room (see Figure/Tables D2.7a). Figure 6-9 displays Work room sill lead levels by job and cleaning method. Similarly, lower sill lead levels were found in the Tool room at all three sampling stages with GMs of 74, 81, and 54 µg/ft² across the three stages using rule cleaning and 117, 103, and 125 µg/ft² using baseline cleaning (see Figure/Tables D2.7b). Not much difference is observed in the Observation room by cleaning method (see Figure/Tables D2.7c).




Figure 6-9. Post-Cleaning Work Room Sill Lead Levels, By Job And Cleaning Method

Analyzing the work room sill lead levels by phase, the largest post-cleaning and post-verification differences are between Phases I and IV, with the proposed rule practices having the lowest GM and the baseline practices having the highest GM (see Figure/Tables D2.8a). Figure 6-10 presents the work room data from these two phases by job, using post-verification levels for Phase I and post-cleaning levels for Phase IV. Figure 6-11 presents the work room data for all four phases using post-verification levels for Phases I and III and post-cleaning levels for Phases II and IV. The largest differences are usually between the Proposed Rule Practices and the Baseline practices; however, in the dry scraping and high heat gun jobs, the plastic/baseline cleaning routine yielded higher GM sill lead levels than no plastic/baseline cleaning. [Note that there was only one Heat Gun < 1100°F experiment that used no plastic/rule cleaning and the corresponding post-verification window sill sample in the Work Room was not received by the laboratory, which explains the missing bar in Figure 6-11.]




Figure 6-10. Post-Job Work Room Sill Lead Levels, By Job And Rule Use




Figure 6-11. Post-Job Work Room Sill Lead Levels, By Job And Phase

- GM Tool room sill lead levels are also lower across the three sampling stages under the Proposed Rule Practices (Phase I) compared to the Baseline Practices (Phase IV) – 57 $\mu\text{g}/\text{ft}^2$ vs. 127 $\mu\text{g}/\text{ft}^2$ at post-work, 55 $\mu\text{g}/\text{ft}^2$ vs. 131 $\mu\text{g}/\text{ft}^2$ at post-cleaning, and 41 $\mu\text{g}/\text{ft}^2$ vs. 150 $\mu\text{g}/\text{ft}^2$ at post-verification. Figure 6-12 displays the post-work Tool room lead levels by job for these two phases.




Figure 6-12. Post-Job Tool Room Sill Lead Levels, By Job And Rule Use

- There is not as much difference between GM Observation room sill lead levels under the Proposed Rule Practices (Phase I) compared to the Baseline Practices (Phase IV) – 53 $\mu\text{g}/\text{ft}^2$ vs. 58 $\mu\text{g}/\text{ft}^2$ at post-work, 35 $\mu\text{g}/\text{ft}^2$ vs. 52 $\mu\text{g}/\text{ft}^2$ at post-cleaning, and 35 $\mu\text{g}/\text{ft}^2$ vs. 49 $\mu\text{g}/\text{ft}^2$ at post-verification (see Figure/Table D2.8c). Figure 6-13 displays the post-job Observation room lead levels by job for these two phases. There are mostly minor differences in the non-restricted practice jobs, whereas the Proposed Rule Practices appear to have led to lower post-job lead levels from the restricted practice jobs.




Figure 6-13. Post-Job Observation Room Sill Lead Levels, By Job And Rule Use

- Use of restricted practices is associated with higher GM sill lead levels in each of the three study rooms. Note that the use of restricted practices yielded higher post-work sill lead levels, which translated to higher post-cleaning and post-verification levels, as well (see Figure/Tables D2.9a-D2.9c).

6.5.3. Hallway/Exit Samples

The study design specified collection of three samples at the end of each experiment along the path from the work room to the entrance used by workers. These samples provide data on both the track-in of lead dust from the outside and tracking of lead dust from the work room through the house as workers enter and exit. The location of the samples was not pre-specified in sampling plans. Technicians were instructed to obtain one sample near the entrance of the house, one from an area closer to the work room, and one in between. In houses where work was done on the second floor, the hallway samples were generally taken from the bottom of the steps, near the entrance, and in between these two areas. The samples were taken following the collection of all post-verification samples in the three main study rooms. At this point, the workers would have removed most if not all of their job-related equipment, and remaining traffic through the house mainly involved removal of study-related equipment.

Appendix H contains a set of exploratory analyses similar to those generated for the other data types. As with the other dust wipe data, the data were log-transformed to get closer to a normal distribution. The bullets below present some key results seen in Appendix H.

- Higher lead levels are seen in exit samples taken after medium intensity jobs with a GM of 507 $\mu\text{g}/\text{ft}^2$ for medium intensity jobs compared to 212 $\mu\text{g}/\text{ft}^2$ for high intensity and 73 $\mu\text{g}/\text{ft}^2$ for low intensity (see Figure/Table H2.1a).
- The GM exit sample lead level for Door Planing jobs was 500 $\mu\text{g}/\text{ft}^2$, much higher than all other jobs (see Figure/Table H2.3a). GMs of the other six jobs range from 21 to 83 $\mu\text{g}/\text{ft}^2$, with the high heat gun job having the next highest level below the door planning job.
- As seen in Figure/Table H2.6a, there is little difference in GM lead levels between jobs that used plastic in the Work room during the work (67 $\mu\text{g}/\text{ft}^2$) and those that did not (69 $\mu\text{g}/\text{ft}^2$).
- The difference in GM lead levels is relatively small between jobs using rule cleaning (59 $\mu\text{g}/\text{ft}^2$) compared to jobs using baseline cleaning (78 $\mu\text{g}/\text{ft}^2$).
- The baseline practices (no plastic/baseline cleaning) yielded higher GM exit levels of 88 $\mu\text{g}/\text{ft}^2$ compared to a range of 55 $\mu\text{g}/\text{ft}^2$ to 69 $\mu\text{g}/\text{ft}^2$ for the other three P/CU routines (see Figure/Table H2.8a).
- Higher hallway lead levels were measured following restricted practice jobs compared to non-restricted jobs with GM of 136 $\mu\text{g}/\text{ft}^2$ versus 34 $\mu\text{g}/\text{ft}^2$ (see Figure/Table H2.9a).
- When the work room floors were in poor condition, hallway lead levels were higher than when work room floors were in good condition with GMs of 143 $\mu\text{g}/\text{ft}^2$ for poor condition floors and 18 $\mu\text{g}/\text{ft}^2$ for floors in good condition (see Figure/Table H2.11a).
- Hallway/exit lead levels were not associated with pre-work or post-work soil lead levels (see Figures H3.4 and H3.5).
- Hallway/exit lead levels do appear to be correlated with average post-work work room floor lead levels with an r-square value of 0.11 (see Figure H3.7).

6.5.4. Exterior Post-Work Tray Samples During Window Replacements

For the experiments where a window was replaced from the interior of a housing unit, one dust collection tray was placed for sampling on top of plastic sheeting on the exterior of the unit, directly below the window. This sampling was done to evaluate potential exterior contamination when performing a window replacement from the inside of the house. Prior to conducting the window replacements, the RRP workers covered the window with plastic from the outside to prevent falling debris from contaminating the ground below. After the replacement was finished, the RRP workers carefully removed the exterior plastic sheeting. The dust collection tray was sampled immediately after the work was completed and the plastic removed. The results of those exterior dust collection tray samples are shown in Table 6-7. The results are not consistent, even when considering variability due to contractor, housing unit, and tray location. For experiments 11 and 42, a significant amount of debris was observed falling from a pocket at the

bottom of the external plastic sheeting when the RRP workers were removing it. The debris fell onto the ground covering and into the dust collection tray. For some of the other experiments, small paint chips were present in the tray when sampled, but no significant debris was observed falling out of the protective plastic.

Table 6-7. Exterior Dust Wipe Samples During Window Replacement

| Experiment | Concentration ($\mu\text{g}/\text{ft}^2$) | Location |
|------------|--|--------------------------------------|
| 9 | 291.2 | Porch roof under second story window |
| 10 | 232 | Porch roof under second story window |
| 11 | 31,715.1 | Ground under second story window |
| 12 | 11.6 | Ground under second story window |
| 41 | 17.0 | Porch floor under first story window |
| 42 | 20,590.9 | Porch floor under first story window |
| 43 | 43.6 | Porch floor under first story window |
| 44 | 338.2 | Porch floor under first story window |

6.6. Interior Air Samples

Indoor air samplers collected samples during each work stage (work, cleaning, and cleaning verification) in each of the three study rooms. The work and cleaning stages included a one-hour wait time following completion of activity to allow settling of airborne dust. The air monitors operated from the beginning of the activity until the end of the one-hour wait time. Field technicians recorded information on flow rate at the beginning and end of the sampling period in order to calculate a mean flow rate. In a few cases, multiple air filters were needed during a single sampling stage because of a filter getting clogged with dust. In these cases, the concentrations obtained for the two samples were averaged and that value used in subsequent analyses.

Appendix F contains detailed exploratory analyses of the indoor air filter samples. Laboratory analysis of the air filter samples had a $2 \mu\text{g}$ detection limit. With many of the filters not running for long, e.g. during the cleaning verification stage that sometimes only lasted 10-15 minutes, this made it more challenging to measure enough lead to be over the detection limit. Additionally, with only small amounts of air monitored, laboratory measurements are relatively variable. Reported levels range anywhere from <2.7 to <20 to $<666 \mu\text{g}/\text{m}^3$. Table 6-8 (also Table F1.1) presents the number and percentage of samples that contained lead below the detection limit. Appendix F presents analyses using the half the reporting limit for each sample that was below the detection limit; thus, the three example values listed above are included as 1.35, 10, and $333 \mu\text{g}/\text{m}^3$ in the analyses.

Table 6-8. Number (and Percentage) of Interior Air Dust Lead Concentration Measurements ($\mu\text{g}/\text{m}^3$) Below Detection Limit Measurements by Room and Stage

| Stage | Room | | |
|-------------------|------------|------------|-------------|
| | Work | Tool | Observation |
| Post-Work | 29 (48.3%) | 43 (71.7%) | 45 (75.0%) |
| Post-Cleaning | 50 (82.0%) | 53 (88.3%) | 54 (90.0%) |
| Post-Verification | 59 (98.3%) | 59 (98.3%) | 58 (96.7%) |

Below are a few findings from the air lead analyses. Since the Tool and Observation rooms have at most 28% reported values in any given stage, no results from those analyses are presented. Similarly, because the post-cleaning and post-verification data in the Work room have no more than 18 percent reported measurements, no results from those analyses are discussed. Because the post-work stage in the work room is the only set of data with more than half of its values actually being reported measurements, only those data are discussed.

- Air lead concentrations in the work room during Medium intensity jobs were higher than the High and Low intensity jobs.
- The finding regarding intensity level is driven largely by the door planing job, which has a GM air lead concentration far greater than any other job – $300 \mu\text{g}/\text{m}^3$ compared to the next highest job, heat gun above 1100 degrees, with $13 \mu\text{g}/\text{m}^3$ (see Figure/Table F2.3a).
- The GM work room air lead level when plastic was used is higher than when plastic was not used - $12 \mu\text{g}/\text{m}^3$ compared to $8 \mu\text{g}/\text{m}^3$ (see Figure/Table F2.6a).
- The GM work room air lead level was higher during restricted practice jobs than other jobs, which is not surprising since the door planing is defined as a restricted practice job (see Figure/Table F2.9a). Figure 6-14 plots air lead concentrations for each job.




Figure 6-14. Post-work Air Lead Concentration in the Work Room, by Job

6.7. Exterior Dust Samples

The exterior study design specified collection of three types of dust collection tray samples – on the Rule plastic, under-the-Rule plastic, and near-the-Rule plastic. Three samples were obtained from each location during each experiment. The size of the Rule plastic varied from job to job. The proposed rule does not identify specific areas of ground to be covered during exterior work, so the size of the rule plastic was determined for each experiment within the constraints of the dimensions of the property being worked on and the need to collect samples near the Rule plastic as well. For this study, vertical containment and additional ground plastic were set up as a precaution to capture dust and debris that might not be captured on the Rule plastic. Table 6-9 contains distances from the work location for all on and near Rule plastic samples, as well as associated results. The under Rule plastic samples were obtained from similar locations to those used for the on Rule plastic samples.

Table 6-9. Distance of Exterior Trays from Work.

| Exp. # | Job Type | Unit ID | Sample # | On top of Rule Plastic | | Near Rule Plastic | |
|--------|-----------------------|---------|----------|--|----------------------|--|------------------------|
| | | | | Loading* ($\mu\text{g}/\text{ft}^2$) | Dist. From Work (ft) | Loading* ($\mu\text{g}/\text{ft}^2$) | Dist. From Work (ft)** |
| 1 | Dry Scrape | H01 | 1 | 12,516,130.5 | 1 | 4,178.0 | 8 |
| | | | 2 | 50,819.0 | 5 | 953.0 | 12 |
| | | | 3 | 8,556.0 | 7 | 929.0 | 17 |
| 2 | Power Sanding | H01 | 1 | 4,666,775.9 | 1 | 58,718.0 | 15 |
| | | | 2 | 341,492.0 | 5 | 85,985.0 | 14 |
| | | | 3 | 106,383.0 | 11 | 65,719.0 | 12 |
| 3 | Power Sanding | H01 | 1 | 8,289,211.2 | 3 | 18,002.0 | 14 |
| | | | 2 | 234,877.0 | 8 | 9,865.0 | 17 |
| | | | 3 | 129,738.0 | 12 | 16,905.0 | 15 |
| 4 | Trim Replacement | H02 | 1 | 4,109.0 | 2 | 61,388.0 | 5 |
| | | | 2 | 1,652,382.1 | 1 | 27,082.0 | 6 |
| | | | 3 | 115,207.0 | 2 | 54,851.0 | 5 |
| 21 | Dry Scrape | H09 | 1 | 1,463,973.8 | 1 | 274.0 | 13 |
| | | | 2 | 2,357.0 | 7 | 172.0 | 18 |
| | | | 3 | 417.0 | 11 | 574.0 | 15 |
| 34 | Replace Exterior Door | H16 | 1 | 217,310.9 | 1 | 31,708.0 | 6 |
| | | | 2 | 79,163.0 | 3 | 84,290.0 | 6 |
| | | | 3 | 14,441.0 | 3 | 1,129.0 | 6 |
| 35 | Replace Exterior Door | H17 | 1 | 30,060.0 | 1 | 3,793.0 | 5 |
| | | | 2 | 43,976.0 | 1 | 30,426.0 | 5.5 |
| | | | 3 | 151,734.0 | 1 | 17,590.0 | 5.5 |
| 36 | Trim Replacement | H10 | 1 | 161,018.0 | 3 | 19,278.0 | 7 |
| | | | 2 | 2,991,198.3 | 2 | 133,690.0 | 7 |
| | | | 3 | 1,794,376.6 | 2 | 217,900.0 | 7 |
| 37 | Torching | H10 | 1 | 1,134,828.9 | 4.5 | 150.0 | 15 |
| | | | 2 | 956.0 | 12 | 198.0 | 15 |
| | | | 3 | 349,643.9 | 10 | 151.0 | 15 |
| 38 | Torching | H13 | 1 | 29,401,680.1 | 2 | 658.0 | 16.5 |
| | | | 2 | 1,560,303.3 | 10.5 | 1,836.0 | 16.5 |
| | | | 3 | 1,819,556.0 | 9 | 1,093.0 | 16.5 |

Table 6-9. (continued) Distance of Exterior Trays from Work.

| Exp. # | Job Type | Unit ID | Sample # | On top of Rule Plastic | | Near Rule Plastic | |
|--------|---------------|---------|----------|--|----------------------|--|------------------------|
| | | | | Loading* ($\mu\text{g}/\text{ft}^2$) | Dist. From Work (ft) | Loading* ($\mu\text{g}/\text{ft}^2$) | Dist. From Work (ft)** |
| 40 | Dry Scrape | H19 | 1 | 14,348.0 | 6 | 7,596.0 | 11 |
| | | | 2 | 11,480,352.4 | 2 | 12,169.0 | 9 |
| | | | 3 | 268,359.2 | 4 | 16,597.0 | 10 |
| 64 | Low Heat Gun | C01 | 1 | 130,674,044.8 | 1 | 2,692,069.2 | 7 |
| | | | 2 | 1,133,090.0 | 5 | 27,650.0 | 8 |
| | | | 3 | 2,538,052.1 | 3 | 16,884.0 | 7 |
| 65 | Needle Gun | C01 | 1 | 381,586.2 | 3 | 21,158.0 | 6 |
| | | | 2 | 22,004.0 | 1 | 8,768.0 | 6 |
| | | | 3 | 888,166.7 | 2 | 1,380.0 | 12 |
| 66 | High Heat Gun | C01 | 1 | 196,759.9 | 7 | 14,689.0 | 11 |
| | | | 2 | 494,822.3 | 5 | 331.0 | 16 |
| | | | 3 | 831,062.0 | 3 | 363.0 | 13 |
| 75 | Dry Scrape | H09 | 1 | 1,961,778.8 | 1 | 1,205.0 | 8 |
| | | | 2 | 14,345.0 | 4 | 190.0 | 15 |
| | | | 3 | 1,845.0 | 7 | 488.0 | 12 |

* Where applicable, the loading represents the sum of the dust wipe plus the bulk sample.

** Distance from work represents the perpendicular distance from the work wall/area to the collection tray

Appendix B contains detailed exploratory analyses of the exterior tray samples by location summarized by intensity level, city, job, contractor, and housing unit. The bulk debris samples are included in these analyses. Appendix E contains the same analyses, but excludes the bulk debris samples. Figures B1.1a-1.3b and Figures E1.1a-1.3b display histograms of the raw and log-transformed data collected for each location – on, under, and near Rule plastic. The log-transformation does lead to a data more closely approximating normality. The following bullets describe selected findings observed from Appendices B and E:

- The GM and median lead levels measured on the Rule plastic across all jobs is much higher than the other two locations with GM of 241,977 $\mu\text{g}/\text{ft}^2$ and median 268,359 $\mu\text{g}/\text{ft}^2$, compared to GM of 479 $\mu\text{g}/\text{ft}^2$ and median of 322 $\mu\text{g}/\text{ft}^2$ under-the-Rule plastic and GM of 5,771 $\mu\text{g}/\text{ft}^2$ and median of 9,865 $\mu\text{g}/\text{ft}^2$ near-the-Rule plastic. Excluding the bulk debris samples reduced the top of Rule plastic GM to 21,292 $\mu\text{g}/\text{ft}^2$ and median to 22,004 $\mu\text{g}/\text{ft}^2$. No bulk debris samples were collected near or under rule plastic.
- The high intensity jobs resulted in higher GM lead levels on and under-the-Rule plastic, when the bulk samples are included, but the high and low level jobs have similar GMs when bulk samples are excluded. The low level jobs yielded higher levels near-the-Rule plastic (see Figure/Tables B2.1a-c). A possible explanation for this is that the Rule plastic covered less area in the low-level jobs (trim/soffit and door replacements and needle gun) because of space constraints.
- The low heat gun job yielded the bulk samples with the most amount of lead, which gave this job a much higher GM on the Rule plastic than all other jobs. With bulk samples excluded, the power sanding job yielded a much higher GM on the Rule plastic. Figures 6-15 and 6-16 present the on and under Rule plastic samples both with and without the bulk debris samples, respectively, by each job. All jobs yielded much higher

lead levels on the plastic than under the plastic regardless of whether the bulk samples are included, except the torch burning job. The torching job has a GM on the Rule plastic of 562,462 $\mu\text{g}/\text{ft}^2$ with the bulk samples included and only 5,447 $\mu\text{g}/\text{ft}^2$ with the bulk samples excluded. The GM of the under Rule plastic samples for the torching jobs is 8,565 $\mu\text{g}/\text{ft}^2$.




Figure 6-15. Exterior Dust Lead Levels On and Under Rule Plastic, by Job (w/ Bulk Samples)




Figure 6-16. Exterior Dust Lead Levels On and Under Rule Plastic, by Job (excl. bulk samples)

- There does appear to be an association between paint lead levels and lead levels measured on and near-the-Rule plastic with r-square values of 0.16 and 0.17, respectively (see Figure B3.1). No association between paint lead level and under Rule plastic samples was found.
- No association is observed between initial soil lead levels and lead measured in any of the three exterior tray locations (see Figure B3.2). While no association is observed between post-work soil lead levels and lead measured on or under Rule plastic, there does appear to be some correlation between post-work soil levels and lead levels measured in trays near-the-Rule plastic (see Figure B3.3).
- There does not appear to be an association between amount of area disturbed by the RRP work and lead measured at any of the three locations (see Figure B3.4).

Prior to performing exterior experiments, one or more dust collection trays were set out in the area of the rule plastic to measure the background concentration of lead at the property. The number of samples collected for each job type and associated lead levels are presented in Table 6-10. In the instances where more than one experiment was performed at the same unit (e.g. the trim replacement and torching at H10), the results of the background tray(s) are included for both experiments.

Table 6-10. Average Background Dust Loading for Exterior Experiments, by Job Type

| Exterior Job | # Samples | Average Background Lead Level ($\mu\text{g}/\text{ft}^2$) |
|-------------------------|------------------|---|
| Trim Replacement | 6 | 13.9 |
| Door Replacement | 6 | < 9.6 |
| Dry Scrape | 5 | 16.4 |
| Power Sanding | 2 | 51.2 |
| Torching | 6 | 32.8 |

6.8. Soil Samples

6.8.1. Soil Sampling for Interior Jobs

For interior experiments, soil samples were collected before work began and again after work was completed at three sampling locations: near the main entrance to the unit used during the experiment, near the path traveled by the workers and study personnel from their vehicles to the unit, and from the ground immediately below a window that led into the Work Room. See Table 6-11 for the all soil lead measurements for each interior experiment. The soil samples were collected to evaluate the possible contamination of the soil by study activities, as well as to get an idea of the potential track-in from the outside. There was no soil or dirt at any of the sampling locations for H31, H32, H33, H36 and C01, thus no soil samples were collected for experiments performed at those units.

Table 6-11. Pre- and Post-Work Soil Sample Results (µg/g) by Interior Experiment

| | 05 - H03 | | 06 - H03 | | 07 - H03 | | 08 - H03 | | 09 - H09 | | 10 - H09 | |
|---------------|----------|-----------|----------|-----------|----------|-----------|----------|-----------|----------|-----------|----------|-----------|
| | Pre-Work | Post-Work |
| Near Entrance | 903 | 1,635 | 1,635 | 737 | 737 | 856 | 856 | 709 | 679 | 391 | 391 | 408 |
| Near Path | 96 | 125 | 125 | 129 | 129 | 86 | 86 | 74 | 401 | 273 | 273 | 317 |
| Under Window | 141 | 385 | 385 | 288 | 288 | 44 | 44 | 105 | 705 | 700 | 700 | 2,077 |
| | 11 - H09 | | 12 - H09 | | 13 - H09 | | 14 - H09 | | 15 - H09 | | 16 - H09 | |
| | Pre-Work | Post-Work |
| Near Entrance | 5,551 | 2,245 | 3,460 | 2,508 | 5,006 | 2,074 | 4,540 | 3,348 | 3,026 | 5,352 | 2,508 | 8,044 |
| Near Path | 276 | 229 | 343 | 291 | 241 | 289 | 367 | 288 | 323 | 230 | 291 | 268 |
| Under Window | 10,361 | 11,226 | 1,746 | 2,117 | 2,411 | 2,845 | 10,097 | 8,643 | 5,672 | 15,150 | 2,117 | 2,442 |
| | 22 - H16 | | 23 - H16 | | 24 - H17 | | 25 - H16 | | 26 - H17 | | 27 - H17 | |
| | Pre-Work | Post-Work |
| Near Entrance | 1,213 | 910 | 910 | 485 | 752 | 677 | 485 | 575 | 616 | 571 | 571 | 685 |
| Near Path | 408 | 429 | 429 | 286 | 334 | 204 | 286 | 274 | 213 | 272 | 272 | 287 |
| Under Window | 1,136 | 1,410 | 1,410 | 1,772 | 622 | 564 | 1,772 | 2,355 | 644 | 911 | 911 | 613 |
| | 28 - H17 | | 29 - H17 | | 30 - H10 | | 31 - H10 | | 32 - H10 | | 33 - H10 | |
| | Pre-Work | Post-Work |
| Near Entrance | 685 | 286 | 286 | 1,105 | 1,230 | 929 | 2,258 | 1,033 | 1,033 | 957 | 957 | 886 |
| Near Path | 287 | 652 | 652 | 329 | 773 | 940 | 700 | 426 | 426 | 877 | 877 | 544 |
| Under Window | 613 | 541 | 541 | 879 | n/a | 1,441 | n/a | 4,031 | 4,031 | 1,505 | 1,505 | 1,154 |
| | 41 - H16 | | 42 - H16 | | 43 - H17 | | 44 - H17 | | 45 - H08 | | 46 - H08 | |
| | Pre-Work | Post-Work |
| Near Entrance | 8,120 | 8,167 | 8,167 | 2,921 | 529 | 622 | 622 | 1,138 | 359 | 308 | 308 | 940 |
| Near Path | 457 | 399 | 399 | 473 | 278 | 203 | 203 | 542 | 133 | 146 | 146 | 121 |
| Under Window | n/a | 386 | 386 | 444 | n/a | 521 | 521 | 346 | 367 | 336 | 336 | 519 |
| | 47 - H08 | | 48 - H08 | | 67 - H16 | | 68 - H17 | | 69 - H08 | | 70 - H35 | |
| | Pre-Work | Post-Work |
| Near Entrance | 450 | 390 | 390 | 359 | 575 | 1,178 | 677 | 616 | 940 | 347 | 496 | 383 |
| Near Path | 218 | 170 | 170 | 133 | 274 | 344 | 204 | 213 | 121 | 118 | 411 | 355 |
| Under Window | 482 | 204 | 204 | 367 | 2,355 | 3,650 | 564 | 644 | 519 | 416 | 752 | 478 |
| | 71 - H35 | | 72 - H35 | | 73 - H35 | | 74 - H35 | | 77 - H08 | | 78 - H08 | |
| | Pre-Work | Post-Work |
| Near Entrance | 471 | 413 | 413 | 772 | 383 | 476 | 476 | 471 | 347 | 395 | 395 | 311 |
| Near Path | 481 | 500 | 500 | 502 | 355 | 337 | 337 | 481 | 118 | 175 | 175 | 139 |
| Under Window | 554 | 567 | 567 | 1,260 | 478 | 426 | 426 | 554 | 416 | n/a | n/a | 478 |
| | 79 - H09 | | 80 - H09 | | | | | | | | | |
| | Pre-Work | Post-Work | Pre-Work | Post-Work | | | | | | | | |
| Near Entrance | 684 | 1,659 | 1,659 | 3,098 | | | | | | | | |
| Near Path | 35 | 49 | 49 | 308 | | | | | | | | |
| Under Window | 11,121 | 16,547 | n/a | 1,387 | | | | | | | | |

If work was performed in the same unit within the same Work Room, the post-work soil samples from the previous experiment were used as the pre-work soil samples for the next experiment. For two experiments performed at H09 and one experiment each at H16 and H17, the Work Room changed from experiment to experiment and pre-soil samples were not collected to correspond to the correct Work Room window. At H10, exterior experiments were performed alternately with interior experiments, resulting in two experiments where there were no pre-work soil samples collected under the Work Room window, and the post-work sample of the previous experiment could not be used due to possible contamination by the exterior experiment.

The samples collected near the main entrance and under the Work Room window were typically higher than the near path samples, due to their proximity to the foundation of the house. Large variations in the lead content of the soil were observed when samples were collected within the same general area. When examining an increase from pre-work soil lead to post-work soil lead, the variability became evident as subsequent samples collected in the same location were consistent with the lower, pre-work samples. An example of this for samples collected near the front porch of H09 is given in Figure 6-17. In cases where post-work samples were collected in the same general area but different locations than the pre-work samples, it is difficult to discern the change due to natural variability and change due to study activities.




Figure 6-17. Time series of soil samples near the front porch at H09. These samples correspond to the near entrance samples and some under the Work Room window samples. Where more than one sample is collected on the same day, the plot shows whether the sample was pre-work or post-work.

Table 6-12 lists the number of collected samples and average post-work to pre-work soil lead level ratio. Instances where the two samples were collected from inconsistent locations are not included in this table. The job type, job intensity, and sample location do not appear to play a significant role in determining the change in soil lead level. This table also depicts the effect of variability as some locations across the study experienced an overall decrease in soil lead levels.

Table 6-12. Average Post-work/Pre-work Ratios for Interior Work Soil Samples, by Job Type

| Interior Job | Near Main Entrance | | Near Path | | Under Work Room Window | |
|--------------------|--------------------|-------|-----------|-------|------------------------|-------|
| | # | Ratio | # | Ratio | # | Ratio |
| Cut-outs | 8 | 1.25 | 8 | 0.91 | 8 | 1.30 |
| Window Replacement | 8 | 0.89 | 8 | 1.12 | 6 | 1.35 |
| Dry Scrape | 8 | 1.33 | 8 | 1.12 | 8 | 1.33 |
| Door Plane | 8 | 1.28 | 8 | 1.74 | 5 | 1.18 |
| Kitchen Gut | 4 | 1.02 | 4 | 1.03 | 4 | 1.03 |
| Heat Gun | 8 | 1.15 | 8 | 1.02 | 6 | 1.17 |

Figures C3.3a-c and C3.4a-c within Appendix C plot pre-work and post-work soil lead levels, respectively, against floor dust lead loadings in the work, tool, and observation rooms. Little if any association is evidenced from these plots between soil lead levels and interior floor lead levels. The highest r-square value (.06) is seen in Figure C3.4a showing slight association between post-work soil lead level and post-cleaning floor lead levels in the work room. Identical analyses are presented in Figures D3.3a-c and D3.4a-c for sill lead levels and no correlation between sill lead levels and soil lead levels is indicated.

There is some evidence of correlation between paint lead levels in the work room and soil lead levels. Within Appendix G, Figures G2.13 and G2.14 plot pre-work and post-work soil lead levels, respectively, by average paint lead levels. The association between pre-work soil lead and average paint lead yielded an r-square of .08 while the association between post-work soil lead and average paint lead yielded an r-square of 0.11.

6.8.2. Soil Sampling for Exterior Jobs

Similar to the interior experiments, soil samples were collected for all exterior experiments at three distinct locations: near the foundation of the house, near the back edge of the rule containment plastic, and near the back edge of the plastic used for property containment purposes. See Table 6-13 for the actual soil lead levels for each exterior experiment. These soil samples were collected to evaluate the possible contamination of the soil resulting from study activities. The samples collected near the foundation of the house were generally higher than the other locations, as the deteriorating paint from house components are more likely to collect there. For H02, H16 and H17, there were no soil samples collected near the foundation due to a concrete sidewalk resting against the house.

Table 6-13. Pre- and Post-Work Soil Sample Results (µg/g) for Exterior Experiments

| | 01 - H01 | | 02 - H01 | | 03 - H01 | | 04 - H02 | | 21 - H09 | |
|----------------------------------|----------|-----------|----------|-----------|----------|-----------|----------|-----------|----------|-----------|
| | Pre-Work | Post-Work |
| Near Foundation | 2,347 | 2,880 | 2,733 | 16,540 | 4,590 | 1,782 | n/a | n/a | 657 | 373 |
| Near Edge of Rule Plastic | 371 | 853 | 111 | 279 | 422 | 480 | 218 | 253 | 352 | 1,882 |
| Near Edge of Containment Plastic | 299 | 480 | 178 | 97 | 258 | 336 | 194 | 147 | 550 | 467 |
| | 34 - H16 | | 35 - H17 | | 36 - H10 | | 37 - H10 | | 38 - H13 | |
| | Pre-Work | Post-Work |
| Near Foundation | n/a | n/a | n/a | n/a | 1,075 | 1,230 | 181 | 2,258 | 1,123 | 1,529 |
| Near Edge of Rule Plastic | 2,953 | 8,120 | 562 | 529 | 944 | 773 | 548 | 700 | 543 | 678 |
| Near Edge of Containment Plastic | 438 | 457 | 294 | 278 | 316 | 358 | 213 | 335 | 439 | 416 |
| | 40 - H19 | | 75 - H09 | | | | | | | |
| | Pre-Work | Post-Work | Pre-Work | Post-Work | | | | | | |
| Near Foundation | 3,164 | 4,522 | 373 | 382 | | | | | | |
| Near Edge of Rule Plastic | 306 | 371 | 1,882 | 1,592 | | | | | | |
| Near Edge of Containment Plastic | 146 | 226 | 467 | 434 | | | | | | |

Variability in the soil lead levels also played a role in the change in pre-work to post-work soil samples for exterior experiments. Samples were sometimes not collected at the same location, making it more difficult to determine the study effect. The number of collected samples and average post-work to pre-work exterior soil lead level ratio for each sampling location, by job, are contained in Table 6-14. Note that the exterior experiments were only performed two or four times, so the averages include a small number (1-2) of values. The largest change is observed near the foundation, while the medium and high level jobs appear to have a larger change in soil lead than the low intensity jobs.

Table 6-14. Ratio of Post-work to Pre-work Soil Lead Level in Exterior Soil Samples, by Job Type

| | Near Foundation | Near Edge of Rule Plastic | Near Edge of Containment Plastic |
|------------------|-----------------|---------------------------|----------------------------------|
| Trim Replacement | 1.144 | .990 | .945 |
| Door Replacement | n/a | 1.846 | .994 |
| Dry Scrape | 2.124 | 4.852 | 2.466 |
| Power Sanding | 3.220 | 1.825 | .924 |
| Torching | 6.918 | 1.263 | 1.260 |

6.9. Length of Activity Data

Field technicians recorded the length of time required to perform various activities throughout each experiment including pre-work set up, renovation work, post-work cleaning, and cleaning verification. The tables included below present summary data on cleaning and cleaning verification activities.

6.9.1. Duration of Post-work Cleaning

The summary data on post-work cleaning times does indicate a small difference in the length of time required to conduct Rule and baseline cleaning – an average of 45 minutes for rule cleaning and 36 minutes for baseline cleaning. Table 6-15 indicates that there is not a difference in cleaning time based on the use of plastic. Some differences are evident across jobs, with higher dust producing jobs (door planing, heat gun) resulting in higher clean-up times, as seen in Table 6-16. Table 6-17 reports that one contractor took approximately 8 minutes longer on average to conduct post-work cleaning than the other two.

Table 6-15. Summary of Post-work Cleaning Times, by Phase (in Minutes)

| P/CU Phase | # Obs. | Avg. | Std. Dev. | Min | Max |
|---|--------|------|-----------|------|------|
| Phase I - Plastic/Rule cleaning | 15 | 44.7 | 18.0 | 20.0 | 80.0 |
| Phase II - Plastic/Baseline cleaning | 14 | 35.6 | 12.3 | 18.0 | 60.0 |
| Phase III - No Plastic/Rule cleaning | 15 | 45.3 | 12.9 | 30.0 | 70.0 |
| Phase IV - No Plastic/Baseline cleaning | 15 | 36.1 | 12.3 | 19.0 | 60.0 |
| Total | 59 | 40.5 | 14.5 | 18.0 | 80.0 |

Table 6-16. Summary of Post-work Cleaning Times, by Job (in Minutes)

| Job | # Obs. | Avg. | Std. Dev. | Min | Max |
|--------------------|--------|------|-----------|------|------|
| Cut-outs | 12 | 38.8 | 12.7 | 18.0 | 62.0 |
| Door Plane | 7 | 45.3 | 20.1 | 25.0 | 80.0 |
| Dry Scrape | 8 | 40.1 | 19.9 | 20.0 | 80.0 |
| High Heat Gun | 12 | 44.9 | 12.6 | 29.0 | 70.0 |
| Kitchen Gut | 8 | 35.9 | 11.1 | 22.0 | 55.0 |
| Low Heat Gun | 4 | 42.5 | 12.6 | 30.0 | 60.0 |
| Window Replacement | 8 | 36.4 | 14.1 | 19.0 | 65.0 |
| Total | 59 | 40.5 | 14.5 | 18.0 | 80.0 |

Table 6-17. Summary of Post-work Cleaning Times, by Contractor (in Minutes)

| Job | # Obs. | Avg. | Std. Dev. | Min | Max |
|--------------|--------|------|-----------|------|------|
| Contractor 2 | 20 | 45.9 | 13.8 | 25.0 | 80.0 |
| Contractor 3 | 17 | 38.1 | 16.5 | 18.0 | 80.0 |
| Contractor 4 | 22 | 37.5 | 12.6 | 20.0 | 65.0 |
| Total | 59 | 40.5 | 14.5 | 18.0 | 80.0 |

6.9.2. Duration of Cleaning Verification

The length of the cleaning verification process was measured from its start to when the last floor verification zone was declared clean. This included time spent recleaning zones if any failed and performing both the wet cloth verification and dry cloth verification, if any were necessary. Across all experiments, the cleaning verification process averaged 21 minutes with a range from 5 minutes to 135 minutes. As seen in Table 6-18, the average cleaning verification length was longer when baseline cleaning was used following work as opposed to Rule cleaning. Summarizing the cleaning verification durations by job, as reported in Table 6-19, the jobs taking longest on average to pass cleaning verification were the kitchen gut (35.5 minutes) and cut out (24.5 minutes) jobs, which were relatively low intensity in terms of dust production. On average, Contractor 3 took longer to conduct the cleaning verifications, as seen in Table 6-20.

Table 6-18. Duration of Cleaning Verification Stages, by Phase (in Minutes)

| Phase | # Obs. | Avg. | Std. Dev. | Min | Max |
|---|--------|------|-----------|------|-------|
| Phase I - Plastic/Rule cleaning | 15 | 12.9 | 5.3 | 7.0 | 25.0 |
| Phase II - Plastic/Baseline cleaning | 14 | 21.8 | 33.4 | 5.0 | 135.0 |
| Phase III - No Plastic/Rule cleaning | 15 | 15.5 | 10.6 | 6.0 | 45.0 |
| Phase IV - No Plastic/Baseline cleaning | 15 | 35.0 | 28.0 | 10.0 | 95.0 |
| Total | 59 | 21.3 | 23.4 | 5.0 | 135.0 |

Table 6-19. Duration of Cleaning Verification Stages, by Job (in Minutes)

| Job | # Obs. | Avg. | Std. Dev. | Min | Max |
|--------------------|--------|------|-----------|------|-------|
| Cut-outs | 12 | 24.5 | 24.4 | 5.0 | 95.0 |
| Door Plane | 7 | 21.0 | 20.8 | 6.0 | 60.0 |
| Dry Scrape | 8 | 22.9 | 29.4 | 8.0 | 95.0 |
| Heat Gun | 12 | 11.1 | 4.9 | 5.0 | 25.0 |
| Kitchen Gut | 8 | 35.5 | 41.4 | 10.0 | 135.0 |
| Low Heat Gun | 4 | 16.3 | 7.5 | 10.0 | 25.0 |
| Window Replacement | 8 | 18.8 | 12.5 | 10.0 | 45.0 |
| Total | 59 | 21.3 | 23.4 | 5.0 | 135.0 |

Table 6-20. Duration of Cleaning Verification Stages, by Job (in Minutes)

| Job | # Obs. | Avg. | Std. Dev. | Min | Max |
|--------------|--------|------|-----------|-----|-------|
| Contractor 2 | 20 | 18.7 | 19.5 | 5.0 | 95.0 |
| Contractor 3 | 17 | 31.2 | 35.7 | 6.0 | 135.0 |
| Contractor 4 | 22 | 16.0 | 9.2 | 8.0 | 40.0 |
| Total | 59 | 21.3 | 23.4 | 5.0 | 135.0 |

6.9.3. Duration of Pre-work Set Up

Before work could begin prior to a job, renovation workers had to prepare for the work by unloading tools and equipment, setting up generators, setting up plastic containment if it was necessary, etc. Table 6-21 reports that experiments that required plastic containment took more time on average to prepare for. There was little difference by contractor, as seen in Table 6-22, or by type of building as seen in Table 6-23.

Table 6-21. Duration of Interior Pre-work Set Up, by Phase (in Minutes)

| Phase | # Obs. | Avg. | Std. Dev. | Min | Max |
|---|--------|------|-----------|------|-------|
| Phase I - Plastic/Rule cleaning | 15 | 96.2 | 27.3 | 60.0 | 140.0 |
| Phase II - Plastic/Baseline cleaning | 14 | 96.6 | 24.8 | 65.0 | 140.0 |
| Phase III - No Plastic/Rule cleaning | 15 | 75.6 | 25.1 | 30.0 | 135.0 |
| Phase IV - No Plastic/Baseline cleaning | 15 | 64.3 | 13.6 | 45.0 | 95.0 |
| Total | 59 | 83.0 | 26.6 | 30.0 | 140.0 |

Table 6-22. Duration of Interior Pre-work Set Up, by Contractor (in Minutes)

| Contractor | # Obs. | Avg. | Std. Dev. | Min | Max |
|------------|--------|------|-----------|------|-------|
| C2 | 20 | 87.0 | 27.3 | 45.0 | 140.0 |
| C3 | 17 | 81.6 | 24.9 | 40.0 | 135.0 |
| C4 | 22 | 80.3 | 28.0 | 30.0 | 135.0 |

Table 6-23. Duration of Interior Pre-work Set Up, by Building Type (in Minutes)

| Unit Type | # Obs. | Avg. | Std. Dev. | Min | Max |
|--------------|--------|------|-----------|------|-------|
| Housing Unit | 47 | 83.8 | 27.4 | 30.0 | 140.0 |
| COF | 12 | 79.6 | 24.1 | 45.0 | 120.0 |

The pre-work set up times for exterior work encompassed a significant amount of study-required set up including vertical containment set up and laying out containment plastic on the ground. Thus, the exterior pre-work set up times are not indicative of set up required by the proposed rule, which would primarily be laying out the rule plastic, and are not presented.

6.9.4. Duration of Interior RRP Work

The length of time that it took to conduct each job for the study varied significantly. A summary of interior work duration times is reported in Table 6-24. The heat gun jobs took the longest averaging three hours for the heat gun <1100 degrees job and about three and half hours for the heat gun >1100 degrees job. On the other hand, the jobs averaging the shortest amount of time were the cut outs and kitchen gut jobs. There is high variability among the cut out jobs as some experiments only involved the cutting of the holes in the wall, but not any electrical or plumbing work, while others included actual installation of wiring, outlets, or lights.

Table 6-24. Duration of Interior Work, by Job (in Minutes)

| Job | # Obs. | Avg. | Std. Dev. | Min | Max |
|-------------------------|--------|-------|-----------|-------|-------|
| Cut-outs | 12 | 49.8 | 48.7 | 7.0 | 170.0 |
| Window Replacement | 8 | 90.9 | 46.6 | 45.0 | 188.0 |
| Dry Scrape | 8 | 95.4 | 44.0 | 65.0 | 201.0 |
| Door Plane | 7 | 60.4 | 31.0 | 30.0 | 125.0 |
| Heat Gun < 1100 degrees | 4 | 180.0 | 24.8 | 145.0 | 200.0 |
| Kitchen Gut | 8 | 50.0 | 23.5 | 25.0 | 90.0 |
| Heat Gun > 1100 degrees | 12 | 214.8 | 44.4 | 145.0 | 300.0 |
| Total | 59 | 105.2 | 75.7 | 7.0 | 300.0 |

A summary of exterior work duration times is reported in Table 6-25. The paint removal jobs conducted at the COF took the longest, while the door replacement and dry scraping jobs took less time on average than the others.

Table 6-25. Duration of Exterior Work, by Job (in Minutes)

| Job | # Obs. | Avg. | Std. Dev. | Min | Max |
|-------------------------|---------------|-------------|------------------|------------|------------|
| Replace Exterior Door | 2 | 47.5 | 10.6 | 40.0 | 55.0 |
| Trim Replacement | 2 | 115.0 | 134.4 | 20.0 | 210.0 |
| Needle Gun | 1 | 239.0 | n/a | 239.0 | 239.0 |
| Dry Scrape | 4 | 70.0 | 63.5 | 35.0 | 165.0 |
| Heat Gun <1100 degrees | 1 | 245.0 | n/a | 245.0 | 245.0 |
| Power Sanding | 2 | 112.5 | 10.6 | 105.0 | 120.0 |
| Heat Gun > 1100 degrees | 1 | 305.0 | n/a | 305.0 | 305.0 |
| Torching | 2 | 152.5 | 31.8 | 130.0 | 175.0 |
| Total | 15 | 128.3 | 91.5 | 20.0 | 305.0 |

6.10. Cleaning Verification Data

The analyses contained in this section explore the impact of the cleaning verification process on lead levels remaining in the Work room at the completion of an RRP job. The analyses explore the association of different factors with post-verification floor and sill lead levels, including phase, job type, contractor, floor type and condition. Of interest were the relation of post-verification levels to EPA clearance standards.

6.10.1. Verification Of Floor Zones

As detailed in Section 3, each interior experiment contained a cleaning verification stage, where the RRP workers performed cleaning verification in accordance with the proposed rule. In an effort to keep the cleaning verification process as close as possible to what the RRP workers would do if the rule was enacted, they were given training on how to do the cleaning verification, and minimal guidance was provided by study personnel during the execution. The decision to pass or fail a verification cloth was left solely up to the RRP workers, although the study field supervisors were instructed to overrule any clearly unwarranted determinations. Information on the cleaning verification for all interior experiments is seen in Table 6-34. All average values presented in this section refer to the Work Room only.

Floor Cleaning Verification by Phase

Figure 6-18 displays the post-verification (PV) floor lead levels for all interior experiments by Phase. Note that the sample results below the detection limit of the laboratory are set to 5 $\mu\text{g}/\text{ft}^2$, one half of the detection limit, for plotting and analysis purposes.




Figure 6-18. Post-verification Floor Lead Loadings by Phase. The reference line is set at the EPA clearance standard of 40 $\mu\text{g}/\text{ft}^2$ for floor surfaces.

When considering the percentage of floor zones that failed cleaning verification on the first wet verification cloth, Table 6-26 reports that 48.6% of floor zones that were tested after Phase IV (no plastic and baseline cleaning) failed. The two phases which involved no use of plastic had the highest average post-verification floor lead levels (313.5 and 192.7 $\mu\text{g}/\text{ft}^2$). When plastic was used and the rule cleaning method performed, the average post-verification floor lead level was the closest to the EPA clearance standard of 40 $\mu\text{g}/\text{ft}^2$. One problem that arose during the study was that after the use of insufficiently diluted Simple Green solution during the rule cleaning and all cleanings after the first wet verification failure, the verification cloths had a gray color to them, making them visibly darker than the verification card. This led to the failure of some floor zones, although the post-cleaning (PC) and post-verification (PV) floor lead levels were below clearance standards. This was especially true for the experiments performed at C01-the school.

Table 6-26. Floor Verification Information by Phase

| Phase | Avg. PC Floor Lead Level (µg/ft ²) | % 1st Wet Cloth Failure | % 2nd Wet Cloth Failure | Avg. PV Floor Lead Level (µg/ft ²) |
|-----------------------------------|--|-------------------------|-------------------------|--|
| I – Plastic/Rule Cleaning | 69.0 | 9.4% | 0.0% | 55.1 |
| II – Plastic/Baseline Cleaning | 172.8 | 10.9% | 4.7% | 121.2 |
| III – No plastic/Rule Cleaning | 305.9 | 4.5% | 0.0% | 313.5 |
| IV – No plastic/Baseline Cleaning | 476.8 | 48.6% | 2.9% | 192.7 |

As seen in Table 6-27, the average percent change (PV versus PC) in floor lead level for Phase III is positive due to an unusual value for experiment 76 where the average post-cleaning floor lead level was less than 10 µg/ft² and the average post-verification lead level was 89.6 µg/ft². If this experiment is excluded, the overall average percent change in floor lead level across all experiments between the post-cleaning and post-verification stages results in a decrease of 29.1%. A greater decrease in the floor lead levels is observed when one or more of the floor zones failed and were re-cleaned at least once. For phases involving baseline cleaning, this meant that the floor was cleaned according to the rule method following the first failure and any subsequent failures, as called for by the design. This shift in cleaning methods for cleaning verification should be considered in interpreting the data from the cleaning verification portion of the experiments.

Table 6-27. Post-cleaning and Post-verification Floor Lead Levels for Experiments with Zero and ≥1 Verification Failures by Phase

| # of Verification Failures | Phase | | | | | | | |
|---|--------|--------|--------|--------|---------|--------|--------|--------|
| | I | | II | | III | | IV | |
| | 0 | ≥1 | 0 | ≥1 | 0* | ≥1 | 0 | ≥1 |
| Average PC Floor Lead Level (µg/ft ²) | 79.1 | 41.3 | 204.1 | 47.6 | 369.442 | 75.4 | 752.8 | 235.3 |
| Average PV Floor Lead Level (µg/ft ²) | 69.0 | 17.0 | 145.7 | 23.0 | 374.192 | 61.6 | 328.2 | 74.2 |
| Avg. % Change per Experiment | -18.6% | -27.2% | -19.5% | -50.7% | -17.4% | -41.5% | -35.1% | -60.2% |
| Overall Avg. Change | -12.7% | -58.9% | -28.6% | -51.6% | 3.2% | -18.3% | -56.4% | -68.4% |

* excludes one experiment with <10 at post-cleaning and 89.6 at post-verification

Floor Cleaning Verification by Job

Figure 6-19 and Table 6-28 display the post-verification floor lead levels for all interior experiments by job type. The jobs with the highest average floor lead level after cleaning verification were the door planing and the high heat gun jobs. The door plane job resulted in a significant amount of fine dust distributed around the entire Work Room, while the other jobs resulted in larger paint chips and pieces of debris. This could be the cause of the high post-verification lead levels, as the fine dust was difficult to clean, especially when the floor surface was not in good condition. The fine dust was also more difficult to see on the verification cloths than any dark, soot-like residue.




Figure 6-19. Post-verification Floor Lead Loadings by Job Type. The reference line is set at the EPA clearance standard of 40 $\mu\text{g}/\text{ft}^2$ for floor surfaces.

Table 6-28. Floor Verification Information by Job Type

| Job Type | Average PC Floor Lead Level ($\mu\text{g}/\text{ft}^2$) | % 1st Wet Cloth Failure | % 2nd Wet Cloth Failure | Average PV Floor Lead Level ($\mu\text{g}/\text{ft}^2$) |
|------------------------|---|-------------------------|-------------------------|---|
| Cut-outs | 19.2 | 33.3% | 2.1% | 12.1 |
| Window Replacement | 109.1 | 11.9% | 0.0% | 65.0 |
| Dry Scrape | 81.3 | 15.0% | 0.0% | 38.6 |
| Door Plane | 431.7 | 28.6% | 2.9% | 284.0 |
| Heat Gun <1100 degrees | 50.4 | 20.0% | 0.0% | 26.2 |
| Kitchen Gut | 45.2 | 20.0% | 10.0% | 37.0 |
| Heat Gun >1100 degrees | 799.8 | 6.1% | 0.0% | 549.4 |

Floor Cleaning Verification by Contractor

Across the study, the cleaning verification was performed variably by the RRP workers. Some of the observed differences included the amount of force applied to the verification cloth, the speed of wiping the verification zones, the cleaning performed if a particular zone or zones failed

verification, and the determination of whether a zone passed or failed. Table 6-29 reports that RRP workers in Pittsburgh were less likely to fail a floor zone, and had an average PV floor lead level of more than double that of Columbus contractors.

Table 6-29. Floor Verification Information by Contractor

| City | Contractor | # of Exp. | Avg. PC Floor Lead Level ($\mu\text{g}/\text{ft}^2$) | % 1st Wet Cloth Failure | % 2nd Wet Cloth Failure | Avg. PV Floor Lead Level ($\mu\text{g}/\text{ft}^2$) |
|------------|------------|-----------|--|-------------------------|-------------------------|--|
| Columbus | C2 | 20 | 175.5 | 28.6% | 6.5% | 65.9 |
| | C3 | 18 | 220.0 | 22.4% | 0.0% | 147.7 |
| Pittsburgh | C4 | 22 | 365.6 | 8.8% | 0.0% | 291.1 |

Floor Cleaning Verification by Floor Type and Condition

Tables 6-30 and 6-31 report the floor verification summary data by floor type and floor condition, respectively. Table 6-30 reports that the first verification cloths taken on floors were more likely to fail on vinyl tile and tile floors even though the post-cleaning levels on average are lower on the tile floors as opposed to the wood floors. The vinyl and tile floors were located in residential kitchens and in the classrooms at the COF. Table 6-31 reports that the floors in poor condition had significantly higher post-verification floor lead levels. Note that nearly all of the wood floors (20 of 22 experiments) were in poor condition.

Table 6-30. Floor Verification Information by Floor Type

| Floor Type | # of Exp | Avg. PC Floor Lead Level ($\mu\text{g}/\text{ft}^2$) | % 1st Wet Cloth Failure | % 2nd Wet Cloth Failure | Avg. PV Floor Lead Level ($\mu\text{g}/\text{ft}^2$) |
|------------|----------|--|-------------------------|-------------------------|--|
| Wood | 22 | 543.5 | 10.6% | 0.0% | 384.5 |
| Vinyl | 21 | 123.8 | 23.7% | 2.1% | 61.4 |
| Tile | 17 | 47.7 | 25.4% | 4.8% | 28.8 |

Table 6-31. Floor Verification Information by Floor Condition

| Floor Type | # of Exp | Avg. PC Floor Lead Level ($\mu\text{g}/\text{ft}^2$) | % 1st Wet Cloth Failure | % 2nd Wet Cloth Failure | Avg. PV Floor Lead Level ($\mu\text{g}/\text{ft}^2$) |
|------------|----------|--|-------------------------|-------------------------|--|
| Good | 22 | 35.8 | 19.4% | 0.0% | 16.8 |
| Fair | 11 | 76.5 | 15.4% | 7.7% | 58.8 |
| Poor | 27 | 508.9 | 15.4% | 1.6% | 341.5 |

Table 6-32 provides information regarding how the interaction between job type and floor type and condition impacts cloth failures and post-verification floor lead levels. Certain jobs occurred only in rooms with certain floor types and conditions, which highlights some differences between and within jobs. While door planing resulted in relatively high post-verification floor lead levels as seen in Table 6-28, the two jobs that occurred on wood floors in poor condition performed significantly worse with a post-verification average of $619 \mu\text{g}/\text{ft}^2$ than the other six jobs that occurred in rooms with vinyl or tile floors. Within the cut out and kitchen jobs, although relatively low post-verification lead levels were found across all jobs, higher levels were found for the jobs performed in rooms with poor floor condition.

Table 6-32. Floor Verification Information by Job Type, Floor Type, and Floor Condition

| Job Type | Floor Type/Condition | # of Exp | Avg. PC Floor Lead Level ($\mu\text{g}/\text{ft}^2$) | % 1st Wet Cloth Failure | % 2nd Wet Cloth Failure | Avg. PV Floor Lead Level ($\mu\text{g}/\text{ft}^2$) |
|------------------------|----------------------|----------|--|-------------------------|-------------------------|--|
| Cut-Outs | Tile-Good | 4 | 10.5 | 50.0% | 0.0% | 5.0 |
| | Vinyl-Good | 4 | 16.4 | 30.0% | 0.0% | 7.2 |
| | Tile-Fair | 2 | 11.6 | 0.0% | 0.0% | 12.4 |
| | Vinyl-Poor | 2 | 49.9 | 40.0% | 10.0% | 36.1 |
| Window Replacement | Wood-Fair | 2 | 96.4 | 0.0% | 0.0% | 82.2 |
| | Wood-Poor | 6 | 113.4 | 16.7% | 0.0% | 59.2 |
| Dry Scrape | Vinyl-Good | 4 | 92.3 | 0.0% | 0.0% | 42.6 |
| | Wood-Poor | 4 | 70.2 | 30.0% | 0.0% | 34.6 |
| Door Plane | Tile-Fair | 2 | 196.6 | 0.0% | 0.0% | 134.5 |
| | Vinyl-Poor | 4 | 443.8 | 50.0% | 5.0% | 191.2 |
| | Wood-Poor | 2 | 642.4 | 0.0% | 0.0% | 619.2 |
| Heat Gun <1100 degrees | Tile-Good | 4 | 50.4 | 20.0% | 0.0% | 26.2 |
| Kitchen Gut | Vinyl-Good | 2 | 14.8 | 0.0% | 0.0% | 8.6 |
| | Tile-Fair | 1 | 71.5 | 100.0% | 100.0% | 41.4 |
| | Vinyl-Fair | 4 | 40.2 | 25.0% | 0.0% | 36.9 |
| | Vinyl-Poor | 1 | 99.7 | 0.0% | 0.0% | 89.6 |
| Heat Gun >1100 degrees | Tile-Good | 4 | 19.8 | 18.8% | 0.0% | 7.3 |
| | Wood-Poor | 8 | 1,189.8 | 0.0% | 0.0% | 820.4 |

Impact of Dry Cloth Verification

Table 6-33 shows the corresponding average post-cleaning, post-wet verification and post-verification floor lead levels for each of the five floor zones that failed the second wet verification cloth. For each experiment, the number of dry verification cloths used is also listed. Each of these three experiments occurred with a tile floor using the kitchen as the work room.

Table 6-33. Floor Zones That Failed Second Wet Cloth Verification

| Exp # - Job | Floor Zone | PC Floor Lead Level ($\mu\text{g}/\text{ft}^2$) | WV Floor Lead Level ($\mu\text{g}/\text{ft}^2$) | # of Dry Cloths | PV Floor Lead Level ($\mu\text{g}/\text{ft}^2$) |
|-------------------|------------|---|---|-----------------|---|
| 45 – Cut outs | 2 | 91.5 | 61.5 | 2 | 37.3 |
| 47 – Door planing | 2 | 1,292.1 | 550.8 | 1 | 643.6 |
| 70 – Kitchen gut | 1 | n/a | 150.7 | 1 | 77.9 |
| | 2 | 46.2 | < 10 | 2 | < 10 |
| | 3 | 147.1 | < 10 | 1 | n/a |

Comparison of Post-cleaning and Post-verification Lead Levels

Figure 6-20 plots the number of experiments in various categories of floor lead levels at the post-cleaning and post-verification stages. With floors, over 50 percent of the experiments ended with average post-verification levels less than 40 $\mu\text{g}/\text{ft}^2$. The number of experiments with average levels over 100 $\mu\text{g}/\text{ft}^2$ dropped from 20 at the post-cleaning stage to 13 at post-verification.




Figure 6-20. Number of Experiments by Post-cleaning and Post-verification Floor Lead Loadings

Table 6-34. Verification Information for Interior Experiments

| Exp. # | Unit ID | Job | Phase | Floor Type | Floor Cond. | Cont. | # of Floor Zones | Avg. PC Floor Lead Level ($\mu\text{g}/\text{ft}^2$) | # Failed 1st Wet Cloths | # Failed 2nd Wet Cloths | Post-Wet Verif. ($\mu\text{g}/\text{ft}^2$) | # Failed Dry Cloths | Avg. PV Floor Lead Level ($\mu\text{g}/\text{ft}^2$) | # PV Samples $>40 \mu\text{g}/\text{ft}^2$ | Verif. Time (min)* |
|--------|---------|---------------|-------|------------|-------------|-------|------------------|--|-------------------------|-------------------------|---|---------------------|--|--|--------------------|
| 23 | H16 | Cut-outs | I | Vinyl | Good | C4 | 5 | 6.6 | 1 | 0 | - | 0 | < 10 | 0 | 19 |
| 55 | C01 | Cut-outs | I | Tile | Good | C2 | 3 | < 10 | 1 | 0 | - | 0 | < 10 | 0 | 15 |
| 72 | H35 | Cut-outs | I | Tile | Fair | C3 | 3 | 14.8 | 0 | 0 | - | 0 | < 10 | 0 | 7 |
| 25 | H16 | Cut-outs | II | Vinyl | Good | C4 | 5 | 11 | 0 | 0 | - | 0 | 8.7 | 0 | 15 |
| 53 | C01 | Cut-outs | II | Tile | Good | C2 | 3 | 7.8 | 0 | 0 | - | 0 | < 10 | 0 | 5 |
| 71 | H35 | Cut-outs | II | Tile | Fair | C3 | 3 | 8.5 | 0 | 0 | - | 0 | 19.8 | 0 | 12 |
| 24 | H17 | Cut-outs | III | Vinyl | Good | C4 | 5 | 31.1 | 0 | 0 | - | 0 | 9.9 | 0 | 15 |
| 46 | H08 | Cut-outs | III | Vinyl | Poor | C3 | 5 | 15.9 | 0 | 0 | - | 0 | 14.9 | 0 | 15 |
| 52 | C01 | Cut-outs | III | Tile | Good | C2 | 3 | 17.8 | 2 | 0 | - | 0 | < 10 | 0 | 20 |
| 22 | H16 | Cut-outs | IV | Vinyl | Good | C4 | 5 | 16.7 | 5 | 0 | - | 0 | < 10 | 0 | 70 |
| 45 | H08 | Cut-outs | IV | Vinyl | Poor | C3 | 5 | 84 | 4 | 1 | 61.5 | 1 | 57.2 | 1 | 95 |
| 54 | C01 | Cut-outs | IV | Tile | Good | C2 | 3 | 11.3 | 3 | 0 | - | 0 | < 10 | 0 | 35 |
| 48 | H08 | Door Plane | I | Vinyl | Poor | C3 | 5 | 180.9 | 0 | 0 | - | 0 | 290.4 | 4 | 8 |
| 79 | H09 | Door Plane | I | Wood | Poor | C3 | 4 | 139.1 | 0 | 0 | - | 0 | 87.4 | 4 | 10 |
| 73 | H35 | Door Plane | II | Tile | Fair | C3 | 3 | 233.9 | 0 | 0 | - | 0 | 116.3 | 3 | 7 |
| 77 | H08 | Door Plane | II | Vinyl | Poor | C3 | 5 | 50.7 | 0 | 0 | - | 0 | 31.4 | 1 | 8 |
| 74 | H35 | Door Plane | III | Tile | Fair | C3 | 3 | 159.4 | 0 | 0 | - | 0 | 152.6 | 4 | 6 |
| 80 | H09 | Door Plane | III | Wood | Poor | C3 | 5 | 1,145.80 | 0 | 0 | - | 0 | 1,150.90 | 4 | 10 |
| 47 | H08 | Door Plane | IV | Vinyl | Poor | C3 | 5 | 1,372.70 | 5 | 1 | 550.8 | 0 | 395.5 | 4 | 55* |
| 78 | H08 | Door Plane | IV | Vinyl | Poor | C3 | 5 | 171 | 5 | 0 | - | 0 | 47.6 | 2 | 40 |
| 5 | H03 | Dry Scrape | I | Wood | Poor | C2 | 5 | 31.6 | 1 | 0 | - | 0 | 28.9 | 2 | 20 |
| 28 | H17 | Dry Scrape | I | Vinyl | Good | C4 | 5 | 104.4 | 0 | 0 | - | 0 | 39.5 | 1 | 8 |
| 6 | H03 | Dry Scrape | II | Wood | Poor | C2 | 5 | 180.5 | 0 | 0 | - | 0 | 58.7 | 4 | 15 |
| 29 | H17 | Dry Scrape | II | Vinyl | Good | C4 | 5 | 156.1 | 0 | 0 | - | 0 | 38.1 | 1 | 10 |
| 8 | H03 | Dry Scrape | III | Wood | Poor | C2 | 5 | 12.9 | 0 | 0 | - | 0 | 9.4 | 0 | 15 |
| 26 | H17 | Dry Scrape | III | Vinyl | Good | C4 | 5 | 23.2 | 0 | 0 | - | 0 | 19.3 | 0 | 10 |
| 7 | H03 | Dry Scrape | IV | Wood | Poor | C2 | 5 | 55.9 | 5 | 0 | - | 0 | 41.2 | 3 | 35 |
| 27 | H17 | Dry Scrape | IV | Vinyl | Good | C4 | 5 | 85.5 | 0 | 0 | - | 0 | 73.6 | 3 | 10 |
| 16 | H09 | Heat Gun>1100 | I | Wood | Poor | C2 | 3 | 54 | 0 | 0 | - | 0 | 65.5 | 4 | 10 |
| 33 | H10 | Heat Gun>1100 | I | Wood | Poor | C4 | 4 | 191.8 | 0 | 0 | - | 0 | 147.5 | 4 | 10 |

Table 6-34. (continued) Verification Information for Interior Experiments

| Exp. # | Unit ID | Job | Phase | Floor Type | Floor Cond. | Cont. | # of Floor Zones | Avg. PC Floor Lead Level (µg/ft ²) | # Failed 1st Wet Cloths | # Failed 2nd Wet Cloths | Post-Wet Verif. (µg/ft ²) | # Failed Dry Cloths | Avg. PV Floor Lead Level (µg/ft ²) | # PV Samples >40 µg/ft ² | Verif. Time (min)* |
|--------|---------|---------------|-------|------------|-------------|-------|------------------|--|-------------------------|-------------------------|---------------------------------------|---------------------|--|-------------------------------------|--------------------|
| 63 | C01 | Heat Gun>1100 | I | Tile | Good | C2 | 4 | < 10 | 0 | 0 | - | 0 | < 10 | 0 | 10 |
| 13 | H09 | Heat Gun>1100 | II | Wood | Poor | C2 | 5 | 97.2 | 0 | 0 | - | 0 | 205.3 | 3 | 10 |
| 31 | H10 | Heat Gun>1100 | II | Wood | Poor | C4 | 4 | 1,393.00 | 0 | 0 | - | 0 | 1,122.90 | 4 | 10 |
| 60 | C01 | Heat Gun>1100 | II | Tile | Good | C2 | 4 | 30.2 | 0 | 0 | - | 0 | 12.9 | 0 | 5 |
| 14 | H09 | Heat Gun>1100 | III | Wood | Poor | C2 | 4 | 84.9 | 0 | 0 | - | 0 | 76.4 | 3 | 8 |
| 32 | H10 | Heat Gun>1100 | III | Wood | Poor | C4 | 4 | 2,876.60 | 0 | 0 | - | 0 | 2,976.10 | 4 | 10 |
| 61 | C01 | Heat Gun>1100 | III | Tile | Good | C2 | 4 | 11.3 | 0 | 0 | - | 0 | < 10 | 0 | 10 |
| 15 | H09 | Heat Gun>1100 | IV | Wood | Poor | C2 | 5 | 2,669.60 | 0 | 0 | - | 0 | 678.9 | 4 | 10 |
| 30 | H10 | Heat Gun>1100 | IV | Wood | Poor | C4 | 4 | 2,151.00 | 0 | 0 | - | 0 | 1,290.70 | 4 | 30 |
| 62 | C01 | Heat Gun>1100 | IV | Tile | Good | C2 | 4 | 32.7 | 3 | 0 | - | 0 | 6.4 | 0 | 25 |
| 51 | H33 | Kitchen Gut | I | Vinyl | Fair | C4 | 3 | 45.4 | 0 | 0 | - | 0 | 42.3 | 2 | 10 |
| 67 | H16 | Kitchen Gut | I | Vinyl | Good | C4 | 5 | < 10 | 0 | 0 | - | 0 | < 10 | 0 | 10 |
| 49 | H31 | Kitchen Gut | II | Vinyl | Fair | C4 | 3 | 45.8 | 3 | 0 | - | 0 | 10.5 | 0 | 35 |
| 68 | H17 | Kitchen Gut | III | Vinyl | Good | C4 | 5 | 24.6 | 0 | 0 | - | 0 | 12.2 | 0 | 34 |
| 76 | H36 | Kitchen Gut | III | Vinyl | Fair | C4 | 3 | < 10 | 0 | 0 | - | 0 | 89.6 | 11 | 15 |
| 50 | H32 | Kitchen Gut | IV | Vinyl | Fair | C4 | 3 | 64.7 | 0 | 0 | - | 0 | < 10 | 0 | 25 |
| 70 | H35 | Kitchen Gut | II | Tile | Fair | C3 | 3 | 71.5 | 3 | 3 | 150.7 <10 <10 | 1 | 41.4 | 1 | 135 |
| 69 | H08 | Kitchen Gut | IV | Vinyl | Poor | C3 | 5 | 99.7 | 0 | 0 | - | 0 | 89.6 | 3 | 20 |
| 59 | C01 | Low Heat Gun | I | Tile | Good | C2 | 6 | 122.2 | 3 | 0 | - | 0 | 29.1 | 2 | 25 |
| 56 | C01 | Low Heat Gun | II | Tile | Good | C2 | 5 | 25.6 | 1 | 0 | - | 0 | 17.2 | 0 | 15 |
| 58 | C01 | Low Heat Gun | III | Tile | Good | C2 | 4 | 9.5 | 0 | 0 | - | 0 | 7.5 | 0 | 10 |
| 57 | C01 | Low Heat Gun | IV | Tile | Good | C2 | 5 | 44.2 | 0 | 0 | - | 0 | 51 | 2 | 10 |
| 12 | H09 | Window Repl. | I | Wood | Poor | C3 | 3 | 60.5 | 0 | 0 | - | 0 | 29.9 | 1 | 10 |
| 41 | H16 | Window Repl. | I | Wood | Poor | C4 | 6 | 69 | 0 | 0 | - | 0 | 41.4 | 3 | 15 |
| 11 | H09 | Window Repl. | II | Wood | Poor | C3 | 5 | 96.9 | 0 | 0 | - | 0 | 33.5 | 1 | 15 |
| 42 | H16 | Window Repl. | II | Wood | Poor | C4 | 6 | 183.4 | 0 | 0 | - | 0 | 96.2 | 4 | 10 |
| 9 | H09 | Window Repl. | III | Wood | Poor | C3 | 5 | 133 | 1 | 0 | - | 0 | 118.2 | 4 | 45 |
| 44 | H17 | Window Repl. | III | Wood | Fair | C4 | 6 | 38.1 | 0 | 0 | - | 0 | 56.1 | 2 | 10 |
| 10 | H09 | Window Repl. | IV | Wood | Poor | C3 | 5 | 137.8 | 4 | 0 | - | 0 | 36 | 1 | 30 |
| 43 | H17 | Window Repl. | IV | Wood | Fair | C4 | 6 | 154.7 | 0 | 0 | - | 0 | 108.3 | 3 | 15 |

* Verification time includes window sill and floor verification, re-cleaning, and wait times.

6.10.2. Verification of Window Sills

Along with the floor zones, each window sill in the Work Room was subject to cleaning verification. As stated previously, all window sills had to pass clearance before the RRP workers moved on to the cleaning verification of the floor. Overall, only three window sills failed the first wet cloth verification, despite the fact that nineteen window sills had post-cleaning lead levels of greater than 250 $\mu\text{g}/\text{ft}^2$. Tables 6-35, 6-36, and 6-37 list the post-cleaning and post-verification average sill lead levels by phase, job intensity level, and contractor respectively. Table 6-39 reports window sill cleaning verification information across all experiments.

Table 6-35. Window Sill Verification Information by Phase

| Phase | PC Sill Lead Level ($\mu\text{g}/\text{ft}^2$) | PV Sill Lead Level ($\mu\text{g}/\text{ft}^2$) | # 1 st Wet Cloth Failures |
|-----------------------------------|--|--|--------------------------------------|
| I – Plastic/Rule Cleaning | 151.8 | 198.7 | 1 |
| II – Plastic/Baseline Cleaning | 761.6 | 119.6 | 0 |
| III – No plastic/Rule Cleaning | 1439.0 | 490.5 | 1 |
| IV – No plastic/Baseline Cleaning | 601.4 | 467.4 | 1 |

Table 6-36. Window Sill Verification Information by Intensity Level

| Intensity Level | PC Sill Lead Level ($\mu\text{g}/\text{ft}^2$) | PV Sill Lead Level ($\mu\text{g}/\text{ft}^2$) | # 1 st Wet Cloth Failures |
|-----------------|--|--|--------------------------------------|
| Low | 159.9 | 155.7 | 2 |
| Medium | 366.1 | 451.9 | 1 |
| High | 1689.3 | 347.6 | 0 |

Table 6-37. Window Sill Verification Information by Contractor

| City | Contractor | # of Exp | Avg. PC Sill Lead Level ($\mu\text{g}/\text{ft}^2$) | % 1st Wet Cloth Failure | % 2nd Wet Cloth Failure | Avg. PV Sill Lead Level ($\mu\text{g}/\text{ft}^2$) |
|------------|------------|----------|---|-------------------------|-------------------------|---|
| Columbus | C2 | 20 | 142.0 | 0.0% | 0.0% | 39.3 |
| | C3 | 18 | 469.2 | 7.7% | 0.0% | 526.8 |
| Pittsburgh | C4 | 22 | 1,500.9 | 3.1% | 0.0% | 381.1 |

No window sills failed a second wet cloth verification. For two of the three window sills that failed the first wet verification cloth, there are no corresponding post-cleaning or post-verification samples. This is because the sampling protocol called for one window sill sample at each sampling stage for interior experiments, while the cleaning verification protocol requires the testing of all window sills within the Work Room. For the one window sill that does correspond to the window used in the three-stage sampling, the post-cleaning lead level was 44.5 $\mu\text{g}/\text{ft}^2$ and the post-verification level was 20 $\mu\text{g}/\text{ft}^2$.

Comparison of Post-cleaning and Post-verification Lead Levels

Figure 6-21 plots the number of experiments in various categories of sill lead levels at the post-cleaning and post-verification stages. The number of experiments with sill lead levels below the clearance standard of 250 $\mu\text{g}/\text{ft}^2$ increased from 41 to 48 between post-cleaning and post-verification. Table 6-38 presents the percent change in window sill lead levels from

post-cleaning to post-verification by phase and whether a cloth failure was identified. It is worth noting that lead levels from 24 experiments were below the detection limit at post-cleaning and 34 experiments are post-verification, with 21 being below the detection limit at both stages (9 from Phase I).




Figure 6-21. Number of Experiments by Post-cleaning and Post-verification Sill Lead Loadings

Table 6-38. Post-cleaning and Post-verification Sill Lead Levels for Experiments with Zero and ≥ 1 Verification Failures by Phase.

| # of Verification Failures | Phase | | | | | | | |
|--|-------|----------|--------|----------|---------|----------|--------|----------|
| | I | | II | | III | | IV | |
| | 0 | ≥ 1 | 0 | ≥ 1 | 0 | ≥ 1 | 0 | ≥ 1 |
| Average PC Sill Lead Level ($\mu\text{g}/\text{ft}^2$) | 156.5 | 85.8 | 761.6 | n/a | 1,538.6 | 44.5 | 614.9 | 411.5 |
| Average PV Sill Lead Level ($\mu\text{g}/\text{ft}^2$) | 208.8 | 57.5 | 118.8 | n/a | 526.7 | 20.0 | 438.4 | 873.3 |
| Avg. % Change per Experiment | 1.7% | -33.0% | -52.5% | n/a | 106.1%* | -55.1% | -44.2% | 112.2% |
| Overall Avg. Change | 33.4% | -33.0% | -84.4% | n/a | -65.8% | -55.1% | -28.7% | 112.2% |

* with exclusion of 2 experiments that changed from below detection limit to 166 and 282 $\mu\text{g}/\text{ft}^2$, average percent change would be -14.2%

Table 6-39. Window Sill Verification Information for Interior Experiments

| Exp. # | Unit ID | Job | Phase | Sill Type | Cont. | # of Sills | PC Sill Lead Level (µg/ft ²) | # Failed 1st Wet Cloths | PV Sill Lead Level (µg/ft ²) | # PV Samples >250 µg/ft ² |
|--------|---------|------------|-------|-----------|-------|------------|--|-------------------------|--|--------------------------------------|
| 23 | H16 | Cut-outs | I | SILL | C4 | 2 | < 40 | 0 | < 40 | 0 |
| 55 | C01 | Cut-outs | I | TRAY | C2 | 1 | < 41.6 | 0 | < 41.6 | 0 |
| 72 | H35 | Cut-outs | I | SILL | C3 | 2 | < 100 | 0 | < 100 | 0 |
| 25 | H16 | Cut-outs | II | SILL | C4 | 2 | < 52.6 | 0 | < 52.6 | 0 |
| 53 | C01 | Cut-outs | II | TRAY | C2 | 1 | 48.7 | 0 | < 45.5 | 0 |
| 71 | H35 | Cut-outs | II | SILL | C3 | 2 | 101.1 | 0 | < 62.5 | 0 |
| 24 | H17 | Cut-outs | III | SILL | C4 | 2 | < 50 | 0 | 166.4 | 0 |
| 46 | H08 | Cut-outs | III | TRAY | C3 | 1 | < 41.6 | 0 | < 41.6 | 0 |
| 52 | C01 | Cut-outs | III | TRAY | C2 | 1 | < 45.5 | 0 | < 45.5 | 0 |
| 22 | H16 | Cut-outs | IV | SILL | C4 | 2 | 198.2 | 0 | < 40 | 0 |
| 45 | H08 | Cut-outs | IV | SILL | C3 | 1 | 416.9 | 0 | 276.6 | 1 |
| 54 | C01 | Cut-outs | IV | TRAY | C2 | 1 | < 41.6 | 0 | < 41.6 | 0 |
| 48 | H08 | Door Plane | I | SILL | C3 | 1 | 521.3 | 0 | 1,707.90 | 1 |
| 79 | H09 | Door Plane | I | TRAY | C3 | 1 | 104.2 | 0 | < 45.5 | 0 |
| 73 | H35 | Door Plane | II | SILL | C3 | 3 | 127.1 | 0 | 115.7 | 0 |
| 77 | H08 | Door Plane | II | TRAY | C3 | 1 | 278.6 | 0 | 61.7 | 0 |
| 74 | H35 | Door Plane | III | SILL | C3 | 2 | 170.4 | 0 | < 100 | 0 |
| 80 | H09 | Door Plane | III | TRAY | C3 | 1 | 2,546.10 | 0 | 3,378.20 | 1 |
| 47 | H08 | Door Plane | IV | SILL | C3 | 1 | 1,798.70 | 0 | 2,625.30 | 1 |
| 78 | H08 | Door Plane | IV | TRAY | C3 | 1 | 277.9 | 0 | 96.5 | 0 |
| 5 | H03 | Dry Scrape | I | TRAY | C2 | 1 | < 10 | 0 | < 10 | 0 |
| 28 | H17 | Dry Scrape | I | SILL | C4 | 2 | 85.8 | 1* | 57.5 | 0 |
| 6 | H03 | Dry Scrape | II | TRAY | C2 | 1 | < 50 | 0 | < 25 | 0 |
| 29 | H17 | Dry Scrape | II | SILL | C4 | 2 | 467 | 0 | 115 | 0 |
| 8 | H03 | Dry Scrape | III | TRAY | C2 | 1 | < 45.5 | 0 | < 45.5 | 0 |
| 26 | H17 | Dry Scrape | III | SILL | C4 | 2 | < 52.6 | 0 | < 52.6 | 0 |
| 7 | H03 | Dry Scrape | IV | TRAY | C2 | 1 | < 50 | 0 | < 50 | 0 |
| 27 | H17 | Dry Scrape | IV | SILL | C4 | 2 | 150.8 | 0 | < 52.6 | 0 |
| 16 | H09 | Heat Gun | I | TRAY | C2 | 1 | < 41.6 | 0 | < 41.6 | 0 |
| 33 | H10 | Heat Gun | I | TRAY | C4 | 1 | 1005.3 | 0 | 790.2 | 1 |
| 63 | C01 | Heat Gun | I | TRAY | C2 | 1 | < 45.5 | 0 | < 45.5 | 0 |
| 13 | H09 | Heat Gun | II | TRAY | C2 | 1 | 253.7 | 0 | 81.4 | 0 |
| 31 | H10 | Heat Gun | II | TRAY | C4 | 1 | 8,838.80 | 0 | 927.2 | 1 |
| 60 | C01 | Heat Gun | II | TRAY | C2 | 1 | 170.4 | 0 | < 45.5 | 0 |
| 14 | H09 | Heat Gun | III | TRAY | C2 | 1 | < 45.5 | 0 | < 45.5 | 0 |
| 32 | H10 | Heat Gun | III | TRAY | C4 | 1 | 18,132.80 | 0 | 2,669.60 | 1 |
| 61 | C01 | Heat Gun | III | TRAY | C2 | 1 | < 41.6 | 0 | < 41.6 | 0 |
| 15 | H09 | Heat Gun | IV | TRAY | C2 | 1 | 1,352.40 | 0 | 182.7 | 0 |
| 30 | H10 | Heat Gun | IV | TRAY | C4 | 1 | 1,697.60 | 0 | 1,784.50 | 1 |

Table 6-39. (continued) Window Sill Verification Information for Interior Experiments

| Exp. # | Unit ID | Job | Phase | Sill Type | Cont. | # of Sills | PC Sill Lead Level ($\mu\text{g}/\text{ft}^2$) | # Failed 1st Wet Cloths | PV Sill Lead Level ($\mu\text{g}/\text{ft}^2$) | # PV Samples $>250 \mu\text{g}/\text{ft}^2$ |
|--------|---------|--------------|-------|-----------|-------|------------|--|-------------------------|--|---|
| 62 | C01 | Heat Gun | IV | TRAY | C2 | 1 | 94.4 | 0 | < 45.5 | 0 |
| 51 | H33 | Kitchen Gut | I | SILL | C4 | 1 | < 45.5 | 0 | < 45.5 | 0 |
| 67 | H16 | Kitchen Gut | I | SILL | C4 | 2 | < 40 | 0 | < 40 | 0 |
| 49 | H31 | Kitchen Gut | II | SILL | C4 | 1 | < 100 | 0 | < 100 | 0 |
| 70 | H35 | Kitchen Gut | II | SILL | C3 | 2 | < 66.6 | 0 | < 66.6 | 0 |
| 68 | H17 | Kitchen Gut | III | SILL | C4 | 2 | 396.5 | 0 | < 52.6 | 0 |
| 76 | H36 | Kitchen Gut | III | SILL | C4 | 1 | 86.2 | 0 | 138.3 | 0 |
| 50 | H32 | Kitchen Gut | IV | SILL | C4 | 1 | 130.3 | 0 | < 41.6 | 0 |
| 69 | H08 | Kitchen Gut | IV | SILL | C3 | 1 | 1,414.20 | 0 | 73.5 | 0 |
| 59 | C01 | Low Heat Gun | I | TRAY | C2 | 1 | 137.7 | 0 | < 41.6 | 0 |
| 56 | C01 | Low Heat Gun | II | TRAY | C2 | 1 | 285.1 | 0 | 133.1 | 0 |
| 58 | C01 | Low Heat Gun | III | TRAY | C2 | 1 | < 41.6 | 0 | n/a | 1 |
| 57 | C01 | Low Heat Gun | IV | TRAY | C2 | 1 | 246.8 | 0 | 70.4 | 0 |
| 12 | H09 | Window Repl. | I | TRAY | C3 | 1 | < 45.5 | 0 | < 45.5 | 0 |
| 41 | H16 | Window Repl. | I | SILL | C4 | 1 | 218.1 | 0 | 176 | 0 |
| 11 | H09 | Window Repl. | II | SILL | C3 | 1 | 106.9 | 0 | < 45.5 | 0 |
| 42 | H16 | Window Repl. | II | SILL | C4 | 1 | 611.9 | 0 | 126.2 | 0 |
| 9 | H09 | Window Repl. | III | SILL | C3 | 2 | 44.5 | 1 | < 40 | 0 |
| 44 | H17 | Window Repl. | III | SILL | C4 | 1 | < 52.6 | 0 | 281.5 | 1 |
| 10 | H09 | Window Repl. | IV | SILL | C3 | 2 | 411.5 | 1* | 873.3 | 1 |
| 43 | H17 | Window Repl. | IV | SILL | C4 | 1 | 784.9 | 0 | 892.5 | 1 |

* The failed verification cloth does not correspond to the sill from which the samples were collected.

7. Statistical Modeling Results

The following sections provide the results of statistical models applied to floor and window sill dust-lead results from the RRP Field Study. The results are organized by Stage (Post Work, Post Cleaning, and Post Verification) and Room (Work, Tool, and Observation) – with separate statistical models being specified within each Stage-by-Room combination to address the multiple inferential objectives mentioned earlier in Section 1. Section 7.1 corresponds to all results obtained in the Post Work Stage of field data collection, with subsections 7.1.1 – 7.1.3 corresponding to results in the Work Room, Tool Room and Observation Room, respectively. Similarly, Section 7.2 and 7.3 (and their associated sub-sections) correspond to the Post Cleaning and Post Verification Stages. Section 7.4 corresponds to a cross-stage analysis that compares full rule implementation (use of plastic sheeting and RRP rule cleaning in the Post-verification Stage) to baseline activities or no rule implementation (no use of plastic sheeting and baseline cleaning in the Post-cleaning Stage).

The results summarized in the following sections provide an overview of the statistical modeling results for floor and window sill dust-lead loadings from interior RRP jobs for two subsets of study data: (1) data limited to residential units only, and (2) Combined data for all interior RRP jobs (both residential and COFs). All analyses that were conducted on the second subset of data include a term in the model that adjusts for differences between residential units and COFs. Thus, a COF variable appears in all models of the Combined data.

The rationale for presenting the analysis results for each Stage-by-Room combination is that the series of statistical models that are fit to a subset of data (e.g. post-cleaning floor dust-lead loadings in the Observation room) are directly comparable using a likelihood ratio test statistic. Differences in reported likelihood fit statistics (-2 Log-Likelihood) between two models applied to the same dataset can be assessed by comparing to the Chi-Squared (χ^2) distribution with degrees of freedom matching the difference in the number of fixed effects included in the two models. Generally, the lower likelihood ratio statistic indicates the better fitting model. Within each subset of data, a potential best model is identified based on evaluation of the likelihood ratio along with the number of variables included and the significance of additional variables.

A mixed models analysis of variance approach including both fixed and random effects was used to fit the statistical models presented in this section and test the various study hypotheses, using Proc Mixed in SAS®. Each of the models explained dust-lead loadings on floors or window sills as a function of one or more fixed effects variables (intensity-level, job-type, use of plastic sheeting, post-work cleaning method, average paint-lead loading on disrupted component(s), square feet of lead-based paint disturbed, etc.) – with some models investigating interactions between some of these fixed effect variables to address specific analysis objectives.

Adjustments were made in the model to account for the data not being independent. There is anticipated positive correlation between the multiple samples of each type taken within the same room during the same experiment, within the same room across experiments, and within the same housing unit across experiments. To account for this, the models applied to floor dust-lead loadings included random effect terms that adjusted for anticipated positive correlation among multiple results observed from within the same unit, among multiple results observed from

within the same room (within a unit), and among multiple results observed from within the same RRP experiment. The models applied to window sill dust-lead loadings included a random effect for the anticipated positive correlation among multiple results observed from within the same room within a unit (a random effect for experiment was unnecessary because there was only one window sill sample obtained from each Stage-by-Room combination within an experiment).

Because the statistical models assume the data are normally distributed and because the dust lead loading data were non-normal (as indicated by various figures in Appendices B-E), all floor and sill data underwent log-transformation to more closely approximate normality, which generally is done with environmental lead data. Although most sets of transformed data still differ significantly enough from normality to be identified as non-normal by the test statistic presented in the appendices, the statistical models utilized are robust enough to account for this level of non-normality. Plots of residuals from each set of data are presented within the section to illustrate the suitability of the models used.

In the sections that follow, we provide summary tables for the models fit for each Stage-by-Room combination of data. The summary tables provide an overview of the p-value associated with each explanatory factor and the likelihood fit statistic for model fit to that particular subset of data. The p-values for categorical variables are based on an F-test for the combined effect across multiple levels. Statistical significance is generally attributed to p-values less than 0.05. P-values between .05 and about .10 are referred to as borderline significant.

Additional detail on the specific parameter estimates and standard errors from each model can be found in Appendices I through N. Residential floor and sill results are in Appendices I and J; COF floor results are in Appendix K; combined interior results are in Appendices L and M; and detailed exterior model results are in Appendix N. Residual plots for the best fitting models are contained in Appendix O. In a few places in this section, we compare the specific parameter estimates for a variable of interest and calculate the model-predicted difference in geometric mean levels based on those estimates. This is done using the formula $100*(1-e^x)$, with “x” being the difference in parameter estimates.

7.1. Post-Work Dust Lead Levels

The following three subsections provide an overview of statistical modeling results for floor and window sill dust lead loading results in the post work stage of the field study, in the Work room (subsection 7.1.1), Tool room (subsection 7.1.2), and Observation room (subsection 7.1.3).

7.1.1. Post-Work Work Room Dust Lead Levels

Table 7-1 provides an overview of results from statistical models developed to describe post-work floor and window sill dust-lead loadings in the Work room across the two subsets of data described earlier (residential units only and all units combined). The results are repeated using the wipe-only dust-lead results, as well as the results that also integrated the bulk samples.

Objective 1-Model 1 assesses the total effect of Intensity-Level (High, Medium, and Low) on floor and window sill dust lead loadings, which was shown to be statistically significant in all models. Objective 1-Model 2 assesses the total effect of Job-Type (a 6-level variable in the residential unit dataset, and a 7-level variable in the all units combined dataset), which explained additional variability in floor and window sill dust-lead loadings as anticipated. Job-type is nested within intensity level by design.

In addition to the models assessing the total effect of intensity level and job type, Objective 1-Models 3 and 4 investigate whether these two variables are still statistically significant predictors of floor and window sill dust lead loadings after adjusting for the paint-lead loading on the surface being disturbed and a measure of the square feet of lead-based paint disturbed during the RRP activity. The summary of results provided in Table 7-1 demonstrate that both Intensity-Level and Job-Type are statistically significant predictors of post-work floor and window sill dust-lead loadings in the work room after adjusting for the effects of paint-lead loading and square footage disturbed, and the addition of these two variables does not always improve the predictive ability of these models. This suggests that these two additional terms may compete for explanatory power with intensity-level and job-type. A comparison of the wipe-only dust-lead loadings with the measures that integrate the bulk samples did not yield any meaningful differences in interpretation of the data.

The highlighted rows in Table 7-1 indicate the models that appear to fit the data best. Objective 1-Model 2, which accounted only for job type and COF, performs best for the residential floor data and both sets of window sill data. Within the combined floor data, the inclusion of area disturbed and average paint lead level improved the model fit slightly with average paint lead significantly impacting the floor lead levels. Section O1 of Appendix O contains the residual plots from these four best fitting models. The floor model residuals appear to be approximately normally distributed. The residuals from the sill models appear to contain some skewness.

Table 7-1: Post-work Work Room Modeling Results

| Model | Variables Included in Model | Floors | | | | Sills | | | |
|---------------------------------|-----------------------------|-----------------|-------------------|----------|-------------------|-----------------|-------------------|----------|-------------------|
| | | All Residential | | Combined | | All Residential | | Combined | |
| | | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood |
| Objective 1: Model 1 | COF | . | 756.3 | 0.20 | 945.5 | . | 214.8 | 0.28 | 263.8 |
| | Intensity level | <.01 | | <.01 | | <.01 | | <.01 | |
| Objective 1: Model 2 | COF | . | 726.7 | 0.05 | 921.3 | . | 192.5 | 0.35 | 231.3 |
| | Job type | <.01 | | <.01 | | <.01 | | <.01 | |
| Objective 1: Model 3 | COF | . | 755.5 | 0.05 | 943.2 | . | 215.2 | 0.16 | 269.4 |
| | Square feet disturbed | 0.34 | | 0.76 | | 0.35 | | 0.95 | |
| | Avg. paint lead | <.01 | | <.01 | | <.01 | | 0.10 | |
| | Intensity level | <.01 | | <.01 | | <.01 | | <.01 | |
| Objective 1: Model 4 | COF | . | 731.7 | 0.03 | 915.4 | . | 197.2 | 0.34 | 236.1 |
| | Square feet disturbed | 0.58 | | 0.82 | | 0.33 | | 0.21 | |
| | Avg. paint lead | 0.04 | | <.01 | | 0.35 | | 0.19 | |
| | Job type | <.01 | | <.01 | | <.01 | | <.01 | |
| Objective 1: Model 1, with bulk | COF | . | 954.5 | 0.67 | 1222.9 | . | 228.4 | 0.28 | 278.4 |
| | Intensity level | <.01 | | <.01 | | <.01 | | <.01 | |
| Objective 1: Model 2, with bulk | COF | . | 931.0 | 0.29 | 1195.3 | . | 205.9 | 0.34 | 247.1 |
| | Job type | <.01 | | <.01 | | <.01 | | <.01 | |
| Objective 1: Model 3, with bulk | COF | . | 952.1 | 0.20 | 1222.3 | . | 228.1 | 0.15 | 283.1 |
| | Square feet disturbed | 0.57 | | 0.20 | | 0.34 | | 0.89 | |
| | Avg. paint lead | <.01 | | <.01 | | <.01 | | 0.07 | |
| | Intensity level | <.01 | | <.01 | | <.01 | | 0.01 | |
| Objective 1: Model 4, with bulk | COF | . | 934.7 | 0.18 | 1193.7 | . | 209.8 | 0.33 | 251.1 |
| | Square feet disturbed | 0.55 | | 0.94 | | 0.32 | | 0.22 | |
| | Avg. paint lead | 0.03 | | <.01 | | 0.33 | | 0.16 | |
| | Job type | <.01 | | <.01 | | <.01 | | <.01 | |

7.1.2. Post-work Tool Room Dust Lead Levels

Table 7-2 provides an overview of results from statistical models developed to describe post-work floor and window sill dust-lead loadings in the Tool room across the two subsets of data described earlier (residential units only and all units combined). The results are provided for the wipe samples only (as there were no bulk samples found in the Tool room).

Objective 1-Model 5 assesses the total effect of Intensity-Level on floor and window sill dust lead loadings, which was shown to be statistically significant in all models. Model 6 assesses the total effect of Job-Type, which explained additional variability in floor and window sill dust-lead loadings as anticipated. In addition to the models assessing the total effect of intensity level and job type, Objective 1-Models 7 and 8 investigate whether these two variables are still statistically significant predictors of floor and window sill dust lead loadings after adjusting for the paint-lead loading on the surface being disturbed and a measure of the square feet of lead-based paint disturbed during the RRP activity.

The summary of results provided in Table 7-2 demonstrate that both Intensity-Level and Job-Type are statistically significant predictors of post-work floor and window sill dust-lead loadings

in the Tool room after adjusting for the effects of paint-lead loading and square footage disturbed. The addition of these two variables does not always improve the predictive ability of these models, which suggests that these two additional terms may compete for explanatory power with intensity-level and job-type.

Models were also developed to assess whether the use of plastic sheeting reduced post-work dust-lead loadings observed in the Tool room. Objective 1–Models 9 and 10 provide the results of these analyses. Although the use of plastic sheeting did not always result in statistically significant reductions in post-work dust lead loadings in the Tool room – inspection of the parameter estimates of these models (found in Appendices I through M) reveals that the effect of using plastic sheeting results in lower estimated post-work dust lead loadings for the Tool Room across all models. The effects of Job-Type and Intensity-Level were found to be statistically significant, after adjusting for the use of plastic sheeting in all models applied to dust lead loadings in the Tool room at the post-work stage.

Objective 1–Model 6, which accounts for job type and the differences between residential units and the COF, is highlighted in Table 7-2 as the best fitting model for all four data sets. Although the log-likelihoods are slightly lower for Objective 1–Model 10, that model also included an additional variable, which did not lead to much gain in the likelihood statistic and was not significant. Although use of plastic was not statistically significant, the detailed results of this model in Table L2 report that combined floor lead levels are 0.32 units lower on the log scale when plastic was used, which equates to geometric means predicted to be 27% lower when plastic was used than when it was not used. Section O2 of Appendix O contains the residual plots from these best fitting models, which all indicate reasonable normal distributions.

Table 7-2: Post-Work Tool Room Modeling Results

| Model | Variables Included in Model | Floors | | | | Sills | | | |
|-----------------------|--|---------------------------|-------------------|------------------------------|-------------------|---------------------------|-------------------|------------------------------|-------------------|
| | | All Residential | | Combined | | All Residential | | Combined | |
| | | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood |
| Objective 1: Model 5 | COF Intensity level | . <.01 | 328.1 | 0.36 <.01 | 436.3 | . 0.03 | 176.4 | 0.32 0.01 | 212.0 |
| Objective 1: Model 6 | COF Job type | . <.01 | 306.5 | 0.31 <.01 | 413.4 | . 0.02 | 164.0 | 0.21 0.02 | 198.2 |
| Objective 1: Model 7 | COF Square feet disturbed Avg. paint lead Intensity level | . 0.78 0.06 <.01 | 334.6 | 0.21 0.78 0.02 <.01 | 441.9 | . 0.09 <.01 <.01 | 172.0 | 0.07 0.18 <.01 0.01 | 211.1 |
| Objective 1: Model 8 | COF Square feet disturbed Avg. paint lead Job type | . 0.07 0.49 <.01 | 311.7 | 0.25 0.32 0.01 <.01 | 417.2 | . 0.50 <.01 0.04 | 164.9 | 0.12 0.72 <.01 0.03 | 199.6 |
| Objective 1: Model 9 | COF Plastic Intensity level | . 0.12 <.01 | 326.0 | 0.36 0.19 <.01 | 435.2 | . 0.32 0.02 | 175.2 | 0.32 0.60 0.01 | 212.0 |
| Objective 1: Model 10 | COF Plastic Job type | . 0.16 <.01 | 305.0 | 0.31 0.20 <.01 | 412.7 | . 0.37 0.02 | 163.1 | 0.22 0.66 0.02 | 198.3 |

7.1.3. Post-Work Observation Room Dust Lead Levels

Table 7-3 provides an overview of results from statistical models developed to describe post-work floor and window sill dust-lead loadings in the Observation room across both residential units only and all units combined. The results are provided for the wipe samples only as there were no bulk samples found in the Observation room.

As in the other two rooms, both intensity level and job type are statistically significant when assessed by themselves – in Objective 1-Model 11, and Objective 1-Model 12, respectively. Again Job Type performs better than intensity level in explaining more variability in the floor and window sill dust-lead loadings as anticipated, achieving lower log-likelihood ratios. Objective 1-Models 13 and 14 investigate whether intensity level and job type were still statistically significant predictors of floor and window sill dust lead loadings after adjusting for the paint-lead loading on the surface being disturbed and area disturbed during the RRP activity. The summary of results provided in Table 7-3 demonstrate that both Intensity-Level and Job-Type are statistically significant predictors of post-work floor and window sill dust-lead loadings in the work room after adjusting for the effects of paint-lead loading and square footage disturbed. The addition of these two variables improved the predictive ability for floors, but not for window sills. Furthermore, average paint-lead loading on components disrupted by the RRP activity was a statistically significant predictor of dust-lead levels found in the Observation room in the post-work stage in most of the models.

Models were also developed to assess whether the use of plastic sheeting reduced dust-lead loadings found in the Observation room in the post work stage. Objective 1–Models 15 and 16 provide the results of these analyses. The use of plastic sheeting resulted in statistically significant reductions in post-work floor lead loadings in the Observation room for residential units only. This effect was only borderline significant in the combined data (p-value=.10), which included the COFs.

The detailed results in Table L3 of Appendix L report floor lead levels from the combined model 0.46 units less when plastic was used, which equates to a predicted GM 36.9% lower than when plastic was not used. The use of plastic sheeting did not significantly lower window sill dust lead loadings in the Observation room at the post-work stage. The effects of Job-Type and Intensity-Level were found to be statistically significant, after adjusting for the use of plastic sheeting in all models applied to dust lead loadings in the observation room at the post-work stage.

The best-fitting models differed across data sets for the post-work Observation room data. As highlighted in Table 7-3, the model adjusting for plastic use in addition to job type performed best for residential floors, while in the combined data the model adjusting for paint lead level and area disturbed performed better. For window sills, the model adjusting only for job type performed best. Section O3 of Appendix O contains the residual plots from these best fitting models, which indicate reasonable normal distributions for floors and some skewness for sills. If additional analyses are performed, these can be investigated further to determine impact of outliers in the window sill data.

Table 7-3: Post-Work Observation Room Modeling Results

| Model | Variables Included in Model | Floors | | | | Sills | | | |
|-----------------------|-----------------------------|-----------------|-------------------|----------|-------------------|-----------------|-------------------|----------|-------------------|
| | | All Residential | | Combined | | All Residential | | Combined | |
| | | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood |
| Objective 1: Model 11 | COF | . | 304.3 | 0.78 | 368.6 | . | 161.7 | 0.23 | 191.3 |
| | Intensity level | <.01 | | <.01 | | 0.02 | | 0.01 | |
| Objective 1: Model 12 | COF | . | 285.8 | 0.85 | 350.1 | . | 151.9 | 0.35 | 179.0 |
| | Job type | <.01 | | <.01 | | 0.04 | | 0.02 | |
| Objective 1: Model 13 | COF | . | 300.6 | 0.24 | 362.9 | . | 165.3 | 0.09 | 197.5 |
| | Square feet disturbed | 0.53 | | 0.58 | | 0.24 | | 0.64 | |
| | Avg. paint lead | <.01 | | <.01 | | <.01 | | 0.02 | |
| | Intensity level | <.01 | | <.01 | | 0.03 | | 0.03 | |
| Objective 1: Model 14 | COF | . | 285.3 | 0.54 | 344.5 | . | 158.1 | 0.23 | 184.5 |
| | Square feet disturbed | 0.18 | | 0.50 | | 0.97 | | 0.79 | |
| | Avg. paint lead | <.01 | | <.01 | | 0.09 | | 0.03 | |
| | Job type | <.01 | | <.01 | | 0.09 | | 0.03 | |
| Objective 1: Model 15 | COF | . | 298.8 | 0.78 | 366.1 | . | 161.9 | 0.24 | 191.9 |
| | Plastic | 0.02 | | 0.09 | | 0.83 | | 0.79 | |
| | Intensity level | <.01 | | <.01 | | 0.02 | | 0.02 | |
| Objective 1: Model 16 | COF | . | 280.4 | 0.86 | 348.1 | . | 152.1 | 0.35 | 179.6 |
| | Plastic | 0.02 | | 0.10 | | 0.80 | | 0.81 | |
| | Job type | <.01 | | <.01 | | 0.04 | | 0.03 | |

7.2. Post Cleaning Stage - Dust Lead Levels

The following three subsections provide an overview of statistical modeling results for floor and window sill dust lead loadings in the post-cleaning stage of the field study, in the Work room (subsection 7.2.1), Tool room (subsection 7.2.2), and Observation room (subsection 7.2.3).

7.2.1. Post-Cleaning Work Room Dust Lead Levels

Table 7-4 provides an overview of results from statistical models developed to describe post-cleaning floor and window sill dust lead loadings in the work room for residential units only and all units combined. The results are provided for the wipe samples only (as there were no bulk samples after the post-work stage). Below are some highlights of some of the models run for these data.

- Objective 1-Models 17 and 18 assess the total effects of Intensity-Level and Job-Type, respectively, on floor and window sill dust lead loadings in the Work room during the post-cleaning stage. Intensity-Level and Job-Type were shown to be statistically significant in all models.
- Objective 1-Models 19 and 20 investigate whether intensity level and job type are still statistically significant predictors of floor and window sill dust lead loadings after adjusting for the paint lead loading on the surface being disturbed and a measure of the square feet of lead-based paint disturbed during the RRP activity. The results in Table 7-4 demonstrate that both Intensity-Level and Job-Type remain statistically significant predictors of post-cleaning floor dust lead loadings in the Work room after adjusting for

the effects of paint lead loading and square footage disturbed. While average paint lead loading was found to be a significant predictor of post-cleaning floor dust lead loadings in the Work room – Models 19 and 20 did not improve the prediction over Models 17 and 18, as evidenced by a comparison of the log-likelihoods. Models 19 and 20 applied to the window sill dust lead loadings demonstrate that the addition of these two variables (average paint-lead loading and square footage disturbed) competes with intensity-level and job-type for predictive power, without improving the model fit.

- Objective 2–Model 1 assesses the total effect of using plastic sheeting on post-cleaning dust lead levels in the work room, which was not a statistically significant predictor (on its own) in any of the models applied to floor and window sill dust lead levels. Inspection of the parameter estimates from these models in Appendices I through M, however, demonstrates that use of plastic sheeting was consistently associated with lower predicted post-cleaning dust lead levels in the Work room.
- Objective 2–Models 2 through 5 assess whether the use of plastic is significant after adjusting for intensity-level or job-type, and whether there is any significant interaction between the use of plastic and either intensity-level or job-type when predicting floor and window sill dust lead loadings following cleaning in the work room. These results follow the same general trend as observed in Objective 2–Model 1, in which the use of plastic sheeting was not statistically significant, but inspection of the parameter estimates is suggestive of a modest protective effect.
- Objective 3–Model 1 assesses the total effect of using RRP rule cleaning on post-cleaning dust-lead levels in the Work room, which was highly statistically significant in lowering dust lead loadings in all of the models.
- Objective 3–Models 2 through 5 assess whether the use of RRP rule cleaning is significant after adjusting for intensity-level or job-type, and whether there is any significant interaction between the use of RRP rule cleaning and either intensity-level or job-type when predicting floor and window sill dust lead loadings following cleaning in the Work room. The use of RRP rule cleaning was highly significant in all models, even after adjusting for intensity-level or job-type. The addition of the interaction term between RRP rule cleaning and either intensity-level or job-type did not significantly improve the prediction of the model – suggesting that the effectiveness of RRP rule cleaning does not change as a function of intensity level or job type.
- The remaining models fit to the post-cleaning stage in the Work room investigate the simultaneous effects of using plastic sheeting and RRP rule cleaning by adding both of these terms and their interaction to the model. Objective 1 – Models 21 and 22 explore the interactive effects of plastic sheeting and RRP rule cleaning on dust lead loadings after adjusting for the effects of intensity-level (21) and job-type (22). Objective Y – Models 1 and 2 build further on these models by also adjusting for average paint lead loading, which was found to be a significant predictor in previously described models.

The results suggest that Model 22, which explains floor dust lead loading as a function of job-type, plastic sheeting, RRP rule cleaning, and the interaction between plastic sheeting and RRP rule cleaning, provides the best fit for the floor data. In this model, post-cleaning work room floor dust lead loadings were lowest in the experiments that combined both proposed rule cleaning and the use of plastic sheeting, next lowest for experiments that just the proposed RRP rule cleaning but not plastic, followed by experiments that only employed the use of plastic.

Each of these three combinations resulted in significantly lower floor dust lead loadings than found in experiments that had baseline cleaning and no use of plastic, as seen in the detailed parameter estimates found in Table I4 of Appendix I and Table L4 of Appendix L.

For window sills, the results suggest that Objective 3–Model 5 provides the best fit by adjusting for job type, cleaning method, and their interaction. It makes sense that use of plastic would have less impact on window sills, as the plastic did not cover the sills as it did floors. Table J4 of Appendix J and Table M4 of Appendix M contain the detailed parameter estimates for this model. Looking at some of the models that explores the differences between phases, such as Objective Y-Model 2, the results indicate that the window sill dust lead loadings were only found to be significantly lower for the experiments that employed proposed rule cleaning and use of plastic on its own did not yield statistically significant lower window sill dust lead loadings.

Section O4 of Appendix O contains the residual plots from some of the best-fitting models, which indicate reasonably normal distributions for floors and some skewness for sills. If additional analyses are performed, these can be investigated further to determine potential causes of normality in these residuals.

Table 7-4: Post-Cleaning Work Room Modeling Results

| Model | Variables Included in Model | Floors | | | | Sills | | | |
|-----------------------|--|------------------------------|-------------------|------------------------------|-------------------|----------------------|-------------------|----------------------|-------------------|
| | | All Residential | | Combined | | All Residential | | Combined | |
| | | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood |
| Objective 1: Model 17 | COF Intensity level | . | 529.6 | 0.16 | 646.6 | . | 173.6 | 0.45 | 208.5 |
| Objective 1: Model 18 | COF Job type | <.01 | 513.4 | <.01 | 634.4 | 0.14 | 164.1 | 0.21 | 197.8 |
| Objective 1: Model 19 | COF Square feet disturbed Avg. paint lead Intensity level | . | 529.2 | 0.02 | 646.5 | . | 178.8 | 0.33 | 216.1 |
| Objective 1: Model 20 | COF Square feet disturbed Avg. paint lead Job type | 0.60 <.01 <.01 | 516.8 | 0.90 <.01 <.01 | 630.5 | 0.18 0.05 0.10 | 171.2 | 0.32 0.16 0.08 | 205.7 |
| Objective 1: Model 21 | COF Avg. paint lead Clean*Plastic Intensity level | . | 510.2 | 0.01 | 623.0 | . | 162.8 | 0.29 | 195.6 |
| Objective 1: Model 22 | COF Avg. paint lead Clean*Plastic Job type | <.01 <.01 <.01 <.01 | 499.0 | <.01 <.01 <.01 <.01 | 607.4 | 0.09 0.02 0.11 | 153.4 | 0.06 <.01 0.03 | 184.1 |
| Objective 2: Model 1 | COF Plastic | . | 542.7 | 0.19 | 661.6 | 0.22 | 176.8 | 0.43 | 213.8 |
| Objective 2: Model 2 | COF Intensity level Plastic | 0.38 <.01 0.08 | 527.2 | 0.37 <.01 0.11 | 644.9 | 0.10 0.15 | 171.4 | 0.44 0.06 0.37 | 208.0 |
| Objective 2: Model 3 | COF Intensity level | . | 521.6 | 0.18 | 639.2 | 0.08 | 165.3 | 0.45 | 202.9 |

Table 7-4: (continued) Post-Cleaning Work Room Modeling Results

| Model | Variables Included in Model | Floors | | | | Sills | | | |
|----------------------|-----------------------------|-----------------|-------------------|----------|-------------------|-----------------|-------------------|----------|-------------------|
| | | All Residential | | Combined | | All Residential | | Combined | |
| | | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood |
| | Plastic | 0.03 | | 0.05 | | 0.15 | | 0.37 | |
| | Intensity level*Plastic | 0.15 | | 0.10 | | 0.25 | | 0.28 | |
| Objective 2: Model 4 | COF | . | 511.7 | 0.01 | 633.4 | . | 162.1 | 0.21 | 197.5 |
| | Job type | <.01 | | <.01 | | 0.12 | | 0.15 | |
| | Plastic | 0.14 | | 0.18 | | 0.17 | | 0.41 | |
| Objective 2: Model 5 | COF | . | 495.2 | 0.01 | 614.8 | . | 147.1 | 0.23 | 179.5 |
| | Job type | <.01 | | <.01 | | 0.14 | | 0.16 | |
| | Plastic | 0.15 | | 0.52 | | 0.16 | | 0.44 | |
| | Job type*Plastic | 0.10 | | 0.13 | | 0.56 | | 0.46 | |
| Objective 3: Model 1 | COF | . | 538.1 | 0.21 | 656.1 | . | 171.8 | 0.41 | 203.5 |
| | Clean | 0.02 | | <.01 | | 0.01 | | <.01 | |
| Objective 3: Model 2 | COF | . | 523.5 | 0.20 | 639.5 | . | 167.0 | 0.42 | 197.5 |
| | Intensity level | <.01 | | <.01 | | 0.12 | | 0.04 | |
| | Clean | <.01 | | <.01 | | 0.01 | | <.01 | |
| Objective 3: Model 3 | COF | . | 521.2 | 0.21 | 636.6 | . | 161.6 | 0.42 | 194.3 |
| | Intensity level | <.01 | | <.01 | | 0.14 | | 0.05 | |
| | Clean | <.01 | | <.01 | | 0.01 | | <.01 | |
| | Intensity level*Clean | 0.76 | | 0.41 | | 0.27 | | 0.54 | |
| Objective 3: Model 4 | COF | . | 506.1 | <.01 | 627.0 | . | 156.1 | 0.19 | 185.2 |
| | Job type | <.01 | | <.01 | | 0.07 | | 0.05 | |
| | Clean | <.01 | | <.01 | | <.01 | | <.01 | |
| Objective 3: Model 5 | COF | . | 494.9 | <.01 | 614.0 | . | 140.9 | 0.19 | 169.5 |
| | Job type | <.01 | | <.01 | | 0.08 | | 0.08 | |
| | Clean | <.01 | | <.01 | | <.01 | | <.01 | |
| | Job type*Clean | 0.57 | | 0.58 | | 0.36 | | 0.47 | |
| Objective Y: Model 1 | COF | . | 509.9 | 0.11 | 621.8 | . | 155.4 | 0.72 | 186.3 |
| | Intensity level | 0.74 | | 0.75 | | 0.49 | | 0.61 | |
| | Avg. PostWork Work | | | | | | | | |
| | Floor Lead | <.01 | | <.01 | | <.01 | | <.01 | |
| | Clean*Plastic | 0.01 | | <.01 | | 0.03 | | <.01 | |
| Objective Y: Model 2 | COF | . | 500.4 | 0.02 | 615.6 | . | 148.4 | 0.37 | 177.4 |
| | Job type | 0.08 | | 0.64 | | 0.55 | | 0.57 | |
| | Avg. PostWork Work | | | | | | | | |
| | Floor Lead | 0.04 | | <.01 | | 0.03 | | <.01 | |
| | Clean*Plastic | 0.01 | | <.01 | | 0.02 | | <.01 | |

7.2.2. Post-Cleaning Tool Room Dust Lead Levels

Table 7-5 provides an overview of results from statistical models developed to describe post-cleaning floor and window sill dust-lead loadings in the Tool room across residential units only and all units combined. The results provided are for wipe samples only as there were no bulk samples found in the Tool room. The bullets below summarize the various models tested.

- Objective 1-Models 23 and 24 assess the total effects of Intensity-Level and Job-Type, respectively, on floor and window sill dust lead loadings in the Tool room during the

post-cleaning stage. Intensity-Level and Job-Type were shown to be statistically significant in all models.

- Regarding Objective 1-Models 25 and 26, the results provided in Table 7-5 demonstrate that both Intensity-Level and Job-Type remain statistically significant predictors of post cleaning floor dust-lead loadings in the Tool room after adjusting for the effects of paint lead loading and square footage disturbed. While average paint-lead loading was found to be a significant predictor of post-cleaning floor and window sill dust lead loadings in the Tool room for most of the models – Models 25 and 26 did not improve the prediction over Models 23 and 24, as evidenced by a comparison of the log-likelihoods.
- Objective 2–Model 6 assesses the total effect of using plastic sheeting on post-cleaning dust lead levels in the tool room, which was not a statistically significant predictor (on its own) in any of the models applied to floor and window sill dust lead levels. Inspection of the parameter estimates from these models in Appendices I through M, however, demonstrates that use of plastic sheeting is consistently associated with lower predicted post-cleaning dust-lead levels in the Tool room.
- Objective 2–Models 7 through 10 assess whether the use of plastic is significant after adjusting for intensity-level or job-type, and whether there is any significant interaction between the use of plastic and either intensity-level or job-type when predicting floor and window sill dust lead loadings following cleaning in the Work room. The results of these analyses suggest that there may be a significant interaction between the use of plastic and job-type when explaining both floor and window sill dust-lead loadings in the tool room following cleaning – and that these models provided the best fit of the data compared to any of the remaining models described below.
- Objective 3–Model 6 assesses the total effect of using the proposed Rule cleaning on post-cleaning dust lead levels in the Tool room, and Objective 3–Models 7 through 10 assess this effect after adjusting for intensity and job-type and their interaction with cleaning method. As anticipated, the method of cleaning applied in the Work room did not influence floor or window sill dust lead levels in the Tool room.
- The remaining models fit to the post-cleaning stage in the Tool room investigate the simultaneous effects of using plastic sheeting and proposed rule cleaning by adding both of these terms and their interaction to the model. These models did not improve upon the models that simply adjusted for the interaction between use of plastic and job-type.

As noted above, Objective2-Model 10 provided the best fit for all four data sets – residential floors and sills and combined floors and sills. Although use of plastic is not found to be significant by this model, there are significant or borderline significant interactions between job type and use of plastic for the floor data. Section O5 in Appendix O contains residual plots for these models, which all are reasonably normally distributed.

Table 7-5: Post-Cleaning Tool Room Modeling Results

| Model | Variables Included in Model | Floors | | | | Sills | | | |
|-----------------------|-----------------------------|-----------------|-------------------|----------|-------------------|-----------------|-------------------|----------|-------------------|
| | | All Residential | | Combined | | All Residential | | Combined | |
| | | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood |
| Objective 1: Model 23 | COF | . | 315.6 | 0.40 | 411.6 | . | 171.4 | 0.25 | 204.9 |
| | Intensity level | <.01 | | <.01 | | 0.05 | | 0.04 | |
| Objective 1: Model 24 | COF | . | 297.9 | 0.39 | 392.8 | . | 157.9 | 0.24 | 189.8 |
| | Job type | <.01 | | <.01 | | 0.02 | | 0.02 | |
| Objective 1: Model 25 | COF | . | 319.0 | 0.08 | 415.4 | . | 168.7 | 0.05 | 205.8 |
| | Square feet disturbed | 0.91 | | 0.97 | | 0.06 | | 0.10 | |
| | Avg. paint lead | <.01 | | <.01 | | <.01 | | <.01 | |
| | Intensity level | <.01 | | <.01 | | <.01 | | 0.01 | |
| Objective 1: Model 26 | COF | . | 300.2 | 0.26 | 392.2 | . | 160.8 | 0.15 | 194.0 |
| | Square feet disturbed | 0.08 | | 0.20 | | 0.97 | | 0.83 | |
| | Avg. paint lead | 0.11 | | <.01 | | 0.02 | | 0.02 | |
| | Job type | <.01 | | <.01 | | 0.03 | | 0.03 | |
| Objective 1: Model 27 | COF | . | 309.2 | 0.21 | 405.9 | . | 161.0 | 0.08 | 197.5 |
| | Avg. paint lead | 0.01 | | <.01 | | <.01 | | <.01 | |
| | Clean*Plastic | 0.54 | | 0.52 | | 0.36 | | 0.31 | |
| | Intensity level | <.01 | | <.01 | | 0.02 | | 0.01 | |
| Objective 1: Model 28 | COF | . | 294.3 | 0.27 | 385.5 | . | 151.1 | 0.12 | 184.3 |
| | Avg. paint lead | 0.05 | | <.01 | | 0.02 | | 0.01 | |
| | Clean*Plastic | 0.53 | | 0.40 | | 0.44 | | 0.32 | |
| | Job type | <.01 | | <.01 | | 0.03 | | 0.02 | |
| Objective 2: Model 6 | COF | . | 328.0 | 0.41 | 424.5 | . | 176.4 | 0.23 | 210.3 |
| | Plastic | 0.34 | | 0.42 | | 0.20 | | 0.20 | |
| Objective 2: Model 7 | COF | . | 312.5 | 0.40 | 410.3 | . | 168.7 | 0.24 | 202.7 |
| | Intensity level | <.01 | | <.01 | | 0.03 | | 0.02 | |
| | Plastic | 0.07 | | 0.18 | | 0.11 | | 0.12 | |
| Objective 2: Model 8 | COF | . | 305.6 | 0.41 | 404.3 | . | 160.7 | 0.25 | 198.2 |
| | Intensity level | <.01 | | <.01 | | 0.04 | | 0.03 | |
| | Plastic | 0.16 | | 0.29 | | 0.24 | | 0.18 | |
| | Intensity level*Plastic | 0.14 | | 0.15 | | 0.10 | | 0.36 | |
| Objective 2: Model 9 | COF | . | 295.5 | 0.39 | 391.9 | . | 155.5 | 0.24 | 187.9 |
| | Job type | <.01 | | <.01 | | 0.01 | | 0.02 | |
| | Plastic | 0.10 | | 0.20 | | 0.12 | | 0.13 | |
| Objective 2: Model 10 | COF | . | 277.4 | 0.42 | 370.5 | . | 137.8 | 0.27 | 168.7 |
| | Job type | <.01 | | <.01 | | 0.01 | | 0.02 | |
| | Plastic | 0.30 | | 0.52 | | 0.40 | | 0.44 | |
| | Job type*Plastic | 0.06 | | 0.04 | | 0.16 | | 0.21 | |
| Objective 3: Model 6 | COF | . | 329.0 | 0.42 | 425.2 | . | 178.1 | 0.25 | 212.0 |
| | Clean | 0.96 | | 0.77 | | 0.77 | | 0.97 | |
| Objective 3: Model 7 | COF | . | 315.8 | 0.41 | 412.1 | . | 171.2 | 0.25 | 205.3 |
| | Intensity level | <.01 | | <.01 | | 0.05 | | 0.04 | |
| | Clean | 0.91 | | 0.72 | | 0.61 | | 0.90 | |
| Objective 3: Model 8 | COF | . | 311.7 | 0.41 | 408.2 | . | 168.0 | 0.26 | 202.9 |
| | Intensity level | <.01 | | <.01 | | 0.07 | | 0.05 | |
| | Clean | 0.83 | | 0.73 | | 0.68 | | 0.91 | |
| | Intensity level*Clean | 0.57 | | 0.43 | | 0.97 | | 0.98 | |

Table 7-5: (continued) Post-Cleaning Tool Room Modeling Results

| Model | Variables Included in Model | Floors | | | | Sills | | | |
|-----------------------|-------------------------------|-----------------|-------------------|----------|-------------------|-----------------|-------------------|----------|-------------------|
| | | All Residential | | Combined | | All Residential | | Combined | |
| | | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood |
| Objective 3: Model 9 | COF | . | 298.1 | 0.41 | 392.9 | . | 158.0 | 0.24 | 190.2 |
| | Job type | <.01 | | <.01 | | 0.02 | | 0.02 | |
| | Clean | 0.81 | | 0.40 | | 0.89 | | 0.79 | |
| Objective 3: Model 10 | COF | . | 285.6 | 0.41 | 379.3 | . | 146.5 | 0.24 | 176.7 |
| | Job type | <.01 | | <.01 | | 0.03 | | 0.03 | |
| | Clean | 0.97 | | 0.70 | | 0.97 | | 0.68 | |
| | Job type*Clean | 0.62 | | 0.69 | | 0.92 | | 0.85 | |
| Objective Y: Model 3 | COF | . | 308.5 | 0.51 | 402.0 | . | 165.0 | 0.43 | 197.5 |
| | Intensity level | 0.25 | | 0.12 | | 0.80 | | 0.92 | |
| | Avg. PostWork Work Floor Lead | <.01 | | <.01 | | 0.01 | | <.01 | |
| | Plastic | 0.23 | | 0.22 | | 0.19 | | 0.12 | |
| Objective Y: Model 4 | COF | . | 296.9 | 0.48 | 391.2 | . | 155.5 | 0.36 | 186.1 |
| | Job type | 0.04 | | 0.06 | | 0.39 | | 0.43 | |
| | Avg. PostWork Work Floor Lead | 0.62 | | 0.08 | | 0.21 | | 0.05 | |
| | Plastic | 0.14 | | 0.24 | | 0.18 | | 0.14 | |

7.2.3. Post-Cleaning Observation Room Dust Lead Levels

Table 7-6 provides an overview of statistical modeling results post-cleaning floor and window sill dust-lead loadings in the Observation room across the residential units only and all units combined data sets. The results are provided for wipe samples only as there were no bulk samples found in the Observation room. The bullets below summarize findings from the various models.

- Objective 1-Models 29 and 30 assess the total effects of Intensity-Level and Job-Type, respectively, on floor and window sill dust lead loadings in the work room during the post-cleaning stage. Intensity-Level and Job-Type were shown to be statistically significant in all models.
- Objective 1-Models 31 and 32 investigate whether intensity level and job type are still statistically significant predictors of floor and window sill dust lead loadings after adjusting for the paint lead loading on the surface being disturbed and a measure of the square feet of lead-based paint disturbed during the RRP activity. The summary of results provided in Table 7-6 demonstrates that both Intensity-Level and Job-Type remain statistically significant predictors of post-cleaning floor dust-lead loadings in the Observation room after adjusting for the effects of paint lead loading and square footage disturbed. While average paint-lead loading was found to be a significant predictor of post-cleaning floor and window sill dust lead loadings in the Observation room in all of the models – these more complex models did not always improve the prediction over Models 29 and 30, suggesting that these terms may compete with intensity-level and job-type for explanatory power.
- Objective 2–Model 11 assesses the total effect of using plastic sheeting on post-cleaning dust-lead levels in the observation room, which a statistically significant predictor for

floors in residential units (p-value = 0.03) and nearly significant for all units (p-value = 0.06). The total effect of plastic on lowering window sill dust lead levels in the Observation room was borderline significant (p-value of 0.10 in residential units and 0.12 in all units combined).

- Objective 2–Models 12 through 15 assess whether the use of plastic was significant after adjusting for intensity-level or job-type, and whether there was any significant interaction between the use of plastic and either intensity-level or job-type when predicting floor and window sill dust lead loadings following cleaning in the work room. Although the F-test associated with the interaction term was not statistically significant across any of these models, Objective 2 – Model 15 provided the best fit of the data across floors and window sills within both subsets of data explored.
- Objective 3–Model 11 assesses the total effect of using the proposed Rule cleaning method on post-cleaning dust-lead levels in the Observation room, and Objective 3–Models 12 through 15 assess this effect after adjusting for intensity and job-type and their interaction with cleaning method. As in the Tool room, the method of cleaning applied in the Work room did not influence floor or window sill dust lead levels in the Observation room.
- The remaining models fit to the post-cleaning stage in the Observation room investigate the simultaneous effects of using plastic sheeting and RRP rule cleaning by adding both of these terms and their interaction to the model. These models did not significantly improve upon the models that simply adjusted for the interaction between use of plastic and job-type.

As noted above, Objective2-Model 15 provided the best fit for all four data sets – residential floors and sills and combined floors and sills. Although use of plastic is not found to be significant by this model, there are significant or borderline significant interactions between job type and use of plastic for the floor data. Section O6 in Appendix O contains residual plots for these models, which all are reasonably normally distributed.

Table 7-6: Post-Cleaning Observation Room Modeling Results

| Model | Variables Included in Model | Floors | | | | Sills | | | |
|-----------------------|-----------------------------|-----------------|-------------------|----------|-------------------|-----------------|-------------------|----------|-------------------|
| | | All Residential | | Combined | | All Residential | | Combined | |
| | | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood |
| Objective 1: Model 29 | COF | . | 298.7 | 0.61 | 363.3 | . | 154.6 | 0.22 | 179.5 |
| | Intensity level | <.01 | | <.01 | | 0.08 | | 0.07 | |
| Objective 1: Model 30 | COF | . | 281.6 | 0.50 | 349.0 | . | 137.5 | 0.33 | 157.1 |
| | Job type | <.01 | | <.01 | | <.01 | | <.01 | |
| Objective 1: Model 31 | COF | . | 294.3 | 0.26 | 356.8 | . | 154.2 | 0.07 | 185.1 |
| | Square feet disturbed | 0.28 | | 0.23 | | 0.19 | | 0.43 | |
| | Avg. paint lead | <.01 | | <.01 | | <.01 | | 0.01 | |
| | Intensity level | <.01 | | <.01 | | 0.04 | | 0.09 | |
| Objective 1: Model 32 | COF | . | 283.6 | 0.36 | 344.6 | . | 138.5 | 0.28 | 160.0 |
| | Square feet disturbed | 0.79 | | 0.80 | | 0.15 | | 0.03 | |
| | Avg. paint lead | <.01 | | <.01 | | 0.04 | | 0.09 | |
| | Job type | <.01 | | <.01 | | <.01 | | <.01 | |
| Objective 1: Model 33 | COF | . | 277.9 | 0.24 | 343.1 | . | 145.0 | 0.09 | 175.5 |
| | Avg. paint lead | <.01 | | <.01 | | <.01 | | 0.02 | |

Table 7-6: (continued) Post-Cleaning Observation Room Modeling Results

| Model | Variables Included in Model | Floors | | | | Sills | | | |
|-----------------------|-------------------------------|-----------------|-------------------|----------|-------------------|-----------------|-------------------|----------|-------------------|
| | | All Residential | | Combined | | All Residential | | Combined | |
| | | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood |
| | Clean*Plastic | 0.01 | | 0.03 | | 0.26 | | 0.25 | |
| | Intensity level | <.01 | | <.01 | | 0.03 | | 0.04 | |
| Objective 1: Model 34 | COF | . | 265.7 | 0.37 | 330.4 | . | 130.9 | 0.25 | 155.8 |
| | Avg. paint lead | <.01 | | <.01 | | 0.02 | | 0.05 | |
| | Clean*Plastic | <.01 | | 0.03 | | 0.26 | | 0.22 | |
| | Job type | <.01 | | <.01 | | <.01 | | <.01 | |
| Objective 2: Model 11 | COF | . | 311.1 | 0.69 | 376.7 | . | 156.8 | 0.19 | 182.2 |
| | Plastic | 0.03 | | 0.06 | | 0.10 | | 0.12 | |
| Objective 2: Model 12 | COF | . | 288.9 | 0.59 | 358.1 | . | 150.5 | 0.22 | 176.7 |
| | Intensity level | <.01 | | <.01 | | 0.02 | | 0.03 | |
| | Plastic | <.01 | | 0.02 | | 0.03 | | 0.06 | |
| Objective 2: Model 13 | COF | . | 286.3 | 0.60 | 355.1 | . | 147.2 | 0.22 | 174.1 |
| | Intensity level | <.01 | | <.01 | | 0.05 | | 0.05 | |
| | Plastic | <.01 | | 0.03 | | 0.07 | | 0.09 | |
| | Intensity level*Plastic | 0.75 | | 0.63 | | 0.61 | | 0.55 | |
| Objective 2: Model 14 | COF | . | 270.8 | 0.72 | 343.4 | . | 133.4 | 0.34 | 154.0 |
| | Job type | <.01 | | <.01 | | <.01 | | <.01 | |
| | Plastic | <.01 | | 0.01 | | 0.03 | | 0.04 | |
| Objective 2: Model 15 | COF | . | 259.7 | 0.74 | 326.6 | . | 120.9 | 0.35 | 139.4 |
| | Job type | <.01 | | <.01 | | <.01 | | <.01 | |
| | Plastic | <.01 | | 0.06 | | 0.14 | | 0.20 | |
| | Job type*Plastic | 0.62 | | 0.27 | | 0.36 | | 0.22 | |
| Objective 3: Model 11 | COF | . | 316.1 | 0.72 | 380.2 | . | 159.3 | 0.21 | 184.4 |
| | Clean | 0.75 | | 0.81 | | 0.60 | | 0.60 | |
| Objective 3: Model 12 | COF | . | 298.5 | 0.62 | 363.6 | . | 154.7 | 0.22 | 180.1 |
| | Intensity level | <.01 | | <.01 | | 0.08 | | 0.07 | |
| | Clean | 0.49 | | 0.61 | | 0.54 | | 0.55 | |
| Objective 3: Model 13 | COF | . | 294.2 | 0.62 | 360.7 | . | 151.6 | 0.22 | 178.1 |
| | Intensity level | <.01 | | <.01 | | 0.11 | | 0.09 | |
| | Clean | 0.50 | | 0.61 | | 0.49 | | 0.51 | |
| | Intensity level*Clean | 0.44 | | 0.66 | | 0.66 | | 0.69 | |
| Objective 3: Model 14 | COF | . | 281.9 | 0.50 | 349.6 | . | 138.3 | 0.33 | 158.3 |
| | Job type | <.01 | | <.01 | | <.01 | | <.01 | |
| | Clean | 0.66 | | 0.84 | | 0.92 | | 0.95 | |
| Objective 3: Model 15 | COF | . | 269.3 | 0.51 | 335.9 | . | 127.8 | 0.30 | 147.9 |
| | Job type | <.01 | | <.01 | | 0.02 | | <.01 | |
| | Clean | 0.63 | | 0.76 | | 0.77 | | 0.85 | |
| | Job type*Clean | 0.55 | | 0.71 | | 0.65 | | 0.68 | |
| Objective Y: Model 5 | COF | . | 284.4 | 0.92 | 351.4 | . | 148.5 | 0.36 | 173.1 |
| | Intensity level | 0.02 | | 0.04 | | 0.81 | | 0.84 | |
| | Avg. PostWork Work Floor Lead | <.01 | | <.01 | | 0.03 | | 0.01 | |
| | Plastic | <.01 | | 0.01 | | 0.08 | | 0.06 | |
| Objective Y: Model 6 | COF | . | 272.4 | 0.99 | 340.2 | . | 134.6 | 0.44 | 155.1 |
| | Job type | <.01 | | 0.02 | | 0.04 | | 0.01 | |
| | Avg. PostWork Work Floor Lead | 0.51 | | 0.02 | | 0.32 | | 0.23 | |
| | Plastic | <.01 | | 0.01 | | 0.05 | | 0.04 | |

7.3. Post-Verification Stage Dust Lead Levels

The following three subsections provide an overview of statistical modeling results for floor and window sill dust lead loading results in the post-verification stage of the field study, in the Work room (subsection 7.3.1), Tool room (subsection 7.3.2), and Observation room (subsection 7.3.3).

7.3.1. Post-Verification Work Room Dust Lead Levels

Table 7-7 provides an overview of results from statistical models developed to describe post-verification floor and window sill dust lead loadings in the work room across the two subsets of data described earlier (residential units only and all units combined). Detailed floor and sill modeling results are contained in Appendices I through M. It is important to keep in mind when considering the Work room data at the post-verification stage that zones of the work room that failed a cleaning verification step underwent recleaning using the proposed Rule cleaning method, regardless of which cleaning method was used at the post-cleaning stage. The bullets below summarize the various models run to explore the post-verification Work room data.

- Objective 1-Models 35 and 36 indicate that Intensity-Level and Job-Type were shown to be statistically significant predictors of post-verification floor dust lead loadings – but not significant predictors of window sill dust-lead loadings.
- Objective 1-Models 37 and 38 demonstrate that intensity-level and job-type are still statistically significant predictors of floor dust lead loadings after adjusting for the paint-lead loading on the surface being disturbed and a measure of the square feet of lead-based paint disturbed during the RRP activity. Average paint-lead loading was found to be a significant predictor of post-verification floor dust lead loadings in the Work room. None of the variables in Models 37 and 38 appeared significantly predictive of window sill dust-lead loadings in the Work room following verification.
- The remaining models fit to the post-verification dust lead loadings in the Work room were largely unremarkable – with the remaining variables (use of plastic, cleaning method, etc.) failing to explain a major portion of variability in post-verification dust lead results. This result suggests that the verification step acts as an equalizer – removing the factors that previously explained elevated dust lead levels in earlier phases of the experiment.
- The fact that intensity-level, job-type, and average paint lead loading are still predictive of post-verification floor dust-lead levels may be a concern. On the other hand, over half of all experiments ended with the average post-verification floor lead levels below 40 $\mu\text{g}/\text{ft}^2$ indicating that the various cleaning techniques utilized were able to return floor levels to a clean condition in the majority of experiments.

Objective 3-Model 20 provided the best fit for three of the four data sets – residential floors and residential and combined sills. This model adjusted for cleaning method, job type, and their interaction. This model performed well for the combined floor data set as well, but Objective 1-Model 40, which adjusted for phase (Clean*Plastic) and average paint lead, may have performed slightly better. Cleaning method was no longer significant at the post-verification stage. Section O7 in Appendix O contains residual plots for these models. The residuals from the floor models

are normally distributed, although there does appear to be an outlier on the upper end of the distribution. The sill models appear to contain some skewness in the residuals.

Table 7-7: Post-Verification Work Room Modeling Results

| Model | Variables Included in Model | Floors | | | | Sills | | | |
|-----------------------|-----------------------------|-----------------|-------------------|----------|-------------------|-----------------|-------------------|----------|-------------------|
| | | All Residential | | Combined | | All Residential | | Combined | |
| | | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood |
| Objective 1: Model 35 | COF | . | 542.0 | 0.16 | 640.6 | . | 167.9 | 0.33 | 194.3 |
| | Intensity level | <.01 | | <.01 | | 0.27 | | 0.10 | |
| Objective 1: Model 36 | COF | . | 520.1 | <.01 | 627.8 | . | 155.6 | 0.12 | 180.5 |
| | Job type | <.01 | | <.01 | | 0.08 | | 0.06 | |
| Objective 1: Model 37 | COF | . | 536.3 | 0.02 | 639.8 | . | 174.5 | 0.30 | 204.3 |
| | Square feet disturbed | 0.92 | | 0.53 | | 0.94 | | 0.70 | |
| | Avg. paint lead | <.01 | | <.01 | | 0.09 | | 0.50 | |
| | Intensity level | <.01 | | <.01 | | 0.28 | | 0.13 | |
| Objective 1: Model 38 | COF | . | 522.4 | <.01 | 623.8 | . | 161.5 | 0.17 | 187.8 |
| | Square feet disturbed | 0.81 | | 0.91 | | 0.12 | | 0.09 | |
| | Avg. paint lead | <.01 | | <.01 | | 0.69 | | 0.90 | |
| | Job type | <.01 | | <.01 | | 0.08 | | 0.03 | |
| Objective 1: Model 39 | COF | . | 526.9 | 0.02 | 629.3 | . | 164.4 | 0.27 | 195.1 |
| | Avg. paint lead | <.01 | | <.01 | | 0.09 | | 0.40 | |
| | Clean*Plastic | 0.27 | | 0.10 | | 0.48 | | 0.44 | |
| | Intensity level | <.01 | | <.01 | | 0.24 | | 0.14 | |
| Objective 1: Model 40 | COF | . | 514.3 | <.01 | 614.3 | . | 153.5 | 0.12 | 181.1 |
| | Avg. paint lead | <.01 | | <.01 | | 0.40 | | 0.59 | |
| | Clean*Plastic | 0.42 | | 0.17 | | 0.37 | | 0.35 | |
| | Job type | <.01 | | <.01 | | 0.13 | | 0.07 | |
| Objective 2: Model 16 | COF | . | 556.5 | 0.19 | 658.9 | . | 170.0 | 0.30 | 198.0 |
| | Plastic | 0.40 | | 0.51 | | 0.29 | | 0.34 | |
| Objective 2: Model 17 | COF | . | 539.9 | 0.17 | 639.9 | . | 166.5 | 0.33 | 193.4 |
| | Intensity level | <.01 | | <.01 | | 0.22 | | 0.08 | |
| | Plastic | 0.09 | | 0.18 | | 0.22 | | 0.23 | |
| Objective 2: Model 18 | COF | . | 535.4 | 0.17 | 637.4 | . | 163.1 | 0.33 | 191.1 |
| | Intensity level | <.01 | | <.01 | | 0.22 | | 0.09 | |
| | Plastic | 0.06 | | 0.16 | | 0.22 | | 0.24 | |
| | Intensity level*Plastic | 0.24 | | 0.47 | | 0.89 | | 0.93 | |
| Objective 2: Model 19 | COF | . | 518.0 | <.01 | 627.5 | . | 154.3 | 0.12 | 179.8 |
| | Job type | <.01 | | <.01 | | 0.07 | | 0.06 | |
| | Plastic | 0.08 | | 0.26 | | 0.22 | | 0.26 | |
| Objective 2: Model 20 | COF | . | 508.2 | <.01 | 617.0 | . | 142.2 | 0.12 | 166.8 |
| | Job type | <.01 | | <.01 | | 0.10 | | 0.08 | |
| | Plastic | 0.10 | | 0.39 | | 0.27 | | 0.33 | |
| | Job type*Plastic | 0.69 | | 0.89 | | 0.86 | | 0.92 | |
| Objective 3: Model 16 | COF | . | 556.6 | 0.21 | 658.2 | . | 170.8 | 0.30 | 198.2 |
| | Clean | 0.42 | | 0.26 | | 0.56 | | 0.38 | |
| Objective 3: Model 17 | COF | . | 542.1 | 0.19 | 640.2 | . | 167.8 | 0.32 | 194.2 |
| | Intensity level | <.01 | | <.01 | | 0.28 | | 0.11 | |
| | Clean | 0.41 | | 0.20 | | 0.58 | | 0.41 | |

Table 7-7: (continued) Post-Verification Work Room Modeling Results

| Model | Variables Included in Model | Floors | | | | Sills | | | |
|-----------------------|-------------------------------|-----------------|-------------------|----------|-------------------|-----------------|-------------------|----------|-------------------|
| | | All Residential | | Combined | | All Residential | | Combined | |
| | | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood |
| Objective 3: Model 18 | COF | . | 540.2 | 0.20 | 639.2 | . | 164.3 | 0.32 | 191.8 |
| | Intensity level | <.01 | | <.01 | | 0.33 | | 0.13 | |
| | Clean | 0.41 | | 0.20 | | 0.62 | | 0.45 | |
| | Intensity level*Clean | 0.92 | | 0.92 | | 0.73 | | 0.81 | |
| Objective 3: Model 19 | COF | . | 520.2 | <.01 | 627.5 | . | 155.0 | 0.12 | 179.7 |
| | Job type | <.01 | | <.01 | | 0.07 | | 0.05 | |
| | Clean | 0.39 | | 0.25 | | 0.39 | | 0.24 | |
| Objective 3: Model 20 | COF | . | 505.6 | <.01 | 612.7 | . | 142.8 | 0.13 | 165.5 |
| | Job type | <.01 | | <.01 | | 0.10 | | 0.09 | |
| | Clean | 0.49 | | 0.39 | | 0.45 | | 0.18 | |
| | Job type*Clean | 0.11 | | 0.27 | | 0.76 | | 0.68 | |
| Objective X: Model 7 | COF | . | 534.9 | 0.31 | 632.9 | . | 156.5 | 0.48 | 185.3 |
| | Intensity level | 0.90 | | 0.59 | | 0.39 | | 0.45 | |
| | Avg. PostWork Work Floor Lead | <.01 | | <.01 | | <.01 | | <.01 | |
| | Clean*Plastic | 0.67 | | 0.35 | | 0.64 | | 0.47 | |
| Objective X: Model 8 | COF | . | 517.6 | <.01 | 623.9 | . | 148.8 | 0.21 | 175.4 |
| | Job type | <.01 | | 0.01 | | 0.42 | | 0.43 | |
| | Avg. PostWork Work Floor Lead | 0.17 | | <.01 | | 0.04 | | 0.04 | |
| | Clean*Plastic | 0.42 | | 0.48 | | 0.54 | | 0.41 | |

7.3.2. Post-Verification Tool Room Dust Lead Levels

Table 7-8 provides an overview of results from models developed to describe post-verification floor and window sill dust lead loadings in the Tool room. The bullets below summarize the various models run.

- Objective 1-Models 41 and 42 assess the total effects of Intensity-Level and Job-Type, respectively, on floor and window sill dust lead loadings in the Tool room during the post-verification stage. Job-Type was shown to still be a statistically significant predictor of post-verification floor dust lead loadings – but not a significant predictor of window sill dust lead loadings. Intensity-level was not a significant predictor of post-verification floor or window sill post-verification dust lead levels in the Tool room.
- In the remaining models fit to the data, average paint lead loading appeared to be predictive of window sill dust lead levels – and models that accounted for the combined effects of job type and cleaning method appeared to be most predictive of window sill dust-lead loadings. Similarly, average paint lead levels appeared only marginally predictive of floor dust-lead loadings, and models that accounted for the combined effects of job-type and use of plastic provided the best fit for the post-verification floor dust lead models for the Tool room.

Objective 2-Model 25, which adjusted for job type, plastic, and their interaction, appeared to be the best-fitting model for the floor lead data. Use of plastic was significant in residential units, but not significant when including the COF data in the analysis. Note that the COF variable was

significant indicating differences between the residential units and the school. In the school, the classroom being worked on was separated into both the Work room and Tool room whereas in houses the Tool room was an adjacent room usually accessed through a doorway. This difference may impact the Tool room results. Interestingly, Objective3-Model 25 fits the sill data best and found a borderline significance for cleaning method in the combined data set. Section O8 in Appendix O contains residual plots for these models. As with most of the other analyses, the residuals from the floor models appear normally distributed while the residuals from the sill models are somewhat skewed.

Table 7-8: Post-Verification Tool Room Modeling Results

| Model | Variables Included in Model | Floors | | | | Sills | | | |
|-----------------------|-----------------------------|-----------------|-------------------|----------|-------------------|-----------------|-------------------|----------|-------------------|
| | | All Residential | | Combined | | All Residential | | Combined | |
| | | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood |
| Objective 1: Model 41 | COF | . | 351.2 | 0.42 | 452.6 | . | 181.6 | 0.29 | 217.2 |
| | Intensity level | 0.08 | | 0.03 | | 0.25 | | 0.13 | |
| Objective 1: Model 42 | COF | . | 334.5 | 0.06 | 436.8 | . | 172.7 | 0.43 | 206.4 |
| | Job type | <.01 | | <.01 | | 0.28 | | 0.23 | |
| Objective 1: Model 43 | COF | . | 357.7 | 0.14 | 461.2 | . | 179.8 | 0.09 | 222.2 |
| | Square feet disturbed | 0.96 | | 0.90 | | 0.19 | | 0.33 | |
| | Avg. paint lead | 0.09 | | 0.10 | | <.01 | | 0.02 | |
| | Intensity level | 0.10 | | 0.06 | | 0.08 | | 0.12 | |
| Objective 1: Model 44 | COF | . | 342.5 | 0.04 | 444.5 | . | 173.0 | 0.32 | 212.5 |
| | Square feet disturbed | 0.67 | | 0.98 | | 0.89 | | 0.64 | |
| | Avg. paint lead | 0.74 | | 0.16 | | <.01 | | 0.08 | |
| | Job type | 0.02 | | 0.02 | | 0.28 | | 0.32 | |
| Objective 1: Model 45 | COF | . | 342.7 | 0.13 | 447.3 | . | 170.2 | 0.04 | 209.9 |
| | Avg. paint lead | 0.14 | | 0.10 | | <.01 | | <.01 | |
| | Clean*Plastic | 0.08 | | 0.09 | | 0.41 | | 0.13 | |
| | Intensity level | 0.03 | | 0.02 | | 0.17 | | 0.14 | |
| Objective 1: Model 46 | COF | . | 328.0 | 0.03 | 431.7 | . | 162.4 | 0.19 | 200.3 |
| | Avg. paint lead | 0.79 | | 0.15 | | <.01 | | 0.02 | |
| | Clean*Plastic | 0.07 | | 0.10 | | 0.40 | | 0.13 | |
| | Job type | <.01 | | <.01 | | 0.25 | | 0.28 | |
| Objective 2: Model 21 | COF | . | 354.7 | 0.37 | 457.8 | . | 185.1 | 0.25 | 221.3 |
| | Plastic | 0.12 | | 0.16 | | 0.65 | | 0.49 | |
| Objective 2: Model 22 | COF | . | 347.4 | 0.39 | 450.0 | . | 181.0 | 0.28 | 216.7 |
| | Intensity level | 0.04 | | 0.02 | | 0.24 | | 0.12 | |
| | Plastic | 0.06 | | 0.09 | | 0.56 | | 0.41 | |
| Objective 2: Model 23 | COF | . | 341.9 | 0.40 | 445.7 | . | 176.4 | 0.28 | 213.4 |
| | Intensity level | 0.04 | | 0.02 | | 0.29 | | 0.15 | |
| | Plastic | 0.06 | | 0.10 | | 0.66 | | 0.47 | |
| | Intensity level*Plastic | 0.41 | | 0.46 | | 0.71 | | 0.88 | |
| Objective 2: Model 24 | COF | . | 330.3 | 0.05 | 434.2 | . | 172.1 | 0.43 | 206.0 |
| | Job type | <.01 | | <.01 | | 0.28 | | 0.23 | |
| | Plastic | 0.04 | | 0.09 | | 0.60 | | 0.45 | |
| Objective 2: Model 25 | COF | . | 313.3 | 0.05 | 417.3 | . | 158.0 | 0.42 | 191.0 |
| | Job type | <.01 | | <.01 | | 0.38 | | 0.34 | |
| | Plastic | 0.03 | | 0.16 | | 0.81 | | 0.70 | |
| | Job type*Plastic | 0.29 | | 0.59 | | 0.89 | | 0.95 | |

Table 7-8: (continued) Post-Verification Tool Room Modeling Results

| Model | Variables Included in Model | Floors | | | | Sills | | | |
|-----------------------|-------------------------------|-----------------|-------------------|----------|-------------------|-----------------|-------------------|----------|-------------------|
| | | All Residential | | Combined | | All Residential | | Combined | |
| | | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood |
| Objective 3: Model 21 | COF | . | 355.6 | 0.39 | 458.7 | . | 184.2 | 0.22 | 219.2 |
| | Clean | 0.20 | | 0.29 | | 0.26 | | 0.10 | |
| Objective 3: Model 22 | COF | . | 349.2 | 0.41 | 451.7 | . | 180.4 | 0.25 | 215.1 |
| | Intensity level | 0.08 | | 0.03 | | 0.29 | | 0.15 | |
| | Clean | 0.16 | | 0.27 | | 0.31 | | 0.13 | |
| Objective 3: Model 23 | COF | . | 344.4 | 0.42 | 447.1 | . | 176.5 | 0.26 | 211.7 |
| | Intensity level | 0.07 | | 0.03 | | 0.31 | | 0.15 | |
| | Clean | 0.18 | | 0.31 | | 0.30 | | 0.14 | |
| | Intensity level*Clean | 0.55 | | 0.38 | | 0.88 | | 0.74 | |
| Objective 3: Model 24 | COF | . | 332.6 | 0.06 | 435.9 | . | 171.1 | 0.38 | 203.6 |
| | Job type | <.01 | | 0.01 | | 0.27 | | 0.19 | |
| | Clean | 0.17 | | 0.28 | | 0.24 | | 0.09 | |
| Objective 3: Model 25 | COF | . | 318.2 | 0.06 | 420.3 | . | 155.9 | 0.41 | 185.6 |
| | Job type | <.01 | | 0.02 | | 0.24 | | 0.16 | |
| | Clean | 0.18 | | 0.38 | | 0.27 | | 0.06 | |
| | Job type*Clean | 0.66 | | 0.71 | | 0.62 | | 0.45 | |
| Objective Y: Model 9 | COF | . | 346.6 | 0.45 | 448.7 | . | 180.9 | 0.35 | 217.4 |
| | Intensity level | 0.57 | | 0.27 | | 0.94 | | 0.62 | |
| | Avg. PostWork Work Floor Lead | 0.03 | | 0.04 | | 0.12 | | 0.21 | |
| | Plastic | 0.11 | | 0.10 | | 0.64 | | 0.42 | |
| Objective Y: Model 10 | COF | . | 331.5 | 0.07 | 435.0 | . | 173.1 | 0.46 | 207.4 |
| | Job type | 0.05 | | 0.10 | | 0.74 | | 0.58 | |
| | Avg. PostWork Work Floor Lead | 0.82 | | 0.31 | | 0.75 | | 0.80 | |
| | Plastic | 0.05 | | 0.09 | | 0.64 | | 0.45 | |

7.3.3. Post-Verification Observation Room Dust Lead Levels

Table 7-9 provides the results from the statistical models developed to describe post-verification floor and window sill dust-lead loadings in the Observation room. Objective 1-Models 47 and 48 assess the total effects of Intensity-Level and Job-Type, respectively, on post-verification floor and window sill dust lead loadings. Both were shown to still be statistically significant predictors of post-verification floor and window sill dust lead loadings in the Observation room. In the remaining models fit to the post-verification Observation room data, average paint lead loading appeared to be predictive of both floor and window sill dust-lead levels, and models that accounted for the combined effects of job type and use of plastic provided the best fit.

Objective 2-Model 30 is highlighted in Table 7-9 as providing the best fit for each of the four data sets; however, the results for these data are not as clear. Use of plastic is found to be borderline significant in the residential data but not is significant in the combined data. When the job type by plastic use interaction is not included, the effect of plastic use is significant for the residential data and for window sills in the combined data. The residual plots in Section O9 of Appendix O appear approximately normal for floors and window sills.

Table 7-9: Post-Verification Observation Room Modeling Results

| Model | Variables Included in Model | Floors | | | | Sills | | | |
|-----------------------|-----------------------------|-----------------|-------------------|----------|-------------------|-----------------|-------------------|----------|-------------------|
| | | All Residential | | Combined | | All Residential | | Combined | |
| | | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood |
| Objective 1: Model 47 | COF | . | 273.0 | 0.84 | 346.8 | . | 151.4 | 0.25 | 176.2 |
| | Intensity level | <.01 | | <.01 | | 0.07 | | 0.05 | |
| Objective 1: Model 48 | COF | . | 249.1 | 0.80 | 325.7 | . | 138.6 | 0.35 | 159.7 |
| | Job type | <.01 | | <.01 | | 0.02 | | <.01 | |
| Objective 1: Model 49 | COF | . | 267.1 | 0.38 | 348.5 | . | 145.9 | 0.03 | 179.2 |
| | Square feet disturbed | 0.82 | | 0.56 | | 0.10 | | 0.25 | |
| | Avg. paint lead | <.01 | | <.01 | | <.01 | | <.01 | |
| | Intensity level | <.01 | | <.01 | | 0.02 | | 0.05 | |
| Objective 1: Model 50 | COF | . | 244.6 | 0.48 | 323.0 | . | 135.2 | 0.24 | 161.8 |
| | Square feet disturbed | 0.03 | | 0.10 | | 0.46 | | 0.10 | |
| | Avg. paint lead | <.01 | | <.01 | | <.01 | | 0.01 | |
| | Job type | <.01 | | <.01 | | <.01 | | <.01 | |
| Objective 1: Model 51 | COF | . | 253.9 | 0.37 | 339.0 | . | 134.6 | 0.08 | 168.4 |
| | Avg. paint lead | <.01 | | <.01 | | <.01 | | <.01 | |
| | Clean*Plastic | 0.08 | | 0.31 | | 0.06 | | 0.12 | |
| | Intensity level | <.01 | | <.01 | | <.01 | | 0.02 | |
| Objective 1: Model 52 | COF | . | 235.5 | 0.48 | 317.4 | . | 123.8 | 0.18 | 153.8 |
| | Avg. paint lead | <.01 | | <.01 | | <.01 | | <.01 | |
| | Clean*Plastic | 0.04 | | 0.39 | | 0.10 | | 0.14 | |
| | Job type | <.01 | | <.01 | | <.01 | | <.01 | |
| Objective 2: Model 26 | COF | . | 292.2 | 0.87 | 366.5 | . | 152.8 | 0.21 | 178.8 |
| | Plastic | 0.26 | | 0.59 | | 0.05 | | 0.08 | |
| Objective 2: Model 27 | COF | . | 268.8 | 0.83 | 346.4 | . | 145.8 | 0.24 | 172.8 |
| | Intensity level | <.01 | | <.01 | | 0.01 | | 0.02 | |
| | Plastic | 0.03 | | 0.29 | | 0.01 | | 0.04 | |
| Objective 2: Model 28 | COF | . | 266.4 | 0.83 | 344.4 | . | 141.4 | 0.24 | 169.1 |
| | Intensity level | <.01 | | <.01 | | 0.03 | | 0.03 | |
| | Plastic | 0.05 | | 0.32 | | 0.04 | | 0.07 | |
| | Intensity level*Plastic | 0.95 | | 0.99 | | 0.32 | | 0.32 | |
| Objective 2: Model 29 | COF | . | 244.7 | 0.80 | 325.6 | . | 133.4 | 0.37 | 156.2 |
| | Job type | <.01 | | <.01 | | <.01 | | <.01 | |
| | Plastic | 0.03 | | 0.32 | | 0.02 | | 0.03 | |
| Objective 2: Model 30 | COF | . | 230.8 | 0.83 | 306.3 | . | 118.9 | 0.38 | 140.3 |
| | Job type | <.01 | | <.01 | | <.01 | | <.01 | |
| | Plastic | 0.06 | | 0.85 | | 0.08 | | 0.13 | |
| | Job type*Plastic | 0.17 | | 0.07 | | 0.21 | | 0.18 | |
| Objective 3: Model 26 | COF | . | 293.0 | 0.88 | 366.7 | . | 155.6 | 0.24 | 180.6 |
| | Clean | 0.44 | | 0.65 | | 0.30 | | 0.25 | |
| Objective 3: Model 27 | COF | . | 272.5 | 0.84 | 347.3 | . | 150.4 | 0.26 | 175.5 |
| | Intensity level | <.01 | | <.01 | | 0.06 | | 0.04 | |
| | Clean | 0.33 | | 0.58 | | 0.22 | | 0.19 | |
| Objective 3: Model 28 | COF | . | 269.8 | 0.83 | 344.4 | . | 147.9 | 0.25 | 173.8 |
| | Intensity level | <.01 | | <.01 | | 0.08 | | 0.06 | |
| | Clean | 0.37 | | 0.60 | | 0.22 | | 0.19 | |
| | Intensity level*Clean | 0.86 | | 0.59 | | 0.85 | | 0.81 | |

Table 7-9: (continued) Post-Verification Observation Room Modeling Results

| Model | Variables Included in Model | Floors | | | | Sills | | | |
|-----------------------|-------------------------------|-----------------|-------------------|----------|-------------------|-----------------|-------------------|----------|-------------------|
| | | All Residential | | Combined | | All Residential | | Combined | |
| | | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood |
| Objective 3: Model 29 | COF | . | 248.9 | 0.79 | 326.6 | . | 138.5 | 0.36 | 159.9 |
| | Job type | <.01 | | <.01 | | 0.02 | | <.01 | |
| | Clean | 0.33 | | 0.84 | | 0.40 | | 0.33 | |
| Objective 3: Model 30 | COF | . | 239.3 | 0.77 | 313.6 | . | 126.9 | 0.35 | 147.6 |
| | Job type | <.01 | | <.01 | | 0.05 | | 0.02 | |
| | Clean | 0.32 | | 0.92 | | 0.33 | | 0.26 | |
| | Job type*Clean | 0.82 | | 0.63 | | 0.55 | | 0.51 | |
| Objective 4: Model Y | COF | . | 266.3 | 0.96 | 342.3 | . | 143.9 | 0.39 | 168.9 |
| | Intensity level | <.01 | | 0.02 | | 0.93 | | 0.97 | |
| | Avg. PostWork Work Floor Lead | 0.02 | | <.01 | | 0.02 | | <.01 | |
| | Plastic | 0.08 | | 0.34 | | 0.05 | | 0.05 | |
| Objective 4: Model Y | COF | . | 246.8 | 0.88 | 326.3 | . | 133.8 | 0.50 | 156.5 |
| | Job type | <.01 | | <.01 | | 0.19 | | 0.16 | |
| | Avg. PostWork Work Floor Lead | 0.79 | | 0.20 | | 0.19 | | 0.11 | |
| | Plastic | 0.03 | | 0.34 | | 0.04 | | 0.04 | |

7.4. Comparison of Rule Practices and Baseline Practices - Post-Job Dust Lead Levels

The following three subsections provide an overview of statistical modeling results for floor and window sill dust lead loadings in a cross-stage analysis comparing full rule implementation (use of plastic sheeting and proposed Rule cleaning at the Post-Verification Stage) to no rule implementation (no use of plastic sheeting and baseline cleaning at the Post-Cleaning Stage).

7.4.1. Post-Job Work Room Dust Lead Levels

Table 7-10 provides an overview of results from the various statistical models applied across stages within the Work room - comparing full rule implementation to no rule implementation. Model 1 assesses the total effect of rule implementation, which was shown to be highly significant in both floors and window sills in the two subsets of data explored. Models 2 through 5 assess the effect of full rule implementation in the Work room, after adjusting for intensity-level or job type and their interaction with full rule implementation. In each of these adjusted models, full rule implementation was associated with significantly lower dust-lead loadings in the Work room. Model 5 appears to fit the data best for each of the four data sets. The residual plots from the floor models appear reasonable, while the residual plots from the sill models appear to be heavy-tailed.

Table 7-10: Post-Job Work Room, Rule vs. Non-Rule Modeling Results

| Model | Variables Included in Model | Floors | | | | Sills | | | |
|----------------------|---|-----------------|-------------------|----------|-------------------|-----------------|-------------------|----------|-------------------|
| | | All Residential | | Combined | | All Residential | | Combined | |
| | | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood |
| Objective X: Model 1 | COF Rule | . | 245.1 | 0.22 | 293.4 | . | 78.1 | 0.31 | 92.8 |
| | | 0.01 | | <.01 | | 0.02 | | <.01 | |
| Objective X: Model 2 | COF Rule Intensity level | . | 238.8 | 0.12 | 285.5 | . | 76.4 | 0.33 | 91.3 |
| | | <.01 | | <.01 | | 0.03 | | <.01 | |
| | | 0.06 | | 0.01 | | 0.93 | | 0.77 | |
| Objective X: Model 3 | COF Rule Intensity level Rule*Intensity level | . | 234.3 | 0.11 | 280.9 | . | 71.4 | 0.33 | 87.8 |
| | | <.01 | | <.01 | | 0.04 | | <.01 | |
| | | 0.17 | | 0.02 | | 0.69 | | 0.61 | |
| | | 0.49 | | 0.23 | | 0.58 | | 0.74 | |
| Objective X: Model 4 | COF Rule Job type | . | 215.9 | <.01 | 268.0 | . | 64.7 | 0.19 | 76.7 |
| | | <.01 | | <.01 | | 0.02 | | <.01 | |
| | | <.01 | | <.01 | | 0.35 | | 0.34 | |
| Objective X: Model 5 | COF Rule Job type Rule*Job type | . | 202.7 | <.01 | 253.2 | . | 49.6 | 0.33 | 59.4 |
| | | <.01 | | <.01 | | 0.10 | | 0.02 | |
| | | <.01 | | <.01 | | 0.61 | | 0.52 | |
| | | 0.35 | | 0.68 | | 0.66 | | 0.60 | |

7.4.2. Post-Job Tool Room Dust Lead Levels

The model results from comparing full rule implementation to no rule implementation within the Tool room are presented in Table 7-11. Model 6 assesses the total effect of rule implementation, which was not a statistically significant predictor of dust lead loadings in the Tool room. Models 7 through 10 assess the effect of full rule implementation in the Work room, after adjusting for intensity-level or job type and their interaction with full rule implementation. These models suggest that full rule implementation was associated with a marginally significant decrease in window sill dust lead levels, after adjusting for the effects of job-type (Model 9). Model 10 appears to provide the best fit, although by adding the rule use by job type interaction the effect of the rule was no longer significant. Section O11 presents the residual plots for Model 10, which appear to be normally distributed except for the residential sill data.

Table 7-11: Post-Job Tool Room, Rule vs. Non-Rule Modeling Results

| Model | Variables Included in Model | Floors | | | | Sills | | | |
|----------------------|---|-----------------|-------------------|----------|-------------------|-----------------|-------------------|----------|-------------------|
| | | All Residential | | Combined | | All Residential | | Combined | |
| | | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood |
| Objective X: Model 6 | COF Rule | . | 180.4 | 0.47 | 233.2 | . | 91.0 | 0.45 | 107.6 |
| | | 0.46 | | 0.46 | | 0.24 | | 0.13 | |
| Objective X: Model 7 | COF Rule Intensity level | . | 171.5 | 0.33 | 224.8 | . | 83.4 | 0.40 | 102.1 |
| | | 0.22 | | 0.23 | | 0.18 | | 0.10 | |
| | | <.01 | | <.01 | | 0.14 | | 0.20 | |
| Objective X: Model 8 | COF Rule Intensity level Rule*Intensity level | . | 165.9 | 0.37 | 220.3 | . | 76.7 | 0.40 | 96.7 |
| | | 0.35 | | 0.31 | | 0.23 | | 0.13 | |
| | | 0.05 | | 0.03 | | 0.12 | | 0.17 | |
| | | 0.78 | | 0.84 | | 0.45 | | 0.59 | |

Table 7-11: (continued) Post-Job Tool Room, Rule vs. Non-Rule Modeling Results

| Model | Variables Included in Model | Floors | | | | Sills | | | |
|-----------------------|-----------------------------|-----------------|-------------------|----------|-------------------|-----------------|-------------------|----------|-------------------|
| | | All Residential | | Combined | | All Residential | | Combined | |
| | | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood |
| Objective X: Model 9 | COF | . | 144.2 | 0.23 | 205.1 | . | 69.2 | 0.54 | 85.8 |
| | Rule | 0.08 | | 0.23 | | 0.09 | | 0.06 | |
| | Job type | <.01 | | <.01 | | 0.07 | | 0.16 | |
| Objective X: Model 10 | COF | . | 131.3 | 0.22 | 186.5 | . | 52.2 | 0.46 | 66.6 |
| | Rule | 0.17 | | 0.36 | | 0.19 | | 0.14 | |
| | Job type | <.01 | | 0.10 | | 0.30 | | 0.36 | |
| | Rule*Job type | 0.97 | | 0.99 | | 0.80 | | 0.91 | |

7.4.3. Post-Job Observation Room Dust Lead Levels

Table 7-12 contains the model results from comparing full rule implementation to no rule implementation across stages within the Observation room. Model 11 assesses the total effect of rule implementation, which was not a statistically significant predictor of dust lead loadings. Models 12 through 15 assess the effect of full rule implementation, after adjusting for intensity-level or job-type and their interaction with full rule implementation. The effect of full rule implementation was not a significant predictor of dust-lead loadings in any of these adjusted models within the Observation room.

Model 15 seems to provide the best fit to the data, but the variable added for the interaction between rule use and job type is not significant at all. The residuals plots for Model 15 contained in Section O12 of Appendix O are approximately normal except for the residential floor data.

Table 7-12: Post-Job Observation Room, Rule vs. Non-Rule Modeling Results

| Model | Variables Included in Model | Floors | | | | Sills | | | |
|-----------------------|-----------------------------|-----------------|-------------------|----------|-------------------|-----------------|-------------------|----------|-------------------|
| | | All Residential | | Combined | | All Residential | | Combined | |
| | | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood | p-value | -2 Log Likelihood |
| Objective X: Model 11 | COF | . | 167.4 | 0.68 | 201.2 | . | 78.3 | 0.33 | 91.7 |
| | Rule | 0.43 | | 0.66 | | 0.43 | | 0.56 | |
| Objective X: Model 12 | COF | . | 154.4 | 0.49 | 191.5 | . | 74.0 | 0.29 | 88.0 |
| | Rule | 0.23 | | 0.40 | | 0.38 | | 0.50 | |
| | Intensity level | <.01 | | 0.01 | | 0.32 | | 0.27 | |
| Objective X: Model 13 | COF | . | 149.2 | 0.50 | 186.9 | . | 69.6 | 0.31 | 84.4 |
| | Rule | 0.23 | | 0.41 | | 0.43 | | 0.54 | |
| | Intensity level | 0.02 | | 0.03 | | 0.44 | | 0.38 | |
| | Rule*Intensity level | 0.77 | | 0.79 | | 0.90 | | 0.85 | |
| Objective X: Model 14 | COF | . | 135.1 | 0.49 | 174.9 | . | 58.9 | 0.34 | 70.7 |
| | Rule | 0.10 | | 0.26 | | 0.23 | | 0.32 | |
| | Job type | <.01 | | <.01 | | 0.06 | | 0.07 | |
| Objective X: Model 15 | COF | . | 122.5 | 0.55 | 157.9 | . | 44.9 | 0.35 | 56.0 |
| | Rule | 0.14 | | 0.35 | | 0.35 | | 0.47 | |
| | Job type | <.01 | | 0.12 | | 0.33 | | 0.32 | |
| | Rule*Job type | 0.96 | | 1.00 | | 0.80 | | 0.93 | |

7.5. Exterior Dust Lead Levels

The main comparisons of interest for the exterior experiments are (1) the levels of lead measured on top of the Rule plastic compared to levels measured under the Rule plastic, and (2) the levels of lead measured on top of the Rule plastic compared to levels measured near the Rule plastic. The first comparison focuses on the effectiveness of the Rule plastic at preventing dust from spreading to the ground underneath it, while the second focuses on whether the Rule plastic was adequate to prevent contamination of the ground a bit further away from the work area. Appendix N contains the detailed model results for the mixed models run on both sets of exterior data. Table 7-13 presents the ratios of the model-predicted lead levels measured at each of the three locations: near (N) Rule plastic vs. on (O) Rule plastic; near (N) Rule plastic vs. Under (U) Rule plastic; and on (O) Rule plastic vs. Under (U) Rule plastic. Bulk debris samples are included in Table 7-13; however, the same statistics are presented in Table 7-14 without the bulk debris samples.

Table 7-13. Comparison Exterior Dust Pan Levels Within Each Job with Bulk Debris Samples Included (Model Based Estimate Differences and Ratios)

| Job Type | Location 1 | Location 2 | Estimate (Log. Scale) | StdErr of Estimate (Log. Scale) | Ratio | 95% Confidence Interval on the Ratio | |
|-----------------------------|------------|------------|-----------------------|---------------------------------|---------|--------------------------------------|----------|
| | | | | | | Lower | Upper |
| Door Replacement | Near | On | -1.50 | 1.19 | 0.2 | 0.0 | 2.4 |
| | Near | Under | 6.03 | 1.19 | 417.0 | 39.6 | 4,386.7 |
| | On | Under | 7.53 | 1.19 | 1,869.9 | 177.7 | 19,672.5 |
| Trim/Soffit Replacement | Near | On | -1.58 | 1.19 | 0.2 | 0.0 | 2.2 |
| | Near | Under | 4.54 | 1.19 | 94.0 | 8.9 | 989.3 |
| | On | Under | 6.13 | 1.19 | 457.1 | 43.5 | 4,809.4 |
| Needle Gun | Near | On | -3.43 | 1.68 | 0.0 | 0.0 | 0.9 |
| | Near | Under | 3.16 | 1.68 | 23.6 | 0.8 | 657.0 |
| | On | Under | 6.59 | 1.68 | 724.9 | 26.0 | 20,213.6 |
| Heat gun under 1100 degrees | Near | On | -4.20 | 1.68 | 0.0 | 0.0 | 0.4 |
| | Near | Under | 3.53 | 1.68 | 34.3 | 1.2 | 955.5 |
| | On | Under | 7.74 | 1.68 | 2,291.3 | 82.2 | 63,895.1 |
| Dry Scrape | Near | On | -4.03 | 0.84 | 0.0 | 0.0 | 0.1 |
| | Near | Under | 2.65 | 0.84 | 14.2 | 2.7 | 75.0 |
| | On | Under | 6.69 | 0.84 | 802.0 | 151.9 | 4,235.4 |
| Power Sanding | Near | On | -2.93 | 1.19 | 0.1 | 0.0 | 0.6 |
| | Near | Under | 1.86 | 1.19 | 6.5 | 0.6 | 67.9 |
| | On | Under | 4.79 | 1.19 | 120.8 | 11.5 | 1,271.1 |
| Torching | Near | On | -7.19 | 1.19 | 0.0 | 0.0 | 0.0 |
| | Near | Under | -3.00 | 1.19 | 0.1 | 0.0 | 0.5 |
| | On | Under | 4.18 | 1.19 | 65.7 | 6.2 | 690.9 |
| Heat gun over 1100 degrees | Near | On | -5.88 | 1.68 | 0.0 | 0.0 | 0.1 |
| | Near | Under | 1.14 | 1.68 | 3.1 | 0.1 | 86.8 |
| | On | Under | 7.02 | 1.68 | 1,113.8 | 39.9 | 31,058.6 |

The Estimate column within tables 7-13 and 7-14 provides the predicted difference from the model for Location 1 – Location 2. Thus, the predicted difference of On-Under for the door replacement job (including bulk debris samples) is 6.9 units on the log scale. This translated to a ratio of 1,870:1 with a lower bound on a 95% confidence interval of 178:1. For the O:U comparison, a ratio greater than one indicates significantly higher levels on the plastic than under, which was expected. For the N:O comparison, a ratio less than one indicates that the lead levels measured near the Rule plastic are lower than those on the Rule plastic.

Table 7-14. Comparison Exterior Dust Pan Levels Within Each Job Excluding Bulk Debris Samples (Model Based Estimate Differences and Ratios)

| Job Type | Location 1 | Location 2 | Estimate (Log. Scale) | StdErr of Estimate (Log. Scale) | Ratio | 95% Confidence Interval on the Ratio | |
|-----------------------------|------------|------------|-----------------------|---------------------------------|---------|--------------------------------------|---------|
| | | | | | | Lower | Upper |
| Door Replacement | Near | On | -0.88 | 0.92 | 0.41 | 0.07 | 2.58 |
| | Near | Under | 6.03 | 0.92 | 416.95 | 66.92 | 2598.06 |
| | On | Under | 6.91 | 0.92 | 1006.52 | 161.53 | 6271.66 |
| Trim Soffit Replacement | Near | On | 0.32 | 0.92 | 1.37 | 0.22 | 8.54 |
| | Near | Under | 4.54 | 0.92 | 94.03 | 15.09 | 585.93 |
| | On | Under | 4.23 | 0.92 | 68.63 | 11.01 | 427.62 |
| Needle Gun | Near | On | -0.19 | 1.30 | 0.82 | 0.06 | 10.94 |
| | Near | Under | 3.16 | 1.30 | 23.56 | 1.77 | 313.20 |
| | On | Under | 3.35 | 1.30 | 28.62 | 2.15 | 380.44 |
| Heat gun under 1100 degrees | Near | On | 0.01 | 1.30 | 1.01 | 0.08 | 13.48 |
| | Near | Under | 2.49 | 1.30 | 12.05 | 0.91 | 160.24 |
| | On | Under | 2.48 | 1.30 | 11.88 | 0.89 | 158.01 |
| Dry Scrape | Near | On | -2.25 | 0.65 | 0.11 | 0.03 | 0.38 |
| | Near | Under | 2.65 | 0.65 | 14.21 | 3.90 | 51.80 |
| | On | Under | 4.90 | 0.65 | 134.58 | 36.91 | 490.70 |
| Power Sanding | Near | On | -1.26 | 0.92 | 0.28 | 0.05 | 1.77 |
| | Near | Under | 1.86 | 0.92 | 6.46 | 1.04 | 40.22 |
| | On | Under | 3.12 | 0.92 | 22.75 | 3.65 | 141.77 |
| Torching | Near | On | -2.55 | 0.92 | 0.08 | 0.01 | 0.49 |
| | Near | Under | -3.00 | 0.92 | 0.05 | 0.01 | 0.31 |
| | On | Under | -0.45 | 0.92 | 0.64 | 0.10 | 3.96 |
| Heat gun over 1100 degrees | Near | On | -2.70 | 1.30 | 0.07 | 0.01 | 0.89 |
| | Near | Under | 1.14 | 1.30 | 3.11 | 0.23 | 41.37 |
| | On | Under | 3.84 | 1.30 | 46.35 | 3.49 | 616.23 |

The results in Table 7-13, which include the bulk debris samples, report that O:U ratios range from 66:1 to 2,291:1 with the power sanding the torch burning jobs having the lowest lower confidence interval bounds at 12:1 and 6:1, respectively. Generally, this indicates that only a small percentage of the lead levels that landed on top of the Rule plastic were measured underneath the plastic. Note that the 95% confidence bounds are very wide because of the relatively small number of samples available for each job. The N:O ratios are less than 0.2:1 across all jobs, although the upper confidence bound on the door replacement and trim/soffit replacement jobs exceeded 1:1.

Because the impact of excluding the bulk debris samples was to significantly lower the amounts of lead measured on top of the Rule plastic, the results in Table 7-14 differ somewhat from those in Table 7-13. The estimated O:U ratio of the torch burning job is below 1:1, as over 99 percent of the on Rule plastic samples were comprised of the bulk debris. The O:U ratios for the other jobs declined, but the lowest predicted ratio other than the torch burning was 12:1 for the heat gun job below 1100 degrees. Similarly, the lower 95% confidence bounds decreased with the torch burning and heat gun <1100 degrees below 1:1. The N:O ratios increased with the decline in the lead levels on the Rule plastic causing two jobs exceed 1:1 – the trim/soffit replacement and the heat gun under 1100 degrees. The upper confidence bounds on five jobs exceeds 1:1 with the exclusion of the bulk debris samples.

Note that the lead levels measured near the Rule plastic are somewhat impacted by the amount of Rule plastic that could be used for a job given the property constraints. Both door replacement jobs only had seven or eight feet of space between the door being worked on and a fence, which limited the size of the Rule plastic that could be used. Similarly, one of the trim/soffit replacement jobs had about the same distance between the porch being worked on and a neighboring fence. For that job especially, which occurred on components about 10 feet off the ground, in a real-world situation more rule plastic would be used than was used in the experiment.

8. Quality Assurance and Quality Control Results

8.1. Field Audit Results

8.1.1. Site Selection Audit

The Battelle Quality Assurance officer conducted audits of the X-ray fluorescence (XRF) measurement procedure and the methodology for collection of paint chip samples on September 11, 2006, and October 24, 2006, respectively. Both audits were performed by observing actual work done in the field. The procedures as performed by the study technicians, including Battelle staff and subcontractors, followed those outlined in the Site Selection QAPP. Only minor suggestions, usually concerning documentation, were offered to the field staff, who immediately implemented the corrective actions as appropriate.

8.1.2. Field Implementation

The Battelle Quality Assurance officer conducted three on-site field audits of renovation work and related environmental sampling. The first audit was of an exterior paint removal job in Columbus on October 19, 2006. Observed was the construction of the containment structure, use of personal protective equipment (PPE), manual paint removal, and sampling by collection of dust and paint chips accumulated on the dust collection trays, followed by subsequent take down of the containment structure. The procedures as performed by the field crew, including Battelle staff and subcontractors, followed those outlined in the Full Study QAPP. Personnel for the on-site RRP contractor were reminded that they must use the appropriate PPE, and they complied immediately; however, no major deficiencies were identified.

An on-site audit of an interior window removal job (Phase III) in Columbus was performed on October 20, 2006. The Battelle auditor observed, among other tasks, removal and replacement of the window, personal and area air sampling, rule cleaning using HEPA vacuums followed by wet mopping, and cleaning verification. Specifically inspected was the method of dust wipe collection in the work, tool, and observation rooms. It was confirmed that the study technicians were following ASTM guidelines to properly collect wipe samples by using a proper "S" pattern and using as much of the wipe surface area as possible in order to maximize dust collection efficiency. The procedures as performed by the field crew, including Battelle staff and subcontractors, followed those outlined in the Full Study QAPP.

A third on-site audit was conducted in Pittsburgh during an interior kitchen gutting (Phase II) on November 6, 2006. Essentially the same activities were observed as for the on-site field audit in Columbus on October 19, 2006, for the window removal job. Specifically inspected was the method of dust wipe collection in the work, tool, and observation rooms. It was confirmed that the study technicians were following ASTM guidelines to properly collect wipe samples. In general, the procedures as performed by the field crew, including Battelle staff and subcontractors, followed those outlined in the Full Study QAPP.

During all three field audits, no major deficiencies were identified; only minor suggestions, usually concerning documentation, were offered to the field staff, who immediately implemented corrective actions as appropriate.

8.1.3. EPA Site Visits

EPA staff made four separate visits to observe the field work in the study, and provided written and oral reports to the Principal Investigator on their observations. The Principal Investigator reviewed the observations in these reports and responded promptly to any concerns.

8.2. Laboratory Audit Results

The Battelle Quality Assurance officer conducted an on-site, day-long inspection of the analytical laboratory, Schneider Laboratories, Incorporated (SLI), in Richmond, VA, on November 13, 2006. Reviewed were: all pertinent documentation, the lab's organization and project staff responsibilities, elements of Quality Assurance and Quality Control, the staff training program, lab safety, document control, as well as a general review of the lab facilities, equipment, and software. In addition, a thorough review was performed of the procedures employed to prepare and analyze samples. During the course of the audit, no significant issues were identified that required follow-up by the Battelle Quality Assurance officer. A formal audit report was prepared and forwarded to Schneider staff and to project leaders.

8.3. QC Sample Results, Issues, and Resolutions

In general, the results of the analysis of the quality control (QC) samples revealed not only that field staff were handling samples appropriately, but also that the results from the contract analytical laboratory, Schneider Laboratories, Inc., (SLI) were accurate and reproducible.

A number of different external QC samples were prepared. Blank wipes were prepared by field technicians who donned clean gloves, opened the wipe packet, and placed the unused wipe into a clean, prelabeled sample vial. Blank air cassettes were flow checked by passing a nominal amount of air through them (no more than approximately 6 L), then were capped and labeled. Spiked wipes and air cassettes were prepared by the Department of Environmental Services (DES) at the University of Cincinnati using National Institutes of Standards and Technology (NIST) Standard Reference Materials. The spikes were then inserted into the sample stream as blind performance evaluation samples to verify the integrity of the analytical results provided by SLI.

Table 8-1 contains the results from analyzing the external quality control samples.

As seen in Table 8-1, for both the spiked wipes and air cassette blanks, more than 95% of the external QC samples came back within the desired tolerance. Approximately 91% of the blank wipes showed values less than the laboratory's reporting limit (10 µg lead), and over 95% of the blank wipes had lead amounts less than 20 µg.

Table 8-1. Summary of External QC Results

| Media | QC Type | Total Number | Acceptable Tolerance | Percent Within Tolerance | Number Out Of Tolerance | Percent Out Of Tolerance |
|-------|---------|--------------|--------------------------|--------------------------|-------------------------|--------------------------|
| Wipe | Spike | 117 | Bias < 20% | 95.7 | 5 | 4.3 |
| Wipe | Blank | 113 | Amount < RL [†] | 91.2 | 10 | 8.8 |
| Air | Spike | 46 | Bias < 20% | 82.6 | 8 | 17.4 |
| Air | Blank | 66 | Amount < RL | 97.0 | 2 | 3.0 |

[†]RL = reporting limit; for wipes, 10 µg lead; for air cassettes, 2 µg lead

A total of eight of the spiked air cassettes were recovered beyond the acceptable bias range of 20%; of these, four consecutively numbered samples (as labeled by UC DES) showed lead levels less than the reporting limit of 2 µg. DES was contacted and the most likely explanation was an error by the preparation laboratory - that blank cassettes were inadvertently mistaken for spiked cassettes. Excluding these four samples, 90% (42 of 46) of the external QC air cassettes demonstrated acceptable recoveries.

In all cases in which the laboratory measured external QC samples outside the acceptable tolerance ranges, it was requested that samples be reanalyzed in order to confirm the original results. In all cases, the initial results were confirmed upon repeat analysis.

An analysis of laboratory's internal quality control data is shown in Table 8-2. These results indicate that the laboratory's internal QC procedures were adequate and, except for the matrix spike, met the study's QC requirements.

Table 8-2. Schneider Laboratories Quality Control Data

| Schneider Laboratories QC Type | Number of Samples | QC Tolerance | # Out of Tolerance | % Out of Tolerance |
|--------------------------------|-------------------|------------------------|--------------------|--------------------|
| Reagent Blank | 908 | < RL ^a | 0 | 0 |
| Wipe Blank | 248 | < RL | 0 | 0 |
| Soil Blank | 61 | < RL | 0 | 0 |
| Paint Blank | 72 | < RL | 0 | 0 |
| Air Filter Blank | 74 | < RL | 0 | 0 |
| Paint Control Sample | 74 | Bias < 20% | 0 | 0 |
| Wipe Control Sample | 248 | Bias < 20% | 0 | 0 |
| Soil Control Sample | 61 | Bias < 20% | 0 | 0 |
| Air Filter Control Sample | 148 | Bias < 20% | 0 | 0 |
| Calibration Verification | 904 | Bias < 15% | 0 | 0 |
| Duplicates | 133 | RPD ^b < 25% | 6 | 4.5% |
| Replicates | 454 | RPD ^b < 25% | 0 | 0 |

^aRL = Reporting Limit ; for most analyses, RL = 10 µg; for air, RL = 2 µg

^bRelative percent deviation: $RPD = |x_1 - x_2| / [(x_1 + x_2) / 2] * 100\%$

Duplicate and replicate tolerances were calculated as relative percent deviation (RPD). A replicate analysis is one in which the sample extract is analyzed twice and is a measure of the repeatability of a measurement (instrument reproducibility). This is substantially different from a duplicate analysis in which a given sample is homogenized and split into two subsamples. Duplicate samples could only be prepared for matrices that could be subsampled, i.e., only for

paint chip and soil samples. Results from duplicate analyses provide a measure of the reproducibility of the sample handling and extraction procedures, superimposed onto any instrumental variability. Approximately 13% of the replicate analyses showed lead concentrations below the applicable reporting limit. In all cases, both sample and replicate values were below the applicable reporting limit; as such, all were within tolerance.

Matrix spikes are prepared in a manner similar to a duplicate sample, with the exception that one of the subsamples was subsequently spiked with 200 µg of lead. In most cases, a sample to be prepared for duplicate analysis was also used for the matrix spike; thus a total of three subsamples were collected: one for the primary sample, one for the duplicate, and one for the matrix spike. The spike amount of 200 µg of lead, however, was generally only a small fraction of the total lead concentration in the samples. Thus, small variations in the amount of lead in the samples, due primarily to the heterogeneity of paint and soil samples, resulted in matrix spike recoveries generally outside of the specified tolerance. For example, one particular paint chip sample extract was found to contain 124,206 µg of lead and its duplicate sample showed 139,579 µg lead (RPD = 11.7 %). The matrix spike should have had 124,406 µg of lead, but instead 130,495 µg was found, which calculates to a spike recovery of $(130,495 - 124,206 \mu\text{g})/200 \mu\text{g} * 100\% = 3,144\%$. Given the relatively low spike amount, the ordinary variation between duplicate subsamples resulted in poor spike recoveries.

8.4. Data Audit Process and Results

Battelle's Quality Assurance officer traced approximately 2% of the data (169 field and QC samples) acquired during the field study and subsequent laboratory analyses from the initial acquisition, through data reduction and statistical analysis to ensure the integrity of the results. All calculations performed on these data were verified as correct. Comments that stemmed from the data audit are listed below.

- The need for recording actual batch IDs for environmental samples in the database was identified, in order to allow linking of QC results to samples in a given batch. If necessary, environmental data associated with out-of-tolerance QC samples could be flagged as potentially suspect.
- Field blank and field spike samples were included in the database table containing all the environmental data. It seemed appropriate to move those data to the table containing QA/QC samples.

8.5. Software Reviews

EPA prepared test data sets of interior and exterior data that were processed using the descriptive and statistical summary programs used to summarize the study data. EPA reviewed the output resulting from the analysis of the test data sets and determined that the analytical programs performed as expected.

9.0 Conclusions

9.1. Results for the Proposed Rule Package versus the Baseline Package

Interior

Application of the package of plastic protective sheeting, HEPA vacuuming and wet mopping, and cleaning verification practices in EPA’s proposed rule did result in lower lead levels at the end of a job than were achieved using baseline practices (no plastic protective sheeting and cleaning with broom and a shop-vacuum vacuum). Descriptive analyses in Section 6 of this report display the lower geometric mean levels achieved consistently across jobs on work room floors and sills (see Figures 9-1 and 9-2). Statistical modeling presented in Section 7 confirms a statistically significant difference between proposed rule and baseline practices for work room floors. The associated hypothesis test had a p-value <.01 from models that compared proposed rule practices to baseline practices adjusting for job type and the interaction between job type and use of rule practices for housing units only and for all units combined. The difference between the proposed rule practices and baseline practices was significant (p-value=<.01) for window sills in the Work room, using the combined housing unit and COF data and adjusting for job type and COF. This comparison was also significant using only the residential data (p-value =.02) and adjusting for job type.




Figure 9-1. Post-Job Work Room Floor Lead Levels, By Job And Rule Use




Figure 9-2. Post-Job Work Room Sill Lead Levels, By Job And Rule Use

For the Tool and Observation room floors, differences between the rule package and baseline package were smaller, not consistent across all jobs, and not statistically significant. Figures 6-6 and 6-7 display smaller and non-uniform differences between use of proposed rule practices and baseline practices in the two non-work rooms for floors, with the rule package being lower than the baseline package in five of seven jobs in each room. For some jobs, Tool and Observation room geometric mean floor lead levels at the end of a job were above the EPA standard, even when the rule package was followed. Application of the same statistical model applied to the Work room achieved a non-significant p-value of .17 in the Tool room and .14 in the Observation room for the difference between rule and baseline practices when looking just at housing units. These p-values were even higher with the combined housing unit and COF data. Figures 6-12 and 6-13 display post-job geometric mean lead levels on window sills in the Tool and Observation Rooms, respectively. The differences between rule and baseline practices were non-uniform. Rule practices had lower levels than baseline practices in five of the seven job types for the Tool room, and for four of the seven job types in the Observation room. In the Tool room, the difference between proposed rule practices and baseline practices was borderline significant for window sills (p-value=.06 combined, p-value=.09 housing units only) adjusting for job type and COF. In the Observation room, the difference between proposed rule practices and baseline practices was not significant for window sills (p-value=.32 combined, p-value=.23 housing units only) in models accounting for job type and COF in the combined model and job type in the housing units only model. Tool and Observation room geometric mean sill lead levels were below the EPA standard for all job types except door planing.

While the rule package resulted in lower lead levels than the baseline package in the work room, the final lead levels measured under the rule package were not always lower than the EPA standards. Table 9-1 and Table 9-2, for floors and sills respectively, show the arithmetic mean post-job lead levels and average number of samples above the EPA standard by job type and study phase. The post-job results displayed include post-verification results for phases with rule cleaning and post-cleaning results for phases with baseline cleaning. The arithmetic average post-job floor lead level over all samples collected in the work room for Phase I (plastic and rule cleaning) is less than 40 $\mu\text{g}/\text{ft}^2$ for all job types except Door Planing and Heat Gun >1100 Degrees. The average number of samples above or equal to 40 $\mu\text{g}/\text{ft}^2$ was two or less out of four in five of the seven job types. The arithmetic average post-job window sill lead level over all samples collected in the work room for Phase I is less than 250 $\mu\text{g}/\text{ft}^2$ for all job types except Door Planing and Heat Gun >1100 Degrees, with the latter job just beyond that clearance standard at 278 $\mu\text{g}/\text{ft}^2$. Consistent with this result is that no post-job sill samples above 250 $\mu\text{g}/\text{ft}^2$ were collected in Phase I except in the Door Planing and High Heat Gun jobs.

Table 9-1. Post-job* Average Floor Lead Levels and Failed Samples by Job Type

| Job Type | Phase | # of Exp. | Post-Job* Average Lead Level (µg/ft ²) | Post-Job* Average # of Samples > 40 (µg/ft ²) |
|-----------------------|--------------------------|-----------|--|---|
| Cut-outs | I (plastic/rule) | 3 | 5.0 | 0.0 |
| | II (plastic/baseline) | 3 | 9.1 | 0.0 |
| | III (no plastic/rule) | 3 | 9.9 | 0.0 |
| | IV (no plastic/baseline) | 3 | 37.3 | 1.3 |
| Window Replacement | I (plastic/rule) | 2 | 35.7 | 2.0 |
| | II (plastic/baseline) | 2 | 140.2 | 4.0 |
| | III (no plastic/rule) | 2 | 87.2 | 3.0 |
| | IV (no plastic/baseline) | 2 | 146.2 | 4.0 |
| Dry Scrape | I (plastic/rule) | 2 | 34.2 | 1.5 |
| | II (plastic/baseline) | 2 | 168.3 | 3.5 |
| | III (no plastic/rule) | 2 | 14.4 | 0.0 |
| | IV (no plastic/baseline) | 2 | 70.7 | 3.5 |
| Door Plane | I (plastic/rule) | 2 | 188.9 | 4.0 |
| | II (plastic/baseline) | 2 | 142.3 | 3.5 |
| | III (no plastic/rule) | 2 | 651.8 | 4.0 |
| | IV (no plastic/baseline) | 2 | 771.9 | 4.0 |
| Heat Gun<1100 Degrees | I (plastic/rule) | 1 | 29.1 | 2.0 |
| | II (plastic/baseline) | 1 | 25.6 | 1.0 |
| | III (no plastic/rule) | 1 | 7.5 | 0.0 |
| | IV (no plastic/baseline) | 1 | 44.2 | 2.0 |
| Kitchen Gut | I (plastic/rule) | 2 | 23.7 | 1.0 |
| | II (plastic/baseline) | 2 | 58.6 | 2.5 |
| | III (no plastic/rule) | 2 | 50.9 | 0.5 |
| | IV (no plastic/baseline) | 2 | 82.2 | 3.0 |
| Heat Gun>1100 Degrees | I (plastic/rule) | 3 | 72.7 | 2.7 |
| | II (plastic/baseline) | 3 | 506.8 | 3.0 |
| | III (no plastic/rule) | 3 | 1,019.2 | 2.3 |
| | IV (no plastic/baseline) | 3 | 1,617.8 | 3.0 |

* Post-job refers to the post-verification values for phases that involve the rule cleaning method (I and III) and the post-cleaning values for phases that involve the baseline cleaning method (II and IV).

Table 9-2. Post-job* Window Sill Average Lead Levels and Failed Samples by Job Type.

| Job Type | Phase | # of Exp. | Post-Job* Average Lead Level (µg/ft ²) | Post-Job* Average # of Samples > 250 (µg/ft ²) |
|------------------------|--------------------------|-----------|--|--|
| Cut-outs | I (plastic/rule) | 3 | 30.3 | 0.0 |
| | II (plastic/baseline) | 3 | 58.7 | 0.0 |
| | III (no plastic/rule) | 3 | 70.0 | 0.0 |
| | IV (no plastic/baseline) | 3 | 212.0 | 0.3 |
| Window Replacement | I (plastic/rule) | 2 | 99.4 | 0.0 |
| | II (plastic/baseline) | 2 | 359.4 | 0.5 |
| | III (no plastic/rule) | 2 | 150.8 | 0.5 |
| | IV (no plastic/baseline) | 2 | 598.2 | 1.0 |
| Dry Scrape | I (plastic/rule) | 2 | 31.3 | 0.0 |
| | II (plastic/baseline) | 2 | 246.0 | 0.5 |
| | III (no plastic/rule) | 2 | 24.5 | 0.0 |
| | IV (no plastic/baseline) | 2 | 87.9 | 0.0 |
| Door Plane | I (plastic/rule) | 2 | 865.3 | 0.5 |
| | II (plastic/baseline) | 2 | 202.9 | 0.5 |
| | III (no plastic/rule) | 2 | 1,714.1 | 0.5 |
| | IV (no plastic/baseline) | 2 | 1,038.3 | 1.0 |
| Heat Gun <1100 Degrees | I (plastic/rule) | 1 | 20.8 | 0.0 |
| | II (plastic/baseline) | 1 | 285.1 | 1.0 |
| | III (no plastic/rule) | 1 | n/a | 1.0 |
| | IV (no plastic/baseline) | 1 | 246.8 | 0.0 |
| Kitchen Gut | I (plastic/rule) | 2 | 21.4 | 0.0 |
| | II (plastic/baseline) | 2 | 41.7 | 0.0 |
| | III (no plastic/rule) | 2 | 82.3 | 0.0 |
| | IV (no plastic/baseline) | 2 | 772.3 | 0.5 |
| Heat Gun >1100 Degrees | I (plastic/rule) | 3 | 277.9 | 0.3 |
| | II (plastic/baseline) | 3 | 3,087.6 | 0.7 |
| | III (no plastic/rule) | 3 | 904.4 | 0.3 |
| | IV (no plastic/baseline) | 3 | 1,048.1 | 0.7 |

* Post-job refers to the post-verification values for phases that involve the rule cleaning method (I and III) and the post-cleaning values for phases that involve the baseline cleaning method (II and IV).

Exterior

The use of plastic as a ground covering during exterior jobs captured large amounts of leaded dust. Figure 6-14 and Figure 6-15 compare the amount of lead on top of the rule plastic to the amount under the rule plastic, with Figure 6-14 including bulk debris samples and Figure 6-15 excluding the bulk debris samples. For most job types, there is a substantial difference between the amount of lead captured by the rule plastic and the amount under the rule plastic. One notable special case is Torching. Without the bulk debris samples, the amount of lead under the plastic for Torching exceeded the amount on top. For all 8 job types, the ratio of the amount of lead on top of the rule plastic to the amount underneath was statistically significant when bulk debris samples were included. This changed to 6 out of the 8 job types when bulk debris samples were excluded.

For some job types, substantial amounts of lead were measured in collection trays just outside the rule plastic. The job types for which substantial amounts of lead were measured just outside the rule plastic were trim/soffit replacement, power sanding, and door replacement.

9.2. Results for Use of Plastic Protective Sheeting on Floors and Doorways versus Non-Use of Plastic Protective Sheeting

Figure 6-3 indicates that use of plastic did not consistently result in lower geometric mean work room floor lead levels across job types at the post-cleaning phase. The use of plastic sheeting, however, did lower geometric means for door planing and high heat gun jobs as measured at the post-cleaning phase. Similar results are found with window sills, as seen in Figure 6-8. Modeling and hypothesis testing of the effect of plastic on lead levels on floors in the Work room was not statistically significant at either the post-cleaning (p-value = .15) or post-verification stages (p-value = .10) for housing units when adjusted for job and interactions with job type. For window sills, statistical modeling and hypothesis testing also showed that the use of plastic was not statistically significant at either the post-cleaning for housing units. Using the combined housing unit and COF data, similar results were obtained.

Conclusions about protective plastic are different when considering other parts of a house or building. Figure/Table C2.6b and C2.6c reported consistently lower geometric mean floor lead levels in the Tool and Observation rooms, respectively, with the use of plastic across all three sampling stages – although the differences were relatively small. For example, Tool room floor geometric mean lead levels were 41, 43, and 39 $\mu\text{g}/\text{ft}^2$ across post-work, post-cleaning, and post-verification stages with plastic compared to 57, 61, and 79 $\mu\text{g}/\text{ft}^2$ without plastic; Observation room geometric mean levels were 18, 17, and 22 $\mu\text{g}/\text{ft}^2$ with plastic compared to 30, 38, and 31 $\mu\text{g}/\text{ft}^2$ without plastic.

When modeling the Tool room floor levels, use of plastic was not significant at the post-work stage (p-value=.20, combined data) adjusting for job type and was not significant at the post-cleaning stage (p-value=.52, combined data) adjusting for job type and interactions with job type. At the post-verification stage, use of plastic was borderline significant using the combined data (p-value=.09, adjusted for job type) and significant (p-value=.03, adjusted for job type and post-work lead levels) using only the housing unit data.

Findings for the Observation room floor levels differ somewhat depending on whether COF data are included in the analysis. For residential units only, modeling Observation room levels resulted in significantly lower levels when using plastic at all three stages with p-values of .02 at post-work (adjusted for job type) and <.01 at post-cleaning and post-verification (adjusted for job type and interactions with job type). When analyzing the combined data, the model predicts lower levels using plastic but the difference is borderline significant (p-value = .10) at the post-work stage; significant at the post-cleaning stage (p-value=.01) when adjusted for job type and average post-work work room floor lead; and not significant at post-verification (p-value=.34) using that same model.

The statistical modeling did not find that the use of plastic significantly impacted sill lead levels in the Tool room at any of the three sampling stages. There is evidence, however, when

analyzing the residential data of use of plastic leading to lower sill lead levels in the Observation room at post-cleaning (p-value =.03) and post-verification (p-value =.02) when adjusting for job type or post-work work room floor lead levels.

9.3. Results for Rule Cleaning with HEPA Vacuum and Wet Mopping with Cleaning Solution versus Baseline Cleaning

The data do provide evidence that the proposed rule cleaning method of HEPA vacuuming followed by wet mopping with a cleaning solution yielded lower lead levels than the baseline cleaning method. Analyzing differences in cleaning method is focused on the Work room, as little impact of cleaning method was observed in either of the two non-work rooms. Table C2.7a reports GM post-cleaning floor lead across all jobs of 34 $\mu\text{g}/\text{ft}^2$ for the Rule cleaning and 75 $\mu\text{g}/\text{ft}^2$ for the baseline cleaning. Figure 6-4, which plots post-cleaning GM floor lead levels by job and cleaning method, reports lower levels across all job types except door planing. Figure 6-9 shows similar results for window sills. The statistical models verify these trends, reporting significantly lower post-cleaning floor lead levels after rule cleaning (p-value <.01). No significant difference is found between cleaning methods for floors at the post-verification stage. It should be noted that any cleaning verification failures after baseline cleaning led to recleanings by rule cleaning method in this study. Significantly lower work room window sill lead levels are also found at the post-cleaning (p-value<.01) stages following rule cleaning. Similar to floor lead levels, however, no significant difference based on cleaning method is found at the post-verification stage.

9.4. Results for Cleaning Verification

The cleaning verification process as stated in the proposed rule resulted in decreases in lead levels, but under the conditions of the study was not always accurate in identifying the presence of levels above EPA standards for floors and sills. Factors such as floor condition, contractor performance, job type, and dust particle characteristics impacted the cleaning verification process in the study. All interior experiments did result in final passed cleaning cloths for all floor zones and for all window sills, but nearly half of the experiments ended with average Work room floor lead levels above 40 $\mu\text{g}/\text{ft}^2$ on floors. Lead levels for the cases above the floor standard were distributed as follows: 10 between 40 and 69, 6 between 70 and 99, 5 between 100 and 199, 3 between 200 and 499, and 5 greater than 500. The eight highest levels were associated with high heat gun or door planing jobs and floors in poor condition. Of the 29 experiments where final lead levels were above 40 $\mu\text{g}/\text{ft}^2$ on floors, 20 were on floors in poor condition. Excluding the door planing and high heat gun jobs, which had higher post-job lead levels than the others and which appeared to generate fine particle size dust and, in the case of the door planing, a white dust that was hard to detect on a white cloth, post-job averages when the proposed rule cleaning was used were below clearance levels. For window sills, approximately 20 percent of the experiments ended with lead levels above 250 $\mu\text{g}/\text{ft}^2$. Almost all of the high levels, well above the standard, were associated with door plane and high temperature heat gun jobs. The study did not yield much evidence to evaluate differences in lead levels after the wet and dry cleaning verification steps because the dry cleaning verification was only required in three experiments.

Table 9-3 summarizes the arithmetic average post-verification lead levels and number of samples > 40 µg/ft² for rule cleaning phases and post-cleaning lead levels and number of samples > 40 µg/ft² for baseline cleaning phases. Note that for Phases II and IV, which included baseline cleaning, any recleanings required were done by rule cleaning methods. Within the no plastic/rule cleaning phase, experiment 32 achieved an average post-verification floor lead level of 2,976 µg/ft². If that experiment were excluded, the average post-verification floor lead level for phase III would become 123.4 µg/ft². Factors such as contractor, floor condition, and floor type impacted the performance of the cleaning verification process. One contractor obtained higher post-verification lead levels than the others due in part to this contractor being more willing to pass a verification cloth.

Table 9-3. Post-job Floor Lead Levels and Number of Samples Failing Clearance

| Phase | RULE CLEANING - Post Verification | | BASELINE CLEANING - Post Cleaning | |
|---|-----------------------------------|------------------|-----------------------------------|-----------------|
| | I - Plastic | III - No plastic | II - Plastic | IV - No plastic |
| Average Lead Level (µg/ft ²) | 55.1 | 313.5* | 172.8 | 305.9 |
| Average # of Dust Wipes > 40 µg/ft ² | 1.8 | 1.4 | 2.5 | 2.9 |

* Excluding Experiment 32, which had a very high post-verification floor level, the average lead level is 123.4 µg/ft²

The door planing and high heat gun jobs resulted in the highest post-job lead levels. Table 9-4 summarizes post-job floor lead levels with these two jobs excluded. Significantly lower levels than those presented in Table 9-3 were achieved with these two jobs excluded. Without the two jobs, the post-verification averages for the rule cleaning phases are below clearance, while the baseline cleaning post-cleaning averages are between 75 and 80 µg/ft². For comparison, Table 9-5 presents the summary data for only these two jobs, which generated a lot of fine dust. The distribution across the four P/CU phases is different for these two jobs, with the combination of use of plastic and baseline cleaning associated with lower post-job levels than no plastic and baseline cleaning. Again, one very high post-verification value (2,976.1) from a Phase III heat gun job impacts that average significantly. With that sample excluded, the post-verification average for phase III for door planes and heat guns becomes 346.2 µg/ft².

Table 9-4. Post-job Floor Lead Levels and Number of Samples Failing Clearance (excluding Door Planing and High Heat Gun)

| Phase | RULE CLEANING - Post Verification | | BASELINE CLEANING - Post Cleaning | |
|---|-----------------------------------|------------------|-----------------------------------|-----------------|
| | I - Plastic | III - No plastic | II - Plastic | IV - No plastic |
| Average Lead Level (µg/ft ²) | 23.1 | 34.2 | 78.7 | 75.5 |
| Average # of Dust Wipes > 40 µg/ft ² | 1.1 | 0.6 | 2.1 | 2.7 |

Table 9-5. Post-job Floor Lead Levels and Number of Samples Failing Clearance (Door Planing and High Heat Gun Jobs Only)

| Phase | RULE CLEANING - Post Verification | | BASELINE CLEANING - Post Cleaning | |
|--|-----------------------------------|------------------|-----------------------------------|-----------------|
| | I - Plastic | III - No plastic | II - Plastic | IV - No plastic |
| Average Lead Level ($\mu\text{g}/\text{ft}^2$) | 119.2 | 872.2 | 361.0 | 1,279.4 |
| Average # of Dust Wipes > 40 $\mu\text{g}/\text{ft}^2$ | 3.2 | 3.0 | 3.2 | 3.4 |

Similar to the post-job floor levels and number of samples above the clearance standard, Table 9-6 summarizes the average post-verification lead levels and number of samples > 250 $\mu\text{g}/\text{ft}^2$ for rule cleaning phases and post-cleaning lead levels and number of samples > 250 $\mu\text{g}/\text{ft}^2$ for baseline cleaning phases. Overall, the two phases involving rule cleaning resulted in lower post-job window sill lead levels than the two phases involving baseline cleaning.

Table 9-6. Post-job Window Sill Lead Levels and Number of Samples Failing Clearance

| Phase | RULE CLEANING - Post Verification | | BASELINE CLEANING - Post Cleaning | |
|---|-----------------------------------|------------------|-----------------------------------|-----------------|
| | I - Plastic | III - No plastic | II - Plastic | IV - No plastic |
| Average Lead Level ($\mu\text{g}/\text{ft}^2$) | 198.7 | 490.5 | 761.6 | 601.4 |
| Average # of Dust Wipes > 250 $\mu\text{g}/\text{ft}^2$ | 0.1 | 0.4 | 0.3 | 0.5 |

Due to the configuration of the study rooms and above clearance pre-work lead levels, dust collection trays were substituted for window sills in the Work Room for half (30) of the interior experiments. Tables 9-7 and 9-8 show the comparison of post-job lead levels and number of failures by cleaning method for sampled window sills and dust collection trays, respectively. The average lead level across the phases appears to be lower when sills were sampled, however, 16 out of 20 door plane and heat gun experiments, noted above as having the most dust generated, were completed with dust collection trays serving as window sills.

Table 9-7. Post-job Window Sill Lead Levels and Number of Samples Failing Clearance for Sampled Window Sills

| Phase | RULE CLEANING - Post Verification | | BASELINE CLEANING - Post Cleaning | |
|---|-----------------------------------|------------------|-----------------------------------|-----------------|
| | I - Plastic | III - No plastic | II - Plastic | IV - No plastic |
| Average Lead Level ($\mu\text{g}/\text{ft}^2$) | 293.4 | 101.3 | 190.5 | 663.2 |
| Average # of Dust Wipes > 250 $\mu\text{g}/\text{ft}^2$ | 0.1 | 0.3 | 0.1 | 0.6 |

Table 9-8. Post-job Window Sill Lead Levels and Number of Samples Failing Clearance for Sampled Dust Collection Trays.

| Phase | RULE CLEANING - Post Verification | | BASELINE CLEANING - Post Cleaning | |
|---|-----------------------------------|------------------|-----------------------------------|-----------------|
| | I - Plastic | III - No plastic | II - Plastic | IV - No plastic |
| Average Lead Level ($\mu\text{g}/\text{ft}^2$) | 115.7 | 879.7 | 1,414.3 | 530.7 |
| Average # of Dust Wipes $> 250 \mu\text{g}/\text{ft}^2$ | 0.1 | 0.6 | 0.4 | 0.4 |